DEPARTMENT OF THE NAVY

ATLANTIC DIVISION, NAVAL FACILITIES ENGINEERING COMMAND

MARINE CORPS AIR STATION, CHERRY POINT, NORTH CAROLINA

REPLACE AIR HANDLING UNITS, BLDG. 133
PHASE 3

PROJECT R46-93C

AT THE

MARINE CORPS AIR STATION

CHERRY POINT, NORTH CAROLINA

DESIGNED BY:

NRW ENGINEERING, P.C.
748 LORD DUNMORE DRIVE, SUITE 101,
VIRGINIA BEACH, VIRGINIA, 23464



SPECIFICATION PREPARED BY:

STRUCTURAL: KEVIN M. ROOMSBURG, P.E.

SPECIFICATION APPROVED BY:

Design Director: _____
PAUL E. CLINE, P.E.

Date: 8/15/14

PROJECT TABLE OF CONTENTS

DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS

00 01 15 LIST OF DRAWINGS

DIVISION 01 - GENERAL REQUIREMENTS

01 11 00 SUMMARY OF WORK
01 14 00 WORK RESTRICTIONS
01 20 00.00 20 PRICE AND PAYMENT PROCEDURES
01 30 00 ADMINISTRATIVE REQUIREMENTS
01 33 00 SUBMITTAL PROCEDURES
01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS
01 45 00.00 20 CONSTRUCTION QUALITY CONTROL
01 50 00 TEMPORARY CONSTRUCTION FACILITIES AND CONTROLS
01 57 19.00 20 TEMPORARY ENVIRONMENTAL CONTROLS
01 62 35 RECYCLED / RECOVERED MATERIALS
01 78 00 CLOSEOUT SUBMITTALS
01 78 23 OPERATION AND MAINTENANCE DATA
01 80 00 REPORTS

DIVISION 02 - EXISTING CONDITIONS

02 41 00 DEMOLITION
02 82 16.00 20 ENGINEERING CONTROL OF ASBESTOS CONTAINING MATERIALS
02 83 13.00 20 LEAD IN CONSTRUCTION

DIVISION 05 - METALS

05 12 00 STRUCTURAL STEEL
05 50 13 MISCELLANEOUS METAL FABRICATIONS
05 52 00 METAL RAILINGS

DIVISION 06 - WOOD, PLASTICS, AND COMPOSITES

06 10 00 ROUGH CARPENTRY

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

07 22 00 ROOF AND DECK INSULATION
07 52 00 MODIFIED BITUMINOUS MEMBRANE ROOFING
07 60 00 FLASHING AND SHEET METAL
07 92 00 JOINT SEALANTS

DIVISION 09 - FINISHES

09 90 00 PAINTS AND COATINGS

DIVISION 23 - HEATING, VENTILATING, AND AIR CONDITIONING

23 00 00 AIR SUPPLY, DISTRIBUTION, VENTILATION, AND EXHAUST SYSTEMS
23 03 00.00 20 BASIC MECHANICAL MATERIALS AND METHODS
23 05 15 COMMON PIPING FOR HVAC
23 05 48.00 40 VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT
23 05 48 VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT
23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC

23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS
23 09 23.13 20 DIRECT DIGITAL CONTROL SYSTEMS FOR HVAC
23 22 26.00 20 STEAM SYSTEM AND TERMINAL UNITS

DIVISION 26 - ELECTRICAL

26 00 00.00 20 BASIC ELECTRICAL MATERIALS AND METHODS
26 20 00 INTERIOR DISTRIBUTION SYSTEM

DIVISION 28 - ELECTRONIC SAFETY AND SECURITY

28 31 64.00 10 FIRE DETECTION AND ALARM SYSTEM, ADDRESSABLE

-- End of Project Table of Contents --

DOCUMENT 00 01 15

LIST OF DRAWINGS
08/11

PART 1 GENERAL

1.1 SUMMARY

This document lists the drawings for the project pursuant to contract clause "DFARS 252.236-7001, Contract Drawings, Maps and Specifications."

1.2 DFARS 252.236.7001,CONTRACT DRAWINGS,MAPS AND SPECIFICATIONS (AUG 2000)

(a) The Government will provide to the Contractor, without charge, one set of contract drawings and specifications, except publications incorporated into the technical provisions by reference, in electronic or paper media as chosen by the Contracting Officer.

(b) The Contractor shall-

(1) Check all drawings furnished immediately upon receipt;

(2) Compare all drawings and verify the figures before laying out the work;

(3) Promptly notify the Contracting Officer of any discrepancies;

(4) Be responsible for any errors that might have been avoided by complying with this paragraph (b); and

(5) Reproduce and print contract drawings and specifications as needed.

(c) In general-

(1) Large-scale drawings shall govern small-scale drawings; and

(2) The Contractor shall follow figures marked on drawings in preference to scale measurements.

(d) Omissions from the drawings or specifications or the misdescription of details of work that are manifestly necessary to carry out the intent of the drawings and specifications, or that are customarily performed, shall not relieve the Contractor from performing such omitted or misdescribed details of the work. The Contractor shall perform such details as if fully and correctly set forth and described in the drawings and specifications.

<PGE/>(e) The work shall conform to the specifications and the contract drawings.

Contract drawings are as follows:

NAVFAC NO.	TITLE
12665241	COVER SHEET
12665242	INDEX OF DRAWINGS
12665243	GENERAL NOTES
12665244	STRUCTURAL ROOF PLAN AREA O
12665245	STRUCTURAL ROOF PLAN AREA L
12665246	PLATFORM FRAMING PLANS
12665247	TYPICAL SECTIONS - TRUSS REINFORCEMENT
12665248	TYPICAL SECTIONS - TRUSS REINFORCEMENT
12665249	TYPICAL SECTIONS - MECHANICAL PLATFORMS
12665250	TYPICAL SECTIONS - MECHANICAL PLATFORMS
12665251	TYPICAL SECTIONS - MECHANICAL PLATFORMS
12665252	TYPICAL DETAILS
12665253	EXISTING CONDITION PHOTOS
12665254	DEMOLITION OVERALL ROOF PLAN - PHASE 3
12665255	DEMOLITION ROOF PLAN, AREA K - PHASE 3
12665256	DEMOLITION ROOF PLAN, AREA O - PHASE 3
12665257	NEW WORK OVERALL ROOF PLAN - PHASE 3
12665258	NEW WORK ROOF PLAN, AREA K - PHASE 3
12665259	NEW WORK ROOF PLAN, AREA O - PHASE 3
12665260	ROOF DETAILS
12665261	ROOF DETAILS
12665262	ROOF DETAILS
12665263	LEGEND, ABBREVIATIONS, & NOTES
12665264	MECHANICAL DEMOLITION FLOOR PLAN AREA K
12665265	MECHANICAL DEMOLITION ROOF PLAN AREA K
12665266	MECHANICAL DEMOLITION FLOOR PLAN AREA O
12665267	MECHANICAL DEMOLITION ROOF PLAN AREA O
12665268	MECHANICAL NEW WORK ROOF PLAN AREA H
12665269	MECHANICAL NEW WORK FLOOR PLAN AREA K
12665270	MECHANICAL NEW WORK ROOF PLAN AREA K
12665271	MECHANICAL NEW WORK FLOOR PLAN AREA L
12665272	MECHANICAL NEW WORK ROOF PLAN AREA L
12665273	MECHANICAL NEW WORK FLOOR PLAN AREA O
12665274	MECHANICAL NEW WORK ROOF PLAN AREA O
12665275	MECHANICAL NEW WORK FLOOR PLAN AREA P
12665276	MECHANICAL NEW WORK ROOF PLAN AREA P
12665277	MECHANICAL DETAILS
12665278	MECHANICAL DETAILS
12665279	MECHANICAL DETAILS
12665280	MECHANICAL DETAILS
12665281	MECHANICAL CONTROLS SCHEMATICS
12665282	MECHANICAL EQUIPMENT SCHEDULES
12665283	LEGEND, ABBREVIATIONS, & NOTES
12665284	PANEL SCHEDULE
12665285	SCHEDULE AND DETAILS
12665286	ELECTRICAL DEMOLITION FLOOR PLAN AREA K
12665287	ELECTRICAL DEMOLITION ROOF PLAN AREA K
12665288	ELECTRICAL DEMOLITION FLOOR PLAN AREA O
12665289	ELECTRICAL DEMOLITION ROOF PLAN AREA O
12665290	ELECTRICAL NEW WORK ROOF PLAN AREA H
12665291	ELECTRICAL NEW WORK FLOOR PLAN AREA K
12665292	ELECTRICAL NEW WORK FLOOR PLAN AREA L

NAVFAC NO.	TITLE
12665293	ELECTRICAL NEW WORK ROOF PLAN AREA L
12665294	ELECTRICAL NEW WORK FLOOR PLAN AREA O
12665295	ELECTRICAL NEW WORK ROOF PLAN AREA O
12665296	ELECTRICAL NEW WORK FLOOR PLAN AREA P
12665297	ELECTRICAL NEW WORK ROOF PLAN AREA P

-- End of Document --

SECTION 01 11 00

SUMMARY OF WORK
08/11

PART 1 GENERAL

1.1 WORK COVERED BY CONTRACT DOCUMENTS

1.1.1 Project Description

The work includes replacement of rooftop HVAC equipment and incidental related work.

1.1.2 Location

The work shall be located at the MCAS Cherry Point, approximately as indicated. The exact location will be shown by the Contracting Officer.

1.2 OCCUPANCY OF PREMISES

The building will be occupied during performance of work under this Contract. Occupancy notifications will be posted in a prominent location in the work area.

Before work is started, the Contractor shall arrange with the Contracting Officer a sequence of procedure, means of access, space for storage of materials and equipment, and use of approaches, corridors, and stairways.

1.3 EXISTING WORK

In addition to "FAR 52.236-9, Protection of Existing Vegetation, Structures, Equipment, Utilities, and Improvements":

a. Remove or alter existing work in such a manner as to prevent injury or damage to any portions of the existing work which remain.

b. Repair or replace portions of existing work which have been altered during construction operations to match existing or adjoining work, as approved by the Contracting Officer. At the completion of operations, existing work shall be in a condition equal to or better than that which existed before new work started.

1.4 LOCATION OF UNDERGROUND FACILITIES

It shall be the responsibility of the contractor to locate all existing underground utilities that are within the limits of work, prior to any excavation activities. These include but are not limited to the following buried utilities: water lines, sanitary and storm sewers, steam condensate, fuel lines, gas lines, electrical ducts and direct buried conductors, commercial telephone, Base telephone, commercial cable TV, Base instructional cable TV, EMCS and fire alarm. The contractor shall employ the services of a qualified Utility locating company to locate, identify, and mark all underground utilities. The entire construction limits shall be thoroughly scanned and researched to determine existing utility locations. Any existing utilities that are indicated on the project drawings shall be considered for reference use by the locating company and shall be verified. All underground utilities shall be clearly marked with

flags, paint or stakes prior to any digging operation except that required to determine exact utility location and depth. CAUTION shall be used when trenching or excavating around or near buried utilities. The contractor shall be responsible for the timely repair and/or replacement of direct and collateral damage on any and all underground utilities that are severed, crushed, broken, displaced or otherwise disturbed by the construction operation. The Government shall not incur any additional cost for such repair or replacement. The contractor shall notify the ROICC a minimum of three working days prior to utility location. Do not continue with excavation or installation of new work without resolving elevation discrepancies and conflicts.

Notify the Contracting Officer at least 15 days prior to starting excavation work.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SECTION 01 14 00

WORK RESTRICTIONS
06/14

PART 1 GENERAL

1.1 SPECIAL SCHEDULING REQUIREMENTS

a. The entire building will remain in operation during the entire construction period. The Contractor shall conduct his operations so as to cause the least possible interference with normal operations of the activity.

b. Air handling units shall remain in operation until its replacement is installed and made operational. Clean ductwork and make ductwork cross connections on weekends only, unless agreed upon by the Contracting Officer and the building occupant.

c. Work associated with placement of structural steel inside the building, demolition of penthouses and subsequent roof deck repairs, shall be accomplished on weekends or nights when no occupants are present in the construction area. Provide debris netting or similar devices to protect equipment and facilities located in the immediate construction area.

d. Crane access and reach to the work area of the roof is limited due to existing conditions. The contractor may transport mechanical equipment and structural steel components across the roof. It is the Contractors responsibility to protect the roof and provide sheathing and/or framing as required to maintain the roofing warranty. The maximum superimposed loading of the roof structure shall not exceed 40 PSF.

1.2 CONTRACTOR ACCESS AND USE OF PREMISES

1.2.1 Regulations

Ensure that Contractor personnel employed on the Activity become familiar with and obey Activity regulations. Keep within the limits of the work and avenues of ingress and egress. Wear hard hats in designated areas. Do not enter any restricted areas unless required to do so and until cleared for such entry. The Contractor's equipment shall be conspicuously marked for identification.

1.2.2 Working Hours

Regular working hours shall consist of an 8 1/2 hour period normally between the hours of 7:00 am to 3:30 pm, Monday through Friday, excluding Government holidays.

1.2.3 Work Outside Regular Hours

Work outside regular working hours requires Contracting Officer approval. Make application 15 calendar days prior to such work to allow arrangements to be made by the Government for inspecting the work in progress. During

periods of darkness, the different parts of the work shall be lighted in a manner approved by the Contracting Officer.

1.2.4 Occupied Building

The Contractor shall be working in and around an existing building which is occupied. Do not enter the building without prior approval of the Contracting Officer.

The existing building and its contents shall be kept secure at all times. Provide temporary closures as required to maintain security as directed by the Contracting Officer.

Provide dust covers or protective enclosures to protect existing work that remains and Government material located in the building during the construction period.

Relocate movable furniture approximately 6 feet away from the Contractor's working area as required to perform the work, protect the furniture, and replace the furniture in its original location upon completion of the work. Leave attached equipment in place, and protect it them against damage, or temporarily disconnect, relocate, protect, and reinstall it at the completion of the work.

The Government will remove and relocate other Government property in the areas of the building scheduled to receive work.

1.2.5 Utility Cutovers and Interruptions

a. Permission to interrupt any Activity utility service shall be requested in writing a minimum of 15 calendar days prior to desired date of interruption.

b. Make utility cutovers and interruptions after normal working hours or on Saturdays, Sundays, and Government holidays. Conform to procedures required in the paragraph "Work Outside Regular Hours."

c. Ensure that new utility lines are complete, except for the connection, before interrupting existing service.

d. Interruption to water, sanitary sewer, storm sewer, telephone service, electric service, air conditioning, heating, fire alarm, compressed air shall be considered utility cutovers pursuant to the paragraph entitled "Work Outside Regular Hours."

e. Operation of Station Utilities: The Contractor shall not operate nor disturb the setting of control devices in the station utilities system, including water, sewer, electrical, and steam services. The Government will operate the control devices as required for normal conduct of the work. The Contractor shall notify the Contracting Officer giving reasonable advance notice when such operation is required.

1.3 SECURITY REQUIREMENTS

1.3.1 Station Regulations

No employee or representative of the contractor will be admitted to the work site without an Identification Badge or is specifically authorized admittance to the work site by the ROICC, NAVFAC Contracts.

1.3.2 Contractor Access to MCAS Cherry Point and Outlying Areas

Documentation requirements for granting access to MCAS Cherry Point for commercial and contract employers and employees. This document is an aid in meeting ASO 5500.14_ requirements and is not a substitute for the order.

1. Prime Contractor will provide a list of employees (prime and/or sub-contractor) that require Station access on company letterhead and include the contract number and a copy of the "base access table" outlined in your contract. NOTE: This list should include employee names ONLY. Do NOT include other personally identifiable information (PII) such as Social Security Number, Date of Birth, etc... Contractors who are hired for a period more than 30 days will be issued a contractor's badge after the conditions outlined in this document are met. The badge must be carried in plain view or readily accessible at all times while on Station. All badges will be issued for a period NOT TO EXCEED ONE YEAR regardless of the length of the contract. Upon the expiration of the badge, the company/employee will provide a new 50 state/national criminal records check and LRC prior to being re-badged. Any access from 1 day to less than 30 days, employers will provide the same documentation as stated above. In place of a badge a copy of this letter with the worker's name highlighted, stamped with the "Pass & ID" stamp, "Criminal Records Check (CRC) Sighted", and we will also annotate below the stamps the following statement: "Valid until (expiration date) then date and initial it." This document will be issued to each worker and IS their authorization to be aboard the installation. This letter must be carried on their person or readily accessible at all times while on Station.

2. Contractor personnel requesting access to MCAS Cherry Point must complete and sign the attached Local Records Check (LRC) Form.

3. Contractor personnel requesting access to MCAS Cherry Point can personally deliver the (original) LRC/ARI and the national background check to MCAS Pass & ID 2 full work days prior to requiring a badge or you may send the completed LRC (original) form to include the national background check in via FEDEX, UPS or EXPRESS Mail to arrive up to 5 days prior to your arrival. Address: Provost Marshal, Attn: Pass & ID Office, Marine Corps Air Station, Cherry Point, NC 28533-0035 or by US Mail, Provost Marshal's Office, Postal Service Center Box 8035, Marine Corps Air Station, Cherry Point, North Carolina 28533-0035. Transit time is 7 to 10 days regular mail. SSN and photo ID will be verified at this time. NOTE: Due to the sensitivity of the personal information contained in the LRC Release, these documents CAN NOT be faxed or e-mailed to MCAS Pass & ID. Per Air Station Order 5500.14.
In order to get a badge, you must be present, as it is photo badge.
If the vetting process works correctly, we should have your approved paperwork on hand pending your arrival.

4. MCAS Pass & ID will complete the local records check prior to contractor arriving for badging. If negative results are found, the sponsoring

company (prime contractor) will be notified. NOTE: LRCs are only valid for 15 days, therefore the contractor must receive their badge within 15 days or they will have to resubmit the paperwork.

5. Individual Contractor Personnel report to Pass & ID for badging according to the following schedule:

LRC & Background Check Submitted:	Earliest Badging Opportunity:
Monday	Thursday
Tuesday	Friday
Wednesday	Monday (the following week)
Thursday	Tuesday (the following week)
Friday	Wednesday (the following week)

6. Individual Contractor Personnel MUST bring the following documents when reporting to Pass & ID for badging:

-Copy of LRC release previously submitted above.
-Picture ID (typically a driver's license)
-Social Security Card or official document listing SSN
-Birth Certificate or Passport to verify citizenship
-If NOT US citizen, provide proof of immigration status
-Copy of 50-State Background Check (must be less than 30-days old)

IMPORTANT NOTE: ROICC personnel (Construction Managers, Engineering Techs, or Contract Specialists) and FSC personnel (Contract Surveillance Reps) will not receive, process, re-transmit or otherwise handle in any way PII information related to the badging process. Do NOT forward any of this information to ROICC or FSC.

7. All employers/employees must provide a CRC from any internet investigative service or any other investigative service company that provides a 50 state/national criminal records check and a check of the Sexual Offenders List. (Local county/state checks are not authorized and will not be accepted.) This records check must be a "complete" check covering the period from at the minimum their 18th birthday to present. The CRC must also have a statement in the records check that this is a "national records check" or the terminology the agency uses to indicate such. Please be sure of what you are requesting. If it is anything less then a national check, it will be rejected. The CRC can not be more than 30 days old at the time it is presented to Pass & ID personnel. CRCs may be obtained from, but not limited to the following sources (*):

A) WWW.SENTRYLINK.COM
B) WWW.INTEGRASCAN.COM
C) WWW.CRIMINALWATCHDOG.COM
D) WWW.CASTLEBRANCH.COM
E) WWW.KROLLBACKGROUNDSCREENING.COM
F) WWW.BACKGROUNDCHECKS.COM
G) WWW.LEXISNEXIS.COM

IMPORTANT NOTE: Cost of a background check can vary anywhere from $19 to $60 based on the type or amount of services requested. Minimum information required for a background check is the individual's last name,

first name, middle name (optional) and date of birth, which must match exactly with your name and DOB on your driver's license or state ID. A social security number verification is also available at an additional cost.

8. In accordance with ASO 5500.14_ (not an all inclusive list), access will be denied if the individual:

A. Conviction of any felony offense.
B. Conviction of any offense involving a weapon.
C. Conviction of any drug offense involving manufacturing or trafficking.
D. More than 1 misdemeanor conviction of drug related offense over applicant's lifetime or 1 misdemeanor drug related offense within the last 5 years.
E. Conviction of any felony assault charge.
F. Conviction of any offense involving theft or larceny in excess of $500.00.
G. Conviction of any offense of felony domestic violence.
H. Conviction of any offense related to the felony abuse/neglect of a child.
I. Conviction of any sexual in nature related offense or registration as a sex offender.
J. Commission of any grievous criminal offense/misconduct while aboard any federal installation to include blatant disregard for rules and regulations of the Air Station (excluding minor traffic offences) .
K. Other Than Honorable, Bad Conduct, and Dishonorable discharges from the U.S. Military.
L. Those identified as undocumented citizens.
M. Those on the National Terrorist Watch List.
N. Any individual who attempts to hide or purposely fails to disclose all past criminal history during the vetting process.
O. Any individual determined by the PMO to present a risk to the security and safety of the Air Station and whose access is deemed not in the best interest of the Marine Corps.
P. Any individual who has been debarred from MCAS Cherry Point by the CO or is currently listed as debarred from any other federal installation.
Q. Any individual with an outstanding warrant for their arrest or apprehension.

9. Picture ID from a state or federal agency (i.e., valid driver's license or state identification card).

10. Social Security Card or any official document listing the SSN (letter from Social Security Administration listing the SSN, W-2 (tax form), DD-214, pay stub listing complete SSN). An additional source may be through the internet with E-Verify.

11. Birth certificates and passports are used when necessary to verify citizenship and are never used as a means to verify social security numbers.

12. If the employee is not a U.S. Citizen, PROOF OF IMMIGRATION STATUS must be provided and carried on their person or be readily accessible at all times while on station. Proof must also be provided if an individual is a naturalized U.S. citizen.

13. Due to recent changes with Privacy laws, please do not include social security numbers in the company letters being sent to this office. Additionally, all criminal record checks must be hand carried by the individual worker or brought in by the supervisor.

14. As of 19 Dec 07 security clearances are no longer valid as a means for

requesting access to the installation. All personnel hired as commercial or contractor employees to work for a company aboard the installation will be required to provide a 50 state/national criminal check.

15. The changes in this document are effective as of 10 Jun 2014.

IMPORTANT NOTE: Until further notice, ID cards and vehicle passes issued to contractors at Camp Lejeune and New River are not valid at Cherry Point without a 50 state/national CRC in their possession at the time they are requesting access at MCAS Cherry Point.

(*) The United States Government and the United States Marine Corps does not endorse nor are they affiliated with any of the screening services mentioned above. We must be able to verify/validate the information contained in the CRC via telephone. If we are unable to validate the CRC the clearance information will not be accepted.

(**) Due to recent developments concerning the screening services of Criminal CBS (also DBA US Criminal Checks, INC), Net Detective, and ABI (Accurate Background Investigations), they are no longer authorized as a means for entry at MCAS Cherry Point.

Questions on these revised procedures should be addressed directly with Pass & ID personnel at CHPT_PASS-ID_OMB@USMC.MIL or 252-466-4683/5921.

1.4 FLEET READINESS CENTER, EAST (FRC EAST) REQUIREMENTS

FRC East is registered to the ISO 9001, ANSI 9100, ISO 14001, and OSHAS 18001 standards. In addition to these, registration under the Occupational Safety and Health Administration's Voluntary Protection Program is in progress. To adhere to the standards required of these programs, FRC East must ensure that all individuals accessing the facility are aware of the conditions and factors that affect the well-being of all employees, temporary workers, contractor personnel, visitors, and any other person in the workplace.

The following are requirements for granting access to Fleet Readiness Center East (FRC East) for commercial and contract employers and employees.

1.4.1 Requirements for All Personnel at FRC East

a. In the event of an emergency, including hazardous material spills, the individual discovering the emergency shall call 911 from any FRC East phone. Relay the grid number listed on the phone for location assistance. If you are calling from a cell phone, call 252-466-3616 - Fire Department Dispatch.

b. Badges will be displayed at all times and shall be returned upon completion of visit/work. Every badge is considered Government Property and all lost badges will be reported to the FRC East Badge and Decal Office located in Trailer 32.

c. Report any injury/illness occurring on site to the FRC East Safety Office (252-464-7015) immediately via e-mail or phone.

d. The facility must be kept clean and orderly at all times. Ensure that you place all waste in proper receptacles so that the facility is maintained in a "Clean as you go" condition.

e. When in the FRC East industrial areas, wear the personal protective equipment (PPE) required for that area. PPE requirements are generally marked but if there is uncertainty, check with the area supervisor. Typically, safety glasses with side shields and steel toed shoes are required in most shops.

f. Smoking is NOT authorized while traveling from one facility location to another while walking or in a vehicle being operated anywhere within the FRC East compound. ABSOLUTELY NO SMOKING on the property except in Designated Smoking Areas.

g. Extra caution shall be taken around the flight line and aircraft turn-up areas to control trash, debris, and materials. Additionally, all personnel on the flight line must be continuously alert and stay clear of helicopter and jet operations in progress.

h. Vehicles must not obstruct aircraft movement or other daily operations.

i. Safety, security, and environmental infractions shall be reported to the appropriate office immediately via the following telephone numbers: Safety 252-464-7015, Security 252-464-7999, Environmental 252-464-8412.

j. If an emergency situation occurs which would endanger the health or safety of personnel, the area shall be evacuated. Re-entry to affected buildings will be at the discretion of uniformed guards, fire department, or safety office personnel only.

k. Decisions to evacuate will be from the FRC East Commanding Officer or his/her representative. Visitors/contractors, along with non-essential facility personnel, south of Harrison Drive, adjacent to Building 4224, will evacuate the facility first. Fifteen minutes later, the visitors/contractors south of Curtis Road, between Buildings 83 & 84, will evacuate the facility. Fifteen minutes later the visitors/contractors north of Curtis Road will evacuate the facility.

l. Cellular phones and photographic equipment are not authorized within FRC East unless they are approved in advance by the Security Office (252-464-7999). Cellular phones may be used on roof areas for emergency purposes only.

m. All vehicles must have proper passes, and no pass may be transferred between vehicles.

n. All vehicles will follow posted speed limits, which are: "Do not exceed 5 MPH on the outside of buildings, nor 3 MPH inside of any building".

o. Vehicle headlights must be on at all times within the facility.

p. All vehicles are required to slow down, sound horn, and proceed with caution at all cross aisles and other locations where vision is obstructed.

q. Personnel are strictly forbidden to introduce any substance into the storm drain system including catch basins, roof drains, and

floor drains.

r. All facility entrants are responsible for all materials they bring into the facility and shall handle them in such a manner to ensure they are not left as "foreign objects" anywhere in the facility.

s. In case of a utility emergency on weekends or after normal work hours, call the Facilities Maintenance trouble call desk at 252-466-4363.

t. The use of gasoline is prohibited for any purpose other than fueling motor vehicles. All gasoline-powered vehicles are prohibited inside FRC East buildings.

1.4.2 Mandatory Contract Performance Requirements for FRC East

a. All personnel working on site at FRC East under this contract must document their receipt and review of the information listed in FRCEASTINST 5000.1A, enclosure (1), annually. The Security Department will provide a means of completing initial review prior to FRC East entrance.

b. All contractors performing work on behalf of FRC East and who have 10 employees at any time during the past calendar year, and whose employees worked 1000 or more hours in any quarter, shall furnish the Contracting Officer their Total Case Incidence Rate for recordable nonfatal injuries and illnesses and their Days Away from Restricted work activity, and/or Job Transfer Rate for the past three years.

c. Foreign object (FO) is defined as any article or substance alien to the aircraft or assembly which is allowed to invade the product. Foreign Object Damage (FOD) is the damage that occurs due to these FOs. All FRC East work sites will be maintained in such a manner as to prevent FOD to aircraft and/or aircraft components. Work sites shall be kept clean at all times. All debris, scrap material, tools, and equipment will be cleared from the work site as work progresses. At no time will hoses, power cords, materials, etc. be permitted to create tripping hazards in areas of the work site.

d. In those cases where a contractor supervisor determines that solving a safety or health problem is beyond their control, but within the control of FRC East, the contractor shall notify the Contracting Officer.

e. All contractor employees performing work on site at FRC East shall immediately report any safety, security, or environmental violation to the Contracting Officer, who will notify the cognizant FRC East Safety/Security/Environmental Office. The initial FRC East notification can be made via phone or e-mail and should include as many applicable details as possible (date, time, identification numbers, tags, company, etc.). This initial notification will be made as soon as possible. A safety incident will require the contractor to complete and submit an incident memo to the Contracting Officer, who will forward a copy to the FRC Safety Office within 24 hours of the accident/incident. This incident memo will include the full name of the person involved in the incident, their age, sex, job title, the name of the employing

company, and the contract number/title. In addition, this memo will include the severity of the illness or injury, indirect cause(s) of the accident, and whether personal protective equipment was available and used.

f. Contractor supervisors shall attend FRC East Environmental Management System Annual Refresher and convey the information to their personnel annually.

g. All contractors and sub-contractors working within FRC East must develop and operate effective safety and health programs.

1.4.3 Additional Contract Performance Requirements for FRC East

a. Work above or anywhere near aircraft or passageways shall be avoided whenever possible. If this is not possible, the cognizant shop supervisor will be informed so arrangements can be made to protect, move, or evacuate assets from the area to minimize foreign object debris potential. The area below the elevated work area will be adequately marked and barricaded at all times. Under no circumstances will work be performed over unprotected spaces.

b. Constant control of tools and materials is required at all times in the following critical areas: Shop 91107 (Rotor Head Shop); Shop 91110 (Ordinance/Survival Shop); Shop 91109 (Aircraft Paint Shop and Aircraft Clean Shop); Shop 91104 (Aircraft Engine Shops); all shops in Building 4225 (Blade Vane); and all 6.2.1 aircraft hangars.

c. Tools and hardware will be controlled at all times to prevent migration out of the work site. Lost tools shall be reported to the Contracting Officer who will then notify the FRC East Tool Control Manager at 252-464-9741. Tools found unattended will be confiscated and reported to the Contracting Officer.

d. Personnel working on the flight line must be continuously alert, and stay clear of helicopter and jet operations in progress.

e. Work requiring any modification to an air pollution control device must be approved in advance by the Contracting Officer, who will obtain approval from the FRC East Air Quality Program Manager. These devices are marked with a 5" x 9" red placard and a contact number, 252-464-7690.

f. Work accomplished that will impact industrial ventilation systems or fans will require prior notification of the Contracting Officer, who will then notify the FRC East Air Quality Program Manager at 252-464-7690 or 252-464-8412. These systems are continuously monitored.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

MCASCHPT/PMO/5500/8

PREVIOUS EDITIONS ARE OBSOLETE

AS0 5560.6
10 Jun 14

UNITED STATES MARINE CORPS

SECURITY & EMERGENCY SERVICES DIRECTORATE
POSTAL SERVICE CENTER BOX 8035
MARINE CORPS AIR STATION
CHERRY POINT, NORTH CAROLINA 28533-0035

IN REPLY REFER TO:
5512
PMO

From: Pass & Identification Office
To: PMO Records Manager

Via: (1) PMO Admin
(2) Criminal Investigation Division Office

Subj: REQUEST FOR LOCAL RECORDS CHECK FOR THE BELOW NAMED INDIVIDUAL

Encl: (1) Background Investigation Questionnaire
(2) Authorization to Release of Information

1. The following information is provided for pending access aboard MCAS, Cherry Point, NC

FULL NAME: _____

FULL SSN: _____

COMPANY/ SPONSOR'S NAME: _____

DATE OF BIRTH: _____

CURRENT ADDRESS: _____

CONTACT PHONE NUMBER: _____

SIGNATURE: _____

PMO / CID USE ONLY **TLO VERIFIED(DATE/TIME/INITIALS)**_____

INDIVIDUAL CONTACTED (DATE/TIME/INITIALS : _____

☐ APPROVED ☐ DENIED

_____
APPROVAL OFFICIAL SIGNATURE

(SORN NM05512-2 Badge and Access Control System Records)
AUTHORITY: 10 U.S.C. 5013, Secretary of the Navy; 10 U.S.C. 5041, Headquarters, Marine Corps; OPNAVINST 5530.14C, Navy Physical Security; Marine Corps Order P5530.14, Marine Corps Physical Security Program Manual; and E.O. 9397 (SSN), as amended.PURPORSE: To control physical access to DoD, Department of the Navy (DoN) or U.S. Marine Corps Installations/Units by identifying or verifying individuals for the purpose of protecting U.S./Coalition/allied government/national security areas of responsibility. ROUTINE USE: The DoD 'Blanket Routine Uses' that appear at the beginning of the Navy's compilation of systems of records notices apply to this system. DISCLOSURE: Disclosure is voluntary; however, failure to provide the requested information may result in the denial of physical access to DoD, DoN, or USMC installations/units.

Enclosure (1)

Authorization for Release of Information

Carefully read this authorization to release information about you, then sign and date it in ink.

I Authorize any investigator, special agent, or other duly accredited representative of the OPM, the Federal Bureau of Investigation, the Department of Defense, the Department of State, and any other authorized Federal agency, to request criminal record information about me from criminal justice agencies for the purpose of determining my eligibility for requesting access to the facilities aboard Marine Corps Air Station Cherry Point N.C.

I Authorize custodians of records and other sources of information pertaining to me to release such information upon request of the investigator, special agent, or other duly accredited representative of any Federal agency authorized above regardless of any previous agreement to the contrary.

I Understand that, for some sources of information, a separate specific release will be needed, and I may be contacted for such a release at a later date.

I Understand that the information released by records custodians and sources of information is for official use by the Federal Government only for the purposes provided above, and it may be disclosed by the Government only as authorized by law.

Photocopies of this authorization that show my signature are NOT VALID.

Signature (sign in ink)	Full Name (First, Middle, Last)	Date Signed(mm/dd/yyyy)
Other Names used	**Date of Birth**	**Social Security Number**
Current Street Address	**City, State, Zip Code**	**Contact Telephone Number**

PRIVACY ACT STATEMENT

(SORN NM05512-2 Badge and Access Control System Records)

AUTHORITY: 10 U.S.C. 5013, Secretary of the Navy; 10 U.S.C. 5041, Headquarters, Marine Corps; OPNAVINST 5530.14C, Navy Physical Security; Marine Corps Order P5530.14, Marine Corps Physical Security Program Manual; and E.O. 9397 (SSN), as amended.

PURPORSE: To control physical access to DoD, Department of the Navy (DoN) or U.S. Marine Corps Installations/Units by identifying or verifying individuals for the purpose of protecting U.S./Coalition/allied government/national security areas of responsibility.

ROUTINE USE: The DoD 'Blanket Routine Uses' that appear at the beginning of the Navy's compilation of systems of records notices apply to this system.

DISCLOSURE: Disclosure is voluntary; however, failure to provide the requested information may result in the denial of physical access to DoD, DoN, or USMC installations/units.

Enclosure (1)

BACKGROUND INVESTIGATION QUESTIONNAIRE

PRIVACY ACT STATEMENT

AUTHORITY: 10 U.S.C. 5013, Secretary of the Navy; 10 U.S.C. 5041, Headquarters, Marine Corps; OPNAVINST 5530.14C, Navy Physical Security; Marine Corps Order P5530.14, Marine Corps Physical Security Program Manual; and E.O. 9397 (SSN). **PURPOSE:** To control physical access to DoD, Department of the Navy (DoN) or U.S. Marine Corps Installations/Units by identifying or verifying individuals for the purpose of protecting U.S./ Coalition/allied government/national security areas of responsibility. **ROUTINE USE:** The DoD 'Blanket rpoutine uses' that appear at the beginning of the navy's compilation of systems of records notices apply to this system. **DISCLOSURE:** Voluntary. However, failure to provide the requested information may result in denial of physical access to DoD, DoN, or USMC installations/units.

PRINT CLEARLY IN BLACK INK

NAME (Last, First, Middle, Jr. or Sr.)	Social Security Number

Current Address (Number, Street),	City	State	Zip Code	County

Date From	Date To

Alias/AKA's If yes, also list the dates used

Home Telephone	Cell Telephone	Email Address

Sex:	Race	Height	Weight	Hair	Eyes	Date of Birth
☐ Male ☐ Female						

Place of Birth: City	State	Country	Driver's License Number	
			State	Number

PREVIOUS ADDRESSES

(List all previous addresses for the past five years, start with the last address and work backward in time.)

Street	City	County	State	Zip Code	Date From	Date To

MILITARY STATUS

Have you ever served in any Armed Forces; Army, Navy, Air Force, Marines, Coast Guard, National Guard, or any reserve unit?
YES ☐ NO ☐ **If YES, provide information below.**

Date From	Date To	Military Branch	Rank	Discharge Type

If you have been discharged from any Military Service with less than an Honorable Discharge, explain below. (For example - general discharge under honorable conditions):

CRIMINAL HISTORY

Excluding minor tickets for traffic and parking violations, have you ever been detained, arrested, cited, convicted, charged or placed in pre-trial diversion, or been a suspect for any offense or violation of any statute, ordinance, law or regulation by any civil or military authority in this country or any other country since reaching the age of 18?

YES ☐ NO ☐

INTENTIONALLY FAILING TO DISCLOSE ALL CRIMINAL HISTORY COULD RESULT IN THE AUTOMATIC DENIAL OF ACCESS TO MCAS CHERRY POINT

Date	Charges	Misdemeanor or Felony	Disposition	City	State

Are you currently on Probation or Parole? YES ☐ NO ☐ If YES, where and for what? List parole/probation start date and end date.

I CERTIFY THAT THE INFORMATION I HAVE PROVIDED IS TRUE TO THE BEST OF MY KNOWLEDGE AND THAT I HAVE NOT WILLFULLY OR INTENTIONALLY WITHHELD ANY INFORMATION. I UNDERSTAND THAT PROVIDING FALSE OR MISLEADING INFORMATION ON MY IDENTITY OR CRMINAL HISTORY CAN RESULT IN THE DENIAL OF ACCESS TO THE AIR STATION AND POSSIBLE CRIMINAL CHARGES UNDER TITLE 18 OF THE U.S. CODE.

FULL NAME

SIGNATURE AND DATE

SECTION 01 20 00.00 20

PRICE AND PAYMENT PROCEDURES
11/11

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. ARMY CORPS OF ENGINEERS (USACE)

EP-1110-1-8	(2009) Construction Equipment Ownership and Operating Expense Schedule

1.2 SUBMITTALS

The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Schedule of prices

1.3 SCHEDULE OF PRICES

1.3.1 Data Required

Within 15 calendar days of notice of award, prepare and deliver to the Contracting Officer a schedule of prices (construction contract). Provide a detailed breakdown of the contract price, giving quantities for each of the various kinds of work, unit prices, and extended prices therefore.

1.3.2 Schedule Instructions

Payments will not be made until the Schedule of Prices has been submitted to and accepted by the Contracting Officer. Identify the cost for site work, and include incidental work to the 5 foot line. Identify costs for the building(s), and include work out to the 5 foot line. Work out to the 5 foot line shall include construction encompassed within a theoretical line 5 feet from the face of exterior walls and shall include attendant construction, such as cooling towers, placed beyond the 5 foot line.

1.3.3 Schedule Requirements for HVAC TAB

The field work Section 23 05 93, "HVAC Testing/Adjusting/Balancing" shall be broken down in the Schedule of Prices and in the Construction Progress Documentation by separate line items which reflect measurable deliverables. Specific payment percentages for each line item shall be determined on a case by case basis for each contract. The line items shall be as follows:

a. Approval of Design Review Report: The TABS Agency is required to conduct a review of the project plans and specifications to identify any feature, or the lack thereof, that would preclude

successful testing and balancing of the project HVAC systems. The resulting findings shall be submitted to the Government to allow correction of the design. The progress payment shall be issued after review and approval of the report.

b. Approval of the pre-field engineering report: The TABS Agency submits a report which outlines the scope of field work. The report shall contain details of what systems will be tested, procedures to be used, sample report forms for reporting test results and a quality control checklist of work items that must be completed before TABS field work commences.

c. Season I field work: Incremental payments are issued as the TABS field work progresses. The TABS Agency mobilizes to the project site and executes the field work as outlined in the pre-field engineering report. The HVAC water and air systems are balanced and operational data shall be collected for one seasonal condition (either summer or winter depending on project timing).

d. Approval of Season I report: On completion of the Season I field work, the data is compiled into a report and submitted to the Government. The report is reviewed, and approved, after ensuring compliance with the pre-field engineering report scope of work.

e. Completion of Season I field QA check: Contract QC and Government representatives meet the TABS Agency at the jobsite to retest portions of the systems reported in the Season I report. The purpose of these tests are to validate the accuracy and completeness of the previously submitted Season I report.

f. Approval of Season II report: The TABS Agency completes all Season II field work, which is normally comprised mainly of taking heat transfer temperature readings, in the season opposite of that under which Season I performance data was compiled. This data shall be compiled into a report and submitted to the Government. On completion of submittal review to ensure compliance with the pre-field engineering report scope, progress payment is issued. Progress payment is less than that issued for the Season I report since most of the water and air balancing work effort is completed under Season I.

1.4 CONTRACT MODIFICATIONS

In conjunction with the Contract Clause "DFARS 252.236-7000, Modification Proposals-Price Breakdown," and where actual ownership and operating costs of construction equipment cannot be determined from Contractor accounting records, equipment use rates shall be based upon the applicable provisions of the EP-1110-1-8.

1.5 CONTRACTOR'S INVOICE

1.5.1 Content of Invoice

Requests for payment in accordance with the terms of the contract shall consist of the following:

a. Contractor's Invoice on NAVFAC Form 7300/30, which shall show, in summary form, the basis for arriving at the amount of the invoice.

b. Contractor's Monthly Estimate for Voucher (LANTNAVFACENGCOM Form 4-4330/110 (New 7/84)), with subcontractor and supplier payment certification.

c. Affidavit to accompany invoice (LANTDIV NORVA Form 4-4235/4 (Rev. 5/81)).

d. Updated copy of submittal register.

e. Updated copy of progress schedule. Furnish as specified in "FAR 52.236-15, Schedules for Construction Contracts."

1.5.2 Monthly Invoices and Supporting Forms

Forms will be furnished by the Contracting Officer. Requests for payment shall be processed in accordance with "FAR 52.232-5, Payments Under Fixed-Price Construction Contracts." Monthly invoices and supporting forms for work performed through the anniversary award date of the contract shall be submitted to the Contracting Officer between the 1st - 7th if contract's last digit is 0, 1, 2; 8th - 14th if contract's last digit is 3 or 4; 15th - 21st if contract's last digit is 5, 6, or 7; 22nd and last if the contract's last digit is 8th or 9th day of the month. Payments will be using Wide Area Workflow (WAWF). Submit the following documents with invoice WAWF:

a. Contractor's invoice

b. Contractor's monthly estimate for voucher

c. Affidavit

d. Updated submittal register

e. Progress schedule

f. Certificate of Progress Payments

g. Contractor Safety Self Evaluation Checklist

1.6 PAYMENTS TO THE CONTRACTOR

Payments will be made on submission of itemized requests by the Contractor which comply with the requirements of this section, and will be subject to reduction for overpayments or increase for underpayments made on previous payments to the Contractor.

1.6.1 Obligation of Government Payments

The obligation of the Government to make payments required under the provisions of this contract will, at the discretion of the Contracting Officer, be subject to reductions and/or suspensions permitted under the FAR and agency regulations including the following in accordance with "FAR 32.503-6:

a. Reasonable deductions due to defects in material or workmanship;

b. Claims which the Government may have against the Contractor under or in connection with this contract;

c. Unless otherwise adjusted, repayment to the Government upon demand for overpayments made to the Contractor; and

d. Failure to provide up to date record drawings not current as stated in Contract Clause "FAC 5252.236-9310, Record Drawings."

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SECTION 01 30 00

ADMINISTRATIVE REQUIREMENTS
05/11

PART 1 GENERAL

1.1 SUBMITTALS

The following shall be submitted per Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

List of contact personnel

1.2 MINIMUM INSURANCE REQUIREMENTS

Procure and maintain during the entire period of performance under this contract the following minimum insurance coverage:

a. Comprehensive general liability: $500,000 per occurrence

b. Automobile liability: $200,000 per person, $500,000 per occurrence for bodily injury, $20,000 per occurrence for property damage

c. Workmen's compensation as required by Federal and State workers' compensation and occupational disease laws.

d. Employer's liability coverage of $100,000, except in States where workers compensation may not be written by private carriers,

e. Others as required by North Carolina State law.

f. The Cancellation clause on the insurance certificate should read:

"Cancellation or any material change in the policies adversely affecting the interest of the Government in such insurance shall not be effective for such period as may be prescribed by the laws of the State in which this contract is to be performed and in no event less than **thirty (30)** days after written notice thereof to the Contracting Officer."

1.3 CONTRACTOR PERSONNEL REQUIREMENTS

1.3.1 Subcontractors and Personnel

Furnish a list of contact personnel of the Contractor and subcontractors including addresses and telephone numbers for use in the event of an emergency. As changes occur and additional information becomes available, correct and change the information contained in previous lists.

1.3.2 Identification Badges

Identification badges will be furnished without charge. Application for and use of badges will be as directed. Immediately report instances of lost or stolen badges to the Contracting Officer.

Commercial and contract employees will be issued a contractor's badge good for one year. Commercial and contract employees are required to resubmit a complete 50 state criminal records check in order to renew their contractor's badge.

If an employee is terminated prior to end of the contract, the contractor shall return the base identification card to the Contracting Officer. This requirement also applies to all sub-contract employees.

In no event will a contractor employee be permitted access to the US Marine Corps Air Station for the purpose of on-site performance without the documentation.

1.3.3 Subcontractor Special Requirements

1.3.3.1 Asbestos Containing Material

All contract requirements assigned to the Private Qualified Person (PQP) shall be accomplished directly by a first tier subcontractor.

1.3.4 Contractor Personnel Requirements

Follow Security requirements addressed in 01 14 00 WORK RESTRICTIONS.

1.4 SUPERVISION

Have at least one qualified supervisor capable of reading, writing, and conversing fluently in the English language on the job site during working hours. In addition, if a Quality Control (QC) representative is required on the contract, then that individual shall also have fluent English communication skills.

1.5 PRECONSTRUCTION CONFERENCE

After award of the contract but prior to commencement of any work at the site, meet with the Contracting Officer to discuss and develop a mutual understanding relative to the administration of the value engineering and safety program, preparation of the schedule prices, shop drawings, and other submittals, scheduling programming, and prosecution of the work. Major subcontractors who will engage in the work shall also attend.

1.6 LEVEL "C" PARTNERING

To most effectively accomplish the contract, the Government requires the formation of a cohesive partnership with the contractor and its subcontractors. The partnering relationship is based upon trust, dedication to common goals, an understanding of each other's expectations and values, and a commitment to success. The goals of the partnering process are improved communication, efficiency and cost effectiveness, increased opportunity for innovation, and the continuous improvement of product quality. The partnership will strive to draw in the strength of each organization in an effort to achieve a quality project done right the first time, within budget, on schedule, and without any safety mishaps, thereby providing the opportunity for the contractor to make a reasonable profit. This level of partnering is an introduction to partnering concepts and benefits and should become a part of the preconstruction conference. The senior ROICC and contract persons present will jointly host the initial session. The partners will determine the frequency of the follow-on sessions. Partnering sessions should be held at or near the location of

the ROICC office.

1.7 ELECTRONIC MAIL (E-MAIL) ADDRESS

The Contractor shall establish and maintain electronic mail (e-mail) capability along with the capability to open various electronic attachments in Microsoft, Adobe Acrobat, and other similar formats. Within 10 days after contractor award, the Contractor shall provide the Contracting Officer a single (only one) e-mail address for electronic communications from the Contracting Officer related to this contract including, but not limited to contract documents, invoice information, request for proposals, and other correspondence. The Contracting Officer may also use e-mail to notify the Contractor of base access conditions when emergency conditions warrant, such as hurricanes, terrorist threats, etc. Multiple e-mail addresses will not be allowed.

It is the Contractor's responsibility to make timely distribution of all Contracting Officer initiated e-mail with its own organization including the field office(s). The Contractor shall promptly notify the Contracting Officer, in writing, of any changes to this e-mail address.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SECTION 01 33 00

SUBMITTAL PROCEDURES
05/11

PART 1 GENERAL

1.1 DEFINITIONS

1.1.1 Submittal

Contract Clauses "FAR 52.236-5, Material and Workmanship," paragraph (b) and "FAR 52.236-21, Specifications and Drawings for Construction," paragraphs (d), (e), and (f) apply to all "submittals."

1.1.2 Submittal Descriptions (SD)

Submittals requirements are specified in the technical sections. Submittals are identified by SD numbers and titles as follows.

SD-01 Preconstruction Submittals

Certificates of insurance.
Surety bonds.
List of proposed subcontractors.
List of proposed products.
Construction Progress Schedule.
Submittal register.
Schedule of prices.
Health and safety plan.
Work plan.
Quality control plan.
Environmental protection plan.

SD-02 Shop Drawings

Drawings, diagrams and schedules specifically prepared to illustrate some portion of the work.

Diagrams and instructions from a manufacturer or fabricator for use in producing the product and as aids to the Contractor for integrating the product or system into the project.

Drawings prepared by or for the Contractor to show how multiple systems and interdisciplinary work will be coordinated.

SD-03 Product Data

Catalog cuts, illustrations, schedules, diagrams, performance charts, instructions and brochures illustrating size, physical appearance and other characteristics of materials, systems or equipment for some portion of the work.

Samples of warranty language when the contract requires extended product warranties.

SD-04 Samples

Fabricated or unfabricated physical examples of materials, equipment or workmanship that illustrate functional and aesthetic characteristics of a material or product and establish standards by which the work can be judged.

Color samples from the manufacturer's standard line (or custom color samples if specified) to be used in selecting or approving colors for the project.

Field samples and mock-ups constructed on the project site establish standards by which the ensuring work can be judged. Includes assemblies or portions of assemblies which are to be incorporated into the project and those which will be removed at conclusion of the work.

SD-05 Design Data

Design calculations, mix designs, analyses or other data pertaining to a part of work.

SD-06 Test Reports

Report signed by authorized official of testing laboratory that a material, product or system identical to the material, product or system to be provided has been tested in accord with specified requirements. (Testing must have been within three years of date of contract award for the project.)

Report which includes findings of a test required to be performed by the Contractor on an actual portion of the work or prototype prepared for the project before shipment to job site.

Report which includes finding of a test made at the job site or on sample taken from the job site, on portion of work during or after installation.

Investigation reports.

Daily logs and checklists.

Final acceptance test and operational test procedure.

SD-07 Certificates

Statements printed on the manufacturer's letterhead and signed by responsible officials of manufacturer of product, system or material attesting that product, system or material meets specification requirements. Must be dated after award of project contract and clearly name the project.

Document required of Contractor, or of a manufacturer, supplier, installer or subcontractor through Contractor, the purpose of which is to further quality of orderly progression of a portion of the work by documenting procedures, acceptability of methods or personnel qualifications.

Confined space entry permits.

Text of posted operating instructions.

SD-08 Manufacturer's Instructions

Preprinted material describing installation of a product, system or material, including special notices and Material Safety Data sheets concerning impedances, hazards and safety precautions.

SD-09 Manufacturer's Field Reports

Documentation of the testing and verification actions taken by manufacturer's representative at the job site, in the vicinity of the job site, or on a sample taken from the job site, on a portion of the work, during or after installation, to confirm compliance with manufacturer's standards or instructions. The documentation must be signed by an authorized official of a testing laboratory or agency and must state the test results; and indicate whether the material, product, or system has passed or failed the test.

Factory test reports.

SD-10 Operation and Maintenance Data

Data that is furnished by the manufacturer, or the system provider, to the equipment operating and maintenance personnel. This data is needed by operating and maintenance personnel for the safe and efficient operation, maintenance and repair of the item.

This Data is intended to be incorporated in an operations and maintenance manual or control system.

SD-11 Closeout Submittals

A collection of documents representing materials and systems installed or provided to the Government during the course of completing all contract requirements. Closeout submittals must include all approved material submittals and other requirements that describe the finished product provided to the Government. Operational and maintenance manuals, if required, are included in these submittals. As-built drawings must actually describe any deviations that were approved by the Contracting Officer. Refer to the specific closeout procedures required by specification Section 01 78 00, "Closeout Submittals".

1.1.3 Approving Authority

Office or designated person authorized to approve submittal.

1.1.4 Work

As used in this section, on- and off-site construction required by contract documents, including labor necessary to produce submittals, construction, materials, products, equipment, and systems incorporated or to be incorporated in such construction.

1.2 SUBMITTALS

1.2.1 Submittal information applying to the entire contract

The Contractor is cautioned that symbols used in the "SUBMITTALS" paragraph of each Section may not always be consistent from one Section to another.

For example, in one Section a "G" symbol may indicate that the submittal should go to the Engineer Of Record; whereas in another Section the single letter "G" may indicate that the submittal should go directly to the Government, with a "GA" or "A" symbol used for submittals intended for the Engineer of Record. In the event of any such inconsistency, the provisions of the particular Section shall govern submittals required by that Section.

1.2.2 Submittal information applying only to this Section (Section 01 33 00, SUBMITTAL PROCEDURES)

The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Submittal register

1.3 USE OF SUBMITTAL REGISTER

Submittal register will be delivered to the Contractor. will have the following fields completed, to the extent that will be required by the Government during subsequent usage.

Column (c): Lists specification section in which submittal is required.

Column (d): Lists each submittal description (SD No. and type, e.g. SD-04 Drawings) required in each specification section.

Column (e): Lists one principal paragraph in specification section where a material or product is specified. This listing is only to facilitate locating submitted requirements. Do not consider entries in column (e) as limiting project requirements.

Column (f): Indicate approving authority for each submittal. A "G" indicates approval by Contracting Officer; a blank indicates approval by QC manager.

Prepare and maintain submittal register, as the work progresses. Do not change data which is output in columns (c), (d), (e), and (f) as delivered by Government; retain data which is output in columns (a), (g), (h), and (i) as approved.

1.3.1 Submittal Register

Submit submittal register with quality control plan and project schedule required by Section 01 45 00.00 20 CONSTRUCTION QUALITY CONTROL. Verify that all submittals required for project are listed and add missing submittals. Complete the following on the register:

Column (a) Activity Number: Activity number from the project schedule.

Column (g) Contractor Submit Date: Scheduled date for approving authority to receive submittals.

Column (h) Contractor Approval Date: Date Contractor needs approval of submittal.

Column (i) Contractor Material: Date that Contractor needs material

delivered to Contractor control.

1.3.2 Contractor Use of Submittal Register

Update the following fields in the Government-furnished submittal register program. .

Column (b) Transmittal Number: Contractor assigned list of consecutive numbers.

Column (j) Action Code (k): Date of action used to record Contractor's review when forwarding submittals to QC.

Column (l) List date of submittal transmission.

Column (q) List date approval received.

1.3.3 Approving Authority Use of Submittal Register

Update the following fields in the Government-furnished submittal register program.

Column (b).

Column (l) List date of submittal receipt.

Column (m) through (p).

Column (q) List date returned to Contractor.

1.3.4 Contractor Action Code and Action Code

Entries used shall be as follows (others may be prescribed by Transmittal Form):

NR - Not Received

AN - Approved as noted

A - Approved

RR - Disapproved, Revise, and Resubmit

1.3.5 Copies Delivered to the Government

Deliver one copy of submittal register updated by Contractor to Government with each invoice request. Deliver in electronic format, unless a paper copy is requested by Contracting Officer.

1.4 PROCEDURES FOR SUBMITTALS

1.4.1 Reviewing, Certifying, Approving Authority

QC organization shall be responsible for reviewing and certifying that submittals are in compliance with contract requirements. At each "Submittal" paragraph in individual specification sections, a notation "G," following a submittal item, indicates Contracting Officer is approving authority for that submittal item. A blank indicates the Architect-Engineer of Record is the approving authority.

1.4.2 Constraints

a. Submittals listed or specified in this contract shall conform to provisions of this section, unless explicitly stated otherwise.

b. Submittals shall be complete for each definable feature of work; components of definable feature interrelated as a system shall be submitted at same time.

c. When acceptability of a submittal is dependent on conditions, items, or materials included in separate subsequent submittals, submittal will be returned without review.

d. Approval of a separate material, product, or component does not imply approval of assembly in which item functions.

1.4.3 Scheduling

a. Coordinate scheduling, sequencing, preparing and processing of submittals with performance of work so that work will not be delayed by submittal processing. Allow for potential requirements to resubmit.

b. Except as specified otherwise, allow review period, beginning with receipt by approving authority, that includes at least 15 working days for submittals for QC Manager approval and 20 working days for submittals for Contracting Officer approval. Period of review for submittals with Contracting Officer approval begins when Government receives submittal from QC organization. Period of review for each resubmittal is the same as for initial submittal.

c. For submittals requiring review by fire protection engineer, allow review period, beginning when Government receives submittal from QC organization, of 30 working days for return of submittal to the Contractor. Period of review for each resubmittal is the same as for initial submittal.

1.4.4 Variations

Variations from contract requirements require Government approval pursuant to contract Clause entitled "FAR 52.236-21, Specifications and Drawings for Construction" and will be considered where advantageous to Government.

1.4.4.1 Considering Variations

Discussion with Contracting Officer prior to submission, will help ensure functional and quality requirements are met and minimize rejections and resubmittals. When contemplating a variation which results in lower cost, consider submission of the variation as a Value Engineering Change Proposal (VECP).

1.4.4.2 Proposing Variations

When proposing variation, deliver written request to the Contracting Officer, with documentation of the nature and features of the variation and why the variation is desirable and beneficial to Government. If lower cost is a benefit, also include an estimate of the cost saving. In addition to documentation required for variation, include the submittals required for

the item. Clearly mark the proposed variation in all documentation.

1.4.4.3 Warranting That Variations Are Compatible

When delivering a variation for approval, Contractor warrants that this contract has been reviewed to establish that the variation, if incorporated, will be compatible with other elements of work.

1.4.4.4 Review Schedule Is Modified

In addition to normal submittal review period, a period of 10working days will be allowed for consideration by the Government of submittals with variations.

1.4.5 Contractor's Responsibilities

a. Determine and verify field measurements, materials, field construction criteria; review each submittal; and check and coordinate each submittal with requirements of the work and contract documents.

b. Transmit submittals to QC organization in accordance with schedule on approved Submittal Register, and to prevent delays in the work, delays to Government, or delays to separate Contractors.

c. Advise Contracting Officer of variation, as required by paragraph entitled "Variations."

d. Correct and resubmit submittal as directed by approving authority. When resubmitting disapproved transmittals or transmittals noted for resubmittal, the Contractor shall provide copy of that previously submitted transmittal including all reviewer comments for use by approving authority. Direct specific attention in writing or on resubmitted submittal, to revisions not requested by approving authority on previous submissions.

e. Furnish additional copies of submittal when requested by Contracting Officer, to a limit of 20 copies per submittal.

f. Complete work which must be accomplished as basis of a submittal in time to allow submittal to occur as scheduled.

g. Ensure no work has begun until submittals for that work have been returned as "approved," or "approved as noted", except to the extent that a portion of work must be accomplished as basis of submittal.

1.4.6 QC Organization Responsibilities

a. Note date on which submittal was received from Contractor on each submittal.

b. Review each submittal; and check and coordinate each submittal with requirements of work and contract documents.

c. Review submittals for conformance with project design concepts and compliance with contract documents.

d. Act on submittals, determining appropriate action based on QC

organization's review of submittal.

(1) When Architect-Engineer of Record is approving authority, forward the submittal to the A&E with the certifying statement or return submittal marked "not reviewed" or "revise and resubmit" as appropriate.

(2) When Contracting Officer is approving authority or when variation has been proposed, forward submittal to Government with certifying statement or return submittal marked "not reviewed" or "revise and resubmit" as appropriate. T

e. Ensure that material is clearly legible.

f. Stamp each sheet of each submittal with QC certifying statement or approving statement, except that data submitted in bound volume or on one sheet printed on two sides may be stamped on the front of the first sheet only.

(1) When approving authority is Contracting Officer, QC organization will certify submittals forwarded to Contracting Officer with the following certifying statement:

"I hereby certify that the (equipment) (material) (article) shown and marked in this submittal is that proposed to be incorporated with contract Number (_____), is in compliance with the contract drawings and specification, can be installed in the allocated spaces, and is submitted for Government approval.

Certified by Submittal Reviewer _____, Date _____
(Signature when applicable)

Certified by QC Manager _____, Date _____"
(Signature)

g. Sign certifying statement or approval statement. The person signing certifying statements shall be QC organization member designated in the approved QC plan. The signatures shall be in original ink. Stamped signatures are not acceptable.

h. Update submittal register as submittal actions occur and maintain the submittal register at project site until final acceptance of all work by Contracting Officer.

i. Retain a copy of approved submittals at project site, including Contractor's copy of approved samples.

1.4.7 Government's Responsibilities

When approving authority is Contracting Officer or Architect-Engineer, , the approving authority will:

a. Note date on which submittal was received from QC manager, on each submittal for which the Contracting Officer is approving authority.

b. Review submittals for approval within scheduling period specified and only for conformance with project design concepts and compliance with contract documents.

c. Identify returned submittals with one of the actions defined in paragraph entitled "Actions Possible" and with markings appropriate for action indicated.

1.4.8 Actions Possible

Submittals will be returned with one of the following notations:

a. Submittals marked "not reviewed" will indicate submittal has been previously reviewed and approved, is not required , does not have evidence of being reviewed and approved by Contractor, or is not complete. A submittal marked "not reviewed" will be returned with an explanation of the reason it is not reviewed. Resubmit submittals returned for lack of review by Contractor or for being incomplete, with appropriate action, coordination, or change.

b. Submittals marked "approved" "approved as submitted" authorize Contractor to proceed with work covered.

c. Submittals marked "approved as noted" or "approval except as noted; resubmission not required" authorize Contractor to proceed with work as noted provided Contractor takes no exception to the notations.

d. Submittals marked "revise and resubmit" or "disapproved" indicate submittal is incomplete or does not comply with design concept or requirements of the contract documents and shall be resubmitted with appropriate changes. No work shall proceed for this item until resubmittal is approved.

1.5 FORMAT OF SUBMITTALS

1.5.1 Transmittal Form

Transmit each submittal, except sample installations and sample panels, to office of approving authority. Transmit submittals with transmittal form prescribed by Contracting Officer and standard for project. The transmittal form shall identify Contractor, indicate date of submittal, and include information prescribed by transmittal form and required in paragraph entitled "Identifying Submittals." Process transmittal forms to record actions regarding sample panels and sample installations.

1.5.2 Identifying Submittals

Identify submittals, except sample panel and sample installation, with the following information permanently adhered to or noted on each separate component of each submittal and noted on transmittal form. Mark each copy of each submittal identically, with the following:

a. Project title and location.

b. Construction contract number.

c. Section number of the specification section by which submittal is required.

d. Submittal description (SD) number of each component of submittal.

e. When a resubmission, add alphabetic suffix on submittal description, for example, SD-10A, to indicate resubmission.

f. Name, address, and telephone number of subcontractor, supplier, manufacturer and any other second tier Contractor associated with submittal.

g. Product identification and location in project.

1.5.3 Format for SD-02 Shop Drawings

a. Shop drawings shall not be less than8 1/2 by 11 inches nor more than30 by 42 inches.

b. Present8 1/2 by 11 inches sized shop drawings as part of the bound volume for submittals required by section. Present larger drawings in sets.

c. Include on each drawing the drawing title, number, date, and revision numbers and dates, in addition to information required in paragraph entitled "Identifying Submittals."

d. Dimension drawings, except diagrams and schematic drawings; prepare drawings demonstrating interface with other trades to scale. Shop drawing dimensions shall be the same unit of measure as indicated on the contract drawings. Identify materials and products for work shown.

e. Drawings shall include the nameplate data, size and capacity. Also include applicable federal, military, industry and technical society publication references.

1.5.4 Format of SD-03 Product Data and SD-08 Manufacturer's Instruction

a. Present product data submittals for each section as a complete, bound volume. Include table of contents, listing page and catalog item numbers for product data.

b. Indicate, by prominent notation, each product which is being submitted; indicate specification section number and paragraph number to which it pertains.

c. Supplement product data with material prepared for project to satisfy submittal requirements for which product data does not exist. Identify this material as developed specifically for project.

d. Product data shall include the manufacturer's name, trade name, place of manufacture, and catalog model or number. Submittals shall also include applicable federal, military, industry and technical society publication references. Should manufacturer's data require supplemental information for clarification, the supplemental information shall be submitted as specified for SD-07 Certificates.

e. Where equipment or materials are specified to conform to industry and technical society reference standards of the organizations such as American National Standards Institute (ANSI), ASTM International (ASTM), National Electrical Manufacturer's

Association (NEMA), Underwriters Laboratories (UL), and Association of Edison Illuminating Companies (AEIC), submit proof of such compliance. The label or listing by the specified organization will be acceptable evidence of compliance. In lieu of the label or listing, submit a certificate from an independent testing organization, competent to perform testing, and approved by the Contracting Officer. The certificate shall state that the item has been tested in accordance with the specified organization's test methods and that the item complies with the specified organization's reference standard.

f. Submit manufacturer's instruction prior to installation.

1.5.5 Format of SD-04 Samples

a. Furnish samples in sizes below, unless otherwise specified or unless the manufacturer has prepackaged samples of approximately same size as specified:

(1) Sample of Equipment or Device: Full size.

(2) Sample of Materials Less Than2 by 3 inches: Built up to8 1/2 by 11 inches.

(3) Sample of Materials Exceeding8 1/2 by 11 inches: Cut down to 8 1/2 by 11 inches and adequate to indicate color, texture, and material variations.

(4) Sample of Linear Devices or Materials: 10 inch length or length to be supplied, if less than10 inches. Examples of linear devices or materials are conduit and handrails.

(5) Sample of Non-Solid Materials: Pint. Examples of non-solid materials are sand and paint.

(6) Color Selection Samples: 2 by 4 inches.

(7) Sample Panel: 4 by 4 feet.

(8) Sample Installation: 100 square feet.

b. Samples Showing Range of Variation: Where variations are unavoidable due to nature of the materials, submit sets of samples of not less than three units showing extremes and middle of range.

c. Reusable Samples: Incorporate returned samples into work only if so specified or indicated. Incorporated samples shall be in undamaged condition at time of use.

d. Recording of Sample Installation: Note and preserve the notation of area constituting sample installation but remove notation at final clean up of project.

e. When color, texture or pattern is specified by naming a particular manufacturer and style, include one sample of that manufacturer and style, for comparison.

1.5.6 Format of SD-05 Design Data and SD-07 Certificates

a. Provide design data and certificates on 8 1/2 by 11 inches paper. Provide a bound volume for submittals containing numerous pages.

1.5.7 Format of SD-06 Test Reports and SD-09 Manufacturer's Field Reports

a. Provide reports on 8 1/2 by 11 inches paper in a complete bound volume.

b. Indicate by prominent notation, each report in the submittal. Indicate specification number and paragraph number to which it pertains.

1.5.8 Format of SD-10 Operation and Maintenance Data (O&M)

a. O&M Data format shall comply with the requirements specified in Section 01 78 23 OPERATION AND MAINTENANCE DATA

1.5.9 Format of SD-01 Preconstruction Submittals and SD-11 Closeout Submittals

a. When submittal includes a document which is to be used in project or become part of project record, other than as a submittal, do not apply Contractor's approval stamp to document, but to a separate sheet accompanying document.

1.6 QUANTITY OF SUBMITTALS

1.6.1 Number of Copies of SD-02 Shop Drawings

a. Submit six copies of submittals of shop drawings requiring review and approval only by QC organization and seven copies of shop drawings requiring review and approval by Contracting Officer.

1.6.2 Number of Copies of SD-03 Product Data and SD-08 Manufacturer's Instructions

Submit in compliance with quantity requirements specified for shop drawings.

1.6.3 Number of Samples SD-04 Samples

a. Submit one sample showing range of variation, of each required item. One approved sample or set of samples will be retained by approving authority and one will be returned to Contractor.

b. Submit one sample panel. Include components listed in technical section or as directed.

c. Submit one sample installation, where directed.

d. Submit one sample of non-solid materials.

1.6.4 Number of Copies SD-05 Design Data and SD-07 Certificates

a. Submit in compliance with quantity requirements specified for shop drawings.

1.6.5 Number of Copies SD-06 Test Reports and SD-09 Manufacturer's Field Reports

b. Submit in compliance with quantity with quality requirements specified for shop drawings.

1.6.6 Number of Copies of SD-10 Operation and Maintenance Data

Submit Five copies of O&M Data to the Contracting Officer for review and approval.

1.6.7 Number of Copies of SD-01 Preconstruction Submittals and SD-11 Closeout Submittals

a. Unless otherwise specified, submit administrative submittals compliance with quantity requirements specified for shop drawings.

1.7 FORWARDING SUBMITTALS

1.7.1 Submittals Required from the Contractor

As soon as practicable after award of contract, and before procurement of fabrication, forward to the Architect-Engineer: NRW ENGINEERING P.C., 748 Lord Dunmore Dr Suite 101, Virginia Beach, Virginia 23464, submittals required in the technical sections of this specification, including shop drawings, product data, and samples. One copy of the transmittal form for all submittals shall be forwarded to the Resident Officer in Charge of Construction, NAVFAC Mid-Atlantic, PSC Box 8006, Building 163, Cherry Point, North Carolina, 28533-0006.

The Architect-Engineer for this project will review and approve for the Contracting Officer those submittals reserved for Contracting Officer approval to verify submittals comply with the contract requirements.

1.7.1.1 O&M Data

The Architect-Engineer for this project will review and approve for the Contracting Officer O&M Data to verify the submittals comply with the contract requirements; submit data specified for a given item within 30 calendar days after the item is delivered to the contract site.

a. In the event the Contractor fails to deliver O&M Data within the time limits specified, the Contracting Officer may withhold from progress payments 50 percent of the price of the item with which such O&M Data are applicable.

1.7.1.2 Submittals Reserved for NAVFAC MIDLANT Approval

As an exception to the standard submittal procedure specified above, submit the following to the Commander, NAVFAC MIDLANT 9742 Maryland Avenue, Bldg. Z-140 Room 126, Norfolk, VA 23511-3095, ATTN: CODE COFP.

a. Section 28 31 64.00 10, "FIRE DETECTION AND ALARM SYSTEM, ADDRESSABLE": All fire alarm system submittals

1.8 SUBMITTAL CLASSIFICATION

Submittals are classified as follows:

1.9 Government Approved

Government approval is required for extensions of design, critical materials, deviations, equipment whose compatibility with the entire system must be checked, and other items as designated by the Contracting Officer. Within the terms of the Contract Clause entitled "Specifications and Drawings for Construction," they are considered to be "shop drawings."

1.10 Information Only

All submittals not requiring Government or Architect-Engineer of Record approval will be for information only. They are not considered to be "shop drawings" within the terms of the Contract Clause referred to above.

1.10.1 APPROVED SUBMITTALS

The Contracting Officer's and Architect-Engineer's approval of submittals shall not be construed as a complete check, but will indicate only that the general method of construction, materials, detailing and other information are satisfactory. Approval will not relieve the Contractor of the responsibility for any error which may exist, as the Contractor under the Contractor Quality Control (CQC) requirements of this contract is responsible for dimensions, the design of adequate connections and details, and the satisfactory construction of all work. After submittals have been approved by the approving authority, no resubmittal for the purpose of substituting materials or equipment will be considered unless accompanied by an explanation of why a substitution is necessary.

1.10.1.1 DISAPPROVED SUBMITTALS

The Contractor shall make all corrections required by the Contracting Officer and promptly furnish a corrected submittal in the form and number of copies specified for the initial submittal. If the Contractor considers any correction indicated on the submittals to constitute a change to the contract, a notice in accordance with the Contract Clause "Changes" shall be given promptly to the Contracting Officer.

1.11 WITHHOLDING OF PAYMENT

Payment for materials incorporated in the work will not be made if required approvals have not been obtained.

1.12 GENERAL

The contractor shall make submittals as required by the specifications. The Contracting Officer may request submittals in addition to those specified when deemed necessary to adequately describe the work covered in the respective sections. Units of weights and measures used on all submittals shall be the same as those used in the contract drawings. Each submittal shall be complete and in sufficient details to allow ready determination of compliance with contract requirements. Prior to submittal, all items shall be checked and approved by the contractor's Quality Control (CQC) System Manager and each item shall be stamped, signed, and dated by the CQC System Manager indicating action taken. Proposed deviations from the contract requirements shall be clearly identified. Submittals shall include items such as: Contractor's manufacturer's, or fabricator's drawings; descriptive literature including (but not limited to) catalog cuts, diagrams, operating charts or curves;

test report; test cylinders; samples; O&M manuals (including parts list); certifications; warranties; and other such required submittals. Submittals requiring Government approval shall be scheduled and made prior to the acquisition of the material or equipment covered thereby. Samples remaining upon completion of the work shall be picked up and disposed of in accordance with manufacturer's Material Safety Data Sheets (MSDS) and in compliance with existing laws and regulations.

1.13 SUBMITTAL REGISTER

At the end of this section is a submittal register showing items of equipment and materials for which submittals are required by the specifications; this list may not be all inclusive and additional submittals may be required. The Government will provide the initial submittal register. Thereafter, the Contractor shall maintain a complete list of all submittals, including completion of all data columns. Dates on which submittals are received and returned by the Government will be included in its export file to the Contractor. The Contractor shall track all submittals.

1.14 SCHEDULING

Submittals covering component items forming a system or items that are interrelated shall be scheduled to be coordinated and submitted concurrently. Certifications to be submitted with the pertinent drawings shall be so scheduled. Adequate time (a minimum of 14 calendar days exclusive of mailing time) shall be allowed and shown on the register for review and approval. No delay damages or time extensions will be allowed for time lost in late submittals.

1.15 TRANSMITTAL FORM (ENG FORM 4025)

The sample transmittal form (ENG Form 4025) attached to this section shall be used for submitting both Government approved and information only submittals in accordance with the instructions on the reverse side of the form. These forms will be furnished to the Contractor. This form shall be properly completed by filling out all the heading blank spaces and identifying each time submitted. Special care shall be exercised to ensure proper listing of the specification paragraph and/or sheet number of the contract drawings pertinent to the data submitted for each item.

1.16 SUBMITTAL PROCEDURES

Submittals shall be made as follows:

1.16.1 Procedures

The Government will further discuss detailed submittal procedures with the contractor at the Preconstruction Conference.

1.16.1.1 Deviations

For submittals which include proposed deviations requested by the Contractor, the column "variation" of ENG form 4025 shall be checked. The Contractor shall set forth in writing the reason for any deviations and annotate such deviations on the submittal. The Government reserves the right to rescind inadvertent approval of submittals containing unnoted deviations.

1.17 CONTROL OF SUBMITTALS

The Contractor shall carefully control his procurement operations to ensure that each individual submittal is made on or before the Contractor scheduled submittal date shown on the approved "Submittal Register".

1.18 GOVERNMENT AND ARCHITECT-ENGINEER

Upon completion of review of submittals requiring Government approval, the submittal will be identified as having received approval by being so stamped and dated. One copy of the submittal will be retained by the Architect-Engineer, three copies will be retained by the Contracting Officer and three copies will be returned to the Contractor.

1.19 INFORMATION ONLY

Normally submittals for information only will not be returned. Approval of the Contracting Officer is not required on information only submittals. The Government reserves the right to require the Contractor to resubmit any item found not to comply with the contract. This does not relieve the Contactor from the obligation to furnish material conforming to the plans and specifications; will not prevent the Contracting Officer from requiring removal and replacement of nonconforming material incorporate in the work; and does not relieve the Contractor of the requirement to furnish samples for testing by the Government laboratory or for check testing by the Government in those instances where the technical specifications so prescribe.

1.20 STAMPS

Stamps used by the Contractor on the submittal data to certify that the submittal meets contract requirements shall be similar to the following:

CONTRACTOR

(Firm Name)

_____ Approved

_____ Approved with corrections as noted on submittal data and/or attached sheets(s).

SIGNATURE: _____

TITLE: _____

DATE: _____

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

REPLACE AIR HANDLING UNITS BLDG 133 PHASE 3

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		01 20 00.00 20	SD-01 Preconstruction Submittals															
			Schedule of prices	1.3														
		01 30 00	SD-01 Preconstruction Submittals															
			List of contact personnel	1.3.1														
		01 33 00	SD-01 Preconstruction Submittals															
			Submittal register	1.3.1														
		01 45 00.00 20	SD-01 Preconstruction Submittals															
			Construction Quality Control (QC)	1.6.1														
			Plan															
		01 50 00	SD-01 Preconstruction Submittals															
			Traffic control plan	1.6														
		01 57 19.00 20	SD-01 Preconstruction Submittals															
			Preconstruction Survey	1.5.1	G													
			Solid Waste Management Plan	3.4	G													
			and Permit															
			Regulatory Notification	1.5.2	G													
			Environmental Protection Plan	3.1	G													
			Contractor/Vendor Environmental	1.5.6	G													
			Service Agreement															
			SD-06 Test Reports															
			Laboratory Analysis	3.5.2														
			Disposal Requirements	3.14.2														
			SD-11 Closeout Submittals															
			Waste Determination	3.5														
			Documentation															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
REPLACE AIR HANDLING UNITS BLDG 133 PHASE 3

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		01 57 19.00 20	Disposal Documentation for	3.6.1														
			Hazardous and Regulated Waste															
			Contractor 40 CFR Employee	1.5.5														
			Training Records															
			Solid Waste Management Report	3.4.1														
			Contractor Hazardous Material	3.5.1	G													
			Inventory Log															
			Contractor Hazardous Material	3.6	G													
			Inventory Log															
			Hazardous Waste/Debris	3.12.1														
			Management															
		01 78 00	SD-10 Operation and Maintenance															
			Data															
			Equipment/Product Warranty List	1.4.1														
			SD-11 Closeout Submittals															
			As-Built Drawings	1.3.1														
			Record Of Materials	1.3.2														
			Equipment/Product Warranty Tag	1.4.2														
			Monthly Project Waste Summary															
			Report															
			Hazardous Material Reporting															
			Certification of EPA Designated	1.2														
			Items															
			Form DD1354	1.7														
			Checklist for Form DD1354	1.7														
		02 41 00	SD-01 Preconstruction Submittals															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
REPLACE AIR HANDLING UNITS BLDG 133 PHASE 3

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		02 41 00	Existing Conditions	1.10															
			SD-07 Certificates																
			Demolition Plan	1.2.1															
			Notification	1.6															
		02 82 16.00 20	SD-03 Product Data																
			Local exhaust equipment	3.1.4															
			Vacuums	3.1.5															
			Respirators	3.1.1.1															
			Pressure differential automatic	3.1.4															
			recording instrument																
			Amended water	1.2.2															
			Glovebags	3.1.7															
			Material Safety Data Sheets	1.3.8															
			(MSDS) for all materials																
			Encapsulants	2.1															
			SD-06 Test Reports																
			Air sampling results	1.5.5															
			Pressure differential recordings	1.5.6															
			for local exhaust system																
			Asbestos disposal quantity report	3.3.3.2															
			Clearance sampling	3.2.6.3															
			SD-07 Certificates																
			Asbestos hazard abatement plan	1.3.9															
			Testing laboratory	1.3.10															
			Private qualified person	1.5.1															
			documentation																

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
REPLACE AIR HANDLING UNITS BLDG 133 PHASE 3

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		02 82 16.00 20	Contractor's license	1.5.4														
			Competent person	1.5.2														
			Worker's license	1.5.3														
			Landfill approval	1.3.11														
			Employee training	1.3.3														
			Medical certification	1.3.12														
			Waste shipment records	1.3.11														
			Respiratory Protection Program	1.3.6														
			Delivery tickets	1.3.11														
			Vacuums	3.1.5														
			Water filtration equipment	3.1.2.3														
			Ventilation systems	3.1.5														
			equipment used to contain	3.1														
			airborne asbestos fibers															
			encapsulants	2.1														
			Notifications	1.3.4														
			SD-11 Closeout Submittals															
			Notifications	1.3.4														
			Rental equipment	1.6.1														
			Respirator program records	1.3.6.1														
			Permits and licenses	1.3.4														
			Protective clothing	1.5.7														
			decontamination quality control															
			records															
			Protective clothing	1.5.8														
			decontamination facility notification															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

REPLACE AIR HANDLING UNITS BLDG 133 PHASE 3

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		02 83 13.00 20	SD-01 Preconstruction Submittals															
			Occupational and Environmental	1.5.2.3														
			Assessment Data Report															
			Lead Compliance Plan	1.5.2.2														
			Competent Person	1.5.1.1														
			Training Certification	1.5.1.2														
			lead waste management plan	1.5.2.8														
			written evidence	3.5.2.1														
			Medical Examinations	1.5.2.4														
			SD-06 Test Reports															
			sampling results	1.5.2.3														
			Occupational and Environmental	1.5.2.3														
			Assessment Data Report															
			SD-07 Certificates															
			Testing laboratory	1.5.1.3														
			Occupant Notification	3.1.1.1														
			Third party consultant	1.5.1.4														
			qualifications															
			Clearance Certification	3.5.1.1														
			SD-11 Closeout Submittals															
			hazardous waste manifest	3.5.2.1														
			turn-in documents or weight	3.5.2.1														
			tickets															
		05 12 00	SD-01 Preconstruction Submittals															
			Erection Drawings	1.4.1.1														
			SD-02 Shop Drawings															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
REPLACE AIR HANDLING UNITS BLDG 133 PHASE 3

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		05 12 00	Fabrication drawings	1.4.2														
			SD-03 Product Data															
			Welding electrodes and rods	2.4.1														
			Direct Tension Indicator Washers	2.3.2.3														
			Non-Shrink Grout	2.4.2														
			Tension control bolts	2.3.3														
			SD-06 Test Reports															
			Bolts, nuts, and washers	2.3														
			Weld Inspection Reports	3.6.1.1														
			Direct Tension Indicator Washer	3.6.2.1														
			Inspection Reports															
			Bolt Testing Reports	3.6.3.1														
			Embrittlement Test Reports	3.6.4														
			SD-07 Certificates															
			Steel	2.2														
			Bolts, nuts, and washers	2.3														
			Galvanizing	2.5														
			AISC Fabrication Plant Quality	1.3														
			Certification															
			Welding procedures and	1.4.3.1														
			qualifications															
			Welding electrodes and rods	2.4.1														
		05 50 13	SD-02 Shop Drawings															
			Floor gratings and roof walkways	2.3														
			Angles and plates	2.4														
			SD-03 Product Data															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

REPLACE AIR HANDLING UNITS BLDG 133 PHASE 3

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		05 50 13	Floor gratings and roof walkways	2.3														
		05 52 00	SD-02 Shop Drawings															
			Fabrication Drawings	3.1														
			Iron and Steel Hardware	2.1														
			Iron and Steel Hardware	3.1														
			Steel Shapes, Plates, Bars and Strips	2.1														
			Steel Shapes, Plates, Bars and Strips	3.1														
			SD-03 Product Data															
			Structural Steel Plates, Shapes, and Bars	2.3														
			Hot-Rolled Carbon Steel Bars	2.4														
			Protective Coating	2.6														
			Steel Railings	2.7														
			SD-07 Certificates															
			Welding Procedures	1.3.1														
			Welder Qualification	1.3.2														
			SD-08 Manufacturer’s Instructions															
			Installation Instructions	3.1														
		06 10 00	SD-06 Test Reports															
			Preservative-treated	1.4.3														
			SD-07 Certificates															
			Certificates of grade	1.8.1														
			Preservative treatment	1.7														
		07 22 00	SD-03 Product Data															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
REPLACE AIR HANDLING UNITS BLDG 133 PHASE 3

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		07 22 00	Fasteners	2.4														
			Insulation	2.1														
			SD-06 Test Reports															
			Flame spread and smoke	1.4.1														
			developed ratings															
			SD-07 Certificates															
			qualifications	1.3														
			SD-08 Manufacturer’s Instructions															
			fasteners	2.4														
			insulation	2.1														
		07 52 00	SD-02 Shop Drawings															
			Roof plan	1.4.6														
			SD-03 Product Data															
			Cold Adhesive Applied Modified	3.3.2.2														
			Bitumen Cap Sheet															
			Cold-Applied Membrane	2.3														
			Adhesive															
			Primer	2.5														
			Modified Bitumen Roof Cement	2.6														
			Modified Bitumen Sheets	2.1														
			Pre-Manufactured Accessories	2.9														
			Fasteners And Plates	2.8														
			Warranty	1.8														
			SD-05 Design Data															
			Wind Uplift Calculations	1.4.5														
			SD-07 Certificates															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
REPLACE AIR HANDLING UNITS BLDG 133 PHASE 3

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		07 52 00	Qualification of Manufacturer	1.4.1														
			Qualification of Applicator	1.4.2														
			Qualification of Engineer of Record	1.4.3														
			Wind Uplift Resistance	1.4.5														
			Fire Resistance	1.4.4														
			SD-08 Manufacturer's Instructions															
			Modified Bitumen Membrane Application	3.3.3														
			Flashing	3.3.4														
			Cold Adhesive Applied Modified Bitumen Cap Sheet	3.3.2.2														
			Primer	2.5														
			Modified Bitumen Roof Cement	2.6														
			Fasteners	2.8.1														
			Cold Weather Installation	1.6														
			SD-11 Closeout Submittals															
			Warranty	1.8														
			Information Card	3.7														
			Instructions To Government Personnel	3.6														
		07 60 00	SD-02 Shop Drawings															
			Gravel stops and fascias	3.1.10														
			Flashing at roof penetrations	3.1.11														
			SD-11 Closeout Submittals															
			Quality Control Plan	3.5														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
REPLACE AIR HANDLING UNITS BLDG 133 PHASE 3

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		07 92 00	SD-03 Product Data																
			Sealants	2.1															
			Primers	2.2															
			Bond breakers	2.3															
			Backstops	2.4															
			SD-07 Certificates																
			Sealant	3.3.6															
		09 90 00	SD-02 Shop Drawings																
			Piping identification	3.9															
			SD-03 Product Data																
			Local/Regional Materials	1.9.1															
			Materials	2.1															
			Coating	2.1															
			Manufacturer's Technical Data	2.1															
			Sheets																
			SD-04 Samples																
			Color	1.11															
			SD-07 Certificates																
			Applicator's qualifications	1.3															
			Qualification Testing	1.4.1.2															
			SD-08 Manufacturer’s Instructions																
			Application instructions	3.2.1															
			Mixing	3.6.2															
			Manufacturer's Material Safety	1.7.2															
			Data Sheets																

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
REPLACE AIR HANDLING UNITS BLDG 133 PHASE 3

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		09 90 00	SD-10 Operation and Maintenance															
			Data															
			Coatings:	2.1														
		23 00 00	SD-03 Product Data															
			Diffusers	2.6.4.1														
			Air Vents, Penthouses, and	2.6.5														
			Goosenecks															
			Air Handling Units	2.8														
			Diagrams	1.2.1.2														
			SD-06 Test Reports															
			Performance Tests	3.8														
			SD-08 Manufacturer’s Instructions															
			Manufacturer's Installation	3.2														
			Instructions															
			Operation and Maintenance	3.9.1														
			Training															
			SD-10 Operation and Maintenance															
			Data															
			Air Handling Units	2.8														
		23 05 15	SD-01 Preconstruction Submittals															
			Material, Equipment, and Fixture	1.2														
			Lists															
			SD-02 Shop Drawings															
			Record Drawings	1.2														
			Connection Diagrams	1.2														
			Installation Drawings	3.1														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
REPLACE AIR HANDLING UNITS BLDG 133 PHASE 3

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		23 05 15	SD-03 Product Data															
			Pipe and Fittings	2.1														
			Piping Specialties	2.2														
			SD-04 Samples															
			Manufacturer's Standard Color	1.2														
			Charts															
			SD-05 Design Data															
			Pipe and Fittings	2.1														
			Piping Specialties	2.2														
			SD-06 Test Reports															
			Hydrostatic Tests	3.1														
			Air Tests	3.1														
			Valve-Operating Tests	3.1														
			Drainage Tests	3.1														
			System Operation Tests	3.1														
			SD-07 Certificates															
			List of Qualified Permanent	1.4.3														
			Service Organizations															
			Listing of Product Installations	1.2														
			Records of Existing Conditions	1.2														
			SD-10 Operation and Maintenance															
			Data															
			Operation and Maintenance	3.4														
			Manuals															
		23 05 48.00 40	SD-03 Product Data															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
REPLACE AIR HANDLING UNITS BLDG 133 PHASE 3

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		23 05 48.00 40	Equipment and Performance	1.2														
			Data															
			Isolators	2.3														
		23 05 48	SD-03 Product Data															
			Equipment and Performance	1.2														
			Data															
			Mountings	2.1.2														
			Bases	2.1.3														
			Isolators	2.3														
		23 05 93	SD-07 Certificates															
			Independent TAB agency and	1.5.1														
			personnel qualifications															
			Advance notice of Pre-Final	3.3.2														
			DALT field work															
			Completed Pre-Final DALT Work	3.7														
			Checklist															
			Completed Pre-Final DALT Work	3.7														
			Checklist															
			Advance Notice of Season 1 TAB	3.7														
			Field Work															
			Completed Season 1 Pre-TAB	3.7														
			Work Checklist															
			Completed Season 1 Pre-TAB	3.7														
			Work Checklist															
			Advance Notice of Season 2 TAB	3.7														
			Field Work															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION

REPLACE AIR HANDLING UNITS BLDG 133 PHASE 3

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		23 05 93	Completed Season 2 Pre-TAB Work Checklist	3.7														
			Completed Season 2 Pre-TAB Work Checklist	3.7														
		23 07 00	SD-02 Shop Drawings															
			MICA Plates	3.2.2.4														
			Pipe Insulation Systems	2.3														
			Pipe Insulation Systems	3.2														
			Duct Insulation Systems	3.3														
			SD-03 Product Data															
			Pipe Insulation Systems	2.3														
			Pipe Insulation Systems	3.2														
			Duct Insulation Systems	3.3														
			SD-08 Manufacturer’s Instructions															
			Pipe Insulation Systems	2.3														
			Pipe Insulation Systems	3.2														
			Duct Insulation Systems	3.3														
		23 09 23.13 20	SD-02 Shop Drawings															
			Control system drawings title sheet	1.4.1.1														
			List of I/O Points	1.4.1.2														
			Control System Components List	1.4.1.3														
			Control system schematics	1.4.1.4														
			HVAC Equipment Electrical Ladder diagrams	1.4.1.5														
			Component wiring diagrams	1.4.1.6														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
REPLACE AIR HANDLING UNITS BLDG 133 PHASE 3

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		23 09 23.13 20	Terminal strip diagrams	1.4.1.7														
			Communication architecture	1.4.1.8														
			schematic															
			SD-03 Product Data															
			Direct Digital Controllers	2.1.1														
			BACnet Gateways	2.1.1.10														
			BACnet Protocol Analyzer	2.1.4														
			DDC Software	2.1.3														
			Sensors and Input Hardware	2.2														
			Output Hardware	2.3														
			Surge and transient protection	2.4.2														
			Indicators	2.6														
			Duct smoke detectors	2.5.1														
			SD-05 Design Data															
			Performance Verification Testing	3.3.2														
			Plan															
			Pre-Performance Verification	3.3.4														
			Testing Checklist															
			SD-06 Test Reports															
			Performance Verification Testing	3.3.11														
			Report															
			SD-07 Certificates															
			Contractor's Qualifications	1.6.6														
			SD-09 Manufacturer’s Field															
			Reports															
			Pre-PVT Checklist	3.3.1														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
REPLACE AIR HANDLING UNITS BLDG 133 PHASE 3

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		23 09 23.13 20	SD-10 Operation and Maintenance															
			Data															
			BACnet Direct Digital Control															
			Systems															
			SD-11 Closeout Submittals															
			Training documentation	3.4.1														
		23 22 26.00 20	SD-03 Product Data															
			Steam to air heating coils	2.2														
			Valves	2.1.7														
			Valve operating mechanism	2.1.7.4														
			Traps	2.1.10.2														
			Strainers	2.1.10.3														
			Instrumentation	2.1.9														
			SD-06 Test Reports															
			Steam piping	2.1.1														
			Valves	2.1.7														
			Instrumentation	2.1.9														
			Pipe and pipe system	2.1														
			Steam to air heating coils	2.2														
			SD-07 Certificates															
			Welding procedure	1.4.1														
			Welder's Performance	1.4.2														
			Qualification Record															
			List of welders and welder's	1.4.2														
			symbols															
		26 20 00	SD-02 Shop Drawings															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
REPLACE AIR HANDLING UNITS BLDG 133 PHASE 3

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		26 20 00	Panelboards	2.12														
			Busway	2.3														
			SD-03 Product Data															
			Receptacles	2.11														
			Circuit breakers	2.12.3														
			Switches	2.9														
			Enclosed circuit breakers	2.13														
			SD-06 Test Reports															
			600-volt wiring test	3.5.2														
			Grounding system test	3.5.4														
			Ground-fault receptacle test	3.5.3														
			SD-07 Certificates															
			Fuses	2.10														
		28 31 64.00 10	SD-02 Shop Drawings															
			Detail Drawings	1.3.2														
			SD-06 Test Reports															
			Testing	3.5														
			SD-07 Certificates															
			Equipment	2.1.6														
			Qualifications	1.3.1														

SECTION 01 35 26

GOVERNMENTAL SAFETY REQUIREMENTS
02/11

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN NATIONAL STANDARD INSTITUE/AMERICAN SOCIETY OF SAFETY ENGINEERS (ANSI/ASSE)

ANSI/ASSE A10.32	(2012) Personal Fall Protection Used in Construction and Demolition Operations
ANSI/ASSE A10.34	(2001; R2012) Protection of the Public on or Adjacent to Construction Sites
ANSI/ASSE Z359.1	(2007) Safety Requirements for Personal Fall Arrest Systems, Subsystems and Components

ASME INTERNATIONAL (ASME)

ASME B30.22	(2010) Articulating Boom Cranes
ASME B30.3	(2009) Tower Cranes
ASME B30.5	(2007) Mobile and Locomotive Cranes
ASME B30.8	(2010) Floating Cranes and Floating Derricks

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 10	(2010) Standard for Portable Fire Extinguishers
NFPA 241	(2009) Standard for Safeguarding Construction,Alteration, and Demolition Operations
NFPA 51B	(2009; TIA 09-1) Standard for Fire Prevention During Welding, Cutting, and Other Hot Work
NFPA 70	(2011; TIA 11-1; Errata 2011) National Electrical Code
NFPA 70E	(2009; Errata 09-1) Standard for Electrical Safety in the Workplace

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2008; Errata 1-2010; Changes 1-3 2010; Changes 4-7 2011) Safety and Health Requirements Manual

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910	Occupational Safety and Health Standards
29 CFR 1910.146	Permit-required Confined Spaces
29 CFR 1915	Confined and Enclosed Spaces and Other Dangerous Atmospheres in Shipyard Employment
29 CFR 1926	Safety and Health Regulations for Construction
29 CFR 1926.500	Fall Protection

1.2 SUBMITTALS

The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

Government acceptance is required for submittals.

SD-01 Preconstruction Submittals

Accident Prevention Plan (APP)

Activity Hazard Analysis (AHA)

Crane Critical Lift Plan

Proof of qualification for Crane Operators

SD-06 Test Reports

Reports

Submit reports as their incidence occurs, in accordance with the requirements of the paragraph entitled, "Reports."

Accident Reports

Monthly Exposure Reports

Crane Reports

Regulatory Citations and Violations

SD-07 Certificates

Confined Space Entry Permit

Hot work permit

Contractor Safety Self-Evaluation Checklist

Certificate of Compliance (Crane)

Submit one copy of each permit/certificate attached to each Daily Production Report.

Machinery & Mechanized Equipment Certification Form

1.2 DEFINITIONS

a. High Visibility Accident. Any mishap which may generate publicity and/or high visibility.

b. Medical Treatment. Treatment administered by a physician or by registered professional personnel under the standing orders of a physician. Medical treatment does not include first aid treatment even through provided by a physician or registered personnel.

c. Recordable Injuries or Illnesses. Any work-related injury or illness that results in:

(1) Death, regardless of the time between the injury and death, or the length of the illness;

(2) Days away from work (any time lost after day of injury/illness onset);

(3) Restricted work;

(4) Transfer to another job;

(5) Medical treatment beyond first aid;

(6) Loss of consciousness; or

(7) A significant injury or illness diagnosed by a physician or other licensed health care professional, even if it did not result in (1) through (6) above.

d. "USACE" property and equipment specified in USACE EM 385-1-1 should be interpreted as Government property and equipment.

e. Weight Handling Equipment (WHE) Accident. A WHE accident occurs when any one or more of the six elements in the operating envelope fails to perform correctly during operation, including operation during maintenance or testing resulting in personnel injury or death; material or equipment damage; dropped load; derailment; two-blocking; overload; and/or collision, including unplanned contact between the load, crane, and/or other objects. A dropped load, derailment, two-blocking, overload and collision are considered accidents even though no material damage or injury occurs. A component failure (e.g., motor burnout, gear tooth failure, bearing failure) is not considered an accident solely due to material or equipment damage unless the component failure results in damage to other components (e.g., dropped boom, dropped load, roll over, etc.).

1.3 CONTRACTOR SAFETY SELF-EVALUATION CHECKLIST

Contracting Officer will provide a "Contractor Safety Self-Evaluation checklist" to the Contractor at the pre-construction conference. The checklist will be completed monthly by the Contractor and submitted with each request for payment voucher. An acceptable score of 90 or greater is required. Failure to submit the completed safety self-evaluation checklist or achieve a score of at least 90, will result in a retention of up to 10 percent of the voucher.

1.5 REGULATORY REQUIREMENTS

In addition to the detailed requirements included in the provisions of this contract, work performed shall comply with USACE EM 385-1-1, and the following federal, state, and local laws, ordinances, criteria, rules and regulations. Submit matters of interpretation of standards to the appropriate administrative agency for resolution before starting work. Where the requirements of this specification, applicable laws, criteria, ordinances, regulations, and referenced documents vary, the most stringent requirements shall apply.

1.4 SITE QUALIFICATIONS, DUTIES AND MEETINGS

1.4.1 Personnel Qualifications

1.4.1.1 Site Safety and Health Officer (SSHO)

Site Safety and Health Officer (SSHO) shall be provided at the work site at all times to perform safety and occupational health management, surveillance, inspections, and safety enforcement for the Contractor. The Contractor Quality Control (QC) person can be the SSHO on this project. The SSHO shall meet the following requirements:

Level 1:
Worked on similar projects.
10-hour OSHA construction safety class or equivalent within last 3 years.
Competent person training as needed.

1.4.1.2 Crane Operators

Crane operators shall meet the requirements in USACE EM 385-1-1, Section 16 and Appendix G. In addition, for mobile cranes with Original Equipment Manufacturer (OEM) rated capacitates of 50,000 pounds or greater, crane operators shall be designated as qualified by a source that qualifies crane operators (i.e., union, a government agency, or and organization that tests and qualifies crane operators). Proof of current qualification shall be provided.

1.4.2 Personnel Duties

1.4.2.1 Site Safety and Health Officer (SSHO)/Superintendent

a. Conduct daily safety and health inspections and maintain a written log which includes area/operation inspected, date of inspection, identified hazards, recommended corrective actions, estimated and actual dates of corrections. Safety inspection logs shall be attached to the Contractors' daily production report.

b. Conduct mishap investigations and complete required reports. Maintain the OSHA Form 300 and Daily Production reports for prime and sub-contractors.

c. Maintain applicable safety reference material on the job site.

d. Attend the pre-construction conference, pre-work meetings including preparatory inspection meeting, and periodic in-progress meetings.

e. Implement and enforce accepted APPS and AHAs.

f. Maintain a safety and health deficiency tracking system that monitors outstanding deficiencies until resolution. A list of unresolved safety and health deficiencies shall be posted on the safety bulletin board.

g. Ensure sub-contractor compliance with safety and health requirements.

Failure to perform the above duties will result in dismissal of the superintendent and/or SSHO, and a project work stoppage. The project work stoppage will remain in effect pending approval of a suitable replacement.

1.4.3 Meetings

1.4.3.1 Preconstruction Conference

a. Contractor representatives who have a responsibility or significant role in accident prevention on the project shall attend the preconstruction conference. This includes the project superintendent, site safety and health officer, quality control supervisor, or any other assigned safety and health professionals who participated in the development of the APP (including the Activity Hazard Analyses (AHAs) and special plans, program and procedures associated with it).

b. The Contractor shall discuss the details of the submitted APP to include incorporated plans, programs, procedures and a listing of anticipated AHAs that will be developed and implemented during the performance of the contract. This list of proposed AHAs will be reviewed at the conference and an agreement will be reached between the Contractor and the Contracting Officer's representative as to which phases will require an analysis. In addition, a schedule for the preparation, submittal, review, and acceptance of AHAs shall be established to preclude project delays.

c. Deficiencies in the submitted APP will be brought to the attention of the Contractor at the preconstruction conference, and the Contractor shall revise the plan to correct deficiencies and re-submit it for acceptance. Work shall not begin until there is an accepted APP.

d. The functions of a Preconstruction conference may take place at the Post-Award Kickoff meeting for Design Build Contracts.

1.5 Safety Meetings

Shall be conducted and documented as required by EM 385-1-1. Minutes showing contract title, signatures of attendees and a list of topics discussed shall be attached to the Contractors' daily production report.

1.6 ACCIDENT PREVENTION PLAN (APP)

The Contractor shall use a qualified person to prepare the written site-specific APP. Prepare the APP in accordance with the format and requirements of USACE EM 385-1-1 and as supplemented herein. Cover all paragraph and subparagraph elements in USACE EM 385-1-1, Appendix A, "Minimum Basic Outline for Accident Prevention Plan". Specific requirements for some of the APP elements are described below. The APP shall be job-specific and shall address any unusual or unique aspects of the project or activity for which it is written. The APP shall interface with the Contractor's overall safety and health program. Any portions of the Contractor's overall safety and health program referenced in the APP shall be included in the applicable APP element and made site-specific. The Government considers the Prime Contractor to be the "controlling authority" for all work site safety and health of the subcontractors. Contractors are responsible for informing their subcontractors of the safety provisions under the terms of the contract and the penalties for noncompliance, coordinating the work to prevent one craft from interfering with or creating hazardous working conditions for other crafts, and inspecting subcontractor operations to ensure that accident prevention responsibilities are being carried out. The APP shall be signed by the person and firm (senior person) preparing the APP, the Contractor, the on-site superintendent, the designated site safety and health officer and any designated CSP and/or CIH.

Submit the APP to the Contracting Officer 15 calendar days prior to the date of the preconstruction conference for acceptance. Work cannot proceed without an accepted APP.

Once accepted by the Contracting Officer, the APP and attachments will be enforced as part of the contract. Disregarding the provisions of this contract or the accepted APP will be cause for stopping of work, at the discretion of the Contracting Officer, until the matter has been rectified.

Once work begins, changes to the accepted APP shall be made with the knowledge and concurrence of the Contracting Officer, project superintendent, SSHO and quality control manager. Should any hazard become evident, stop work in the area, secure the area, and develop a plan to remove the hazard. Notify the Contracting Officer within 24 hours of discovery. Eliminate/remove the hazard. In the interim, all necessary action shall be taken to restore and maintain safe working conditions in order to safeguard onsite personnel, visitors, the public (as defined by ANSI/ASSE A10.34,) and the environment.

Copies of the accepted plan will be maintained at the Contracting Officer's office and at the job site.
The APP shall be continuously reviewed and amended, as necessary, throughout the life of the contract. Unusual or high-hazard activities not identified in the original APP shall be incorporated in the plan as they are discovered.

1.6.1 EM 385-1-1 Contents

In addition to the requirements outlines in Appendix A of USACE EM 385-1-1, the following is required:

a. Names and qualifications (resumes including education, training, experience and certifications) of all site safety and health personnel

designated to perform work on this project to include the designated site safety and health officer and other competent and qualified personnel to be used such as CSPs, CIHs, STSs, CHSTs. The duties of each position shall be specified.

b. Qualifications of competent and of qualified persons. As a minimum, competent persons shall be designated and qualifications submitted for each of the following major areas: excavation; scaffolding; fall protection; hazardous energy; confined space; health hazard recognition, evaluation and control of chemical, physical and biological agents; personal protective equipment and clothing to include selection, use and maintenance.

c. Confined Space Entry Plan. Develop a confined space entry plan in accordance with USACE EM 385-1-1, applicable OSHA standards 29 CFR 1910, 29 CFR 1915, and 29 CFR 1926, and any other federal, state and local regulatory requirements identified in this contract. Identify the qualified person's name and qualifications, training, and experience. Delineate the qualified person's authority to direct work stoppage in the event of hazardous conditions. Include procedure for rescue by contractor personnel and the coordination with emergency responders. (If there is no confined space work, include a statement that no confined space work exists and none will be created.)

d. Crane Critical Lift Plan. Prepare and sign weight handling critical lift plans for lifts over 75 percent of the capacity of the crane or hoist (or lifts over 50 percent of the capacity of a barge mounted mobile crane's hoists) at any radius of lift; lifts involving more than one crane or hoist; lifts of personnel; and lifts involving non-routine rigging or operation, sensitive equipment, or unusual safety risks. The plan shall be submitted 15 calendar days prior to on-site work and include the requirements of USACE EM 385-1-1, paragraph 16.C.18. and the following:

(1) For lifts of personnel, the plan shall demonstrate compliance with the requirements of 29 CFR 1926.550(g).

e. Fall Protection and Prevention (FP&P) Plan. The plan shall be site specific and address all fall hazards in the work place and during different phases of construction. It shall address how to protect and prevent workers from falling to lower levels when they are exposed to fall hazards above 1.8 m (6 feet). A qualified person for fall protection shall prepare and sign the plan. The plan shall include fall protection and prevention systems, equipment and methods employed for every phase of work, responsibilities, assisted rescue, self-rescue and evacuation procedures, training requirements, and monitoring methods. Fall Protection and Prevention Plan shall be revised every six months for lengthy projects, reflecting any changes during the course of construction due to changes in personnel, equipment, systems or work habits. The accepted Fall Protection and Prevention Plan shall be kept and maintained at the job site for the duration of the project. The Fall Protection and Prevention Plan shall be included in the Accident Prevention Plan (APP).

e. Lead Compliance Plan. The safety and health aspects of lead work, prepared in accordance with Section 02 83 13.00 20 LEAD IN CONSTRUCTION.

f. Asbestos Hazard Abatement Plan. The safety and health aspects of asbestos work, prepared in accordance with Section 02 82 16.00 20

ENGINEERING CONTROL OF ASBESTOS CONTAINING MATERIALS.

g. Site Demolition Plan. The safety and health aspects prepared in accordance with Section 02 41 00 DEMOLITION and referenced sources.

1.7 ACTIVITY HAZARD ANALYSIS (AHA)

The Activity Hazard Analysis (AHA) format shall be in accordance with USACE EM 385-1-1. Submit the AHA for review at least 15 calendar days prior to the start of each phase. Format subsequent AHAs as amendments to the APP. The analysis should be used during daily inspections to ensure the implementation and effectiveness of the activity's safety and health controls.

The AHA list will be reviewed periodically (at least monthly) at the Contractor supervisory safety meeting and updated as necessary when procedures, scheduling, or hazards change.

The activity hazard analyses shall be developed using the project schedule as the basis for the activities performed. Any activities listed on the project schedule will require an AHA. The AHAs will be developed by the contractor, supplier or subcontractor and provided to the prime contractor for submittal to the Contracting Officer.

1.8 DISPLAY OF SAFETY INFORMATION

Within 1 calendar days after commencement of work, erect a safety bulletin board at the job site. The safety bulletin board shall include information and be maintained as required by EM 385-1-1, section 01.A.06. Additional items required to be posted include:

a. Confined space entry permit.

b. Hot work permit.

1.9 SITE SAFETY REFERENCE MATERIALS

Maintain safety-related references applicable to the project, including those listed in the article "References." Maintain applicable equipment manufacturer's manuals.

1.10 EMERGENCY MEDICAL TREATMENT

Contractors will arrange for their own emergency medical treatment. Government has no responsibility to provide emergency medical treatment.

1.11 REPORTS

1.11.1 Accident Reports

a. For recordable injuries and illnesses, and property damage accidents resulting in at least $2,000 in damages, the Prime Contractor shall conduct an accident investigation to establish the root cause(s) of the accident, complete the and provide the report to the Contracting Officer within 5 calendar day(s) of the accident. The Contracting Officer will provide copies of any required or special forms.

b. For any weight handling equipment accident (including rigging gear

accidents) the Prime Contractor shall conduct an accident investigation to establish the root cause(s) of the accident, complete the WHE Accident Report (Crane and Rigging Gear) form and provide the report to the Contracting Officer within 30 calendar days of the accident. Crane operations shall not proceed until cause is determined and corrective actions have been implemented to the satisfaction of the contracting officer. The Contracting Officer will provide a blank copy of the accident report form.

1.11.2 Accident Notification

Notify the Contracting Officer as soon as practical, but not later than four hours, after any accident meeting the definition of Recordable Injuries or Illnesses or High Visibility Accidents, property damage equal to or greater than $2,000, or any weight handling equipment accident. Information shall include contractor name; contract title; type of contract; name of activity, installation or location where accident occurred; date and time of accident; names of personnel injured; extent of property damage, if any; extent of injury, if known, and brief description of accident (to include type of construction equipment used, PPE used, etc.). Preserve the conditions and evidence on the accident site until the Government investigation team arrives on-site and Government investigation is conducted.

1.11.3 Monthly Exposure Reports

Monthly exposure reporting to the Contracting Officer is required to be attached to the monthly billing request. This report is a compilation of employee-hours worked each month for all site workers, both prime and subcontractor. The Contracting Officer will provide copies of any special forms.

1.11.4 Crane Reports

Submit crane inspection reports required in accordance with USACE EM 385-1-1, Appendix H and as specified herein with Daily Reports of Inspections.

1.11.5 Certificate of Compliance

The Contractor shall provide a Certificate of Compliance for each crane entering an activity under this contract (see Contracting Officer for a blank certificate). Certificate shall state that the crane and rigging gear meet applicable OSHA regulations (with the Contractor citing which OSHA regulations are applicable, e.g., cranes used in construction, demolition, or maintenance shall comply with 29 CFR 1926 and USACE EM 385-1-1 section 16 and Appendix H. Certify on the Certificate of Compliance that the crane operator(s) is qualified and trained in the operation of the crane to be used. The Contractor shall also certify that all of its crane operators working on the DOD activity have been trained in the proper use of all safety devices (e.g., anti-two block devices). These certifications shall be posted on the crane.

1.12 HOT WORK

Prior to performing "Hot Work" (welding, cutting, etc.) or operating other flame-producing/spark producing devices, a written permit shall be requested from the Fire Division. CONTRACTORS ARE REQUIRED TO MEET ALL CRITERIA BEFORE A PERMIT IS ISSUED. The Contractor will provide at least two (2) twenty (20) pound 4A:20 BC rated extinguishers for normal "Hot

Work". All extinguishers shall be current inspection tagged, approved safety pin and tamper resistant seal. It is also mandatory to have a designated FIRE WATCH for any "Hot Work" done at this activity. The Fire Watch shall be trained in accordance with NFPA 51B and remain on-site for a minimum of 30 minutes after completion of the task or as specified on the hot work permit.

When starting work in the facility, Contractors shall require their personnel to familiarize themselves with the location of the nearest fire alarm boxes and place in memory the emergency Fire Division phone number. ANY FIRE, NO MATTER HOW SMALL, SHALL BE REPORTED TO THE RESPONSIBLE FIRE DIVISION IMMEDIATELY.

Obtain services from a NFPA Certified Marine Chemist for "HOT WORK" within or around flammable materials (such as fuel systems, welding/cutting on fuel pipes) or confined spaces (such as sewer wet wells, manholes, vaults, etc.) that have the potential for flammable or explosive atmospheres.

PART 2 PRODUCTS

2.1 CONFINED SPACE SIGNAGE

The Contractor shall provide permanent signs integral to or securely attached to access covers for new permit-required confined spaces. Signs wording: "DANGER--PERMIT-REQUIRED CONFINED SPACE - DO NOT ENTER -" in bold letters a minimum of 25 mm (one inch) in height and constructed to be clearly legible with all paint removed. The signal word "DANGER" shall be red and readable from 1.52 m (5 feet).

2.2 FALL PROTECTION ANCHORAGE

Fall protection anchorage, conforming to ANSI/ASSE Z359.1, installed under the supervision of a qualified person in fall protection, shall be left in place for continued customer use and so identified by signage stating the capacity of the anchorage (strength and number of persons who may be tied-off to it at any one time).

PART 3 EXECUTION

3.1 CONSTRUCTION AND/OR OTHER WORK

The Contractor shall comply with USACE EM 385-1-1, NFPA 241, the APP, the AHA, Federal and/or State OSHA regulations, and other related submittals and activity fire and safety regulations. The most stringent standard shall prevail.

3.1.1 Hazardous Material Use

Each hazardous material must receive approval prior to being brought onto the job site or prior to any other use in connection with this contract. Allow a minimum of 10 working days for processing of the request for use of a hazardous material.

3.1.2 Hazardous Material Exclusions

Notwithstanding any other hazardous material used in this contract, radioactive materials or instruments capable of producing ionizing/non-ionizing radiation (with the exception of radioactive material and devices used in accordance with USACE EM 385-1-1 such as nuclear

density meters for compaction testing and laboratory equipment with radioactive sources) as well as materials which contain asbestos, mercury or polychlorinated biphenyls, di-isocynates, lead-based paint are prohibited. The Contracting Officer, upon written request by the Contractor, may consider exceptions to the use of any of the above excluded materials.

3.1.3 Unforeseen Hazardous Material

The design should have identified materials such as PCB, lead paint, and friable and non-friable asbestos. If additional material, not indicated, that may be hazardous to human health upon disturbance during construction operations is encountered, stop that portion of work and notify the Contracting Officer immediately. Within 14 calendar days the Government will determine if the material is hazardous. If material is not hazardous or poses no danger, the Government will direct the Contractor to proceed without change. If material is hazardous and handling of the material is necessary to accomplish the work, the Government will issue a modification pursuant to "FAR 52.243-4, Changes" and "FAR 52.236-2, Differing Site Conditions."

3.2 PRE-OUTAGE COORDINATION MEETING

Contractors are required to apply for utility outages at least 15 days in advance. As a minimum, the request should include the location of the outage, utilities being affected, duration of outage and any necessary sketches. Special requirements for electrical outage requests are contained elsewhere in this specification section. Once approved, and prior to beginning work on the utility system requiring shut down, the Contractor shall attend a pre-outage coordination meeting with the Contracting Officer to review the scope of work and the lock-out/tag-out procedures for worker protection. No work will be performed on energized electrical circuits unless proof is provided that no other means exist.

3.3 FALL HAZARD PROTECTION AND PREVENTION PROGRAM

The Contractor shall establish a fall protection and prevention program, for the protection of all employees exposed to fall hazards. The program shall include company policy, identify responsibilities, education and training requirements, fall hazard identification, prevention and control measures, inspection, storage, care and maintenance of fall protection equipment and rescue and evacuation procedures.

3.3.1 Training

The Contractor shall institute a fall protection training program. As part of the Fall Hazard Protection and Prevention Program, the Contractor shall provide training for each employee who might be exposed to fall hazards. A competent person for fall protection shall provide the training. Training requirements shall be in accordance with USACE EM 385-1-1, section 21.A.16.

3.3.2 Fall Protection Equipment and Systems

The Contractor shall enforce use of the fall protection equipment and systems designated for each specific work activity in the Fall Protection and Prevention Plan and/or AHA at all times when an employee is exposed to a fall hazard. Employees shall be protected from fall hazards as specified in EM 385-1-1, section 21. In addition to the required fall protection systems, safety skiff, personal floatation devices, life rings etc., are

required when working above or next to water in accordance with USACE EM 385-1-1, paragraphs 05.H. and 05.I. Personal fall arrest systems are required when working from an articulating or extendible boom, swing stages, or suspended platform. In addition, personal fall arrest systems are required when operating other equipment such as scissor lifts if the work platform is capable of being positioned outside the wheelbase. The need for tying-off in such equipment is to prevent ejection of the employee from the equipment during raising, lowering, or travel. Fall protection must comply with 29 CFR 1926.500, Subpart M, USACE EM 385-1-1 and ANSI/ASSE A10.32.

3.3.2.1 Personal Fall Arrest Equipment

Personal fall arrest equipment, systems, subsystems, and components shall meet ANSI/ASSE Z359.1. Only a full-body harness with a shock-absorbing lanyard or self-retracting lanyard is an acceptable personal fall arrest body support device. Body belts may only be used as a positioning device system (for uses such as steel reinforcing assembly and in addition to an approved fall arrest system). Harnesses shall have a fall arrest attachment affixed to the body support (usually a Dorsal D-ring) and specifically designated for attachment to the rest of the system. Only locking snap hooks and carabiners shall be used. Webbing, straps, and ropes shall be made of synthetic fiber. The maximum free fall distance when using fall arrest equipment shall not exceed 1.8 m (6 feet). The total fall distance and any swinging of the worker (pendulum-like motion) that can occur during a fall shall always be taken into consideration when attaching a person to a fall arrest system.

3.3.3 Fall Protection for Roofing Work

Fall protection controls shall be implemented based on the type of roof being constructed and work being performed. The roof area to be accessed shall be evaluated for its structural integrity including weight-bearing capabilities for the projected loading.

a. Low Sloped Roofs:

(1) For work within 1.8 m (6 feet) of an edge, on low-slope roofs, personnel shall be protected from falling by use of personal fall arrest systems, guardrails, or safety nets.

(2) For work greater than 1.8 m (6 feet) from an edge, warning lines shall be erected and installed in accordance with 29 CFR 1926.500 and USACE EM 385-1-1.

b. Steep-Sloped Roofs: Work on steep-sloped roofs requires a personal fall arrest system, guardrails with toe-boards, or safety nets. This requirement also includes residential or housing type construction.

3.3.4 Existing Anchorage

Existing anchorages, to be used for attachment of personal fall arrest equipment, shall be certified (or re-certified) by a qualified person for fall protection in accordance with ANSI/ASSE Z359.1. Exiting horizontal lifeline anchorages shall be certified (or re-certified) by a registered professional engineer with experience in designing horizontal lifeline systems.

3.3.5 Horizontal Lifelines

Horizontal lifelines shall be designed, installed, certified and used under the supervision of a qualified person for fall protection as part of a complete fall arrest system which maintains a safety factor of 2 (29 CFR 1926.500).

3.3.6 Guardrails and Safety Nets

Guardrails and safety nets shall be designed, installed and used in accordance with EM 385-1-1 and 29 CFR 1926 Subpart M.

3.3.7 Rescue and Evacuation Procedures

When personal fall arrest systems are used, the contractor must ensure that the mishap victim can self-rescue or can be rescued promptly should a fall occur. A Rescue and Evacuation Plan shall be prepared by the contractor and include a detailed discussion of the following: methods of rescue; methods of self-rescue; equipment used; training requirement; specialized training for the rescuers; procedures for requesting rescue and medical assistance; and transportation routes to a medical facility. The Rescue and Evacuation Plan shall be included in the Activity Hazard Analysis (AHA) for the phase of work, in the Fall Protection and Prevention (FP&P) Plan, and the Accident Prevention Plan (APP).

3.4 SCAFFOLDING

3.4.1 Stilts

The use of stilts for gaining additional height in construction, renovation, repair or maintenance work is prohibited.

3.5 EQUIPMENT

3.5.1 Material Handling Equipment

a. Material handling equipment such as forklifts shall not be modified with work platform attachments for supporting employees unless specifically delineated in the manufacturer's printed operating instructions.

b. The use of hooks on equipment for lifting of material must be in accordance with manufacturer's printed instructions.

c. Operators of forklifts or power industrial trucks shall be licensed in accordance with OSHA.

3.5.2 Weight Handling Equipment

a. Cranes and derricks shall be equipped as specified in EM 385-1-1, section 16.

b. The Contractor shall notify the Contracting Officer 15 days in advance of any cranes entering the activity so that necessary quality assurance spot checks can be coordinated. Prior to cranes entering federal activities, a Crane Access Permit must be obtained from the Contracting Officer. A copy of the permitting process will be provided at the Preconstruction Conference. Contractor's operator shall remain with the crane during the spot check.

c. The Contractor shall comply with the crane manufacturer's specifications and limitations for erection and operation of cranes and hoists used in support of the work. Erection shall be performed under the supervision of a designated person (as defined in ASME B30.5). All testing shall be performed in accordance with the manufacturer's recommended procedures.

d. The Contractor shall comply with ASME B30.5 for mobile and locomotive cranes, ASME B30.22 for articulating boom cranes, ASME B30.3 for construction tower cranes, and ASME B30.8 for floating cranes and floating derricks.

e. Under no circumstance shall a Contractor make a lift at or above 90% of the cranes rated capacity in any configuration.

f. When operating in the vicinity of overhead transmission lines, operators and riggers shall be alert to this special hazard and shall follow the requirements of USACE EM 385-1-1 section 11 and ASME B30.5 or ASME B30.22 as applicable.

g. Crane suspended personnel work platforms (baskets) shall not be used unless the Contractor proves that using any other access to the work location would provide a greater hazard to the workers or is impossible. Personnel shall not be lifted with a line hoist or friction crane.

h. Portable fire extinguishers shall be inspected, maintained, and recharged as specified in NFPA 10, Standard for Portable Fire Extinguishers.

i. All employees shall be kept clear of loads about to be lifted and of suspended loads.

j. The Contractor shall use cribbing when performing lifts on outriggers.

k. The crane hook/block must be positioned directly over the load. Side loading of the crane is prohibited.

l. A physical barricade must be positioned to prevent personnel from entering the counterweight swing (tail swing) area of the crane.

m. Certification records which include the date of inspection, signature of the person performing the inspection, and the serial number or other identifier of the crane that was inspected shall always be available for review by Contracting Officer personnel.

n. Written reports listing the load test procedures used along with any repairs or alterations performed on the crane shall be available for review by Contracting Officer personnel.

o. Certify that all crane operators have been trained in proper use of all safety devices (e.g. anti-two block devices).

p. Take steps to ensure that wind speed does not contribute to loss of control of the load during lifting operations. Prior to conducting lifting operations the contractor shall set a maximum wind speed at which a crane can be safely operated based on the equipment being used,

the load being lifted, experience of operators and riggers, and hazards on the work site. This maximum wind speed determination shall be included as part of the activity hazard analysis plan for that operation.

3.5.3 Equipment and Mechanized Equipment

a. Proof of qualifications for operator shall be kept on the project site for review.

b. Manufacture specifications or owner's manual for the equipment shall be on-site and reviewed for additional safety precautions or requirements that are sometimes not identified by OSHA or USACE EM 385-1-1. Such additional safety precautions or requirements shall be incorporated into the AHAs.

c. A Machinery & Mechanized Equipment Certification Form shall be submitted for acceptance by the Contracting Officer prior to being placed into use. A copy of the certification form will be provided during the Pre-construction Conference.

3.6 EXCAVATIONS

The competent person shall perform soil classification in accordance with 29 CFR 1926.

3.6.1 Utility Locations

Prior to digging, the appropriate digging permit must be obtained. All underground utilities in the work area must be positively identified by a private utility locating service in addition to any station locating service and coordinated with the station utility department. Any markings made during the utility investigation must be maintained throughout the contract.

3.6.2 Utility Location Verification

The Contractor must physically verify underground utility locations by hand digging using wood or fiberglass handled tools when any adjacent construction work is expected to come within three feet of the underground system. Digging within 0.061 m (2 feet) of a known utility must not be performed by means of mechanical equipment; hand digging shall be used. If construction is parallel to an existing utility the utility shall be exposed by hand digging every 30.5 m (100 feet) if parallel within 1.5 m (5 feet) of the excavation.

3.6.3 Shoring Systems

Trench and shoring systems must be identified in the accepted safety plan and AHA. Manufacture tabulated data and specifications or registered engineer tabulated data for shoring or benching systems shall be readily available on-site for review. Job-made shoring or shielding shall have the registered professional engineer stamp, specifications, and tabulated data. Extreme care must be used when excavating near direct burial electric underground cables.

3.6.4 Trenching Machinery

Trenching machines with digging chain drives shall be operated only when

the spotters/laborers are in plain view of the operator. Operator and spotters/laborers shall be provided training on the hazards of the digging chain drives with emphasis on the distance that needs to be maintained when the digging chain is operating. Documentation of the training shall be kept on file at the project site.

3.7 UTILITIES WITHIN CONCRETE SLABS

Utilities located within concrete slabs or pier structures, bridges, and the like, are extremely difficult to identify due to the reinforcing steel used in the construction of these structures. Whenever contract work involves concrete chipping, saw cutting, or core drilling, the existing utility location must be coordinated with station utility departments in addition to a private locating service. Outages to isolate utility systems shall be used in circumstances where utilities are unable to be positively identified. The use of historical drawings does not alleviate the contractor from meeting this requirement.

3.8 ELECTRICAL

3.8.1 Conduct of Electrical Work

Underground electrical spaces must be certified safe for entry before entering to conduct work. Cables that will be cut must be positively identified and de-energized prior to performing each cut. Positive cable identification must be made prior to submitting any outage request for electrical systems. Arrangements are to be coordinated with the Contracting Officer and Station Utilities for identification. The Contracting Officer will not accept an outage request until the Contractor satisfactorily documents that the circuits have been clearly identified. Perform all high voltage cable cutting remotely using hydraulic cutting tool. When racking in or live switching of circuit breakers, no additional person other than the switch operator will be allowed in the space during the actual operation. Plan so that work near energized parts is minimized to the fullest extent possible. Use of electrical outages clear of any energized electrical sources is the preferred method. When working in energized substations, only qualified electrical workers shall be permitted to enter. When work requires Contractor to work near energized circuits as defined by the NFPA 70, high voltage personnel must use personal protective equipment that includes, as a minimum, electrical hard hat, safety shoes, insulating gloves with leather protective sleeves, fire retarding shirts, coveralls, face shields, and safety glasses. In addition, provide electrical arc flash protection for personnel as required by NFPA 70E. Insulating blankets, hearing protection, and switching suits may also be required, depending on the specific job and as delineated in the Contractor's AHA.

3.8.2 Portable Extension Cords

Portable extension cords shall be sized in accordance with manufacturer ratings for the tool to be powered and protected from damage. All damaged extension cords shall be immediately removed from service. Portable extension cords shall meet the requirements of NFPA 70.

3.9 WORK IN CONFINED SPACES

The Contractor shall comply with the requirements in Section 06.I of USACE EM 385-1-1, OSHA 29 CFR 1910.146 and OSHA 29 CFR 1926.21(b)(6). Any potential for a hazard in the confined space requires a permit system to be

used.

a. Entry Procedures. Prohibit entry into a confined space by personnel for any purpose, including hot work, until the qualified person has conducted appropriate tests to ensure the confined or enclosed space is safe for the work intended and that all potential hazards are controlled or eliminated and documented. (See Section 06.I.06 of USACE EM 385-1-1 for entry procedures.) All hazards pertaining to the space shall be reviewed with each employee during review of the AHA.

b. Forced air ventilation is required for all confined space entry operations and the minimum air exchange requirements must be maintained to ensure exposure to any hazardous atmosphere is kept below its' action level.

c. Sewer wet wells require continuous atmosphere monitoring with audible alarm for toxic gas detection.

-- End of Section --

SECTION 01 45 00.00 20

CONSTRUCTION QUALITY CONTROL
02/10

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2003) Safety -- Safety and Health Requirements

1.2 SUBMITTALS

The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Construction Quality Control (QC) Plan

Submit a Construction QC Plan within 20 calendar days after receipt of Notice of Award.

The QC Plan shall include a preliminary submittal of the list of definable features of work that shall cover the first 90 days of construction.

1.3 INFORMATION FOR THE CONTRACTING OFFICER

At the Preconstruction Conference, the Contractor can obtain a single copy set of the current report forms from the Contracting Officer. The report forms will consist of the Contractor Production Report, Contractor Production Report (Continuation Sheet), Contractor Quality Control Report, Contractor Quality Control Report (Continuation Sheet), Preparatory Phase Checklist, Initial Phase Checklist, Rework Items List, and Testing Plan and Log, Other reports referenced below may be in formats customarily used by the Contractor, Testing laboratories, etc. and will contain the information required by this specification.

Deliver the following to the Contracting Officer during Construction:

a. Combined Contractor Production Report/Contractor Quality Control Report; original and 1 copy by 10:00AM the next working day after each day that work is performed.

b. Preparatory Phase Checklist: Original attached to the original Contractor Quality Control Report and 1 copy attached to each copy.

c. Initial Phase Checklist: Original attached to the original Contractor Quality Control Report and 1 copy attached to each copy.

d. Field Test Reports: 2 copies, with 2 working days after the test is performed, attached to the Contractor Quality Control Report.

e. Monthly Summary Report of Tests: 2 copies attached to the Contractor Quality Control Report.

f Testing Plan and Log: 2 copies at the end of each month.

g. Rework Items List: 2 copies, by the last working day of the month.

h. CQC Meeting Minutes: 2 copies, within 2 working days after the meeting.

i. QC Certifications: As required by the paragraph entitled "QC Certifications."

1.4 QC PROGRAM REQUIREMENTS

Establish and maintain a QC program as described in this section. This QC program is a key element in meeting the objectives of NAVFAC Commissioning. The QC program consists of a QC Organization, QC Plan, QC Plan Meeting(s), a Coordination and Mutual Understanding Meeting, QC meetings, three phases of control, submittal review and approval, testing, completion inspections, and QC certifications and documentation necessary to provide materials, equipment, workmanship, fabrication, construction and operations which comply with the requirements of this Contract. The QC program shall cover on-site and off-site work and shall be keyed to the work sequence. No construction work or testing may be performed unless the QC Manager is on the work site. The QC Manager shall report to an officer of the firm and shall not be subordinate to the Project Superintendent or the Project Manager. The QC Manager, Project Superintendent and Project Manager must work together effectively. Although the QC Manager is the primary individual responsible for quality control, all individuals will be held responsible for the quality of work on the job.

1.4.1 Acceptance of the Construction Quality Control (QC) Plan

Acceptance of the QC Plan is required prior to the start of construction. The Contracting Officer reserves the right to require changes in the QC Plan and operations as necessary, including removal of personnel, to ensure the specified quality of work. The Contracting Officer reserves the right to interview any member of the QC organization at any time in order to verify the submitted qualifications. All QC organization personnel shall be subject to acceptance by the Contracting Officer. The Contracting Officer may require the removal of any individual for non-compliance with quality requirements specified in the Contract.

1.4.2 Preliminary Construction Work Authorized Prior to Acceptance

The only construction work that is authorized to proceed prior to the acceptance of the QC Plan is mobilization of storage and office trailers, temporary utilities, and surveying.

1.4.2.1 Approval

Approval of the QC Plan is required prior to the start of construction. The contracting Officer reserves the right to require changes in the QC Plan and operations as necessary, including removal of personnel, to ensure

the specified quality of work. The Contacting Officer reserves the right to interview any member of the QC organization at any time in order to verify the submitted qualifications. All QC organization personnel shall be subject to acceptance by the Contracting Officer. The Contracting Officer may require the removal of any individual for non-compliance with quality requirements specified in the contract.

1.4.3 Notification of Changes

Notify the Contracting Officer, in writing, of any proposed changes in the QC Plan or changes to the QC organization personnel, a minimum of 7 work days prior to a proposed change. Proposed changes shall be subject to acceptance by the Contracting Officer.

1.5 QC ORGANIZATION

1.5.1 QC Manager

1.5.1.1 Duties

Provide a QC Manager at the work site to implement and manage the QC program. In addition to implementing and managing the QC program, the QC Manager may perform the duties of Project Superintendent. The QC Manager shall be designated as the safety competent person as defined by EM 385-1-1. The QC Manager is required to attend the partnering meetings, QC Plan Meetings, Coordination and Mutual Understanding Meeting, conduct the QC meetings, perform the three phases of control , perform submittal review and approval, ensure testing is performed and provide QC certifications and documentation required in this Contract. The QC Manager is responsible for managing and coordinating the three phases of control and documentation performed by testing laboratory personnel and any other inspection and testing personnel required by this Contract. The QC Manager is the manager of all QC activities.

1.5.1.2 Qualifications

An individual with a minimum of 10 years combined experience in the following positions: Project Superintendent, QC Manager, Project Manager, Project Engineer or Construction Manager on similar size and type construction contracts which included the major trades that are part of this Contract. The individual shall have at least two years experience as a QC Manager. The individual must be familiar with the requirements of EM 385-1-1, and have experience in the areas of hazard identification, safety compliance, and sustainability or a graduate of a four year accredited college or university program in one of the following disciplines: Engineering, Architecture, Construction Management, Engineering Technology, Building Construction, or Building Science, with a minimum of 5 years experience as a Project Superintendent, QC Manager, Project Manager, Project Engineer or Construction Manager on similar size and type construction contracts which included the major trades that are part of this Contract. The individual shall have at least two years experience as a QC Manager. The individual must be familiar with the requirements of EM 385-1-1, and have experience in the areas of hazard identification, safety compliance, and sustainability.

1.5.2 Construction Quality Management Training

In addition to the above experience and education requirements, the QC Manager shall have completed the course entitled "Construction Quality

Management (CQM) for Contractors." If the QC Manager does not have a current certification, they shall obtain the CQM for Contractors course certification within 90 days of award. This course is periodically offered by the Naval Facilities Engineering Command and the Army Corps of Engineers. Contact the Contracting Officer for information on the next scheduled class.

1.5.3 Alternate QC Manager Duties and Qualifications

Designate an alternate for the QC Manager at the work site to serve in the event of the designated QC Manager's absence. The period of absence may not exceed two weeks at one time, and not more than 30 workdays during a calendar year. The qualification requirements for the Alternate QC Manager shall be the same as for the QC Manager.

1.6 QUALITY CONTROL (QC) PLAN

1.6.1 Construction Quality Control (QC) Plan

1.6.1.1 Requirements

Provide, for acceptance by the Contracting Officer, a Construction QC Plan submitted in a three-ring binder that includes a table of contents, with major sections identified with tabs, with pages numbered sequentially that covers both on-site and off-site work and includes the following:,

I. QC ORGANIZATION: A chart showing the QC organizational structure.

II. NAMES AND QUALIFICATIONS: Names and qualifications, in resume format, for each person in the QC organization. Include the CQM for Contractors course certifications for the QC Manager and Alternate QC Manager as required by the paragraphs entitled "Construction Quality Management Training" and "Alternate QC Manager Duties and Qualifications".

III. DUTIES, RESPONSIBILITY AND AUTHORITY OF QC PERSONNEL: Duties, responsibilities, and authorities of each person in the QC organization.

IV. OUTSIDE ORGANIZATIONS: A listing of outside organizations, such as architectural and consulting engineering firms, that will be employed by the Contractor and a description of the services these firms will provide.

V. APPOINTMENT LETTERS: Letters signed by an officer of the firm appointing the QC Manager and Alternate QC Manager and stating that they are responsible for implementing and managing the QC program as described in this Contract. Include in this letter the responsibility of the QC Manager and Alternate QC Manager to implement and manage the three phases of control, and their authority to stop work which is not in compliance with the Contract. The QC Manager shall issue letters of direction to all other QC Specialists outlining their duties, authorities, and responsibilities. Copies of the letters shall be included in the QC Plan.

VI. SUBMITTAL PROCEDURES AND INITIAL SUBMITTAL REGISTER: Procedures for reviewing, approving, and managing submittals. Provide the name(s) of the person(s) in the QC organization authorized to review and certify submittals prior to approval. Provide the initial submittal of the Submittal Register as specified in section 01 33 00 SUBMITTAL

PROCEDURES.

VII. TESTING LABORATORY INFORMATION: Testing laboratory information required by the paragraphs entitled "Accreditation Requirements", as applicable.

VIII. TESTING PLAN AND LOG: A Testing Plan and Log that includes the tests required, referenced by the specification paragraph number requiring the test, the frequency, and the person responsible for each test.

IX. PROCEDURES TO COMPLETE REWORK ITEMS: Procedures to identify, record, track, and complete rework items. Use Government forms to record and track rework items.

X. DOCUMENTATION PROCEDURES: Use Government form.

XI. LIST OF DEFINABLE FEATURES: A Definable Feature of Work (DFOW) is a task that is separate and distinct from other tasks and has control requirements and work crews unique to that task, has the same control requirements and work crews.. A DFOW is identified by different trades or disciplines and is an item or activity on the construction schedule. The list of DFOWs shall include, but not be limited to, all critical path activities on the NAS. Include all activities for which this specification requires. Each design development stage and submittal package shall have separate DFOWs in the Network Analysis Schedule.

XII. PROCEDURES FOR PERFORMING THE THREE PHASES OF CONTROL: Identify procedures you will use to ensure the three phases of control are used to manage the quality on this project. For each DFOW, a Preparatory and Initial phase checklist will be filled out during the Preparatory and Initial phase meetings. The Preparatory and Initial Phases and meetings shall be conducted with a view towards obtaining quality construction by planning ahead and identifying potential problems for each DFOW.

XIII. PERSONNEL MATRIX: A personnel matrix showing for each section of the specification who will review and approve submittals, who will perform and document the three phases of control, and who will perform and document the testing.

XIV. PROCEDURES FOR COMPLETION INSPECTION: Procedures for identifying and documenting the completion inspection process. Include in these procedures the responsible party for punch out inspection, pre-final inspection, and final acceptance inspection.

XV. ORGANIZATION AND PERSONNEL CERTIFICATIONS LOG: Procedures for coordinating, tracking and documenting all certifications on subcontractors, testing laboratories, suppliers, personnel, etc. QC Manager will ensure that certifications are current, appropriate for the work being performed, and will not lapse during any period of the contract that the work is being performed.

1.7 QC PLAN MEETINGS

Prior to submission of the QC Plan, the QC Manager will meet with the Contracting Officer to discuss the QC Plan requirements of this Contract. The purpose of this meeting is to develop a mutual understanding of the QC

Plan requirements prior to plan development and submission and to agree on the Contractor's list of DFOWs.

1.8 COORDINATION AND MUTUAL UNDERSTANDING MEETING

After submission of the QC Plan, and prior to the start of construction, the QC Manager will meet with the Contracting Officer to present the QC program required by this Contract. When a new QC Manager is appointed, the coordination and mutual understanding meeting shall be repeated.

1.8.1 Purpose

The purpose of this meeting is to develop a mutual understanding of the QC details, including documentation, administration for on-site and off-site work, , coordination of activities to be performed, and the coordination of the Contractor's management, production, and QC personnel. At the meeting, the Contractor will be required to explain in detail how three phases of control will be implemented for each DFOW, as well as how each DFOW will be affected by each management plan or requirement as listed below:

1.8.2 Coordination of Activities

Activities included in various sections shall be coordinated to assure efficient and orderly installation of each component. Coordinate operations included under different sections that are dependent on each other for proper installation and operation. Schedule construction operations with consideration for indoor air quality as specified in the IAQ Management Plan. Coordinate prefunctional tests and startup testing with Cx.

1.8.3 Attendees

As a minimum, the Contractor's personnel required to attend shall include an officer of the firm, the Project Manager, Project Superintendent, QC Manager, Alternate QC Manager, and subcontractor representatives. Each subcontractor who will be assigned QC responsibilities shall have a principal of the firm at the meeting. Minutes of the meeting will be prepared by the QC Manager and signed by the Contractor and the Contracting Officer. The Contractor shall provide a copy of the signed minutes to all attendees.

1.9 QC MEETINGS

After the start of construction, the QC Manager shall conduct weekly QC meetings at the work site with the Project Superintendent and the foremen who are performing the work of the DFOWs. The QC Manager shall prepare the minutes of the meeting and provide a copy to the Contracting Officer within two working days after the meeting. The Contracting Officer may attend these meetings. As a minimum, the following shall be accomplished at each meeting:

a. Review the minutes of the previous meeting;

b. Review the schedule and the status of work and rework;

c. Review the status of submittals;

d. Review the work to be accomplished in the next two weeks and documentation required;

e. Resolve QC and production problems (RFI, etc.);

f. Address items that may require revising the QC Plan;

g. Review Accident Prevention Plan (APP);

h. Review environmental requirements and procedures;

i. Review Waste Management Plan;

1.10 DESIGN REVIEW AND DOCUMENTATION

1.11 THREE PHASES OF CONTROL

The Three Phases of Control shall adequately cover both on-site and off-site work and shall include the following for each DFOW.

1.11.1 Preparatory Phase

Notify the Contracting Officer at least two work days in advance of each preparatory phase meeting. The meeting shall be conducted by the QC Manager and attended by the Project Superintendent, and the foreman responsible for the DFOW. When the DFOW will be accomplished by a subcontractor, that subcontractor's foreman shall attend the preparatory phase meeting. Document the results of the preparatory phase actions in the daily Contractor Quality Control Report and in the Preparatory Phase Checklist. Perform the following prior to beginning work on each DFOW:

a. Review each paragraph of the applicable specification sections;

b. Review the Contract drawings;

c. Verify that field measurements are as indicated on construction and/or shop drawings before confirming product orders, in order to minimize waste due to excessive materials;

d. Verify that appropriate shop drawings and submittals for materials and equipment have been submitted and approved. Verify receipt of approved factory test results, when required;

e. Review the testing plan and ensure that provisions have been made to provide the required QC testing;

f. Examine the work area to ensure that the required preliminary work has been completed;

g. Coordinate the schedule of product delivery to designated prepared areas in order to minimize site storage time and potential damage to stored materials;

h. Arrange for the return of shipping/packaging materials, such as wood pallets, where economically feasible;

i. Examine the required materials, equipment and sample work to ensure that they are on hand and conform to the approved shop drawings and submitted data;

j. Discuss construction methods, construction tolerances, workmanship

standards, and the approach that will be used to provide quality construction by planning ahead and identifying potential problems for each DFOW;

k. Review the APP and appropriate Activity Hazard Analysis (AHA) to ensure that applicable safety requirements are met, and that required Material Safety Data Sheets (MSDS) are submitted; and

1.11.2 Initial Phase

Notify the Contracting Officer at least two work days in advance of each initial phase. When construction crews are ready to start work on a DFOW, conduct the initial phase with the Project Superintendent, and the foreman responsible for that DFOW. Observe the initial segment of the DFOW to ensure that the work complies with Contract requirements. Document the results of the initial phase in the daily CQC Report and in the Initial Phase Checklist. Repeat the initial phase for each new crew to work on-site, or when acceptable levels of specified quality are not being met. Perform the following for each DFOW:

a. Establish the quality of workmanship required;

b. Resolve conflicts;

c. Ensure that testing is performed by the approved laboratory;

d. Check work procedures for compliance with the APP and the appropriate AHA to ensure that applicable safety requirements are met; and

1.11.3 Follow-Up Phase

Perform the following for on-going work daily, or more frequently as necessary, until the completion of each DFOW and document in the daily CQC Report:

a. Ensure the work is in compliance with Contract requirements;

b. Maintain the quality of workmanship required;

c. Ensure that testing is performed by the approved laboratory;

d. Ensure that rework items are being corrected;

e. Perform safety inspections; and

1.11.4 Additional Preparatory and Initial Phases

Additional preparatory and initial phases shall be conducted on the same DFOW if the quality of on-going work is unacceptable, if there are changes in the applicable QC organization, if there are changes in the on-site production supervision or work crew, if work on a DFOW is resumed after substantial period of inactivity, or if other problems develop.

1.11.5 Notification of Three Phases of Control for Off-Site Work

Notify the Contracting Officer at least two weeks prior to the start of the preparatory and initial phases.

1.12 SUBMITTAL REVIEW AND APPROVAL

Procedures for submission, review and approval of submittals are described in Section 01 33 00 SUBMITTAL PROCEDURES.

1.13 TESTING

Except as stated otherwise in the specification sections, perform sampling and testing required under this Contract.

1.13.1 Accreditation Requirements

Construction materials testing laboratories must be accredited by a laboratory accreditation authority and will be required to submit a copy of the Certificate of Accreditation and Scope of Accreditation. The laboratory's scope of accreditation must include the appropriate ASTM standards (E 329, C 1077, D 3666, D 3740, A 880, E 543) listed in the technical sections of the specifications. Laboratories engaged in Hazardous Materials Testing shall meet the requirements of OSHA and EPA. The policy applies to the specific laboratory performing the actual testing, not just the Corporate Office.

1.13.2 Laboratory Accreditation Authorities

Laboratory Accreditation Authorities include the National Voluntary Laboratory Accreditation Program (NVLAP) administered by the National Institute of Standards and Technology at http://ts.nist.gov/ts/htdocs/210/214/214.htm , the American Association of State Highway and Transportation Officials (AASHTO) program at http://www.transportation.org/aashto/home.nsf/frontpage , International Accreditation Services, Inc. (IAS) at http://www.iasonline.org, U. S. Army Corps of Engineers Materials Testing Center (MTC)at http://www.wes.army.mil/SL/MTC/, the American Association for Laboratory Accreditation (A2LA) program at http://www.a2la.org/, the Washington Association of Building Officials (WABO) at http://www.wabo.org/ (Approval authority for WABO is limited to projects within Washington State), and the Washington Area Council of Engineering Laboratories (WACEL) at http://www.wacel.org/labaccred.html (Approval authority by WACEL is limited to projects within Facilities Engineering Command (FEC) Washington geographical area).

1.13.3 Capability Check

The Contracting Officer retains the right to check laboratory equipment in the proposed laboratory and the laboratory technician's testing procedures, techniques, and other items pertinent to testing, for compliance with the standards set forth in this Contract.

1.13.4 Test Results

Cite applicable Contract requirements, tests or analytical procedures used. Provide actual results and include a statement that the item tested or analyzed conforms or fails to conform to specified requirements. If the item fails to conform, notify the Contracting Officer immediately. Conspicuously stamp the cover sheet for each report in large red letters "CONFORMS" or "DOES NOT CONFORM" to the specification requirements, whichever is applicable. Test results shall be signed by a testing laboratory representative authorized to sign certified test reports. Furnish the signed reports, certifications, and other documentation to the

Contracting Officer via the QC Manager. Furnish a summary report of field tests at the end of each month, per the paragraph entitled "INFORMATION FOR THE CONTRACTING OFFICER".

1.13.5 Test Reports and Monthly Summary Report of Tests

The QC Manager shall furnish the signed reports, certifications, and a summary report of field tests at the end of each month to the Contracting Officer. Attach a copy of the summary report to the last daily Contractor Quality Control Report of each month. A copy of the signed test reports and certifications shall be provided to the OMSI preparer for inclusion into the OMSI documentation.

1.14 QC CERTIFICATIONS

1.14.1 CQC Report Certification

Each CQC Report shall contain the following statement: "On behalf of the Contractor, I certify that this report is complete and correct and equipment and material used and work performed during this reporting period is in compliance with the contract drawings and specifications to the best of my knowledge, except as noted in this report."

1.14.2 Invoice Certification

Furnish a certificate to the Contracting Officer with each payment request, signed by the QC Manager, attesting that as-built drawings are current, coordinated and attesting that the work for which payment is requested, including stored material, is in compliance with Contract requirements.

1.14.3 Completion Certification

Upon completion of work under this Contract, the QC Manager shall furnish a certificate to the Contracting Officer attesting that "the work has been completed, inspected, tested and is in compliance with the Contract."

1.15 COMPLETION INSPECTIONS

1.15.1 Punch-Out Inspection

Near the completion of all work or any increment thereof, established by a completion time stated in the Contract Clause entitled "Commencement, Prosecution, and Completion of Work," or stated elsewhere in the specifications, the QC Manager and the CA shall conduct an inspection of the work and develop a "punch list" of items which do not conform to the approved drawings, specifications and Contract. Include in the punch list any remaining items on the "Rework Items List", which were not corrected prior to the Punch-Out Inspection. The punch list shall include the estimated date by which the deficiencies will be corrected. A copy of the punch list shall be provided to the Contracting Officer. The QC Manager, or staff, shall make follow-on inspections to ascertain that all deficiencies have been corrected. Once this is accomplished, the Contractor shall notify the Government that the facility is ready for the Government "Pre-Final Inspection".

1.15.2 Pre-Final Inspection

The Government will perform this inspection to verify that the facility is complete and ready to be occupied. A Government "Pre-Final Punch List" may

be developed as a result of this inspection. The QC Manager shall ensure that all items on this list are corrected prior to notifying the Government that a "Final" inspection with the Client can be scheduled. Any items noted on the "Pre-Final" inspection shall be corrected in a timely manner and shall be accomplished before the contract completion date for the work,or any particular increment thereof, if the project is divided into increments by separate completion dates.

1.15.3 Final Acceptance Inspection

The Contractor shall notify the Contracting Officer at least 14 calendar days prior to the date a final acceptance inspection can be held. The notice shall state that all items previously identified on the pre-final punch list will be corrected and acceptable, along with any other unfinished Contract work, by the date of the final acceptance inspection. The Contractor shall be represented by the QC Manager, the Project Superintendent, the CA, and others deemed necessary. Attendees for the Government will include the Contracting Officer, other ROICC personnel, and personnel representing the Client. Failure of the Contractor to have all contract work acceptably complete for this inspection will be cause for the Contracting Officer to bill the Contractor for the Government's additional inspection cost in accordance with the Contract Clause entitled "Inspection of Construction."

1.16 DOCUMENTATION

Maintain current and complete records of on-site and off-site QC program operations and activities.

1.16.1 Construction Documentation

Reports are required for each day that work is performed and shall accompany the submission of the Contractor Quality Control Report prepared for the same day. Maintain current and complete records of on-site and off-site QC program operations and activities. The forms identified under the paragraph "INFORMATION FOR THE CONTRACTING OFFICER" shall be used. Reports are required for each day work is performed. Account for each calendar day throughout the life of the Contract. Every space on the forms must be filled in. Use N/A if nothing can be reported in one of the spaces. The Project Superintendent and the QC Manager must prepare and sign the Contractor Production and CQC Reports, respectively. The reporting of work shall be identified by terminology consistent with the construction schedule. In the "remarks" sections of the reports, enter pertinent information including directions received, problems encountered during construction, work progress and delays, conflicts or errors in the drawings or specifications, field changes, safety hazards encountered, instructions given and corrective actions taken, delays encountered and a record of visitors to the work site, quality control problem areas, deviations from the QC Plan, construction deficiencies encountered, meetings held. For each entry in the report(s), identify the Schedule Activity No. that is associated with the entered remark.

1.16.2 Quality Control Validation

Establish and maintain the following in a series of three ring binders. Binders shall be divided and tabbed as shown below. These binders shall be readily available to the Contracting Officer during all business hours.

a. All completed Preparatory and Initial Phase Checklists, arranged by

specification section.

b. All milestone inspections, arranged by Activity Number.

c. An up-to-date copy of the Testing Plan and Log with supporting field test reports, arranged by specification section.

d. Copies of all contract modifications, arranged in numerical order. Also include documentation that modified work was accomplished.

e. An up-to-date copy of the Rework Items List.

f. Maintain up-to-date copies of all punch lists issued by the QC staff to the Contractor and Sub-Contractors and all punch lists issued by the Government.

1.16.3 Testing Plan and Log

As tests are performed, the QC Manager shall record on the "Testing Plan and Log" the date the test was performed and the date the test results were forwarded to the Contracting Officer. Attach a copy of the updated "Testing Plan and Log" to the last daily CQC Report of each month.

1.16.4 Rework Items List

The QC Manager shall maintain a list of work that does not comply with the Contract, identifying what items need to be reworked, the date the item was originally discovered, the date the item will be corrected by, and the date the item was corrected. There is no requirement to report a rework item that is corrected the same day it is discovered. Attach a copy of the "Rework Items List" to the last daily CQC Report of each month. The Contractor shall be responsible for including those items identified by the Contracting Officer.

1.16.5 As-Built Drawings

The QC Manager is required to ensure the as-built drawings, required by Section 01 78 00 CLOSEOUT PROCEDURES are kept current on a daily basis and marked to show deviations which have been made from the Contract drawings. Ensure each deviation has been identified with the appropriate modifying documentation (e.g. PC No., Modification No., Request for Information No., etc.). The QC Manager shall initial each revision. Upon completion of work, the QC Manager shall furnish a certificate attesting to the accuracy of the as-built drawings prior to submission to the Contracting Officer.

1.17 NOTIFICATION ON NON-COMPLIANCE

The Contracting Officer will notify the Contractor of any detected non-compliance with the Contract. The Contractor shall take immediate corrective action after receipt of such notice. Such notice, when delivered to the Contractor at the work site, shall be deemed sufficient for the purpose of notification. If the Contractor fails or refuses to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders shall be made the subject of claim for extension of time for excess costs or damages by the Contractor.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.1 PREPARATION

Designate receiving/storage areas for incoming material to be delivered according to installation schedule and to be placed convenient to work area in order to minimize waste due to excessive materials handling and misapplication. Store and handle materials in a manner as to prevent loss from weather and other damage. Keep materials, products, and accessories covered and off the ground, and store in a dry, secure area. Prevent contact with material that may cause corrosion, discoloration, or staining. Protect all materials and installations from damage by the activities of other trades.

-- End of Section --

SECTION 01 50 00

TEMPORARY CONSTRUCTION FACILITIES AND CONTROLS
10/11

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 241	(2004) Safeguarding Construction,Alteration, and Demolition Operations
NFPA 70	(2011; Errata 2 2012) National Electrical Code

U.S. FEDERAL HIGHWAY ADMINISTRATION (FHWA)

FHWA SA-89-006	(2009) Manual on Uniform Traffic Control Devices for Streets and Highways

1.2 SUBMITTALS

The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Traffic control plan

SD-06 Test Reports

SD-07 Certificates

1.3 Contractor Utilities

The Contractor shall provide his own utilities.

1.4 Utilities at Special Locations

Reasonable amounts of utilities will be made available to the Contractor at the prevailing Government rates. These rates may be obtained upon application to the Commanding Officer, by way of the Contracting Officer. A $300.00 deposit will be required before connecting electricity. The Contractor will be responsible for making connections, providing transformers and meters, (THE CONTRACTOR MUST CERTIFY THAT ALL TRANSFORMERS INSTALLED FOR TEMPORARY POWER DURING THIS CONTRACT ARE PCB FREE), and making disconnections; and for providing backflow preventer devices on connections to domestic water lines. Under no circumstances will taps to base fire hydrants be allowed for obtaining domestic water. Neither potable water nor sanitary facilities will be available at the main

Contractor laydown area at Marine Corps Air Station (MCAS), Cherry Point, NC.

1.5 WEATHER PROTECTION

Take necessary precautions to ensure that roof openings and other critical openings in the building are monitored carefully. Take immediate actions required to seal off such openings when rain or other detrimental weather is imminent, and at the end of each workday. Ensure that the openings are completely sealed off to protect materials and equipment in the building from damage.

1.5.1 Building and Site Storm Protection

When a warning of gale force winds is issued, take precautions to minimize danger to persons, and protect the work and nearby Government property. Precautions shall include, but are not limited to, closing openings; removing loose materials, tools and equipment from exposed locations; and removing or securing scaffolding and other temporary work. Close openings in the work when storms of lesser intensity pose a threat to the work or any nearby Government property.

1.5.1.1 Hurricane Condition of Readiness

Unless directed otherwise, comply with:

a. Condition FOUR (Sustained winds of 50 knots or greater expected within 72 hours): Normal daily jobsite cleanup and good housekeeping practices. Collect and store in piles or containers scrap lumber, waste material, and rubbish for removal and disposal at the close of each work day. Maintain the construction site including storage areas, free of accumulation of debris. Stack form lumber in neat piles less than 4 feet high. Remove all debris, trash, or objects that could become missile hazards. Contact Contracting Officer for Condition of Readiness (COR) updates and completion of required actions.

b. Condition THREE (Sustained winds of 50 knots or greater expected within 48 hours): Maintain "Condition FOUR" requirements and commence securing operations necessary for "Condition ONE" which cannot be completed within 18 hours. Cease all routine activities which might interfere with securing operations. Commence securing and stow all gear and portable equipment. Make preparations for securing buildings. Review requirements pertaining to "Condition TWO" and continue action as necessary to attain "Condition THREE" readiness. Contact Contracting Officer for weather and COR updates and completion of required actions.

c. Condition TWO (Sustained winds of 50 knots or greater expected within 24 hours): Curtail or cease routine activities until securing operation is complete. Reinforce or remove form work and scaffolding. Secure machinery, tools, equipment, materials, or remove from the jobsite. Expend every effort to clear all missile hazards and loose equipment from general base areas. Contact Contracting Officer for weather and Condition of Readiness (COR) updates and completion of required actions.

d. Condition ONE. (Sustained winds of 50 knots or greater expected within 12 hours): Secure the jobsite, and leave Government

premises.

1.6 Interruption of Vehicular Traffic

If during the performance of work, it becomes necessary to modify vehicular traffic patterns at any locations, notify the Contracting Officer at least 15 calendar days prior to the proposed modification date, and provide a Traffic Control Plan detailing the proposed controls to traffic movement for approval. The plan shall be in accordance with State and local regulations and the FHWA SA-89-006, Part VI. Make all notifications and obtain any permits required for modification to traffic movements outside Station's jurisdiction. Provide cones, signs, barricades, lights, or other traffic control devices and personnel required to control traffic. Do not use foil-backed material for temporary pavement marking because of its potential to conduct electricity during accidents involving downed power lines.

1.7 TEMPORARY SANITARY FACILITIES

Provide adequate sanitary conveniences of a type approved for the use of persons employed on the work, properly secluded from public observation, and maintained in such a manner as required and approved by the Contracting Officer. Maintain these conveniences at all times without nuisance. Upon completion of the work, remove the conveniences from the premises, leaving the premises clean and free from nuisance. Dispose of sewage through connection to a municipal, district sanitary sewage system. Where such systems are not available, use chemical toilets or comparably effective units, and periodically empty wastes into a municipal, district sanitary sewage system, or remove waste to a commercial facility. Obtain approval from the system owner prior to discharge into any municipal, district, or commercial sanitary sewer system. Any penalties and / or fines associated with improper discharge shall be the responsibility of the Contractor.

NOTE - FOR FRC, EAST JOBS ONLY

If required, a laydown site will be provided within five miles of the construction site and will be identified at the preconstruction conference. If a material storage trailer is used at the laydown site, it shall be anchored to resist high winds and must meet applicable state or local standards for anchoring mobile trailers. All trailers and storage buildings shall be suitably painted, kept in a good state of repair, and clearly identified with the Contractor's name and telephone number. Space for an office trailer will not be provided at the construction site. A staging area will be provided immediately adjacent to the construction site. The staging area will be the minimum amount of area necessary for maneuverability of equipment and temporary placement of materials intended for immediate incorporation into the work. All laydown sites, staging area, and construction sites shall be kept free of debris and trash, fences maintained, and all vegetation trimmed.

1.8 Maintenance of Temporary Facilities

Suitably paint and maintain the temporary facilities. Failure to do so will be sufficient reason to require their removal.

PART 2 PRODUCTS

PART 3 EXECUTION

3.1 TEMPORARY PHYSICAL CONTROLS

3.1.1 Access Controls

3.1.1.1 Temporary Barricades

Contractor shall provide for barricading around all work areas to prevent public access.

3.1.1.2 Fencing

Fencing shall be provided along the construction site for each road segment and isolated area of work to prevent access by unauthorized people (special emphasis shall be placed on preventing access by children). Fencing shall be a four feet high orange plastic grid supported at intervals sufficient to resist at least 250 pounds of force applied against the fence. Fencing shall be moved as work progresses. Place fencing on the side opposite the street side of the walkway to allow adequate work space for the Contractor's activities.

3.1.1.3 Signs

Place warning signs at the construction area perimeter designating the presence of construction hazards requiring unauthorized persons to keep out. Signs must be placed on all sides of the project, with at least one sign every 300 feet. All points of entry shall have signs designating the construction site as a hard hat area.

3.1.1.4 Traffic Work

All work around/involving roadways, to include roadway excavations and utility crossings, will be conducted in accordance with Manual of Traffic Control Devices. Contractors shall provide and ensure appropriate road closure and detour signs are established as necessary for motor traffic management. All road closures shall be coordinated with the Contracting Officer in advance. Self-illuminated (lighted) barricades shall be provided during hours of darkness. Brightly-colored (orange) vests are required for all personnel working in roadways. Road closures shall require a road closure plan showing the location of signage.

3.2 TEMPORARY WIRING

Provide temporary wiring in accordance with NFPA 241 and NFPA 70, Article 305-6(b), Assured Equipment Grounding Conductor Program. Program shall include frequent inspection of all equipment and apparatus.

3.3 GRASS CUTTING

Cut grass (or annual weeds) within construction and storage sites to a maximum 4 inch height at least once a week during the growing season unless the grass area is not visible to the public. Trim the grass around fences at time of grass cutting. Maintain grass or weeds on stockpiled earth as described above.

-- End of Section --

management. All road closures shall be coordinated with the Contracting Officer in advance. Self-illuminated (lighted) barricades shall be provided during hours of darkness. Brightly-colored (orange) vests are required for all personnel working in roadways. Road closures shall require a road closure plan showing the location of signage.

3.2 TEMPORARY WIRING

Provide temporary wiring in accordance with NFPA 241 and NFPA 70, Article 305-6(b), Assured Equipment Grounding Conductor Program. Program shall include frequent inspection of all equipment and apparatus.

3.3 GRASS CUTTING

Cut grass (or annual weeds) within construction and storage sites to a maximum 4 inch height at least once a week during the growing season unless the grass area is not visible to the public. Trim the grass around fences at time of grass cutting. Maintain grass or weeds on stockpiled earth as described above.

-- End of Section --

SECTION 01 57 19.00 20

TEMPORARY ENVIRONMENTAL CONTROLS
02/10

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.120	Hazardous Waste Operations and Emergency Response
40 CFR 112	Oil Pollution Prevention
40 CFR 241	Guidelines for Disposal of Solid Waste
40 CFR 243	Guidelines for the Storage and Collection of Residential, Commercial, and Institutional Solid Waste
40 CFR 258	Subtitle D Landfill Requirements
40 CFR 261	Identification and Listing of Hazardous Waste
40 CFR 262	Standards Applicable to Generators of Hazardous Waste
40 CFR 263	Standards Applicable to Transporters of Hazardous Waste
40 CFR 264	Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities
40 CFR 265	Interim Status Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities
40 CFR 266	Standards for the Management of Specific Hazardous Wastes and Specific Types of Hazardous Waste Management Facilities
40 CFR 268	Land Disposal Restrictions
40 CFR 279	Standards for the Management of Used Oil
40 CFR 300	National Oil and Hazardous Substances Pollution Contingency Plan
40 CFR 355	Emergency Planning and Notification

40 CFR 372-SUBPART D	Specific Toxic Chemical Listings
49 CFR 173	Shippers - General Requirements for Shipments and Packagings
49 CFR 178	Specifications for Packagings

1.2 DEFINITIONS

1.2.1 Sediment

Soil and other debris that have eroded and have been transported by runoff water or wind.

1.2.2 Solid Waste

Garbage, refuse, debris, sludge, or other discharged material, including solid, liquid, semisolid, or contained gaseous materials resulting from domestic, industrial, commercial, mining, or agricultural operations. Types of solid waste typically generated at construction sites may include:

a. Green waste: The vegetative matter from landscaping, land clearing and grubbing, including, but not limited to, grass, bushes, scrubs, small trees and saplings, tree stumps and plant roots. Marketable trees, grasses and plants that are indicated to remain, be re-located, or be re-used are not included.

b. Surplus soil: Existing soil that is in excess of what is required for this work, including aggregates intended, but not used, for on-site mixing of concrete, mortars and paving. Contaminated soil meeting the definition of hazardous material or hazardous waste is not included.

c. Debris: Non-hazardous solid material generated during the construction, demolition, or renovation of a structure which exceeds 2.5 inch particle size that is: a manufactured object; plant or animal matter; or natural geologic material (e.g. cobbles and boulders), broken or removed concrete, masonry, and rock asphalt paving; ceramics; roofing paper and shingles. Inert materials may be reinforced with or contain ferrous wire, rods, accessories and weldments. A mixture of debris and other material such as soil or sludge is also subject to regulation as debris if the mixture is comprised primarily of debris by volume, based on visual inspection..

d. Wood: Dimension and non-dimension lumber, plywood, chipboard, hardboard. Treated and/or painted wood that meets the definition of lead contaminated or lead based contaminated paint is not included.

e. Scrap metal: Scrap and excess ferrous and non-ferrous metals such as reinforcing steel, structural shapes, pipe and wire that are recovered or collected and disposed of as scrap. Scrap metal meeting the definition of hazardous material or hazardous waste is not included.

f. Paint cans: Metal cans that are empty of paints, solvents, thinners and adhesives. If permitted by the paint can label, a

thin dry film may remain in the can.

g. Recyclables: Materials, equipment and assemblies such as doors, windows, door and window frames, plumbing fixtures, glazing and mirrors that are recovered and sold as recyclable. Metal meeting the definition of lead contaminated or lead based paint contaminated may be included as recyclable if sold to a scrap metal company. Paint cans may not be included as recyclable if sold to a scrap metal company.

h. Hazardous Waste: By definition, to be a hazardous waste a material must first meet the definition of a solid waste. Hazardous waste and hazardous debris are special cases of solid waste. They have additional regulatory controls and must be handled separately. They are thus defined separately in this document.

   Material not regulated as solid waste are: nuclear source or byproduct materials regulated under the Federal Atomic Energy Act of 1954 as amended; suspended or dissolved materials in domestic sewage effluent or irrigation return flows, or other regulated point source discharges; regulated air emissions; and fluids or wastes associated with natural gas or crude oil exploration or production.

1.2.3 Hazardous Debris

As defined in Solid Waste paragraph, debris that contains listed hazardous waste (either on the debris surface, or in its interstices, such as pore structure) per 40 CFR 261; or debris that exhibits a characteristic of hazardous waste per 40 CFR 261.

1.2.4 Chemical Wastes

This includes salts, acids, alkalizes, herbicides, pesticides, and organic chemicals.

1.2.5 Garbage

Refuse and scraps resulting from preparation, cooking, dispensing, and consumption of food.

1.2.6 Hazardous Waste (Including Universal Hazardous Waste)

Hazardous Wastes are defined by the Resource Conservation and Recovery Act (RCRA - Subtitle C) as wastes which first meet the definition of "solid" wastes and are then further defined in 40CFR Parts 261.21, 261.22, 261.23, 261.24, 261.31, 261.32, 261.33(e), and 261.33(f) with regard to their hazardous waste properties and / or characteristics (to include U.S. EPA's lists of Hazardous Wastes. These regulations cover a wide range of process and product generated wastes, and discarded (including materials intended to be discarded) or unusable materials in solid, liquid, and gaseous forms.

Universal (Hazardous) Wastes are a subset of Hazardous Waste, and are defined in 40CFR Part 273.2, 273.3. 273.4, and 273.5 and include batteries, pesticides, mercury containing equipment, and lamps.

Contractors must be intimately familiar with the above-detailed Hazardous Waste regulations to ensure compliance with section 1.4.1.

1.2.7 Hazardous Materials

Hazardous material is any material that:

a. Is regulated as a hazardous material per 49 CFR 173, or

b. Requires a Material Safety Data Sheet (MSDS) per 29 CFR 1910.120, or

c. During end use, treatment, handling, packaging, storage, transpiration, or disposal meets or has components that meet or have potential to meet the definition of a hazardous waste as defined by 40 CFR 261 Subparts A, B, C, or D.

Designation of a material by this definition, when separately regulated or controlled by other instructions or directives, does not eliminate the need for adherence to that hazard-specific guidance which takes precedence over this instruction for "control" purposes. Such material include ammunition, weapons, explosive actuated devices, propellants, pyrotechnics, chemical and biological warfare materials, medical and pharmaceutical supplies, medical waste and infectious materials, bulk fuels, radioactive materials, and other materials such as asbestos, mercury, and polychlorinated biphenyls (PCBs). Nonetheless, the exposure may occur incident to manufacture, storage, use and demilitarization of these items.

1.2.8 Waste Hazardous Material and Substances

Waste hazardous materials and substances are those materials which do not meet any of the regulatory definitions of either Hazardous Waste or Universal (Hazardous) Waste, but which still may pose a threat to human health or the environment or cause significant legal liabilities under CERCLA if not properly managed. In general, such materials may be defined as those which pose a threat to human health and / or the environment due to their quantity, concentration, or their physical, chemical, or infectious characteristics and which have been so designated by federal, state, or local agencies.

1.2.9 Used Oil and Oily Wastes

Used Oil is defined in 40CFR Part 279 to include a wide variety of oils and fuels and how they must be properly managed to ensure proper disposal, reclamation, and / or recycling. Animal and vegetable oils do not fall under this regulatory classification. Grease does not fall under this regulatory classification

Those materials which are, or were, mixed with used oil and have become separated from that used oil. Oily wastes also means materials, including wastewaters, centrifuge solids, filter residues or sludges, bottom sediments, tank bottoms, and sorbents which have come into contact with and have been contaminated by, used oil and may be appropriately tested and discarded in a manner which is in compliance with other State and local requirements.

This definition includes materials such as oily rags, "kitty litter" sorbent clay and organic sorbent material. These materials may be land filled provided that:

a. It is not prohibited in other State regulations or local

ordinances

b. The amount generated is "de minimus" (a small amount)

c. It is the result of minor leaks or spills resulting from normal process operations

d. All free-flowing oil has been removed to the practical extent possible

Large quantities of this material, generated as a result of a major spill or in lieu of proper maintenance of the processing equipment, are a solid waste. As a solid waste, a hazardous waste determination must be performed prior to disposal. As this can be an expensive process, it is recommended that this type of waste be minimized through good housekeeping practices and employee education.

1.2.10 Regulated Waste

Those solid waste that have specific additional Federal, state, or local controls for handling, storage, or disposal.

1.2.11 Class I Ozone Depleting Substance (ODS)

Class I ODS is defined in Section 602(a) of The Clean Air Act and includes the following chemicals:

chlorofluorocarbon-11 (CFC-11)	chlorofluorocarbon-213 (CFC-213)
chlorofluorocarbon-12 (CFC-12)	chlorofluorocarbon-214 (CFC-214)
chlorofluorocarbon-13 (CFC-13)	chlorofluorocarbon-215 (CFC-215)
chlorofluorocarbon-111 (CFC-111)	chlorofluorocarbon-216 (CFC-216)
chlorofluorocarbon-112 (CFC-112)	chlorofluorocarbon-217 (CFC-217)
chlorofluorocarbon-113 (CFC-113)	halon-1211
chlorofluorocarbon-114 (CFC-114)	halon-1301
chlorofluorocarbon-115 (CFC-115)	halon-2402
chlorofluorocarbon-211 (CFC-211)	carbon tetrachloride
chlorofluorocarbon-212 (CFC-212)	methyl chloroform

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Preconstruction Survey; G

Solid Waste Management Plan and Permit; G

Regulatory Notification; G

Environmental Protection Plan; G

Contractor/Vendor Environmental Service Agreement; G

SD-06 Test Reports

Laboratory Analysis

Disposal Requirements

SD-11 Closeout Submittals

Some of the records listed below are also required as part of other submittals. For the "Records" submittal, maintain on-site a separate three-ring Environmental Records binder and submit at the completion of the project. Make separate parts to the binder corresponding to each of the applicable sub items listed below.

Waste Determination Documentation

Disposal Documentation for Hazardous and Regulated Waste

Contractor 40 CFR Employee Training Records

Solid Waste Management Report

Contractor Hazardous Material Inventory Log; G

Hazardous Waste/Debris Management

1.4 ENVIRONMENTAL PROTECTION REQUIREMENTS

Provide and maintain, during the life of the contract, environmental protection as defined. Plan for and provide environmental protective measures to control pollution that develops during normal construction practice. Plan for and provide environmental protective measures required to correct conditions that develop during the construction of permanent or temporary environmental features associated with the project. Comply with Federal, State, and local regulations pertaining to the environment, including water, air, solid waste, hazardous waste and substances, oily substances, and noise pollution.

Marine Corps Air Station, Cherry Point is listed on the National Priorities List pursuant to the Comprehensive Environmental Response, Compensation and Liabilities Act 42 USCA, Section 9601.et seq. as amended April 15, 1996 (CERCLA). Bogue Field, Oakgrove, BT-11 and Atlantic Field are not listed on the National Priorities List. The Contractor shall immediately bring to the Contracting Officer's attention any unanticipated site condition which may involve hazardous materials or hazardous waste and the Contractor shall not disturb such conditions without the Contracting Officer's prior written documentation as to whether such conditions are outside the contract requirements.

1.4.1 Facility Hazardous Waste Generator Status

Marine Corps Air Station Cherry Point is designated as a Large Quantity Generator (LQG) of Hazardous Waste, a Large Quantity Handler of Universal (Hazardous) Waste, and maintains a Treatment, Storage, and Disposal facility. Accordingly, MCAS Cherry Point is required to actively maintain and comply with a RCRA Part "B" operating permit issued by the State of North Carolina. All work conducted within the boundaries of this activity must be in compliance with the Part B permit, and the generator's various designations and operational requirements. Contractors will comply with all federal, state, and local regulatory requirements governing the proper

training of personnel, and proper identification, generation, management, storage, handling, manifesting, transportation, and disposal of any Hazardous Waste(s) which they may cause to be generated in the course of the execution of their contract(s).

1.5 QUALITY ASSURANCE

1.5.1 Preconstruction Survey

Perform a Preconstruction Survey of the project site with the Contracting Officer, and take photographs showing existing environmental conditions in and adjacent to the site. Submit a report for the record.

1.5.2 Regulatory Notification

The Contractor is responsible for all Regulatory Notification requirements in accordance with Federal, State and local regulations. In cases where the Navy must also provide public notification (such as stormwater permitting), the Contractor must coordinate with the Contracting Officer. The Contractor shall submit copies of all regulatory notifications to the Contracting Officer prior to commencement of work activities. Typically, regulatory notifications must be provided for the following (this listing is not all inclusive): demolition, renovation, NPDES defined site work, remediation of controlled substances (asbestos, hazardous waste, lead paint).

1.5.3 Environmental Brief

Attend an environmental brief to be included in the preconstruction meeting. Provide the following information: types, quantities, and use of hazardous materials that will be brought onto the activity; types and quantities of wastes/wastewater that may be generated during the contract. Discuss the results of the Preconstruction Survey at this time.

Prior to initiating any work on site, meet with the Contracting Officer and activity environmental staff to discuss the proposed Environmental Protection Plan. Develop a mutual understanding relative to the details of environmental protection, including measures for protecting natural resources, required reports, required permits, permit requirements, and other measures to be taken.

1.5.4 Environmental Manager

Appoint in writing an Environmental Manager for the project site. The Environmental Manager will be directly responsible for coordinating contractor compliance with Federal, State, local, and station requirements. The Environmental Manager will ensure compliance with Hazardous Waste Program requirements (including hazardous waste handling, storage, manifesting, and disposal); implement the Environmental Protection Plan; ensure that all environmental permits are obtained, maintained, and closed out; ensure compliance with Storm Water Program Management requirements; ensure compliance with Hazardous Materials (storage, handling, and reporting) requirements; and coordinate any remediation of regulated substances (lead, asbestos, PCB transformers). This can be a collateral position; however the person in this position must be trained to adequately accomplish the following duties: ensure waste segregation and storage compatibility requirements are met; inspect and manage Satellite Accumulation areas; ensure only authorized personnel add wastes to containers; ensure all Contractor personnel are trained in 40 CFR

requirements in accordance with their position requirements; coordinate removal of waste containers; and maintain the Environmental Records binder and required documentation, including environmental permits compliance and close-out.

1.5.5 Contractor 40 CFR Employee Training Records

Prepare and maintain employee training records throughout the term of the contract meeting applicable 40 CFR requirements. Submit these training records to the Contracting Officer at the conclusion of the project, unless otherwise directed.

1.5.6 Contractor Environmental Management System (EMS) Requirements

The Contractor shall perform work under this contract consistent with the policy, objectives, and targets identified in Marine Corps Air Station Cherry Point's Environmental Management System (EMS). Executive Order 13423, Strengthening Federal Environmental, Energy, and Transportation Management and Marine Corps Order P5090.2A, Environmental Compliance and Protection Manual require that all Federal agencies implement, utilize, and maintain an EMS. The Contractor shall perform work in a manner that does not circumvent objectives and targets, environmental programs goals, and operational controls identified by the EMS. The Contractor is also required not to impede compliance with the provisions of Executive Order 13423. The work performed under this contract affects practices that have been identified as significant, and requires more stringent requirements to adhere to the objectives and targets identified for MCAS Cherry Point.

The Contractor shall assume liability for nonconformances and noncompliances resulting from the Contractor's activities and work with Air Station personnel to conduct corrective and preventive actions. The Contractor is responsible for ensuring that their employees receive applicable environmental training, along with any applicable environmental management systems training, and are knowledgeable of current regulatory required specific training for the type of work to be conducted on-site. The Contractor personnel and their subcontractor personnel shall have the appropriate education, training, and experience in order to perform the work specified under this contract. Upon contract award, the Contractor shall review the Contractor Environmental Training Binder and Training Presentation and sign the Contractor/Vendor Environmental Service Agreement. Training and Service Agreement Documents are located on-line at http://www.marines.mil/unit/mcascherrypoint/Pages/EA/EA.aspx

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.1 ENVIRONMENTAL PROTECTION PLAN

Prior to initiating any work on site, the Contractor will meet with the Contracting Officer to discuss the proposed Environmental Protection Plan and develop a mutual understanding relative to the details of environmental protection, including measures for protecting natural resources, required reports, and other measures to be taken. The Environmental Protection Plan will be submitted in the following format and will, at a minimum, address

the following elements:

a. Description of the Environmental Protection Plan

(1) General overview and purpose

(2) General site information

b. Protection of Natural Resources

(1) Land resources

(2) Tree protection

(3) Replacement of damaged landscape features

(4) Temporary construction

(5) Stream crossings

(6) Fish and wildlife resources

(7) Wetland areas

c. Protection of Historical and Archaeological Resources

(1) Objectives

(2) Methods

d. Storm Water Management and Control

(1) Ground cover

(2) Erodible soils

(3) Temporary measures

(a) Mechanical retardation and control of runoff

(b) Vegetation and mulch

e. Protection of the Environment from Waste Derived from Contractor Operations

(1) Control and disposal of solid and sanitary waste

(2) Control and disposal of hazardous waste (Hazardous Waste Management Section)

This item will consist of the management procedures for all hazardous waste to be generated. The elements of those procedures will coincide with the Activity Hazardous Waste Management Plan. A copy of the Activity Hazardous Waste Management Plan will be provided by the Contracting Officer. As a minimum, include the following:

(a) Procedures to be employed to ensure a written waste determination is made for appropriate wastes which are to be

generated;

(b) Sampling/analysis plan;

(c) Methods of hazardous waste accumulation/storage (i.e., in tanks and/or containers);

(d) Management procedures for storage, labeling, transportation, and disposal of waste (treatment of waste is not allowed unless specifically noted);

(e) Management procedures and regulatory documentation ensuring disposal of hazardous waste complies with Land Disposal Restrictions (40 CFR 268);

(f) Management procedures for recyclable hazardous materials such as lead-acid batteries, used oil, and the like;

(g) Used oil management procedures in accordance with 40 CFR 279;

(h) Pollution prevention\hazardous waste minimization procedures;

(i) Plans for the disposal of hazardous waste by permitted facilities;

(j) Procedures to be employed to ensure all required employee training records are maintained.

f. Prevention of Releases to the Environment

(1) Procedures to prevent releases to the environment

(2) Notifications in the event of a release to the environment

g. Regulatory Notification and Permits

(1) List what notifications and permit applications must be made. Include copies of all applicable, environmental permits.

3.1.1 Environmental Protection Plan Review

Fourteen days after the environmental protection meeting, submit the proposed Environmental Protection Plan for further discussion, review, and approval. Commencement of work will not begin until the environmental protection plan has been approved.

3.1.2 Licenses and Permits

Obtain licenses and permits pursuant to the "Permits and Responsibilities" FAR Clause.

Where required by the State regulatory authority, the inspections and certifications will be provided through the services of a Professional Engineer (PE), registered in the State where the work is being performed.

3.2 PROTECTION OF NATURAL RESOURCES

Preserve the natural resources within the project boundaries and outside the limits of permanent work. Restore to an equivalent or improved condition upon completion of work. Confine construction activities to within the limits of the work indicated or specified.

3.2.1 Erosion and Sediment Control Measures

3.2.1.1 Burnoff

Burnoff of the ground cover is not permitted.

3.2.1.2 Protection of Erodible Soils

Immediately finish the earthwork brought to a final grade, as indicated or specified. Immediately protect the side slopes and back slopes upon completion of rough grading. Plan and conduct earthwork to minimize the duration of exposure of unprotected soils.

3.3 HISTORICAL AND ARCHAEOLOGICAL RESOURCES

Carefully protect in-place and report immediately to the Contracting Officer historical and archaeological items or human skeletal remains discovered in the course of work. Upon discovery, notify the Contracting Officer. Stop work in the immediate area of the discovery until directed by the Contracting Officer to resume work. The Government retains ownership and control over historical and archaeological resources.

3.4 SOLID WASTE MANAGEMENT PLAN and PERMIT

Provide to the contracting officer written notification of the quantity of solid waste/debris that is anticipated to be generated by construction. Include in the report the locations where various types of waste will be disposed or recycled. Include letters of acceptance or as applicable, submit one copy of a State local permit or license showing such agencies' approval of the disposal plan before transporting wastes off Government property.

3.4.1 Solid Waste management Report

Monthly, submit a solid waste disposal report to the Contracting Officer. For each waste, the report will state the classification (using the definitions provided in this section), amount, location, and name of the business receiving the solid waste. Include copies of the waste handling facilities' weight tickets, receipts, bills of sale, and other sales documentation. In lieu of sales documentation, the Contractor may submit a statement indicating the disposal location for the solid waste which is signed by an officer of the Contractor firm authorized to legally obligate or bind the firm. The sales documentation or Contractor certification will include the receiver's tax identification number and business, EPA or State registration number, along with the receiver's delivery and business addresses and telephone numbers. For each solid waste retained by the Contractor for his own use, the Contractor will submit on the solid waste disposal report the information previously described in this paragraph. Prices paid or received will not be reported to the Contracting Officer unless required by other provisions or specifications of this Contract or public law.

3.4.2 Control and Disposal of Solid Wastes

Pick up solid wastes, and place in covered containers which are regularly emptied. Do not prepare or cook food on the project site. Prevent contamination of the site or other areas when handling and disposing of wastes. At project completion, leave the areas clean. Recycling is encouraged and can be coordinated with the Contracting Officer and the activity recycling coordinator. Remove all solid waste (including non-hazardous debris) from Government property and dispose off-site at an approved landfill. Solid waste disposal off-site must comply with most stringent local, State, and Federal requirements including 40 CFR 241, 40 CFR 243, and 40 CFR 258.

3.5 WASTE DETERMINATION DOCUMENTATION

Complete a Waste Determination form (provided at the pre-construction conference) for all contractor derived wastes to be generated. Base the waste determination upon either a constituent listing from the manufacturer used in conjunction with consideration of the process by which the waste was generated, EPA approved analytical data, or laboratory analysis (Material Safety Data Sheets (MSDS) by themselves are not adequate). Attach all support documentation to the Waste Determination form. As a minimum, a Waste Determination form must be provided for the following wastes (this listing is not all inclusive): oil and latex based painting and caulking products, solvents, adhesives, aerosols, petroleum products, and all containers of the original materials.

3.5.1 Contractor Hazardous Material Inventory Log

Submit the Contractor Hazardous Material Inventory Log (found at: http://www.wbdg.org/ccb/NAVGRAPH/01575n.pdf), which provides information required by (EPCRA Sections 312 and 313) along with corresponding Material Safety Data Sheets (MSDS) to the Contracting Officer at the start and at the end of construction (30 days from final acceptance), and update no later than January 31 of each calendar year during the life of the contract. Documentation for any spills/releases, environmental reports or off-site transfers may be requested by the Contracting Officer.

3.5.2 Laboratory Analysis

Submit a copy of a Laboratory Analysis of solid waste and debris with the potential of becoming classified as a hazardous waste (i.e., abrasive/sand blasting debris, etc.). Waste stream determinations are required at the point of generation and must sufficiently document whether the waste will be a solid waste, hazardous waste, or Resource Conservation and Recovery Act (RCRA) exempt waste. Determinations must use EPA approved methods and provide written rational for whether the waste is classified as hazardous or non-hazardous. The Contractor will bear the cost of the waste stream determinations, and the Contracting Officer reserves the right to request waste stream determinations on questionable waste streams.

3.6 CONTRACTOR HAZARDOUS MATERIAL INVENTORY LOG

Submit the "Contractor Hazardous Material Inventory Log"(found at: http://www.lantdiv.navfac.navy.mil/pls/lantdiv/docs/FOLDER/EICO/UFGS/GRAPHICS/01575.pdf), which provides information required by (EPCRA Sections 312 and 313) along with corresponding Material Safety Data Sheets (MSDS) to the Contracting Officer at the start and at the end of construction (30 days from final acceptance), and update no later than January 31 of each

calendar year during the life of the contract. Documentation for any spills/releases, environmental reports or off-site transfers may be requested by the Contracting Officer.

3.6.1 Disposal Documentation for Hazardous and Regulated Waste

Manifest, pack, ship and dispose of hazardous or toxic waste and universal waste that is generated as a result of construction in accordance with the generating facilities generator status under the Recourse Conservation and Recovery Act. Contact the Contracting Officer for the facility RCRA identification number that is to be used on each manifest.

3.7 POLLUTION PREVENTION/HAZARDOUS WASTE MINIMIZATION

minimize the use of hazardous materials and the generation of hazardous waste. Include procedures for pollution prevention/ hazardous waste minimization in the Hazardous Waste Management Section of the Environmental Protection Plan. Consult with the activity Environmental Office for suggestions and to obtain a copy of the installation's pollution prevention/hazardous waste minimization plan for reference material when preparing this part of the plan. If no written plan exists, obtain information by contacting the Contracting Officer. Describe the types of the hazardous materials expected to be used in the construction when requesting information.

3.8 WHM/HW MATERIALS PROHIBITION

No waste hazardous material or hazardous waste shall be disposed of on government property. No hazardous material shall be brought onto government property that does not directly relate to requirements for the performance of this contract. The government is not responsible for disposal of Contractor's waste material brought on the job site and not required in the performance of this contract. The intent of this provision is to dispose of that waste identified as waste hazardous material/hazardous waste as defined herein that was generated as part of this contract and existed within the boundary of the Contract limits and not brought in from offsite by the Contractor. Incidental materials used to support the contract including, but not limited to aerosol cans, waste paint, cleaning solvents, contaminated brushes, rags, clothing, etc. are the responsibility of the Contractor. The list is illustrative rather than inclusive. The Contractor is not authorized to discharge any materials to sanitary sewer, storm drain, or to the river or conduct waste treatment or disposal on government property without written approval of the Contracting Officer.

3.9 HAZARDOUS MATERIAL CONTROL

Include hazardous material control procedures in the Safety Plan. Address procedures and proper handling of hazardous materials, including the appropriate transportation requirements. Submit a MSDS and estimated quantities to be used for each hazardous material to the Contracting Officer prior to bringing the material on base. Typical materials requiring MSDS and quantity reporting include, but are not limited to, oil and latex based painting and caulking products, solvents, adhesives, aerosol, and petroleum products. At the end of the project, provide the Contracting Officer with the maximum quantity of each material that was present at the site at any one time, the dates the material was present, the amount of each material that was used during the project, and how the material was used. Ensure that hazardous materials are utilized in a

manner that will minimize the amount of hazardous waste that is generated. Ensure that all containers of hazardous materials have NFPA labels or their equivalent. Keep copies of the MSDS for hazardous materials on site at all times and provide them to the Contracting Officer at the end of the project. Certify that all hazardous materials removed from the site are hazardous materials and do not meet the definition of hazardous waste per 40 CFR 261.

3.10 PETROLEUM PRODUCTS

Conduct the fueling and lubricating of equipment and motor vehicles in a manner that protects against spills and evaporation. Manage all used oil generated on site in accordance with 40 CFR 279. Determine if any used oil generated while on-site exhibits a characteristic of hazardous waste. Used oil containing 1000 parts per million of solvents will be considered a hazardous waste and disposed of at Contractor's expense. Used oil mixed with a hazardous waste will also be considered a hazardous waste.

3.10.1 Oily and Hazardous Substances

Prevent oil or hazardous substances from entering the ground, drainage areas, or navigable waters. In accordance with 40 CFR 112, surround all temporary fuel oil or petroleum storage tanks with a temporary berm or containment of sufficient size and strength to contain the contents of the tanks, plus 10 percent freeboard for precipitation. The berm will be impervious to oil for 72 hours and be constructed so that any discharge will not permeate, drain, infiltrate, or otherwise escape before cleanup occurs.

3.11 RELEASES/SPILLS OF OIL AND HAZARDOUS SUBSTANCES

Exercise due diligence to prevent, contain, and respond to spills of hazardous material, hazardous substances, hazardous waste, sewage, regulated gas, petroleum, lubrication oil, and other substances regulated by environmental law. Maintain spill cleanup equipment and materials at the work site. In the event of a spill, take prompt, effective action to stop, contain, curtail, or otherwise limit the amount, duration, and severity of the spill/release. In the event of any releases of oil and hazardous substances, chemicals, or gases; immediately (within 15 minutes) notify the Base or Activity Fire Department, the activity's Command Duty Officer, and the Contracting Officer. If the contractor's response is inadequate, the Navy may respond. If this should occur, the contractor will be required to reimburse the government for spill response assistance and analysis.

The Contractor is responsible for verbal and written notifications as required by the federal 40 CFR 355, State, local regulations and Navy Instructions. Spill response will be in accordance with 40 CFR 300 and applicable State and local regulations. Contain and clean up these spills without cost to the Government. If Government assistance is requested or required, the Contractor will reimburse the Government for such assistance. Provide copies of the written notification and documentation that a verbal notification was made within 20 days.

Maintain spill cleanup equipment and materials at the work site. Clean up all hazardous and non-hazardous (WHM) waste spills. The Contractor shall reimburse the government for all material, equipment, and clothing generated during any spill cleanup. The Contractor shall reimburse the government for all costs incurred including sample analysis materials,

equipment, and labor if the government must initiate its own spill cleanup procedures, for Contractor responsible spills, when:

a. The Contractor has not begun spill cleanup procedure within one hour of spill discovery/occurrence, or

b. If, in the government's judgment, the Contractor's spill cleanup is not adequately abating life threatening situation and/or is a threat to any body of water or environmentally sensitive areas.

3.12 CONTROL AND DISPOSAL OF HAZARDOUS WASTES

3.12.1 Hazardous Waste/Debris Management

Identify all construction activities which will generate hazardous waste/debris. Provide a documented waste determination for all resultant waste streams. Hazardous waste/debris will be identified, labeled, handled, stored, and disposed of in accordance with all Federal, State, and local regulations including 40 CFR 261, 40 CFR 262, 40 CFR 263, 40 CFR 264, 40 CFR 265, 40 CFR 266, and 40 CFR 268. Hazardous waste will also be managed in accordance with the approved Hazardous Waste Management Section of the Environmental Protection Plan. Store hazardous wastes in approved containers in accordance with 49 CFR 173 and 49 CFR 178. Hazardous waste generated within the confines of Government facilities will be identified as being generated by the Government. Prior to removal of any hazardous waste from Government property, all hazardous waste manifests must be signed by activity personnel from the Station Environmental Office. No hazardous waste will be brought onto Government property. Provide to the Contracting Officer a copy of waste determination documentation for any solid waste streams that have any potential to be hazardous waste or contain any chemical constituents listed in 40 CFR 372-SUBPART D. For hazardous wastes spills, verbally notify the Contracting Officer immediately.

3.12.1.1 Regulated Waste Storage/Satellite Accumulation/90 Day Storage Areas

If the work requires the temporary storage/collection of regulated or hazardous wastes, the Contractor will request the establishment of a Regulated Waste Storage Area, a Satellite Accumulation Area, or a 90 Day Storage Area at the point of generation. The Contractor must submit a request in writing to the Contracting Officer providing the following information:

Contract Number	_____	Contractor	_____
Haz/Waste or Regulated Waste POC	_____	Phone Number	_____
Type of Waste	_____	Source of Waste	_____
Emergency POC	_____	Phone Number	_____

Location of the Site: _____
(Attach Site Plan to the Request)

Attach a waste determination form. Allow ten working days for processing this request.

3.12.2 Class I ODS Prohibition

Class I ODS as defined and identified herein will not be used in the performance of this contract, nor be provided as part of the equipment. This prohibition will be considered to prevail over any other provision, specification, drawing, or referenced documents.

3.13 DUST CONTROL

Keep dust down at all times, including during nonworking periods. Sprinkle or treat, with dust suppressants, the soil at the site, haul roads, and other areas disturbed by operations. Dry power brooming will not be permitted. Instead, use vacuuming, wet mopping, wet sweeping, or wet power brooming. Air blowing will be permitted only for cleaning nonparticulate debris such as steel reinforcing bars. Only wet cutting will be permitted for cutting concrete blocks, concrete, and bituminous concrete. Do not unnecessarily shake bags of cement, concrete mortar, or plaster.

3.13.1 Dirt and Dust Control Plan

Submit truck and material haul routes along with a plan for controlling dirt, debris, and dust on base roadways. As a minimum, identify in the plan the subcontractor and equipment for cleaning along the haul route and measures to reduce dirt, dust, and debris from roadways.

3.14 ABRASIVE BLASTING

3.14.1 Blasting Operations

The use of silica sand is prohibited in sandblasting.

Provide tarpaulin drop cloths and windscreens to enclose abrasive blasting operations to confine and collect dust, abrasive, agent, paint chips, and other debris

3.14.2 Disposal Requirements

Submit analytical results of the debris generated from abrasive blasting operations per paragraph entitled Laboratory Analysis of this section. Hazardous waste generated from blasting operations will be managed in accordance with paragraph entitled "Hazardous Waste\Debris Management" of this section and with the approved HWMP.

3.15 NOISE

Make the maximum use of low-noise emission products, as certified by the EPA. Blasting or use of explosives will not be permitted without written permission from the Contracting Officer, and then only during the designated times.

3.16 Soil

Soils encountered during project activities shall be managed per Air Station soil management polices in affect for the duration of the project. If soil is encountered during construction operations that may be contaiminated (as indicated by odor, color, or unusual appearance) that was not previously indicated as contaminated, stop the portion of work immediately and notify the Contracting Officer immediately.

3.16.1 Quarantne for Imported Fire Ants

Onslow, Jones, and Carteret Counties and portions of Duplin and Craven Counties have been declared a generally infested area by the United States Department of Agriculture (USDA) for the imported fire ant. Compliance with the quarantine regulations established by this authority as set forth is USDA Publication 301.81 of 31 December 1992, is required for operations hereunder. Pertinent requirements of quarantine for materials originating on the Camp Lejeune reservation, the Marine Corps Air Station (Helicopter), New River and the Marine Corps Air Station, Cherry Point, which are to be transported outside Onslow County or adjacent suppression areas, include the following:

a. Certification is required for the following articles and theu shall not be moved from the reservation to any point outside Onslow County and adjacent designated areas unless accompanied by a valid inspection certificate issued by an Officer of the Plant Protection and AQuarantine Program (PPQ) of the U.S. Department of Agriculture.

(1) Bulk soil

(2) Used Mechanized soil-moving equipment. (Used mechanized soil-moving equipment is exempt if cleaned of loose non compacted soil).

(3) Other products, articles, or means of conveyances, if it is determined by an inspector that they present a hazard of transporting spread of the imported fire ant and the person in possession therof has been so notified.

b. Authorization for movement of equipment outside the imported fire and regulated area shall be obtained from USDA, APHIS, PPQ, Attn: JB Perry, C/o NCSPA, 113 Arendell St. Room 216, Morehead City, NC 28557, telephone (252) 726-4358, fax (252) 726-5713. Requests for inspection shall be made sufficiently in advance of the date of movement to permit arrangement for the services of authorized inspectors. The equipment shall be prepared and assembled so that it may be readily inspected. Soil on or attached to equipment, supplies, and materials shall be removed by washing with water or such other means as necessary to accomplish complete removal. Resulting spoil shall be wasted as necessary and as directed.

-- End of Section --

SECTION 01 62 35

RECYCLED / RECOVERED MATERIALS

07/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

40 CFR 247	Comprehensive Procurement Guideline for Products Containing Recovered Materials

1.2 OBJECTIVES

Government procurement policy is to acquire, in a cost effective manner, items containing the highest percentage of recycled and recovered materials practicable consistent with maintaining a satisfactory level of competition without adversely affecting performance requirements or exposing suppliers' employees to undue hazards from the recovered materials. The Environmental Protection Agency (EPA) has designated certain items which must contain a specified percent range of recovered or recycled materials. EPA designated products specified in this contract comply with the stated policy and with the EPA guidelines. The Contractor shall make all reasonable efforts to use recycled and recovered materials in providing the EPA designated products and in otherwise utilizing recycled and recovered materials in the execution of the work.

EPA maintains a Database of Manufacturers and Suppliers for each designated item at http://www.epa.gov/cpg/database.htm. Use of sources from this database is not required. It is intended as a tool to assist purchasers in locating products with recycled content.

1.3 EPA DESIGNATED ITEMS INCORPORATED IN THE WORK

Various sections of the specifications contain requirements for materials that have been designated by EPA as being products which are or can be made with recovered or recycled materials. These items, when incorporated into the work under this contract, shall contain at least the specified percentage of recycled or recovered materials unless adequate justification for non-use is provided. The following are considered adequate justifications for non-use:

a. The product does not meet appropriate performance standards.

b. The product is not available within a reasonable time frame.

c. The product is not available competitively (from two or more sources).

d. The product is only available at an unreasonable price (compared

with a comparable non-recycled content product).

When a designated item is specified as an option to a non-designated item, the designated item requirements apply only if the designated item is used in the work.

1.4 EPA PROPOSED ITEMS INCORPORATED IN THE WORK

Products other than those designated by EPA are still being researched and are being considered for future Comprehensive Procurement Guideline (CPG) designation. It is recommended that these items, when incorporated in the work under this contract, contain the highest practicable percentage of recycled or recovered materials, provided specified requirements are also met.

1.5 EPA LISTED ITEMS USED IN CONDUCT OF THE WORK BUT NOT INCORPORATED IN THE WORK

There are many products listed in 40 CFR 247 which have been designated or proposed by EPA to include recycled or recovered materials that may be used by the Contractor in performing the work but will not be incorporated into the work. These products include office products, temporary traffic control products, and pallets. It is recommended that these non-construction products, when used in the conduct of the work, contain the highest practicable percentage of recycled or recovered materials and that these products be recycled when no longer needed.

-- End of Section --

SECTION 01 78 00

CLOSEOUT SUBMITTALS
05/10

PART 1 GENERAL

1.1 SUBMITTALS

The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-10 Operation and Maintenance Data

Equipment/Product Warranty List

Submit Data Package 1 in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

SD-11 Closeout Submittals

As-Built Drawings

Record Of Materials

Equipment/Product Warranty Tag

Monthly Project Waste Summary Report

Hazardous Material Reporting

Certification of EPA Designated Items

Form DD1354

Checklist for Form DD1354

1.2 CERTIFICATION OF EPA DESIGNATED ITEMS

Submit the Certification of EPA Designated Items as required by FAR 52.223-9, "Certification and Estimate of Percentage of Recovered Material Content for EPA Designated Items". The certification form shall include the following information: project name, project number, Contractor name, license number, Contractor address, and certification. The certification shall read as follows and shall be signed and dated by the Contractor. Each product used in the project that has a requirement or option of containing recycled or biobased content in accordance with Section 01 62 35 RECYCLED/RECOVERED MATERIALS shall be recorded, noting total price, total value of post-industrial recycled content, total value of post-consumer recycled content, total value of biobased content, exemptions (1, 2, 3, or 4, as indicated), and comments. Recycled and biobased content values may be determined by weight or volume percent, but must be consistent throughout.

1.3 PROJECT RECORD DOCUMENTS

1.3.1 As-Built Drawings

"NFAS 5252.236-9310, Record Drawings." The Contractor shall maintain at the job site two sets of full-size prints of the contract drawings, accurately marked in red with adequate dimensions, to show all variations between the construction actually provided and that indicated or specified in the contract documents, including buried or concealed construction. Special attention shall be given to recording the horizontal and vertical location of all buried utilities that differ from the contract drawings. Existing utility lines and features revealed during the course of construction, shall also be accurately located and dimensioned. Variations in the interior utility systems shall be clearly defined and dimensioned; and coordinated with exterior utility connections at the building five-foot line, where applicable. Existing topographic features which differ from those shown on the contract drawings shall also be accurately located and recorded. Where a choice of materials or methods is permitted herein, or where variations in scope or character of methods is permitted herein, or where variations in scope or character of work from that of the original contract are authorized, the drawings shall be marked to define the construction actually provided. The representations of such changes shall conform to standard drafting practice and shall include such supplementary notes, legends, and details as necessary to clearly portray the as-built construction. These drawings shall be available for review by the Contracting Officer at all times. Upon completion of the work, both sets of the marked up prints shall be certified as correct, signed by the Contractor, and delivered to the Contracting Officer for his approval before acceptance. Requests for partial payments will not be approved if the marked prints are not kept current, and request for final payment will not be approved until the marked prints are delivered to the Contracting Officer.

1.3.2 As-Built Record of Materials

Furnish a record of materials.

Where several manufacturers' brands, types, or classes of the item listed have been used in the project, designate specific areas where each item was used. Designations shall be keyed to the areas and spaces depicted on the contract drawing. Furnish the record of materials used in the following format:

MATERIALS DESIGNATION	SPECIFICATION	MANUFACTURER	MATERIALS USED (MANUFACTURER'S DESIGNATION)	WHERE USED
Roofing	_____	_____	_____	_____
	_____	_____	_____	_____

1.4 EQUIPMENT/PRODUCT WARRANTIES

1.4.1 Equipment/Product Warranty List

Furnish to the Contracting Officer a bound and indexed notebook containing written warranties for equipment/products furnished under the contract, and prepare a complete listing of such equipment/products. The

equipment/products list shall state the specification section applicable to the equipment/product, duration of the warranty therefore, start date of the warranty, ending date of the warranty, and the point of contact for fulfillment of the warranty. The warranty period shall begin on the same date as project acceptance and shall continue for the full product warranty period. Execute the full list and deliver to the Contracting Officer prior to final acceptance of the facility.

1.4.2 Equipment Warranty Tags and Guarantor's Local Representative

Furnish with each warranty the name, address, and telephone number of the guarantor's representative nearest to the location where the equipment and appliances are installed. The guarantor's representative, upon request of the station representative, shall honor the warranty during the warranty period, and shall provide the services prescribed by the terms of the warranty. At the time of installation, tag each item of warranted equipment with a durable, oil- and water-resistant tag approved by the Contracting Officer. Attach tag with copper wire and spray with a clear silicone waterproof coating. Leave the date of acceptance and QC's signature blank until project is accepted for beneficial occupancy. Tag shall show the following information:

EQUIPMENT/PRODUCT WARRANTY TAG

Type of Equipment/Product _____
Warranty Period _____ From _____ To _____
Contract No. _____
Inspector's Signature _____ Date Accepted _____

Construction Contractor:
Name: _____
Address: _____
Telephone: _____

Warranty Contact: _____
Name: _____
Address: _____
Telephone: _____

STATION PERSONNEL TO PERFORM ONLY OPERATIONAL MAINTENANCE

1.5 MECHANICAL TESTING AND BALANCING

All contract requirements of Section 23 09 23.13 20 BACnet DIRECT DIGITAL CONTROL SYSTEMS FOR HVAC shall be fully completed, including all testing, prior to contract completion date. In addition, all contract requirements of Section 23 05 93 HVAC TESTING/ADJUSTING/BALANCING shall be fully completed, including testing and inspection, prior to contract completion date, except as noted otherwise in Section 23 05 93. The time required to complete all work and testing as prescribed by Sections 23 09 23.13 20 and 23 05 93 is included in the allotted calendar days for completion.

1.6 CLEANUP

Leave premises "broom clean." Clean interior and exterior glass surfaces exposed to view; remove temporary labels, stains and foreign substances; polish transparent and glossy surfaces; vacuum carpeted and soft surfaces. Clean equipment and fixtures to a sanitary condition. Replacefilters of operating equipment. Clean debris from roofs, gutters, downspouts and

drainage systems. Sweep paved areas and rake clean landscaped areas. Remove waste and surplus materials, rubbish and construction facilities from the site.

1.7 REAL PROPERTY RECORD

Near the completion of Project, but a minimum of 60 days prior to final acceptance of the work, complete, update draft attached to this section, and submit an accounting of all installed property on Form DD1354 "Transfer and Acceptance of Military Real Property." Contact the Contracting Officer for any project specific information necessary to complete the DD Form 1354. For information purposes, a blank DD Form 1354 (fill-able) in ADOBE (PDF) may be obtained at the following web site:

http://www.dtic.mil/whs/directives/infomgt/forms/eforms/dd1354.pdf

Submit the completed Checklist for Form DD1354 of Government-Furnished and Contractor-Furnished/Contractor Installed items. Attach this list to the updated DD Form 1354. Instructions for completing the form and a blank checklist (fill-able) in ADOBE (PDF) may be obtained at the following web site:

http://www.hnd.usace.army.mil/techinfo/UFC/UFC1-300-08/UFC1-300-08.pdf

See Appendix D of this pdf for the checklist.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SECTION 01 78 23

OPERATION AND MAINTENANCE DATA
07/06

PART 1 GENERAL

1.1 SUBMISSION OF OPERATION AND MAINTENANCE DATA

Submit Operation and Maintenance (O&M) Data specifically applicable to this contract and a complete and concise depiction of the provided equipment, product, or system, stressing and enhancing the importance of system interactions, troubleshooting, and long-term preventative maintenance and operation. The subcontractors shall compile and prepare data and deliver to the Contractor prior to the training of Government personnel. The Contractor shall compile and prepare aggregate O&M data including clarifying and updating the original sequences of operation to as-built conditions. Organize and present information in sufficient detail to clearly explain O&M requirements at the system, equipment, component, and subassembly level. Include an index preceding each submittal. Submit in accordance with this section and Section 01 33 00 SUBMITTAL PROCEDURES.

1.1.1 Package Quality

Documents must be fully legible. Poor quality copies and material with hole punches obliterating the text or drawings will not be accepted.

1.1.2 Package Content

Data package content shall be as shown in the paragraph titled "Schedule of Operation and Maintenance Data Packages." Comply with the data package requirements specified in the individual technical sections, including the content of the packages and addressing each product, component, and system designated for data package submission, except as follows. Commissioned items without a specified data package requirement in the individual technical sections shall use Data Package 3. Commissioned items with a Data Package 1 or 2 requirement shall use instead Data Package 3.

1.1.3 Changes to Submittals

Manufacturer-originated changes or revisions to submitted data shall be furnished by the Contractor if a component of an item is so affected subsequent to acceptance of the O&M Data. Changes, additions, or revisions required by the Contracting Officer for final acceptance of submitted data, shall be submitted by the Contractor within 30 calendar days of the notification of this change requirement.

1.2 TYPES OF INFORMATION REQUIRED IN O&M DATA PACKAGES

1.2.1 Operating Instructions

Include specific instructions, procedures, and illustrations for the following phases of operation for the installed model and features of each system:

1.2.1.1 Safety Precautions

List personnel hazards and equipment or product safety precautions for all

operating conditions.

1.2.1.2 Operator Prestart

Include procedures required to install, set up, and prepare each system for use.

1.2.1.3 Startup, Shutdown, and Post-Shutdown Procedures

Provide narrative description for Startup, Shutdown and Post-shutdown operating procedures including the control sequence for each procedure.

1.2.1.4 Normal Operations

Provide narrative description of Normal Operating Procedures. Include Control Diagrams with data to explain operation and control of systems and specific equipment.

1.2.1.5 Emergency Operations

Include Emergency Procedures for equipment malfunctions to permit a short period of continued operation or to shut down the equipment to prevent further damage to systems and equipment. Include Emergency Shutdown Instructions for fire, explosion, spills, or other foreseeable contingencies. Provide guidance and procedures for emergency operation of all utility systems including required valve positions, valve locations and zones or portions of systems controlled.

1.2.1.6 Operator Service Requirements

Include instructions for services to be performed by the operator such as lubrication, adjustment, inspection, and recording gage readings.

1.2.1.7 Environmental Conditions

Include a list of Environmental Conditions (temperature, humidity, and other relevant data) that are best suited for the operation of each product, component or system. Describe conditions under which the item equipment should not be allowed to run.

1.2.2 Preventive Maintenance

Include the following information for preventive and scheduled maintenance to minimize corrective maintenance and repair for the installed model and features of each system. Include potential environmental and indoor air quality impacts of recommended maintenance procedures and materials.

1.2.2.1 Lubrication Data

Include preventative maintenance lubrication data, in addition to instructions for lubrication provided under paragraph titled "Operator Service Requirements":

a. A table showing recommended lubricants for specific temperature ranges and applications.

b. Charts with a schematic diagram of the equipment showing lubrication points, recommended types and grades of lubricants, and capacities.

c. A Lubrication Schedule showing service interval frequency.

1.2.2.2 Preventive Maintenance Plan and Schedule

Include manufacturer's schedule for routine preventive maintenance, inspections, tests and adjustments required to ensure proper and economical operation and to minimize corrective maintenance. Provide manufacturer's projection of preventive maintenance work-hours on a daily, weekly, monthly, and annual basis including craft requirements by type of craft. For periodic calibrations, provide manufacturer's specified frequency and procedures for each separate operation.

1.2.2.3 Equipment Replacement Cost

For all equipment requiring preventive maintenance, provide length of useful life information and current equipment replacement costs for each piece of equipment. The following list should not be considered all inclusive, but provides examples of typical equipment requiring preventive maintenance:

Generator set
Air compressor
Air conditioner-condensing unit
Air conditioner-chiller
Air conditioner-air handler
Air conditioner-package unit
Compressed air dryer
Air washer/dryer
Vacuum pump
Air diffuser system
Air purifier
Dust collector/recovery unit
Down draft system
Hangar door motor
Dumbwaiter (vertical platform lift)
Ventilation/exhaust fan
Automatic gate opener
Heat pump
Make-up air unit
Hydraulic system
Pit pump
Oxygen breathing regulator
Scrubber
Distilled water system still
Drinking water fountain
Automatic roll-up door motor

1.2.3 Corrective Maintenance (Repair)

Include manufacturer's recommended procedures and instructions for correcting problems and making repairs.

1.2.3.1 Troubleshooting Guides and Diagnostic Techniques

Include step-by-step procedures to promptly isolate the cause of typical malfunctions. Describe clearly why the checkout is performed and what conditions are to be sought. Identify tests or inspections and test

equipment required to determine whether parts and equipment may be reused or require replacement.

1.2.3.2 Wiring Diagrams and Control Diagrams

Wiring diagrams and control diagrams shall be point-to-point drawings of wiring and control circuits including factory-field interfaces. Provide a complete and accurate depiction of the actual job specific wiring and control work. On diagrams, number electrical and electronic wiring and pneumatic control tubing and the terminals for each type, identically to actual installation configuration and numbering.

1.2.3.3 Maintenance and Repair Procedures

Include instructions and a list of tools required to repair or restore the product or equipment to proper condition or operating standards.

1.2.3.4 Removal and Replacement Instructions

Include step-by-step procedures and a list required tools and supplies for removal, replacement, disassembly, and assembly of components, assemblies, subassemblies, accessories, and attachments. Provide tolerances, dimensions, settings and adjustments required. Instructions shall include a combination of text and illustrations.

1.2.3.5 Spare Parts and Supply Lists

Include lists of spare parts and supplies required for maintenance and repair to ensure continued service or operation without unreasonable delays. Special consideration is required for facilities at remote locations. List spare parts and supplies that have a long lead-time to obtain.

1.2.4 Corrective Maintenance Work-Hours

Include manufacturer's projection of corrective maintenance work-hours including requirements by type of craft. Corrective maintenance that requires completion or participation of the equipment manufacturer shall be identified and tabulated separately.

1.2.5 Appendices

Provide information required below and information not specified in the preceding paragraphs but pertinent to the maintenance or operation of the product or equipment. Include the following:

1.2.5.1 Product Submittal Data

Provide a copy of all SD-03 Product Data submittals required in the applicable technical sections.

1.2.5.2 Manufacturer's Instructions

Provide a copy of all SD-08 Manufacturer's Instructions submittals required in the applicable technical sections.

1.2.5.3 O&M Submittal Data

Provide a copy of all SD-10 Operation and Maintenance Data submittals

required in the applicable technical sections.

1.2.5.4 Parts Identification

Provide identification and coverage for all parts of each component, assembly, subassembly, and accessory of the end items subject to replacement. Include special hardware requirements, such as requirement to use high-strength bolts and nuts. Identify parts by make, model, serial number, and source of supply to allow reordering without further identification. Provide clear and legible illustrations, drawings, and exploded views to enable easy identification of the items. When illustrations omit the part numbers and description, both the illustrations and separate listing shall show the index, reference, or key number that will cross-reference the illustrated part to the listed part. Parts shown in the listings shall be grouped by components, assemblies, and subassemblies in accordance with the manufacturer's standard practice. Parts data may cover more than one model or series of equipment, components, assemblies, subassemblies, attachments, or accessories, such as typically shown in a master parts catalog

1.2.5.5 Warranty Information

List and explain the various warranties and clearly identify the servicing and technical precautions prescribed by the manufacturers or contract documents in order to keep warranties in force. Include warranty information for primary components such as the compressor of air conditioning system.

1.2.5.6 Personnel Training Requirements

Provide information available from the manufacturers that is needed for use in training designated personnel to properly operate and maintain the equipment and systems.

1.2.5.7 Testing Equipment and Special Tool Information

Include information on test equipment required to perform specified tests and on special tools needed for the operation, maintenance, and repair of components.

1.2.5.8 Testing and Performance Data

Include completed prefunctional checklists, functional performance test forms, and monitoring reports. Include recommended schedule for retesting and blank test forms.

1.2.5.9 Contractor Information

Provide a list that includes the name, address, and telephone number of the General Contractor and each Subcontractor who installed the product or equipment, or system. For each item, also provide the name address and telephone number of the manufacturer's representative and service organization that can provide replacements most convenient to the project site. Provide the name, address, and telephone number of the product, equipment, and system manufacturers.

1.3 TYPES OF INFORMATION REQUIRED IN CONTROLS O&M DATA PACKAGES

Include Data Package 5 and the following for control systems:

a. Narrative description on how to perform and apply all functions, features, modes, and other operations, including unoccupied operation, seasonal changeover, manual operation, and alarms. Include detailed technical manual for programming and customizing control loops and algorithms.

b. Full as-built sequence of operations.

c. Copies of all checkout tests and calibrations performed by the Contractor (not Cx tests).

d. Full points list. A listing of rooms shall be provided with the following information for each room:

(1) Floor

(2) Room number

(3) Room name

(4) Air handler unit ID

(5) Reference drawing number

(6) Air terminal unit tag ID

(7) Heating and/or cooling valve tag ID

(8) Minimum cfm

(9) Maximum cfm

1.4 SCHEDULE OF OPERATION AND MAINTENANCE DATA PACKAGES

Furnish the O&M data packages specified in individual technical sections. The required information for each O&M data package is as follows:

1.4.1 Data Package 1

a. Safety precautions

b. Cleaning recommendations

c. Maintenance and repair procedures

d. Warranty information

e. Contractor information

f. Spare parts and supply list

1.4.2 Data Package 2

a. Safety precautions

b. Normal operations

c. Environmental conditions

d. Lubrication data

e. Preventive maintenance plan and schedule

f. Cleaning recommendations

g. Maintenance and repair procedures

h. Removal and replacement instructions

i. Spare parts and supply list

j. Parts identification

k. Warranty information

l. Contractor information

1.4.3 Data Package 3

a. Safety precautions

b. Operator prestart

c. Startup, shutdown, and post-shutdown procedures

d. Normal operations

e. Emergency operations

f. Environmental conditions

g. Lubrication data

h. Preventive maintenance plan and schedule

i. Cleaning recommendations

j. Troubleshooting guides and diagnostic techniques

k. Wiring diagrams and control diagrams

l. Maintenance and repair procedures

m. Removal and replacement instructions

n. Spare parts and supply list

o. Product submittal data

p. O&M submittal data

q. Parts identification

r. Warranty information

s. Testing equipment and special tool information

t. Testing and performance data

u. Contractor information

1.4.4 Data Package 4

a. Safety precautions

b. Operator prestart

c. Startup, shutdown, and post-shutdown procedures

d. Normal operations

e. Emergency operations

f. Operator service requirements

g. Environmental conditions

h. Lubrication data

i. Preventive maintenance plan and schedule

j. Cleaning recommendations

k. Troubleshooting guides and diagnostic techniques

l. Wiring diagrams and control diagrams

m. Maintenance and repair procedures

n. Removal and replacement instructions

o. Spare parts and supply list

p. Corrective maintenance man-hours

q. Product submittal data

r. O&M submittal data

s. Parts identification

t. Warranty information

u. Personnel training requirements

v. Testing equipment and special tool information

w. Testing and performance data

x. Contractor information

1.4.5 Data Package 5

a. Safety precautions

b. Operator prestart

c. Start-up, shutdown, and post-shutdown procedures

d. Normal operations

e. Environmental conditions

f. Preventive maintenance plan and schedule

g. Troubleshooting guides and diagnostic techniques

h. Wiring and control diagrams

i. Maintenance and repair procedures

j. Removal and replacement instructions

k. Spare parts and supply list

l. Product submittal data

m. Manufacturer's instructions

n. O&M submittal data

o. Parts identification

p. Testing equipment and special tool information

q. Warranty information

r. Testing and performance data

s. Contractor information

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SECTION 01 80 00

REPORTS
07/06

PART 1 GENERAL

1.1 REPORTS INCLUDED

1.1.1 Asbestos and Lead Paint Inspection Report

Asbestos and Lead paint Survey Reports, dtd Oct. 12, 2009.

1.2 USE OF INFORMATION

1.2.1 Warranty

The information disclosed in the referenced reports is based on data obtained in specific locations and is assumed to be representative of conditions throughout the site. This information is furnished without warranty and is only for general information to be used by the contractor in the preparation of his bid and work schedule. It is not intended as a replacement for personal investigation and judgment, or interpretation of the information furnished, as required of the contractor in the performance of this contract.

1.2.2 Site Visit

Bidders should visit the site and acquaint themselves with all existing conditions prior to preparing their bid. This will include a review of the conditions contained in the enclosed report as they relate to the site. The contractor is responsible for including in his bid and work schedule, procedures for handling existing site conditions delineated in the included reports in accord with applicable laws and regulations as those conditions may effect the work.

1.2.3 Application of Information

Recommendations contained in the reports are to be used by the contractor only to the extent that these recommendations comply with applicable laws, regulations, and other sections of the these specifications.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.1 VARYING CONDITIONS

If during the course of the work, conditions are encountered which are not covered in the included reports or are different from conditions that would be reasonably anticipated from the included reports, the contractor shall immediately notify the Officer in Charge of Construction. If such conditions are hazardous or the continuation of work would cause a hazardous condition to develop, he shall stop work and proceed as directed by the Officer in Charge of Construction as directed by provisions contained in other sections of this specification. This may include

modifications to, or the development of a new, Health and Safety Plan for this project, and alternate or additional appropriate abatement procedures.

3.2 CHANGES TO THE CONTRACT

Any changes to the contract made as a result of site conditions which differ from those delineated in the report may result in an adjustment of the contract amount. The adjustment will be an increase or decrease depending on the scope and nature of the change and will be in accord with other provisions of these specifications.

-- End of Section --

October 12, 2009

NRW Engineering PC
748 Lord Dunmore Drive
Suite 101
Virginia Beach, VA 23464

Attention: Mr. Kevin Roomsburg, P.E.

Reference: **Report of Industrial Hygiene Services**
Building B133 HVAC Replacement Project
Marine Corps Air Station at Cherry Point
Cherry Point, North Carolina
S&ME Project No. 1054-09-143C

Dear Mr. Roomsburg:

S&ME, Inc. (S&ME) is pleased to provide this report for Industrial Hygiene Services performed at the above-referenced site. These services included a lead-containing paint screening and an asbestos containing materials survey. Our services were provided in general accordance with our proposal (S&ME Proposal No. P4724-09V dated June 18, 2009). This report outlines the results of the lead-containing paint and asbestos containing material (ACM) surveys, and presents our findings and recommendations.

PROJECT SUMMARY

Based on an email correspondence between Steve Harvey with Dewberry and Davis, Inc. and Chris Hamblet of S&ME on June 16, 2009, we understand that NRW Engineering PC and Dewberry and Davis, Inc. are developing specifications for the replacement of the HVAC system in Building B133 at the Marine Corps Air Station located in Cherry Point, North Carolina. The project involves the removal of the existing HVAC equipment and rooftop mechanical equipment penthouses and replacing them with a self-supported HVAC system to be re-connected to the existing ductwork. Mr. Harvey provided a copy of the Department of Navy's Indefinite Quantity Contract No. N40085-08-D-9301, Project R46-93 via email, which provided additional information regarding the scope of work. You requested S&ME to perform an asbestos survey and lead-containing paint screening of the impacted areas in the building and on the roof. This survey was conducted only for the areas to be impacted by the HVAC replacement as depicted in the drawings, and did not include other areas of the building.

You provided a copy of a set of drawings entitled Design for Asbestos Removal – Building 133, approved on June 18, 1993, that you obtained from the engineering department files. The drawings identified specific asbestos containing materials to be removed from throughout the building and the rooftop penthouses. Two specific areas labeled as hazardous plating areas located in the eastern portion of the building were not included in the abatement design, and no indication that the roof system in the area to be impacted was included in the removal was shown on the drawings. Mr. Hamblet contacted Mr. Paul Cline, Head of the Facilities Engineering Department, on September 2, 2009 to inquire about any documentation that the proposed asbestos removal had been completed or if any documentation of abatement of the roof system was available. Mr. Cline indicated that he could not locate any documentation that the removal had been completed, or of any roof abatement.

ASBESTOS-CONTAINING MATERIALS SURVEY

Asbestos surveys are required to be conducted prior to demolition/renovation activities according to the Environmental Protection Agency (EPA) regulation 40 CFR, part 61, subpart M, Final Rule National Emissions Standards for Hazardous Air Pollutants (NESHAP). Surveys performed by S&ME for asbestos-suspect materials are limited to those materials that are reasonably accessible at the time of the survey. Suspect materials hidden in pipe chases, behind walls and mechanical equipment, above solid ceilings, in locked rooms or encased in columns that were not sampled during this survey should be assumed to contain asbestos. Further sampling of suspect materials in these areas, if/when discovered, is recommended in order to confirm the presence or absence of asbestos.

Samples of suspect ACM collected by S&ME on August 31, 2009 and October 1, 2009 were submitted to S&ME, Inc.'s asbestos laboratory in Charlotte, North Carolina. S&ME's asbestos laboratory is accredited under the National Voluntary Laboratory Accreditation Program, NVLAP ID 102075-0. The collected samples were analyzed for asbestos using polarized light microscopy (PLM) coupled with dispersion staining (EPA 600/R-93/116 Method). This technique identifies asbestos fibers based on six unique optical and morphological characteristics: morphology, color, refractive index, extinction angle, signs of elongation and dispersion staining colors. The asbestos sampling table in Appendix II summarizes the results of the samples collected. Asbestos content is estimated and expressed as a percent of the total sample. The laboratory analytical report is included in Appendix III.

The EPA considers a material to be asbestos-containing if the asbestos content is greater than 1% by weight/volume. Asbestos-containing materials can be classified as friable or non-friable. Friable materials are more susceptible to damage and may potentially release fibers more readily than non-friable materials. Friable materials can be differentiated (from non-friable materials) as they can be readily crushed when dry with moderate hand pressure. Examples of typically friable ACM include ceiling tiles and thermal system insulation. Friable materials that contain asbestos or non-friable asbestos containing

materials that are rendered friable by demolition activities are classified as Regulated Asbestos Containing Materials (RACM) under the NESHAP. Under NESHAP non-friable materials are divided into two additional classifications, Category I and Category II. Category I non-friable asbestos-containing material includes asbestos-containing packings, gaskets, resilient floor covering and asphalt roofing products containing more than 1% asbestos. Category II asbestos-containing materials are all other non-friable materials.

Any material found to contain greater than 1% asbestos when analyzed using the EPA 600/R-93/116 Method must be considered to be an asbestos-containing material. If the material contains less than 1% asbestos, as analyzed by this method, it must be presumed to contain asbestos unless the asbestos concentration has been verified by an additional "Point Count" analysis. Point Count Analysis may also be conducted for any results that indicate less than 10% asbestos by standard analysis in the event that standard methods returned an erroneously high result.

Asbestos Survey Findings

Mr. Chris Hamblet (NC Inspector No. 11679) and Mrs. Jo Martin (NC Inspector No. 12580) of S&ME visited the site August 31, 2009 and Mr. Hamblet returned on October 1, 2009 to perform the asbestos survey. A total of 40 bulk samples, representing 19 homogeneous areas of suspect materials, were collected for asbestos analysis. A homogeneous area refers to a grouping of suspect ACMs that are similar in color, texture, size and construction dates. Based on observation of the areas to be impacted, it appears that most of the asbestos materials shown on the asbestos removal design have been removed in these areas, including pipe insulation and vibration dampeners.

The EPA 600/R-93/116 Method mandates independent analysis for each layer of asbestos-suspect material encountered in each sample; therefore some materials sampled required more than one analysis. Examples of suspect ACM consisting of more than one layer would be thermal system insulation that includes an insulation layer and a cloth wrap. Figures identifying the sample locations are attached in Appendix I. Types of materials sampled during this survey are indicated in the attached Asbestos Sampling Table in Appendix II.

Based on laboratory analysis, the following materials were found to contain greater than 1% asbestos:

- Black caulk located on the HVAC equipment joints in several of the penthouses. The caulk appeared to be original and was observed to be in good condition. The caulk was found to contain between up to 12% Chrysotile asbestos. This material is considered a Category II Non-friable material. There is approximately 1,000 linear feet of this material was observed in the following penthouses:
  Penthouses 1, 2, 3, 6, 8, 10, 11 and 12.

- Black tar paper felt on the lower portion of the exterior of the penthouses; this material is considered a Category II non-friable material. The felt was observed to be in fair condition and was found to contain 2% Chrysotile asbestos in only one of the two samples of this material collected. This material is located behind vertical metal panel siding and may be remnant roof flashing that was not removed during roof replacement due to its location. The amount of this material present will need to be quantified prior to demolition after removing the siding panels.

- Remnant rigid white pipe insulation observed on elbows on a 6" terminated steam line; this material is considered a friable material. The insulation material was found to contain 35% Chrysotile asbestos and no asbestos was detected in the wrapping material. Only two of these elbows were observed at one location near Column B21. It appears that this material was missed during the previous asbestos removal. There is the potential that this material is present in other areas of the building that were inaccessible during this survey.

- Remnant fiberglass pipe insulation with a cloth wrap observed on piping on a 6" terminated steam line; this material is considered a Category II non-friable material. The wrapping material was found to contain 2% Chrysotile asbestos in only one of the two samples of this material collected, and no asbestos was detected in the fiberglass insulation material. Only approximately two linear feet of this material was observed at the same location near Column B21. It appears that this material was missed during the previous asbestos removal. There is the potential that this material is present in other areas of the building that were inaccessible during this survey.

Please see the asbestos sampling table in Appendix II and the laboratory analytical report in Appendix III for additional details.

Asbestos Survey Recommendations

It is our understanding that plans are to demolish the existing buildings. For building demolition, ACM is required to be removed if the material is friable, or if the material is non-friable and the demolition operations will render the material to be friable and therefore a "Regulated Asbestos-Containing Material (RACM)". According to the NESHAP RACM is (a) friable ACM, (b) Category I non-friable ACM that has become friable, (c) Category I non-friable ACM that will be or has been subjected to sanding, grinding, cutting or abrading, or (d) Category II non-friable ACM that has a high probability of becoming or has become crumbled, pulverized, or reduced to powder by forces expected to act on the material during demolition or renovation operations.

Activities involving the removal of ACM must be performed in accordance with the NESHAP and other regulations prior to building demolition The North Carolina Department of Environment and Natural Resources, Health Hazards Control Unit,

requires that an *Asbestos Permit Application and Notification for Demolition/Renovation* be submitted by the owner or operator at least ten working days prior to the removal start date if more than 160 square feet, 260 linear feet or 35 cubic feet or greater of RACM are to be removed. Even if no RACM is scheduled for removal, the notification for the demolition activity is still required. If requested, S&ME would appreciate the opportunity to provide a proposal for asbestos abatement design services and air monitoring services for this project. North Carolina regulations require that accredited personnel be utilized for asbestos removal operations on projects such as this.

The quantities of ACM identified in this report are intended only to be approximations based on site observations during the survey. The estimated quantities are not intended to include the entire amount of ACM present within the structure. S&ME recommends that the asbestos abatement designer selected to develop removal specifications verify the amount of ACM to be removed. We recommend that asbestos abatement contractors also verify the amount of ACM to be removed and submit their estimations as part of their scope of work.

LEAD-CONTAINING PAINT SCREENING

On August 31, 2009 and October 1, 2009, Chris Hamblet (NC Lead-Based Paint Inspector and Risk Assessor No. 120010) of S&ME also performed a lead-containing paint screening of interior and exterior building surfaces in the areas to be impacted by the HVAC replacement. S&ME personnel conducted the limited lead-containing paint screening by collecting paint chip samples of various common painted surfaces for lead content analysis. The Occupational Safety and Health Administration (OSHA) has not established a threshold level to define lead-containing paint. OSHA considers paint to be lead-containing if there is any detectable lead above the detection limit for the paint using standard atomic absorption methods of analysis. EPA Method SW 846 3050B*/7420 has been validated for sample weights of 0.02 grams or greater with a Limit of Detection (LOD) of 0.01% by weight for the 0.02 gram size sample. However, the LOD is dependent upon the sample size - the larger the sample size the lower the LOD will be. The location of the painted surface, the condition of the paint, and the work to be performed are other factors that determine if there is a lead hazard and actions required to mitigate the hazard.

It is our understanding that a full United States Department of Housing and Urban Development (HUD) LBP inspection and/or risk assessment in general accordance with HUD Title 10 Guidelines, in conformance with 24CFR35, is not required. A LBP inspection or risk assessment following the HUD guidelines would require a substantially greater level of effort to identify LBP or LBP hazards on a surface-by-surface basis.

S&ME collected a total of 17 paint chip samples from accessible interior and exterior painted surfaces, which may be disturbed during the demolition. S&ME collected paint chip samples from the substrates and locations listed in Table I below.

The paint chip samples were submitted to EMSL's lead laboratory located in Kernersville, North Carolina (AIHA ELLAP lab code #102564) for analysis by Flame Atomic Absorption Spectroscopy, Method SW 846-3050B and 7420 (AAS). This testing method is accurate to 100 parts per billion or micrograms per kilogram. In any lead-containing paint survey, it is possible to fail to detect some paints or types of substrates, especially when lead-containing paint is hidden by an outer paint layer. To address your needs for a limited screening, we have; (1) visually examined representative areas of the buildings that may be affected by the demolition for common painted surfaces observed to be prevalent on the building components, and (2) collected paint chip samples from representative accessible surfaces for analysis of the presence of lead-containing paint.

Only a limited number of paint chip samples were collected and analyzed for lead content as representative results. Therefore, a comprehensive lead based paint survey in general accordance with Chapter 7: Lead-Based Paint Inspection of the HUD *Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing* was not included in our scope of work.

Lead-Containing Paint Findings

The following table summarizes the analysis results of the paint chip samples that were collected during the lead-containing paint screening. Figures identifying the sample locations are attached in Appendix I. The laboratory report for the paint chip analysis is included in Appendix III.

Table I
PAINT CHIP LEAD ANALYSIS RESULTS
MCAS Cherry Point
Cherry Point, North Carolina
Samples Collected August 31, 2009 and October 1, 2009

Building No./ Sample No.	Paint Color	Material Description	Lead Analysis Results (%) wt.
B133-L01	**Green**	**Rooftop Metal Fresh Air Intakes**	**2.9**
B133-L02	**Beige**	**Masonite Wall Boards in Penthouses**	**0.047**
B133-L03	**Silver**	**Penthouse Louvers**	**0.039**
B133-L04	**Yellow**	**Masonite Wall Boards in Penthouses**	**0.036**
B133-L05	**Blue**	**Masonite Wall Boards in Penthouses**	**0.043**
B133-L06	**Yellow**	**Metal Penthouse Roof Access Ladder**	**0.019**
B133-L07	**Beige**	**Penthouse Wood Trusses/Ceiling**	**0.037**
B133-L08	Silver	Rooftop Metal Vents	<0.010
B133-L09	**White**	**Masonite Wall Boards in Penthouses**	**0.021**
B133-L10	Beige	Metal Exterior Doors in Penthouses	<0.010
B133-L11	Brown	Wood Exterior Doors in Penthouses	<0.033
B133-L12	**Yellow**	**Metal Supports for Exterior HVAC Equipment**	**14**
B133-L13	**White**	**Wood Interior Truss System**	**2.1**
B133-L14	**Yellow**	**Wood Interior Truss System**	**2.5**
B133-L15	**Red**	**Floor Paint**	**0.11**
B133-L16	**White**	**Floor Paint**	**0.33**
B133-L17	**White**	**Brick Walls**	**0.32**

Fourteen of the 17 paint chip samples tested positive for lead above the laboratory's detection limits. The components coated with lead-containing paint need to be considered during the demolition of the structures if the paints are to be disturbed. It should be noted that not all painted surfaces were sampled, but representative colors were sampled from the accessible interior and exterior components of the buildings that were observed to be chipping or flaking.

Lead-Containing Paint Recommendations

For building demolition, the State of North Carolina and the EPA will allow a building to be demolished without removing the LBP. It is considered a type of component removal since the lead paint and its substrate typically remain intact. The advantages of removing the component are lower exposure to lead-containing dust and the ability to dispose of the components at most sanitary landfills.

In cases where the paint is to be removed from the substrate or otherwise disturbed, it is recommended that any renovation activities be treated as a lead-containing paint abatement project, using necessary engineering controls to protect the workers and the public. Also, the contractor is required to comply with OSHA regulation 29 CFR 1926.62 concerning lead exposure to its workers during activities that cause the

disturbance of lead paint. **Under no condition should unprotected workers perform sanding, cutting or welding activities on any surface coated with lead-containing paint.**

Lead exposure to construction workers is regulated by the OSHA Standard 29 CFR 1926.62. OSHA considers paint a *potential* hazard if it contains any amount of lead by dry weight when analyzed using ASTM D335-85A "Standard Method to Test for Low Concentrations of Lead in Paint by Atomic Absorption Spectroscopy (AAS)". This standard applies to areas that may be disturbed during renovation or demolition activities. Other factors, such as the location and condition of the paint and work to be done around the paint, determine if there is a lead hazard and what actions need to be taken.

If workers are to disturb the lead-containing paint as described above, they need to be trained in the hazards of lead, in the requirements of 29 CFR 1926.62, and in the requirements of HUD Guidelines[1]. This training includes a detailed description of the hazards to the developing fetus in pregnant women exposed to lead and the importance of personal hygiene, including decontamination procedures for controlling the spread of the lead hazard. The workers are also required to be trained according to 29 CFR 1910.1200 (Hazard Communication). All personnel working with lead are to be medically qualified as required by 29 CFR 1926.62, having completed and passed the physical examination specified therein.

OSHA also requires employers to perform an initial exposure assessment of their workers to assess their exposure to lead-containing dust. Workers are to be protected during the exposure assessment and, if high levels of lead are found in the air, they must continue to wear personal protective equipment and use engineering controls to reduce the airborne lead levels[2]. The employer must demonstrate that worker exposure is below the 30 $\mu g/m^3$ eight-hour time weighted average action level to eliminate further exposure assessment of a specific task.

SOLE USE STATEMENT

All materials and information used on this project were obtained by S&ME. The resulting report is provided for the sole use of our client. Reliance on this report by any third parties will be at such party's sole risk and S&ME disclaims liability for any use of or reliance on this report by third parties. All portions of this report, including attachments, are interrelated and integral to this report and should not be transmitted independent of each other.

1- The (HUD) guidelines do not apply to renovation or other non-target housing/child occupied facilities.
2- Protection is not required for mechanical demolition during the assessment period unless there is reason to expect lead exposures.
3- 30 Micrograms per cubic meter (30 $\mu g/m^3$).

CLOSING

We appreciate the opportunity to serve as your industrial hygiene and environmental consultant for this project and look forward to working with you again in the future. If you have any questions or if we can be of further assistance please call our office at (919) 872-2660.

Sincerely,
S&ME, Inc.

Chris Hamblet, CHMM
Environmental Scientist

Tom Raymond, P.E.
Environmental Services Manager

Attachments: Appendix I – Sample Location Figures
Appendix II – Asbestos Sampling Table
Appendix III – Laboratory Analytical Reports

APPENDIX I

Sample Location Figures



LEGEND

A01 - ASBESTOS SAMPLE LOCATION
L01 - PAINT SAMPLE LOCATION

GRAPHIC SCALE
800 0 400 800
(IN FEET)

DATE: OCT. 2009
SCALE: 1" = 800'
DRAWN BY: BTR
PROJECT NUMBER: 1054-09-143C
CHECKED BY:
DRAWING NUMBER: B-1202

S&ME
WWW.SMEINC.COM
NC ENGINEER LICENSE #F-0176
3201 SPRING FOREST RD, RALEIGH, NC 27616

ROOF / PENTHOUSE SAMPLE LOCATIONS

BUILDING B133 HVAC REPLACEMENT - MCAS CHERRY POINT
CHERRY POINT, NORTH CAROLINA

FIGURE NO.
1

S:\PROJECTS\2009\09-143 MCAS Cherry Point Env and IH Services\CAD\B1202.dwg, B1202, 10/12/2009 4:36:20 PM, 1:1



LEGEND

A01 - ASBESTOS SAMPLE LOCATION
L01 - PAINT SAMPLE LOCATION

GRAPHIC SCALE
800 0 400 800
(IN FEET)

SCALE: 1" = 800'	PROJECT NUMBER: 1054-09-143C	DRAWN BY: BTR	DATE: OCT. 2009
	DRAWING NUMBER: B-1203	CHECKED BY:	

S&ME
WWW.SMEINC.COM
NC ENGINEER LICENSE #F-0176
3201 SPRING FOREST RD, RALEIGH, NC 27616

INTERIOR SAMPLE LOCATIONS

BUILDING B133 HVAC REPLACEMENT - MCAS CHERRY POINT
CHERRY POINT, NORTH CAROLINA

FIGURE NO.
2

S:\PROJECTS\2009\09-143 MCAS Cherry Point Env and IH Services\CAD\B1203.dwg, B1203, 10/12/2009 4:36:46 PM, 1:1

APPENDIX II

Asbestos Sampling Table

ASBESTOS SAMPLING TABLE
Building B133 HVAC Replacement
MCAS Cherry Point
Cherry Point, North Carolina
S&ME PROJECT NO. 1054-09-143C

HOMOGENEOUS AREA (HA)			SAMPLE			ASSESSMENT	
Name	Description	Location	Number	PLM Results	Count Results	Condition	Approx. Amount
A	TSI-NF-II Cloth wrap over fiberglass duct insulation	Throughout penthouses	B133-A01	ND	N/A	N/A	N/A
			B133-A02	ND	N/A		
B	TSI-NF-II Cloth wrap over fiberglass pipe insulation	Throughout penthouses	B133-A03	ND	N/A	N/A	N/A
			B133-A11	ND	N/A		
C	MISC-NF-II Silver exterior paint	Louvers on penthouse walls	B133-A04	ND	N/A	N/A	N/A
			B133-A18	ND	N/A		
D	MISC-NF-II Exterior caulk	Around louvers and penetrations on penthouse walls	B133-A05	ND	N/A	N/A	N/A
			B133-A09	ND	N/A		
E	**MISC-NF-II Black caulk on HVAC system**	**HVAC equipment joints - observed in Penthouses 1, 2, 3, 6, 8, 10, 11, and 12**	**B133-A06**	**ND**	**N/A**	**Fair**	**~1,000 lf**
			B133-A12	**12% chrysotile asbestos**	**N/A**		
F	MISC-NF-II Gray duct sealant	Ductwork - observed in Penthouse 3	B133-A10	ND	N/A	N/A	N/A
			B133-A21	ND	N/A		

Inspector: Chris Hamblet (NC 11679)
Jo Martin (NC 12580)
Sampling Date: 8/31/2009 and 10/1/09

ND = None Detected
DNA = Did not analyze
N/A = Not Applicable
sf = square feet

SURF = Surfacing material
MISC = Miscellaneous material
TSI = Thermal system insulation
lf = linear feet

F = Friable material
NF-I = Category I non-friable material
NF-II = Category II non-friable material

ASBESTOS SAMPLING TABLE
Building B133 HVAC Replacement
MCAS Cherry Point
Cherry Point, North Carolina
S&ME PROJECT NO. 1054-09-143

S&ME PROJECT NO. 1054-09-143C			SAMPLE			ASSESSMENT	
Name	Description	Location	Number	PLM Results	Point Count Results	Condition	Approx. Amount
G	MISC-NF-II White pipe sealant	HVAC system piping in penthouses	B133-A08	ND	N/A	N/A	N/A
			B133-A13	ND	N/A		
H	MISC-NF-II Silver exterior paint	HVAC equipment supports on roof	B133-A10	ND	N/A	N/A	N/A
			B133-A21	ND	N/A		
I	MISC-NF-II Tar paper felt	Observed on penthouse walls around louvers	B133-A14	ND	N/A	N/A	N/A
			B133-A17	ND	N/A		
J	**MISC-NF-II Tar paper felt**	**Lower portion of exterior walls of penthouses behind vertical aluminum siding panels**	**B133-A15**	**ND**	**N/A**	**Good**	**Unknown**
			B133-A16	**2% Chrysotile**	**N/A**		
K	MISC-NF-II Silver exterior paint	Roof vents/equipment	B133-A19	ND	N/A	N/A	N/A
			B133-A20	ND	N/A		
L	MISC-NF-I Suprema layered roof system - roll asphalt, foil, foam and felt layers - flashing	Main and penthouse roofs	B133-A23	ND	N/A	N/A	N/A
			B133-A25	ND	N/A		
			B133-A28	ND	N/A		

Inspector: Chris Hamblet (NC 11679)
Jo Martin (NC 12580)

Sampling Date: 8/31/2009 and 10/1/09

ND = None Detected
DNA = Did not analyze
N/A = Not Applicable
sf = square feet

SURF = Surfacing material
MISC = Miscellaneous material
TSI = Thermal system insulation
lf = linear feet

F = Friable material
NF-I = Category I non-friable material
NF-II = Category II non-friable material

ASBESTOS SAMPLING TABLE
Building B133 HVAC Replacement
MCAS Cherry Point
Cherry Point, North Carolina
S&ME PROJECT NO. 1054-09-143

S&ME PROJECT NO. 1054-09-143C			SAMPLE			ASSESSMENT	
Name	**Description**	**Location**	**Number**	**PLM Results**	**Point Count Results**	**Condition**	**Approx. Amount**
M	MISC-NF-I Suprema layered roof system - roll asphalt, foil, foam and felt layers - field of roof	Main and penthouse roofs	B133-A24	ND	N/A	N/A	N/A
			B133-A26	ND	N/A		
			B133-A27	ND	N/A		
N	MISC-NF-II Layered asphalt felt siding	Exterior walls of penthouses behind vertical aluminum siding panels	B133-A29	ND	N/A	N/A	N/A
			B133-A30	ND	N/A		
O	TSI-NF-II Cloth wrap over fiberglass pipe insulation	Interior HVAC system piping	B133-A31	ND	N/A	N/A	N/A
			B133-A32	ND	N/A		
P	**TSI-F** **Remnant rigid white pipe insulation on elbows of interior 6" steam line**	**Near column B21 above access ladder - may exist in other areas**	**B133-A33**	**Wrap = ND** **Insulation = 35% Chrysotile**	**N/A**	**Poor**	**2 elbows observed**
			B133-A39	**Wrap = ND** **Insulation = 35% Chrysotile**	**N/A**		
Q	**TSI-NF-II** **Remnant cloth wrap over fiberglass pipe insulation**	**Near column B21 above access ladder - may exist in other areas**	**B133-A34**	**Wrap = 2% Chrysotile** **Insulation = ND**	**N/A**	**Fair**	**2 lf observed**
			B133-A40	**Wrap = ND** **Insulation = ND**	**N/A**		
R	MISC-NF-II Remnant interior HVAC system vibration dampener	Near column B28 near access ladder	B133-A35	ND	N/A	N/A	N/A
			B133-A36	ND	N/A		

Inspector: Chris Hamblet (NC 11679)
Jo Martin (NC 12580)

Sampling Date: 8/31/2009 and 10/1/09

ND = None Detected
DNA = Did not analyze
N/A = Not Applicable
sf = square feet

SURF = Surfacing material
MISC = Miscellaneous material
TSI = Thermal system insulation
lf = linear feet

F = Friable material
NF-I = Category I non-friable material
NF-II = Category II non-friable material

ASBESTOS SAMPLING TABLE
Building B133 HVAC Replacement
MCAS Cherry Point
Cherry Point, North Carolina
S&ME PROJECT NO. 1054-09-143

S&ME PROJECT NO. 1054-09-143C			SAMPLE			ASSESSMENT	
Name	Description	Location	Number	PLM Results	Point Count Results	Condition	Approx. Amount
S	MISC-NF-II Black HVAC equipment caulk	Interior HVAC equipment	CP-A-37	ND	N/A	N/A	N/A
			CP-A-38	ND	N/A		

Inspector: Chris Hamblet (NC 11679)
Jo Martin (NC 12580)

Sampling Date: 8/31/2009 and 10/1/09

ND = None Detected
DNA = Did not analyze
N/A = Not Applicable
sf = square feet

SURF = Surfacing material
MISC = Miscellaneous material
TSI = Thermal system insulation
lf = linear feet

F = Friable material
NF-I = Category I non-friable material
NF-II = Category II non-friable material

APPENDIX III

Laboratory Analytical Reports

S&ME
9731G Southern Pine Boulevard
Charlotte, NC 28273
704-940-1830 Fax 704-565-4929
NVLAP ID 102075-0

POLARIZED LIGHT MICROSCOPY
Performed by EPA 600/R-93/116 Method

Asbestos Analysis Summary

Client Name Raleigh Branch
Client Job MCAS Cherry Pt. B133 HVAC Replacement

3201 Spring Forest Rd.
Raleigh NC 27616

Date Received 9/3/2009
Date Analyzed 9/4/2009

Job Number 1054-09-143C

Lab ID:	*Sample #:*	*Appearance*	*Comments*	*Asbestos %/Type*	*Non-Asbestos Fibrous %/Type*	*Non-Fibrous %/Type*
09-18326	B133-A01	BEIGE FIBROUS		ND	98 CELLULOSE 1 GLASS	1 OTHER
09-18327	B133-A02	BEIGE/SILVER FIBROUS		ND	90 CELLULOSE 5 GLASS	5 OTHER
09-18328	B133-A03	BEIGE/SILVER FIBROUS		ND	30 CELLULOSE 10 GLASS	60 OTHER
09-18329	B133-A04	SILVER NONFIBROUS		ND		100 OTHER

Analyzed by: Jane Wasilewski
Additional Comments:

Jane Wasilewski
Laboratory Manager

For heterogeneous samples easily separated into subsamples, and for layered samples, each component is analyzed separately. ND = None Detected (Asbestos Not Present In Representative Sample). RCF= (Refractory Ceramic Fiber) The results pertain only to the sample identification above.
The sample may not be fully representative of the larger material in question. This sheet may not be reproduced except with permission from SME, Inc. This report may not be used to claim product endorsement by NVLAP or any agency of the U.S. Government. Although Polarized Light Microscopy (PLM/Dispersion Staining) (Method EPA 600/R-93/116) is the specified method for analysis of bulk material samples for asbestos under the EPA Asbestos Hazard Emergency Response Act, there have been reports that this method may not identify asbestos when fiber sizes are extremely small or if they are bound in a resinous material. Such materials include floor tile, mastic and asphaltic roofing. Currently, reanalysis by Transmission Electron Microscopy (TEM) to verify results of <1% or "None Detected" for these materials is recommended.

Job Number 1054-09-143C

Lab ID:	*Sample #:*	*Appearance*	*Comments*	*Asbestos %/Type*	*Non-Asbestos Fibrous %/Type*	*Non-Fibrous %/Type*
09-18330	B133-A05	BEIGE PLIABLE		ND		100 OTHER
09-18331	B133-A06	BLACK NONFIBROUS		ND		100 OTHER
09-18332	B133-A07	GREY NONFIBROUS		ND		100 OTHER
09-18333	B133-A09	BEIGE PLIABLE		ND		100 OTHER
09-18334	B133-A10	GREY NONFIBROUS		ND	<1 CELLULOSE	100 OTHER
09-18335	B133-A11	GREY FIBROUS		ND	5 CELLULOSE 5 GLASS	90 OTHER

Analyzed by: Jane Wasilewski

Additional Comments:

Jane Wasilewski
Laboratory Manager

For heterogeneous samples easily separated into subsamples, and for layered samples, each component is analyzed separately. ND = None Detected (Asbestos Not Present In Representative Sample). RCF= (Refractory Ceramic Fiber) The results pertain only to the sample identification above.
The sample may not be fully representative of the larger material in question. This sheet may not be reproduced except with permission from SME, Inc. This report may not be used to claim product endorsement by NVLAP or any agency of the U.S. Government. Although Polarized Light Microscopy (PLM/Dispersion Staining) (Method EPA 600/R-93/116) is the specified method for analysis of bulk material samples for asbestos under the EPA Asbestos Hazard Emergency Response Act, there have been reports that this method may not identify asbestos when fiber sizes are extremely small or if they are bound in a resinous material. Such materials include floor tile, mastic and asphaltic roofing. Currently, reanalysis by Transmission Electron Microscopy (TEM) to verify results of <1% or "None Detected" for these materials is recommended.

Job Number 1054-09-143C

Lab ID:	*Sample #:*	*Appearance*	*Comments*	*Asbestos %/Type*	*Non-Asbestos Fibrous %/Type*	*Non-Fibrous %/Type*
09-18336	B133-A12	BLACK FIBROUS		12 CHRYSOTILE		88 OTHER
09-18337	B133-A13	TAN NONFIBROUS		ND		100 OTHER
09-18338	B133-A14	BLACK FIBROUS		ND	75 CELLULOSE	25 OTHER
09-18339	B133-A15	BLACK FIBROUS		ND	10 CELLULOSE <1 GLASS	90 OTHER
09-18339A	B133-A08	BEIGE PLIABLE		ND	1 CELLULOSE <1 WOLLASTONITE	99 OTHER
09-18340	B133-A16	BLACK FIBROUS		2 CHRYSOTILE	35 CELLULOSE	63 OTHER

Analyzed by: Jane Wasilewski

Additional Comments:

Jane Wasilewski
Laboratory Manager

For heterogeneous samples easily separated into subsamples, and for layered samples, each component is analyzed separately. ND = None Detected (Asbestos Not Present In Representative Sample). RCF= (Refractory Ceramic Fiber) The results pertain only to the sample identification above.
The sample may not be fully representative of the larger material in question. This sheet may not be reproduced except with permission from SME, Inc. This report may not be used to claim product endorsement by NVLAP or any agency of the U.S. Government. Although Polarized Light Microscopy (PLM/Dispersion Staining) (Method EPA 600/R-93/116) is the specified method for analysis of bulk material samples for asbestos under the EPA Asbestos Hazard Emergency Response Act, there have been reports that this method may not identify asbestos when fiber sizes are extremely small or if they are bound in a resinous material. Such materials include floor tile, mastic and asphaltic roofing. Currently, reanalysis by Transmission Electron Microscopy (TEM) to verify results of <1% or "None Detected" for these materials is recommended.

Job Number 1054-09-143C

Lab ID:	*Sample #:*	*Appearance*	*Comments*	*Asbestos %/Type*	*Non-Asbestos Fibrous %/Type*	*Non-Fibrous %/Type*
09-18341	B133-A17	BLACK FIBROUS		ND	75 CELLULOSE <1 SYNTHETIC	25 OTHER
09-18342	B133-A18	SILVER NONFIBROUS		ND		100 OTHER
09-18343	B133-A19	SILVER NONFIBROUS		ND	2 CELLULOSE	98 OTHER
09-18344	B133-A20	SILVER NONFIBROUS		ND	2 CELLULOSE	98 OTHER
09-18345	B133-A21	SILVER NONFIBROUS		ND	2 CELLULOSE	98 OTHER
09-18346	B133-A22	GREY NONFIBROUS		ND		100 OTHER

Analyzed by: Jane Wasilewski

Additional Comments:

Jane Wasilewski
Laboratory Manager

For heterogeneous samples easily separated into subsamples, and for layered samples, each component is analyzed separately. ND = None Detected (Asbestos Not Present In Representative Sample). RCF= (Refractory Ceramic Fiber) The results pertain only to the sample identification above. The sample may not be fully representative of the larger material in question. This sheet may not be reproduced except with permission from SME, Inc. This report may not be used to claim product endorsement by NVLAP or any agency of the U.S. Government. Although Polarized Light Microscopy (PLM/Dispersion Staining) (Method EPA 600/R-93/116) is the specified method for analysis of bulk material samples for asbestos under the EPA Asbestos Hazard Emergency Response Act, there have been reports that this method may not identify asbestos when fiber sizes are extremely small or if they are bound in a resinous material. Such materials include floor tile, mastic and asphaltic roofing. Currently, reanalysis by Transmission Electron Microscopy (TEM) to verify results of <1% or "None Detected" for these materials is recommended.

BULK SAMPLE

CHAIN OF CUSTODY RECORD

S&ME
ENVIRONMENTAL SERVICES
ENGINEERING • TESTING

PROJECT NO.	PROJECT NAME	RELINQUISHED BY:	DATE	TIME	RECEIVED BY:
10511 09-143 C	Building B133 HVAC Replacement	Chris Hamblet	9/2/09	1600	9/3/09
FACILITY		RELINQUISHED BY:	DATE	TIME	RECEIVED BY:
MCAS Cherry Pt.					
SAMPLER(S)	**DATE TAKEN**	RELINQUISHED BY:	DATE	TIME	RECEIVED BY:
Chris Hamblet / Jo Martin	8/31/09				

SAMPLE #	HOMOGENEOUS AREA	MATERIAL TYPE	LAB NUMBER	DATE ANALYZED	ANALYSTS INITIALS	ASBESTOS +	ASBESTOS N/D	ARCHIVE NUMBER	DATE ARCH	ARCHIVER INITIALS	SPECIAL INSTRUCTIONS
B133-A01	A	P	09-18326								Duct Insulation
02	A	P	27								↓
03	B	E	28								
04	C	P	29								Silver coating
05	D	P	30								Caulk
06	E	P	31								↓
07	F	P	32								Duct sealant
09	D	P	33								Caulk
10	H	P	34								Silver coating
11	B	E	35								
12	E	P	36								Caulk
13	G	P	37								↓
14	I	P	38								Felt
15	J	P	09-18339								Asphaltic siding
~~08~~ 16	G	P	39A								Caulk

ALL SAMPLES WILL BE DISPOSED OF NINETY DAYS AFTER ANALYSIS UNLESS OTHERWISE REQUESTED

MATERIAL TYPES

A - <4" Pipe Fitting	G - 9-14" Pipe	M - A.H.U. Exp. Jt.
B - 4-8" Pipe Fitting	H - >14" Pipe	N - Ceiling/Wall Tile
C - 9-14" Pipe Fitting	I - Spray-On/Trowel	O - Fiberboard
D - >14" Pipe Fitting	J - Floor Tile	P - Other (See notes - Front or back)
E - <4" Pipe	K - Tanks/Boiler	
F - 4-8" Pipe	L - A.H.U. Insul.	

72 hr. turn. Thanks,
Chris

S&ME SFI-002 (REV. 5/93) This document was prepared pursuant to a specific agreement to address the unique requirements of an S&ME client. Prior to further use, an S&ME professional should be contacted for a complete explanation of its preparation and contents.

BULK SAMPLE

CHAIN OF CUSTODY RECORD

S&ME
ENVIRONMENTAL SERVICES
ENGINEERING • TESTING

PROJECT NO.	PROJECT NAME	RELINQUISHED BY:	DATE	TIME	RECEIVED BY:
105Y-09-143C	Building B133 HVAC Replacement	Chris Hambley	9/2/09	1600	9/3/09
FACILITY		RELINQUISHED BY:	DATE	TIME	RECEIVED BY:
MCAS Cherry Point					
SAMPLER(S)	**DATE TAKEN**	RELINQUISHED BY:	DATE	TIME	RECEIVED BY:
Chris Hambley / Jo Martin	8/31/09				

SAMPLE #	HOMOGENEOUS AREA	MATERIAL TYPE	LAB NUMBER	DATE ANALYZED	ANALYSTS INITIALS	ASBESTOS +	ASBESTOS N/D	ARCHIVE NUMBER	DATE ARCH	ARCHIVER INITIALS	SPECIAL INSTRUCTIONS
B133-A16	J	P	09-18340								Asphaltic siding
-A17	L	P	"								Felt
18	C	P	"								Silver Coating
19	K	P	"								"
20	K	P	"								"
21	H	P	"								"
22	F	P	09-18346								"

ALL SAMPLES WILL BE DISPOSED OF NINETY DAYS AFTER ANALYSIS UNLESS OTHERWISE REQUESTED

MATERIAL TYPES

A - <4" Pipe Fitting
B - 4-8" Pipe Fitting
C - 9-14" Pipe Fitting
D - >14" Pipe Fitting
E - <4" Pipe
F - 4-8" Pipe
G - 9-14" Pipe
H - >14" Pipe
I - Spray-On/Trowel
J - Floor Tile
K - Tanks/Boiler
L - A.H.U. Insul.
M - A.H.U. Exp. Jt.
N - Ceiling/Wall Tile
O - Fiberboard
P - Other (See notes - Front or back)

S&ME SFI-002 (REV. 5/93) This document was prepared pursuant to a specific agreement to address the unique requirements of an S&ME client. Prior to further use, an S&ME professional should be contacted for a complete explanation of its preparation and contents.

S&ME
9731G Southern Pine Boulevard
Charlotte, NC 28273
704-940-1830 Fax 704-565-4929
NVLAP ID 102075-0

POLARIZED LIGHT MICROSCOPY
Performed by EPA 600/R-93/116 Method

Asbestos Analysis Summary

Client Name Raleigh Branch
3201 Spring Forest Rd.
Raleigh NC 27616

Client Job MCAS Cherry Pt B133 HVAC Replacement

Date Received 10/5/2009
Date Analyzed 10/6/2009

Job Number 1054-09-143C

Lab ID:	Sample #:	Appearance	Comments	Asbestos %/Type	Non-Asbestos Fibrous %/Type	Non-Fibrous %/Type
09-19946A	B133-A23	BLACK FIBROUS	ROOF	ND	10 SYNTHETIC	90 OTHER
09-19946B	B133-A23	GREY/SILVER FIBROUS	INSULATION	ND	10 GLASS 1 CELLULOSE	85 GYPSUM 4 OTHER
09-19946C	B133-A23	YELLOW SPONGY	FOAM	ND		100 OTHER
09-19946D	B133-A23	BLACK FIBROUS	FELT	ND	65 CELLULOSE	35 OTHER

Jane Wasilewski
Laboratory Manager

Analyzed by: Jane Wasilewski

Additional Comments:

For heterogeneous samples easily separated into subsamples, and for layered samples, each component is analyzed separately. ND = None Detected (Asbestos Not Present In Representative Sample). RCF= (Refractory Ceramic Fiber) The results pertain only to the sample identification above.
The sample may not be fully representative of the larger material in question. This sheet may not be reproduced except with permission from SME, Inc. This report may not be used to claim product endorsement by NVLAP or any agency of the U.S. Government. Although Polarized Light Microscopy (PLM/Dispersion Staining) (Method EPA 600/R-93/116) is the specified method for analysis of bulk material samples for asbestos under the EPA Asbestos Hazard Emergency Response Act, there have been reports that this method may not identify asbestos when fiber sizes are extremely small or if they are bound in a resinous material. Such materials include floor tile, mastic and asphaltic roofing. Currently, reanalysis by Transmission Electron Microscopy (TEM) to verify results of <1% or "None Detected" for these materials is recommended.

EMSL Analytical, Inc.
706 Gralin Street, Kernersville, NC 27284
Phone: (336) 992-1025 Fax: (336) 992-4175 Email: greensborolab@emsl.com

Attn: **Chris Hamblet**
S&ME, Inc.
3201 Spring Forest Road
Raleigh, NC 27616

Fax: (919) 790-9827 Phone: (919) 872-2660
Project: **1054-09-143C/ MCAS Cherry Point**

Customer ID: SMEI60
Customer PO: 17948
Received: 09/03/09 10:00 AM
EMSL Order: 020905173

EMSL Proj:

Test Report: Lead in Paint Chips by Flame AAS (SW 846 3050B*/7000B)

Client Sample Description	*Lab ID*	*Collected*	*Analyzed*	*Lead Concentration*
B133-L01	*0001*		9/3/2009	2.9 % wt
B133-L02	*0002*		9/3/2009	0.047 % wt
B133-L03	*0003*		9/3/2009	0.039 % wt
B133-L04	*0004*		9/3/2009	0.036 % wt
B133-L05	*0005*		9/3/2009	0.043 % wt
B133-L06	*0006*		9/3/2009	0.019 % wt
B133-L07	*0007*		9/3/2009	0.037 % wt
B133-L08	*0008*		9/3/2009	<0.010 % wt
B133-L09	*0009*		9/3/2009	0.021 % wt
B133-L10	*0010*		9/3/2009	<0.010 % wt
B133-L11	*0011*		9/3/2009	<0.033 % wt
B133-L12	*0012*		9/3/2009	14 % wt

Suggested sample weight for chips is .2 grams. B133-L11 had weight of .0602 grams causing the reporting limit to be <0.033%.

James Cole

James Cole, Laboratory Manager
or other approved signatory

Reporting limit is 0.01 % wt. The QC data associated with these results included in this report meet the method QC requirements, unless specifically indicated otherwise. Unless noted, esults in this report are not blank corrected. EMSL bears no responsibility for sample collection activities. Samples received in good condition unless otherwise noted. * slight nodifications to methods applied.
Samples analyzed by EMSL Analytical, Inc. Kernersville 706 Gralin Street, Kernersville NC AIHA ELLAP 102564

Chain of Custody 5173

Lead Lab Services

EMSL Analytical, Inc.
706 Gralin Street
Kernersville, NC 27284

Phone: (336) 992-1025
Fax: (336) 992-4175
http://www.emsl.com

Please print all information legibly.

Company:	S&ME	***Bill To:***	S&ME
Address1:	3201 Spring Forest Road	*Address1:*	3201 Spring Forest Road
Address2:		*Address2:*	
City, State:	Raleigh, NC	*City, State:*	Raleigh, NC
Zip/Post Code:	27616	*Zip/Post Code:*	27616
Country:	US	*Country:*	US
Contact Name:	Chris Hamblet	***Attn:***	Chris Hamblet
Phone:	(919)872-2660	*Phone:*	(919)872-2660
Fax:	(919) 876-3958	*Fax:*	(919) 876-3958
Email:	jmartin@smeinc.com	*Email:*	jmartin@smeinc.com
EMSL Rep:	Jason MacDonald	***P.O. Number:***	17948
Project Name/Number: 1054-09-~~237~~ -143 C / MCAS Cherry Point			

MATRIX	METHOD	INSTRUMENT	RL (Reporting Limit)	TAT
Lead Chips*	SW846-7420, 3050B Mod./AOAC(974.02)	Flame Atomic Absorption	0.01% ++	48 hr.
Lead WasteWater	SW846-7420	Flame Atomic Absorption	0.4 mg/l water	
Lead Soil +			40 mg/kg (ppm) soil	
	or SW846-6010B	ICP	0.1 mg/l water	
			10 mg/kg (ppm) soil	
Lead in Air ***	NIOSH 7082 Mod.	Flame Atomic Absorption	4 ug/filter	
	or NIOSH 7300 Mod.	ICP	3.0 ug/filter	
Lead in Wipe^ ☐ -ASTM *List Wipe Type* _____ ☐ -non ASTM	SW846-7420 / HUD Appendix 14.2 Digest	Flame Atomic Absorption	10 ug/wipe	
	or SW846-6010B	ICP	3.0 ug/wipe	
TCLP Lead **	SW846-1311/ 7420	Flame Atomic Absorption	0.4 mg/l (ppm)	
	or SW846-6010B	ICP	0.1 mg/l (ppm)	
STLC Lead (California) #	CA Title 22 66261.126/ SW846-7420	Flame Atomic Absorption	0.4 mg/l (ppm)	
	or SW846-6010B	ICP	0.1 mg/l (ppm)	
Lead in Air ****	NIOSH 7105 Mod.	Graphite Furnace Atomic Absorption	0.03 ug/filter	
Lead WasteWater	SW846-7421	Graphite Furnace Atomic Absorption	0.003 mg/l (ppm) water	
Lead Soil +			0.03 mg/kg (ppm) soil	
Lead in Drinking Water (check state Certification requirements)	EPA 239.2 / 200.9	Graphite Furnace Atomic Absorption	0.003 mg/l (ppm)	
Total Dust	NIOSH 0500-0600	Gravimetric Reduction	0.0001g	

TAT (Turnaround) - Same day, 24 hr - 1 Day, 2 Days, 3 Days, 4 Days, 5 Days, 6-10 Days
*, **, ***, ****, +, ++ ,# Please Refer to Price Quote
^ If no box is checked, non-ASTM is assumed

KH 9/3 10:00

Chain of Custody

EMSL Analytical, Inc.
706 Gralin Street

Lead Lab Services 5173

Kernersville, NC 27284
Phone: (336) 992-1025
Fax: (336) 992-4175
http://www.emsl.com

Please print all information legibly.

SAMPLE #	LOCATION	Air Volume, L Area, in²	LAB #
B133-LD1	Green, roof make-up unit, metal 2 units		
B133-L-02	Beige, masonite boards, Penthouse 6 on walls & doors		
B133-L03	Silver, paint on louvres, Penthouse 8		
B133-L04	Yellow, masonite panels 6' to floor, Penthouse 8		
B133-L05	Blue, masonite panels 6' to ceiling Penthouse 8		
B133 L06	Yellow, roof access ladder on Penthouse No. 5, metal	FG piping	
B133-L07	Beige on wood supports (trusses) Penthouse 4	> white - empty	
No. 3 → Large Unit - Asb Sample			
B133-L08	Silver, exterior rooftop unit		
No 9 → ½ empty - unit running other half, beige/white paint			
B133-L09	White, int masonite panels Penthouse 9		caulking on door frames
B133-L10	Beige on metal doors Penthouse 9		
B133-L11	Brown, on exit door to Pf. 12, wood		

@Relinquished By: (Person) Chris Hamblett **Date:** 9/2/09

Received at EMSL by: _____ **Date:** _____

Received at EMSL by: _____ **Date:** _____

Note: Please duplicate this form and use additional sheets if necessary.

@ The individual signing and relinquishing these samples to the laboratory attests to the accuracy of the information reported on this chain of custody.

Lead Lab Services 5173

EMSL
Kernersville, NC 27284
Phone: (336) 992-1025
Fax: (336) 992-4175
http://www.emsl.com

Please print all information legibly.

SAMPLE #	LOCATION	Air Volume, L Area, in²	LAB #
B133 - L12	Yellow, support beam to large duct, metal		
	Penthouse 2	12' + 8'	
	System Running		
	large system 3		
	Beige-Yellow walls	interior → 2nd floor	
			pt 3 " exterior side

@Relinquished By: (Person) Chris Hamblet Date: 9/2/09

Received at EMSL by: _____ Date: _____

Received at EMSL by: _____ Date: _____

Note: Please duplicate this form and use additional sheets if necessary.

@ The individual signing and relinquishing these samples to the laboratory attests to the accuracy of the information reported on this chain of custody.

EMSL Analytical, Inc.
706 Gralin Street, Kernersville, NC 27284
Phone: (336) 992-1025 Fax: (336) 992-4175 Email: greensborolab@emsl.com

Attn: **Chris Hamblet**
S&ME, Inc.
3201 Spring Forest Road
Raleigh, NC 27616

Fax: (919) 790-9827 Phone: (919) 872-2660
Project: **1054-09-143C**

Customer ID: SMEI60
Customer PO: 17948
Received: 10/05/09 10:00 AM
EMSL Order: 020905836

EMSL Proj:

Test Report: Lead in Paint Chips by Flame AAS (SW 846 3050B*/7000B)

Client Sample Description	*Lab ID*	*Collected*	*Analyzed*	*Lead Concentration*
B133-L-14	*0001*		10/6/2009	2.5 % wt
B133-L-13	*0002*		10/6/2009	2.1 % wt
B133-L-15	*0003*		10/6/2009	0.11 % wt
B133-L-16	*0004*		10/6/2009	0.33 % wt
B133-L-17	*0005*		10/6/2009	0.32 % wt

James Cole

James Cole, Laboratory Manager
or other approved signatory

Reporting limit is 0.01 % wt. The QC data associated with these results included in this report meet the method QC requirements, unless specifically indicated otherwise. Unless noted, results in this report are not blank corrected. EMSL bears no responsibility for sample collection activities. Samples received in good condition unless otherwise noted. * slight modifications to methods applied.

Samples analyzed by EMSL Analytical, Inc. Kernersville 706 Gralin Street, Kernersville NC AIHA ELLAP 102564

Chain of Custody 58336

Lead Lab Services

EMSL Analytical, Inc.
706 Gralin Street
Kernersville, NC 27284

Phone: (336) 992-1025
Fax: (336) 992-4175
http://www.emsl.com

Please print all information legibly.

Company:	S&ME	***Bill To:***	S&ME
Address1:	3201 Spring Forest Road	*Address1:*	3201 Spring Forest Road
Address2:		*Address2:*	
City, State:	Raleigh, NC	*City, State:*	Raleigh, NC
Zip/Post Code:	27616	*Zip/Post Code:*	27616
Country:	USA	*Country:*	USA
Contact Name:	Chris Hamblet	***Attn:***	Chris Hamblet
Phone:	919-801-5683	*Phone:*	919-801-5683
Fax:		*Fax:*	
Email:	chamblet@smeinc.com	*Email:*	chamblet@smeinc.com
EMSL Rep:		***P.O. Number:***	17948
Project Name/Number: 1054-09-143C			

MATRIX	METHOD	INSTRUMENT	RL (Reporting Limit)	TAT
Lead Chips*	SW846-7420, 3050B Mod./AOAC(974.02)	Flame Atomic Absorption	0.01% ++	24 hr.
Lead WasteWater	SW846-7420	Flame Atomic Absorption	0.4 mg/l water 40 mg/kg (ppm) soil	
Lead Soil +	or SW846-6010B	ICP	0.1 mg/l water 10 mg/kg (ppm) soil	
Lead in Air ***	NIOSH 7082 Mod.	Flame Atomic Absorption	4 ug/filter	
	or NIOSH 7300 Mod.	ICP	3.0 ug/filter	
Lead in Wipe^ ☐-ASTM *List Wipe Type* _____ ☐-non ASTM	SW846-7420 / HUD Appendix 14.2 Digest	Flame Atomic Absorption	10 ug/wipe	
	or SW846-6010B	ICP	3.0 ug/wipe	
TCLP Lead **	SW846-1311/ 7420	Flame Atomic Absorption	0.4 mg/l (ppm)	
	or SW846-6010B	ICP	0.1 mg/l (ppm)	
STLC Lead (California) #	CA Title 22 66261.126/ SW846-7420	Flame Atomic Absorption	0.4 mg/l (ppm)	
	or SW846-6010B	ICP	0.1 mg/l (ppm)	
Lead in Air ****	NIOSH 7105 Mod.	Graphite Furnace Atomic Absorption	0.03 ug/filter	
Lead WasteWater	SW846-7421	Graphite Furnace Atomic Absorption	0.003 mg/l (ppm) water	
Lead Soil +			0.03 mg/kg (ppm) soil	
Lead in Drinking Water (check state Certification requirements)	EPA 239.2 / 200.9	Graphite Furnace Atomic Absorption	0.003 mg/l (ppm)	
Total Dust	NIOSH 0500-0600	Gravimetric Reduction	0.0001g	

TAT (Turnaround) - Same day, 24 hr - 1 Day, 2 Days, 3 Days, 4 Days, 5 Days, 6-10 Days
*, **, ***, ****, +, ++ ,# Please Refer to Price Quote
^ If no box is checked, non-ASTM is assumed

CH 10/5 10:00

Chain of Custody

EMSL Analytical, Inc.
706 Gralin Street

Lead Lab Services

58316

Kernersville, NC 27284

Phone: (336) 992-1025
Fax: (336) 992-4175
http://www.emsl.com

Please print all information legibly.

SAMPLE #	LOCATION	Air Volume, L Area, in^2	LAB #
B133-L 14	B-28 Yellow		
13	B-21 White Truss + Ceiling		
15	Red/Green Floor		
16	White/Gray Floor		
17	E-6 White/Red/Green wall	Brick	

@Relinquished By: (Person) Chris Hamblet Date: 10/2/09

Received at EMSL by: _____ Date: _____

Received at EMSL by: _____ Date: _____

Note: Please duplicate this form and use additional sheets if necessary.

@ The individual signing and relinquishing these samples to the laboratory attests to the accuracy of the information reported on this chain of custody.

SECTION 02 41 00

DEMOLITION
05/10

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AIR-CONDITIONING, HEATING AND REFRIGERATION INSTITUTE (AHRI)

AHRI Guideline K	(2009) Guideline for Containers for Recovered Non-Flammable Fluorocarbon Refrigerants

AMERICAN SOCIETY OF SAFETY ENGINEERS (ASSE/SAFE)

ASSE/SAFE A10.6	(2006) Safety Requirements for Demolition Operations

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2008; Errata 1-2010; Changes 1-3 2010; Changes 4-6 2011; Change 7 2012) Safety and Health Requirements Manual

U.S. DEFENSE LOGISTICS AGENCY (DLA)

DLA 4145.25	(June 2000) Storage and Handling of Liquefied and Gaseous Compressed Gases and Their Full and Empty Cylinders

U.S. DEPARTMENT OF DEFENSE (DOD)

DOD 4000.25-1-M	(2006) MILSTRIP - Military Standard Requisitioning and Issue Procedures
MIL-STD-129	(2014; Rev R) Military Marking for Shipment and Storage

U.S. FEDERAL AVIATION ADMINISTRATION (FAA)

FAA AC 70/7460-1	(2007; Rev K) Obstruction Marking and Lighting

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

40 CFR 61	National Emission Standards for Hazardous Air Pollutants
49 CFR 173.301	Shipment of Compressed Gases in Cylinders and Spherical Pressure Vessels

1.2 PROJECT DESCRIPTION

1.2.1 Demolition Plan

Prepare a Demolition Plan and submit proposed demolition and removal procedures for approval before work is started. Include in the plan procedures for careful removal and disposition of materials specified to be salvaged, coordination with other work in progress, a disconnection schedule of utility services, a detailed description of methods and equipment to be used for each operation and of the sequence of operations. Identify components and materials to be salvaged for reuse or recycling with reference to paragraph Existing Facilities to be Removed. Append tracking forms for all removed materials indicating type, quantities, condition, destination, and end use. Coordinate with Waste Management Plan.

Include statements affirming Contractor inspection of the existing roof deck and its suitability to perform as a safe working platform or if inspection reveals a safety hazard to workers, state provisions for securing the safety of the workers throughout the performance of the work. Provide procedures for safe conduct of the work in accordance with EM 385-1-1. Plan shall be approved by Contracting Officer prior to work beginning.

1.2.2 General Requirements

Do not begin demolition until authorization is received from the Contracting Officer. The work of this section is to be performed in a manner that maximizes the value derived from the salvage and recycling of materials. Remove rubbish and debris from the station daily; do not allow accumulations inside or outside the building. The work includes demolition, salvage of identified items and materials, and removal of resulting rubbish and debris. Remove rubbish and debris from Government property daily, unless otherwise directed. Store materials that cannot be removed daily in areas specified by the Contracting Officer. In the interest of occupational safety and health, perform the work in accordance with EM 385-1-1, Section 23, Demolition, and other applicable Sections.

1.3 ITEMS TO REMAIN IN PLACE

Take necessary precautions to avoid damage to existing items to remain in place, to be reused, or to remain the property of the Government. Repair or replace damaged items as approved by the Contracting Officer. Coordinate the work of this section with all other work indicated. Construct and maintain shoring, bracing, and supports as required. Ensure that structural elements are not overloaded. Increase structural supports or add new supports as may be required as a result of any cutting, removal, deconstruction, or demolition work performed under this contract. Do not overload structural elements. Provide new supports and reinforcement for existing construction weakened by demolition, deconstruction, or removal work. Repairs, reinforcement, or structural replacement require approval by the Contracting Officer prior to performing such work.

1.3.1 Existing Construction Limits and Protection

Do not disturb existing construction beyond the extent indicated or necessary for installation of new construction. Provide temporary shoring and bracing for support of building components to prevent settlement or other movement. Provide protective measures to control accumulation and migration of dust and dirt in all work areas. Remove dust, dirt, and debris from work areas daily.

1.3.2 Weather Protection

For portions of the building to remain, protect building interior and materials and equipment from the weather at all times. Where removal of existing roofing is necessary to accomplish work, have materials and workmen ready to provide adequate and temporary covering of exposed areas.

1.3.3 Utility Service

Maintain existing utilities indicated to stay in service and protect against damage during demolition operations. Prior to start of work, the Government will disconnect and seal utilities serving each area of alteration or removal upon written request from the Contractor.

1.3.4 Facilities

Protect electrical and mechanical services and utilities. Where removal of existing utilities and pavement is specified or indicated, provide approved barricades, temporary covering of exposed areas, and temporary services or connections for electrical and mechanical utilities. Floors, roofs, walls, columns, pilasters, and other structural components that are designed and constructed to stand without lateral support or shoring, and are determined to be in stable condition, must remain standing without additional bracing, shoring, or lateral support until demolished or deconstructed, unless directed otherwise by the Contracting Officer. Ensure that no elements determined to be unstable are left unsupported and place and secure bracing, shoring, or lateral supports as may be required as a result of any cutting, removal, deconstruction, or demolition work performed under this contract.

1.4 BURNING

The use of burning at the project site for the disposal of refuse and debris will not be permitted.

1.5 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Existing Conditions

SD-07 Certificates

Demolition Plan
Notification

1.6 QUALITY ASSURANCE

Submit timely notification of demolition and renovation projects to Federal, State, regional, and local authorities in accordance with 40 CFR 61, Subpart M. Notify the Regional Office of the United States Environmental Protection Agency (USEPA), State's environmental protection agency, local air pollution control district/agency and the Contracting Officer in writing 10 working days prior to the commencement of work in accordance

with 40 CFR 61, Subpart M. Comply with federal, state, and local hauling and disposal regulations. In addition to the requirements of the "Contract Clauses," conform to the safety requirements contained in ASSE/SAFE A10.6. Comply with the Environmental Protection Agency requirements specified. Use of explosives will not be permitted.

1.6.1 Dust and Debris Control

Prevent the spread of dust and debris to occupied portions of the building and on airfield pavements and avoid the creation of a nuisance or hazard in the surrounding area. Do not use water if it results in hazardous or objectionable conditions such as, but not limited to, ice, flooding, or pollution. Sweep pavements as often as necessary to control the spread of debris that may result in foreign object damage potential to aircraft.

1.7 PROTECTION

1.7.1 Traffic Control Signs

a. Where pedestrian and driver or aircraft safety is endangered in the area of removal work, use traffic barricades with flashing lights. Anchor barricades in a manner to prevent displacement by wind, jet or prop blast. Notify the Contracting Officer prior to beginning such work.

Provide a minimum of 2 aviation red or high intensity white obstruction lights on temporary structures (including cranes) over 100 feet above ground level. Light construction and installation shall comply with FAA AC 70/7460-1. Lights shall be operational during periods of reduced visibility, darkness, and as directed by the Contracting Officer. Maintain the temporary services during the period of construction and remove only after permanent services have been installed and tested and are in operation.

1.7.2 Protection of Personnel

Before, during and after the demolition work continuously evaluate the condition of the structure being demolished and take immediate action to protect all personnel working in and around the project site. No area, section, or component of floors, roofs, walls, columns, pilasters, or other structural element will be allowed to be left standing without sufficient bracing, shoring, or lateral support to prevent collapse or failure while workmen remove debris or perform other work in the immediate area.

1.8 FOREIGN OBJECT DAMAGE (FOD)

Aircraft and aircraft engines are subject to FOD from debris and waste material lying on airfield pavements. Remove all such materials that may appear on operational aircraft pavements due to the Contractor's operations. If necessary, the Contracting Officer may require the Contractor to install a temporary barricade at the Contractor's expense to control the spread of FOD potential debris. The barricade shall include a fence covered with a fabric designed to stop the spread of debris. Anchor the fence and fabric to prevent displacement by winds or jet/prop blasts. Remove barricade when no longer required.

1.9 RELOCATIONS

Perform the removal and reinstallation of relocated items as indicated with workmen skilled in the trades involved. Repair or replace items to be

relocated which are damaged by the Contractor with new undamaged items as approved by the Contracting Officer.

1.10 EXISTING CONDITIONS

Before beginning any demolition work, survey the site and examine the drawings and specifications to determine the extent of the work. Record existing conditions in the presence of the Contracting Officer showing the condition of structures and other facilities adjacent to areas of alteration or removal. Photographs sized 4 inch will be acceptable as a record of existing conditions. Include in the record the elevation of the top of foundation walls, finish floor elevations, possible conflicting electrical conduits, plumbing lines, alarms systems, the location and extent of existing cracks and other damage and description of surface conditions that exist prior to before starting work. It is the Contractor's responsibility to verify and document all required outages which will be required during the course of work, and to note these outages on the record document. Submit survey results.

PART 2 PRODUCTS

Not Used.

PART 3 EXECUTION

3.1 EXISTING FACILITIES TO BE REMOVED

Inspect and evaluate existing structures onsite for reuse. Existing construction scheduled to be removed for reuse shall be disassembled. Dismantled and removed materials are to be separated, set aside, and prepared as specified, and stored or delivered to a collection point for reuse, remanufacture, recycling, or other disposal, as specified. Materials shall be designated for reuse onsite whenever possible.

3.1.1 Structures

a. Remove existing structures indicated to be removed.

b. Demolish structures in a systematic manner from the top of the structure to the base. Remove structural framing members and lower to ground by means of derricks, platforms hoists, or other suitable methods as approved by the Contracting Officer.

c. Locate demolition equipment throughout the structure and remove materials so as to not impose excessive loads to supporting walls, floors, or framing.

3.1.2 Utilities and Related Equipment

3.1.2.1 General Requirements

Do not interrupt existing utilities serving occupied or used facilities, except when authorized in writing by the Contracting Officer. Do not interrupt existing utilities serving facilities occupied and used by the Government except when approved in writing and then only after temporary utility services have been approved and provided. Do not begin demolition or deconstruction work until all utility disconnections have been made. Shut off and cap utilities for future use, as indicated.

3.1.2.2 Disconnecting Existing Utilities

Remove existing utilities, as indicated and terminate in a manner conforming to the nationally recognized code covering the specific utility and approved by the Contracting Officer. When utility lines are encountered but are not indicated on the drawings, notify the Contracting Officer prior to further work in that area. Remove meters and related equipment and deliver to a location in accordance with instructions of the Contracting Officer.

3.1.3 Roofing

Remove existing roof system and associated components in their entirety down to existing roof deck. Remove roofing to effect the connections with new flashing or roofing. Remove roofing system without damaging the roof deck. Sequence work to minimize building exposure between demolition or deconstruction and new roof materials installation.

3.1.3.1 Temporary Roofing

Install temporary roofing and flashing as necessary to maintain a watertight condition throughout the course of the work. Remove temporary work prior to installation of permanent roof system materials unless approved otherwise by the Contracting Officer. Make provisions for worker safety during demolition, deconstruction, and installation of new materials as described in paragraphs entitled "Statements" and "Regulatory and Safety Requirements."

3.1.3.2 Reroofing

When removing the existing roofing system from the roof deck, remove only as much roofing as can be recovered by the end of the work day, unless approved otherwise by the Contracting Officer. Do not attempt to open the roof covering system in threatening weather. Reseal all openings prior to suspension of work the same day.

3.1.4 Patching

Where removals leave holes and damaged surfaces exposed in the finished work, patch and repair these holes and damaged surfaces to match adjacent finished surfaces, using on-site materials when available. Where new work is to be applied to existing surfaces, perform removals and patching in a manner to produce surfaces suitable for receiving new work. Finished surfaces of patched area shall be flush with the adjacent existing surface and shall match the existing adjacent surface as closely as possible as to texture and finish. 3.1.5 Air Conditioning Equipment

Remove air conditioning, refrigeration, and other equipment containing refrigerants without releasing chlorofluorocarbon refrigerants to the atmosphere in accordance with the Clean Air Act Amendment of 1990. Recover all refrigerants prior to removing air conditioning, refrigeration, and other equipment containing refrigerants and dispose of in accordance with the paragraph entitled "Disposal of Ozone Depleting Substance (ODS)." Turn in salvaged Class I ODS refrigerants as specified in paragraph, "Salvaged Materials and Equipment."

3.1.6 Mechanical Equipment and Fixtures

Disconnect mechanical hardware at the nearest connection to existing

services to remain, unless otherwise noted. Disconnect mechanical equipment and fixtures at fittings. Remove service valves attached to the unit. Salvage each item of equipment and fixtures as a whole unit; listed, indexed, tagged, and stored. Salvage each unit with its normal operating auxiliary equipment. Transport salvaged equipment and fixtures, including motors and machines, to a designated storage area as directed by the Contracting Officer. Do not remove equipment until approved. Do not offer low-efficiency equipment for reuse; provide to recycling service for disassembly and recycling of parts.

3.1.6.1 Preparation for Storage

Remove water, dirt, dust, and foreign matter from units; tanks, piping and fixtures shall be drained; interiors, if previously used to store flammable, explosive, or other dangerous liquids, shall be steam cleaned. Seal openings with caps, plates, or plugs. Secure motors attached by flexible connections to the unit. Change lubricating systems with the proper oil or grease.

3.1.6.2 Piping

Disconnect piping at unions, flanges and valves, and fittings as required to reduce the pipe into straight lengths for practical storage. Store salvaged piping according to size and type. If the piping that remains can become pressurized due to upstream valve failure, end caps, blind flanges, or other types of plugs or fittings with a pressure gage and bleed valve shall be attached to the open end of the pipe to ensure positive leak control. Carefully dismantle piping that previously contained gas, gasoline, oil, or other dangerous fluids, with precautions taken to prevent injury to persons and property. Store piping outdoors until all fumes and residues are removed. Box prefabricated supports, hangers, plates, valves, and specialty items according to size and type. Wrap sprinkler heads individually in plastic bags before boxing. Classify piping not designated for salvage, or not reusable, as scrap metal.

3.1.6.3 Ducts

Classify removed duct work as scrap metal.

3.1.6.4 Fixtures, Motors and Machines

Remove and salvage fixtures, motors and machines associated with plumbing, heating, air conditioning, refrigeration, and other mechanical system installations. Salvage, box and store auxiliary units and accessories with the main motor and machines. Tag salvaged items for identification, storage, and protection from damage. Classify broken, damaged, or otherwise unserviceable units and not caused to be broken, damaged, or otherwise unserviceable as debris to be disposed of by the Contractor.

3.1.7 Electrical Equipment and Fixtures

Salvage motors, motor controllers, and operating and control equipment that are attached to the driven equipment. Salvage wiring systems and components. Box loose items and tag for identification. Disconnect primary, secondary, control, communication, and signal circuits at the point of attachment to their distribution system.

3.1.7.1 Fixtures

Remove and salvage electrical fixtures. Salvage unprotected glassware from the fixture and salvage separately. Salvage incandescent, mercury-vapor, and fluorescent lamps and fluorescent ballasts manufactured prior to 1978, boxed and tagged for identification, and protected from breakage.

3.1.7.2 Electrical Devices

Remove and salvage switches, switchgear, transformers, conductors including wire and nonmetallic sheathed and flexible armored cable, regulators, meters, instruments, plates, circuit breakers, panelboards, outlet boxes, and similar items. Box and tag these items for identification according to type and size.

3.1.7.3 Wiring Ducts or Troughs

Remove and salvage wiring ducts or troughs. Dismantle plug-in ducts and wiring troughs into unit lengths. Remove plug-in or disconnecting devices from the busway and store separately.

3.1.7.4 Conduit and Miscellaneous Items

Salvage conduit except where embedded in concrete or masonry. Consider corroded, bent, or damaged conduit as scrap metal. Sort straight and undamaged lengths of conduit according to size and type. Classify supports, knobs, tubes, cleats, and straps as debris to be removed and disposed.

3.1.8 Elevators and Hoists

Remove elevators, hoists, and similar conveying equipment and salvage as whole units, to the most practical extent. Remove and prepare items for salvage without damage to any of the various parts. Salvage and store rails for structural steel with the equipment as an integral part of the unit.

3.1.9 Items With Unique/Regulated Disposal Requirements

Remove and dispose of items with unique or regulated disposal requirements in the manner dictated by law or in the most environmentally responsible manner.

3.2 DISPOSITION OF MATERIAL

3.2.1 Title to Materials

Except for salvaged items specified in related Sections, and for materials or equipment scheduled for salvage, all materials and equipment removed and not reused or salvaged, shall become the property of the Contractor and shall be removed from Government property. Title to materials resulting from demolition and deconstruction, and materials and equipment to be removed, is vested in the Contractor upon approval by the Contracting Officer of the Contractor's demolition, deconstruction, and removal procedures, and authorization by the Contracting Officer to begin demolition and deconstruction. The Government will not be responsible for the condition or loss of, or damage to, such property after contract award. Showing for sale or selling materials and equipment on site is prohibited.

3.2.2 Salvaged Materials and Equipment

Remove materials and equipment that are indicated and specified to be removed by the Contractor and that are to remain the property of the Government, and deliver to the Government.

a. Salvage items and material to the maximum extent possible.

b. Store all materials salvaged for the Contractor as approved by the Contracting Officer and remove from Government property before completion of the contract. On site sales of salvaged material is prohibited.

c. Remove salvaged items to remain the property of the Government in a manner to prevent damage, and packed or crated to protect the items from damage while in storage or during shipment. Items damaged during removal or storage must be repaired or replaced to match existing items. Properly identify the contents of containers.

d. Remove and capture all Class I ODS refrigerants in accordance with the Clean Air Act Amendment of 1990, and turn in to the Navy as directed by the Commanding Officer.

3.2.3 Disposal of Ozone Depleting Substance (ODS)

Class I and Class II ODS are defined in Section, 602(a) and (b), of The Clean Air Act. Prevent discharge of Class I and Class II ODS to the atmosphere. Place recovered ODS in cylinders meeting AHRI Guideline K suitable for the type ODS (filled to no more than 80 percent capacity) and provide appropriate labeling. Recovered ODS shall be put back into the existing equipment or turned over to the Contracting Officer.

3.2.3.1 Special Instructions

No more than one type of ODS is permitted in each container. A warning/hazardous label shall be applied to the containers in accordance with Department of Transportation regulations. All cylinders including but not limited to fire extinguishers, spheres, or canisters containing an ODS shall have a tag with the following information:

a. Activity name and unit identification code

b. Activity point of contact and phone number

c. Type of ODS and pounds of ODS contained

d. Date of shipment

e. National stock number (for information, call (804) 279-4525).

3.2.4 Transportation Guidance

Ship all ODS containers in accordance with MIL-STD-129, DLA 4145.25 (also referenced one of the following: Army Regulation 700-68, Naval Supply Instruction 4440.128C, Marine Corps Order 10330.2C, and Air Force Regulation 67-12), 49 CFR 173.301, and DOD 4000.25-1-M.

3.3 CLEANUP

Remove debris and rubbish from basement and similar excavations. Remove and transport the debris in a manner that prevents spillage on streets or adjacent areas. Apply local regulations regarding hauling and disposal.

3.4 DISPOSAL OF REMOVED MATERIALS

3.4.1 Regulation of Removed Materials

Dispose of debris, rubbish, scrap, and other nonsalvageable materials resulting from removal operations with all applicable federal, state and local regulations as contractually specified in the Waste Management Plan. Storage of removed materials on the project site is prohibited.

3.4.2 Burning on Government Property

Burning of materials removed from demolished and deconstructed structures will not be permitted on Government property.

3.4.3 Removal from Government Property

Transport waste materials removed from demolished and deconstructed structures, from Government property for legal disposal.

3.5 REUSE OF SALVAGED ITEMS

Recondition salvaged materials and equipment designated for reuse before installation. Replace items damaged during removal and salvage operations or restore them as necessary to usable condition.

-- End of Section --

SECTION 02 82 16.00 20

ENGINEERING CONTROL OF ASBESTOS CONTAINING MATERIALS
08/11

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN INDUSTRIAL HYGIENE ASSOCIATION (AIHA)

AIHA Z88.6	(2006) Respiratory Protection - Respirator Use-Physical Qualifications for Personnel

AMERICAN SOCIETY OF SANITARY ENGINEERING (ASSE)

ASSE Z9.2	(2012) Fundamentals Governing the Design and Operation of Local Exhaust Ventilation Systems

ASTM INTERNATIONAL (ASTM)

ASTM C732	(2006; R 2012) Aging Effects of Artificial Weathering on Latex Sealants
ASTM D2794	(1993; R 2010) Resistance of Organic Coatings to the Effects of Rapid Deformation (Impact)
ASTM D522/D522M	(2014) Mandrel Bend Test of Attached Organic Coatings
ASTM E119	(2012a) Standard Test Methods for Fire Tests of Building Construction and Materials
ASTM E1368	(2014) Visual Inspection of Asbestos Abatement Projects
ASTM E736	(2000; R 2011) Cohesion/Adhesion of Sprayed Fire-Resistive Materials Applied to Structural Members
ASTM E84	(2013a) Standard Test Method for Surface Burning Characteristics of Building Materials
ASTM E96/E96M	(2013) Standard Test Methods for Water Vapor Transmission of Materials

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)

EPA 560/5-85-024	(1985) Guidance for Controlling Asbestos-Containing Materials in Buildings

(Purple Book)

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1926.103	Respiratory Protection
29 CFR 1926.1101	Asbestos
29 CFR 1926.200	Accident Prevention Signs and Tags
29 CFR 1926.51	Sanitation
29 CFR 1926.59	Hazard Communication
40 CFR 61-SUBPART A	General Provisions
40 CFR 61-SUBPART M	National Emission Standard for Asbestos
40 CFR 763	Asbestos

U.S. NAVAL FACILITIES ENGINEERING COMMAND (NAVFAC)

ND OPNAVINST 5100.23	(2005; Rev G) Navy Occupational Safety and Health (NAVOSH) Program Manual

UNDERWRITERS LABORATORIES (UL)

UL 586	(2009) Standard for High-Efficiency Particulate, Air Filter Units

1.2 DEFINITIONS

1.2.1 ACM

Asbestos Containing Materials.

1.2.2 Amended Water

Water containing a wetting agent or surfactant with a maximum surface tension of 0.00042 psi.

1.2.3 Area Sampling

Sampling of asbestos fiber concentrations which approximates the concentrations of asbestos in the theoretical breathing zone but is not actually collected in the breathing zone of an employee.

1.2.4 Asbestos

The term asbestos includes chrysotile, amosite, crocidolite, tremolite asbestos, anthophyllite asbestos, and actinolite asbestos and any of these minerals that has been chemically treated or altered. Materials are considered to contain asbestos if the asbestos content of the material is determined to be at least one percent.

1.2.5 Asbestos Control Area

That area where asbestos removal operations are performed which is isolated by physical boundaries which assist in the prevention of the uncontrolled

release of asbestos dust, fibers, or debris.

1.2.6 Asbestos Fibers

Those fibers having an aspect ratio of at least 3:1 and longer than 5 micrometers as determined by National Institute for Occupational Safety and Health (NIOSH) Method 7400.

1.2.7 Asbestos Permissible Exposure Limit

0.1 fibers per cubic centimeter of air as an 8-hour time weighted average measured in the breathing zone as defined by 29 CFR 1926.1101 or other Federal legislation having legal jurisdiction for the protection of workers health.

1.2.8 Background

The ambient airborne asbestos concentration in an uncontaminated area as measured prior to any asbestos hazard abatement efforts. Background concentrations for other (contaminated) areas are measured in similar but asbestos free locations.

1.2.9 Contractor

The Contractor is that individual, or entity under contract to the Navy to perform the herein listed work.

1.2.10 Competent Person

A person meeting the requirements for competent person as specified in 29 CFR 1926.1101 including a person capable of identifying existing asbestos hazards in the workplace and selecting the appropriate control strategy for asbestos exposure, who has the authority to take prompt corrective measures to eliminate them, and is specifically trained in a training course which meet the criteria of EPA's Model Accreditation Plan (40 CFR 763) for project designer or supervisor, or its equivalent. The competent person shall have a current asbestos contractors or supervisors license issued by North Carolina Department of Health and Human Services, Health Hazards Control Unit (NCDHHS HHCU).

1.2.11 Encapsulation

The abatement of an asbestos hazard through the appropriate use of chemical encapsulants.

1.2.12 Encapsulants

Specific materials in various forms used to chemically or physically entrap asbestos fibers in various configurations to prevent these fibers from becoming airborne. There are four types of encapsulants as follows which must comply with performance requirements as specified herein.

a. Removal Encapsulant (can be used as a wetting agent)

b. Bridging Encapsulant (used to provide a tough, durable surface coating to asbestos containing material)

c. Penetrating Encapsulant (used to penetrate the asbestos containing material encapsulating all asbestos fibers and preventing fiber release

due to routine mechanical damage)

d. Lock-Down Encapsulant (used to seal off or "lock-down" minute asbestos fibers left on surfaces from which asbestos containing material has been removed).

1.2.13 Friable Asbestos Material

One percent asbestos containing material that can be crumbled, pulverized, or reduced to powder by hand pressure when dry.

1.2.14 Glovebag Technique

Those asbestos removal and control techniques put forth in 29 CFR 1926.1101 Appendix G.

1.2.15 HEPA Filter Equipment

High efficiency particulate air (HEPA) filtered vacuum and/or exhaust ventilation equipment with a filter system capable of collecting and retaining asbestos fibers. Filters shall retain 99.97 percent of particles 0.3 microns or larger as indicated in UL 586.

1.2.16 Navy Consultant (NC)

That qualified person employed directly by the Government to monitor, sample, inspect the work or in some other way advise the Contracting Officer. The NC is normally a private consultant, but can be an employee of the Government.

1.2.17 Negative Pressure Enclosure (NPE)

That engineering control technique described as a negative pressure enclosure in 29 CFR 1926.1101.

1.2.18 Nonfriable Asbestos Material

Material that contains asbestos in which the fibers have been immobilized by a bonding agent, coating, binder, or other material so that the asbestos is well bound and will not normally release asbestos fibers during any appropriate use, handling, storage or transportation. It is understood that asbestos fibers may be released under other conditions such as demolition, removal, or mishap.

1.2.19 Personal Sampling

Air sampling which is performed to determine asbestos fiber concentrations within the breathing zone of a specific employee, as performed in accordance with 29 CFR 1926.1101.

1.2.20 Private Qualified Person (PQP)

That qualified person hired by the Contractor to perform the herein listed tasks.

1.2.21 Qualified Person (QP)

A Registered Architect, Professional Engineer, Certified Industrial Hygienist, consultant or other qualified person who has successfully

completed training and is therefore accredited under a legitimate State Model Accreditation Plan as described in 40 CFR 763 as a Building Inspector, Contractor/Supervisor Abatement Worker, and Asbestos Project Designer; and has successfully completed the National Institute of Occupational Safety and Health (NIOSH) 582 course "Sampling and Evaluating Airborne Asbestos Dust" or equivalent. The QP must be qualified to perform visual inspections as indicated in ASTM E1368. The QP shall be appropriately by NCDHHS HHCU.

1.2.22 TEM

Refers to Transmission Electron Microscopy.

1.2.23 Time Weighted Average (TWA)

The TWA is an 8-hour time weighted average airborne concentration of asbestos fibers.

1.2.24 Wetting Agent

A chemical added to water to reduce the water's surface tension thereby increasing the water's ability to soak into the material to which it is applied. An equivalent wetting agent must have a surface tension of at most 0.00042 psi.

1.3 REQUIREMENTS

1.3.1 Description of Work

The work covered by this section includes the handling and control of asbestos containing materials and describes some of the resultant procedures and equipment required to protect workers, the environment and occupants of the building or area, or both, from contact with airborne asbestos fibers. The work also includes the disposal of any asbestos containing materials generated by the work. More specific operational procedures shall be outlined in the Asbestos Hazard Abatement Plan called for elsewhere in this specification. The asbestos work includes the removal and disposal of the following asbestos containing building materials as indicated in the applicable sections of the Report of Industrial Hygiene Services, Building 133 HVAC Replacement Project and as indicated below:

- Black caulk located on the HVAC equipment joints in several of the penthouses. The caulk appeared to be original and was observed to be in good condition. The caulk was found to contain between up to 12% Chrysotile asbestos. This material is considered a Category II Non-friable material. This material was observed in the following penthouses:
Penthouses 1, 2, 3, 6, 8, 10, 11 and 12.

- Black tar paper felt on the lower portion of the exterior of the penthouses; this material is considered a Category II non-friable material. The felt was observed to be in fair condition and was found to contain 2% Chrysotile asbestos in only one of the two samples of this material collected. This material is located behind vertical metal panel siding and may be remnant roof flashing that was not removed during roof replacement due to its location.

Asbestos containing pipe insulation and/or associated insulation fittings shall be removed using glove-bag techniques. Each glove-bag shall be smoke tested to ensure no leaks are present.

1.3.2 Medical Requirements

Provide medical requirements including but not limited to medical surveillance and medical record keeping as listed in 29 CFR 1926.1101.

1.3.2.1 Medical Examinations

Before exposure to airborne asbestos fibers, provide workers with a comprehensive medical examination as required by 29 CFR 1926.1101 or other pertinent State or local directives. This requirement must have been satisfied within the 12 months prior to the start of work on this contract. The same medical examination shall be given on an annual basis to employees engaged in an occupation involving asbestos and within 30 calendar days before or after the termination of employment in such occupation. Specifically identify x-ray films of asbestos workers to the consulting radiologist and mark medical record jackets with the word "ASBESTOS."

1.3.2.2 Medical Records

Maintain complete and accurate records of employees' medical examinations, medical records, and exposure data for a period of 50 years after termination of employment and make records of the required medical examinations and exposure data available for inspection and copying to: The Assistant Secretary of Labor for Occupational Safety and Health (OSHA), or authorized representatives of them, and an employee's physician upon the request of the employee or former employee.

1.3.3 Employee Training

Submit certificates, prior to the start of work but after the main abatement submittal, signed by each employee indicating that the employee has received training in the proper handling of materials and wastes that contain asbestos in accordance with 40 CFR 763; understands the health implications and risks involved, including the illnesses possible from exposure to airborne asbestos fibers; understands the use and limits of the respiratory equipment to be used; and understands the results of monitoring of airborne quantities of asbestos as related to health and respiratory equipment as indicated in 29 CFR 1926.1101 on an initial and annual basis. Certificates shall be organized by individual worker, not grouped by type of certification. Post appropriate HHCU accreditations and/or evidence of compliance with the training requirements of 40 CFR 763. Train all personnel involved in the asbestos control work in accordance with United States Environmental Protection Agency (USEPA) Asbestos Hazard Emergency Response Act (AHERA) training criteria or State training criteria whichever is more stringent. The Contractor shall document the training by providing: dates of training, training entity, course outline, names of instructors, and qualifications of instructors upon request by the Contracting Officer. Furnish each employee with respirator training and fit testing administered by the PQP as required by 29 CFR 1926.1101. Fully cover engineering and other hazard control techniques and procedures. All asbestos workers shall have a current asbestos worker's license issued by NCDHHS HHCU.

1.3.4 Permits , Licenses, and Notifications

Obtain necessary permits and licenses, application and notification for demolition (DHHS 3768) in conjunction with asbestos removal, encapsulation,

hauling, and disposition, and furnish notification of such actions required by Federal, State, regional, and local authorities prior to the start of work. Notify the NCDHHS, Health Hazards Control Unit in writing at least 10 working days prior to commencement of work and the Contracting Officer in writing 20 working days prior to commencement of work in accordance with 40 CFR 61-SUBPART M. Notify the Contracting Officer and other appropriate Government agencies in writing 20 working days prior to the start of asbestos work as indicated in applicable laws, ordinances, criteria, rules, and regulations. Submit copies of all Notifications to the Contracting Officer.

1.3.5 Environment, Safety and Health Compliance

In addition to detailed requirements of this specification, comply with those applicable laws, ordinances, criteria, rules, and regulations of Federal, State, regional, and local authorities regarding handling, storing, transporting, and disposing of asbestos waste materials. Comply with the applicable requirements of the current issue of 29 CFR 1926.1101, 40 CFR 61-SUBPART A, 40 CFR 61-SUBPART M, and ND OPNAVINST 5100.23. Submit matters of interpretation of standards to the appropriate administrative agency for resolution before starting the work. Where the requirements of this specification, applicable laws, rules, criteria, ordinances, regulations, and referenced documents vary, the most stringent requirement as defined by the Government shall apply.

1.3.6 Respiratory Protection Program

Establish and implement a respirator program as required by AIHA Z88.6, 29 CFR 1926.1101, and 29 CFR 1926.103. Submit a written description of the program to the Contracting Officer. Submit a written program manual or operating procedure including methods of compliance with regulatory statutes.

1.3.6.1 Respirator Program Records

Submit records of the respirator program as required by AIHA Z88.6, 29 CFR 1926.103, and 29 CFR 1926.1101.

1.3.7 Asbestos Hazard Control Supervisor

The Contractor shall be represented on site by a supervisor, trained using the model Contractor accreditation plan as indicated in the Federal statutes for all portions of the herein listed work.

1.3.8 Hazard Communication

Adhere to all parts of 29 CFR 1926.59 and provide the Contracting Officer with a copy of the Material Safety Data Sheets (MSDS) for all materials brought to the site.

1.3.9 Asbestos Hazard Abatement Plan

Submit a detailed plan of the safety precautions such as lockout, tagout, tryout, fall protection, and confined space entry procedures and equipment and work procedures to be used in the removal of materials containing asbestos. The plan, not to be combined with other hazard abatement plans, shall be prepared, signed, and sealed by the PQP. Provide a Table of Contents for each abatement submittal, which shall follow the sequence of requirements in the contract. Such plan shall include but not be limited

to the precise personal protective equipment to be used including, but not limited to, respiratory protection, type of whole-body protection and if reusable coveralls are to be employed decontamination methods (operations and quality control plan), the location of asbestos control areas including clean and dirty areas, buffer zones, showers, storage areas, change rooms, removal method, interface of trades involved in the construction, sequencing of asbestos related work, disposal plan, type of wetting agent and asbestos sealer to be used, locations of local exhaust equipment, planned air monitoring strategies, and a detailed description of the method to be employed in order to control environmental pollution. The plan shall also include (both fire and medical emergency) response plans. The Asbestos Hazard Abatement Plan must be approved in writing prior to starting any asbestos work. The Contractor, Asbestos Hazard Control Supervisor, and PQP shall meet with the Contracting Officer prior to beginning work, to discuss in detail the Asbestos Hazard Abatement Plan, including work procedures and safety precautions. Once approved by the Contracting Officer, the plan will be enforced as if an addition to the specification. Any changes required in the specification as a result of the plan shall be identified specifically in the plan to allow for free discussion and approval by the Contracting Officer prior to starting work.

1.3.10 Testing Laboratory

Submit the name, address, and telephone number of each testing laboratory selected for the sampling, analysis, and reporting of airborne concentrations of asbestos fibers along with evidence that each laboratory selected holds the appropriate State license and/or permits and certification that each laboratory is American Industrial Hygiene Association (AIHA) accredited and that persons counting the samples have been judged proficient by current inclusion on the AIHA Asbestos Analysis Registry (AAR) and successful participation of the laboratory in the Proficiency Analytical Testing (PAT) Program. Where analysis to determine asbestos content in bulk materials or transmission electron microscopy is required, submit evidence that the laboratory is accredited by the National Institute of Science and Technology (NIST) under National Voluntary Laboratory Accreditation Program (NVLAP) for asbestos analysis. The testing laboratory firm shall be independent of the asbestos contractor and shall have no employee or employer relationship which could constitute a conflict of interest.

1.3.11 Landfill Approval

Submit written evidence that the landfill is for asbestos disposal by the U.S. Environmental Protection Agency, Region 3, Air Enforcement Section (38W12), and local regulatory agencies. Within 3 working days after delivery, submit detailed delivery tickets, prepared, signed, and dated by an agent of the landfill, certifying the amount of asbestos materials delivered to the landfill. Submit a copy of the waste shipment records within 1 day of the shipment leaving the project site.

1.3.12 Medical Certification

Provide a written certification for each worker and supervisor, signed by a licensed physician indicating that the worker and supervisor has met or exceeded all of the medical prerequisites listed herein and in 29 CFR 1926.1101 and 29 CFR 1926.103 as prescribed by law. Submit certificates prior to the start of work but after the main abatement submittal.

1.4 SUBMITTALS

The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Local exhaust equipment

Vacuums

Respirators

Pressure differential automatic recording instrument

Amended water

Glovebags

Material Safety Data Sheets (MSDS) for all materials proposed for transport to the project site

Encapsulants

SD-06 Test Reports

Air sampling results

Pressure differential recordings for local exhaust system

Asbestos disposal quantity report

Clearance sampling

SD-07 Certificates

Asbestos hazard abatement plan

Testing laboratory

Private qualified person documentation

Contractor's license

Competent person documentation

Worker's license

Landfill approval

Employee training

Medical certification requirements

Waste shipment records and if applicable exemption report

Respiratory Protection Program

Delivery tickets

Vacuums

Water filtration equipment

Ventilation systems

Other equipment used to contain airborne asbestos fibers

Chemical encapsulants sealers

Notifications

Show compliance with ASSE Z9.2 by providing manufacturers' certifications.

SD-11 Closeout Submittals

Notifications

Rental equipment

Respirator program records

Permits and licenses

Protective clothing decontamination quality control records

Protective clothing decontamination facility notification

1.5 QUALITY ASSURANCE

1.5.1 Private Qualified Person Documentation

Submit the name, address, and telephone number of the Private Qualified Person (PQP) selected to prepare the Asbestos Hazard Abatement Plan, direct monitoring and training, and documented evidence that the PQP has successfully completed training in and is accredited and where required is certified as, a Building Inspector, Contractor/Supervisor Abatement Worker, and Asbestos Project Designer as described by 40 CFR 763 and has successfully completed the National Institute of Occupational Safety and Health (NIOSH) 582 course "Sampling and Evaluating Airborne Asbestos Dust" or equivalent. The PQP shall be appropriately licensed by NCDHHS Health Hazards Control Unit as an Air Monitor. The PQP and the asbestos contractor shall not have an employee/employer relationship or financial relationship which could constitute a conflict of interest. The PQP shall be a first tier subcontractor.

1.5.2 Competent Person Documentation

Submit training certification and a current NCDHHS HHCU Asbestos Contractor's and Supervisor's License.

1.5.3 Worker's License

Submit documentation that requires all workers have a current NCDHHS HHCU Asbestos Workers License.

1.5.4 Contractor's License

Contractor shall have current asbestos contractor's license issued by NCDHHS, Health Hazards Control Unit. Submit a copy of the asbestos contractor's license issued by NCDHHS HHCU.

1.5.5 Air Sampling Results

Complete fiber counting and provide results to the PQP for review within 16 hours of the "time off" of the sample pump. Notify the Contracting Officer immediately of any airborne levels of asbestos fibers in excess of the acceptable limits. Submit sampling results to the Contracting Officer and the affected Contractor employees where required by law within 3 working days, signed by the testing laboratory employee performing air sampling, the employee that analyzed the sample, and the PQP. Notify the Contractor and the Contracting Officer immediately of any variance in the pressure differential which could cause adjacent unsealed areas to have asbestos fiber concentrations in excess of 0.01 fibers per cubic centimeter or background whichever is higher. In no circumstance shall levels exceed 0.1 fibers per cubic centimeter.

1.5.6 Pressure Differential Recordings for Local Exhaust System

Provide a local exhaust system that creates a negative pressure of at least 0.02 inches of water relative to the pressure external to the enclosure and operate it continuously, 24 hours a day, until the temporary enclosure of the asbestos control area is removed. Submit pressure differential recordings for each work day to the PQP for review and to the Contracting Officer within 24 hours from the end of each work day.

1.5.7 Protective Clothing Decontamination Quality Control Records

Provide all records that document quality control for the decontamination of reusable outer protective clothing.

1.5.8 Protective Clothing Decontamination Facility Notification

Submit written evidence that persons who decontaminate, store, or transport asbestos contaminated clothing used in the performance of this contract were duly notified in accordance with 29 CFR 1926.1101.

1.6 EQUIPMENT

1.6.1 Rental Equipment

Provide a copy of the written notification to the rental company concerning the intended use of the equipment and the possibility of asbestos contamination of the equipment.

PART 2 PRODUCTS

2.1 ENCAPSULANTS

Shall conform to current USEPA requirements, shall contain no toxic or hazardous substances as defined in 29 CFR 1926.59, and shall conform to the following performance requirements.

2.1.1 Removal Encapsulants

Requirement	Test Standard
Flame Spread - 25, Smoke Emission - 50	ASTM E84
Life Expectancy - 20 years	ASTM C732 Accelerated Aging Test
Permeability - Minimum 0.4 perms	ASTM E96/E96M
Fire Resistance - Negligible affect on fire resistance rating over 3 hour test (Classified by UL for use over fibrous and cementitious sprayed fireproofing)	ASTM E119
Impact Resistance - Minimum 43 in/lb	ASTM D2794 Gardner Impact Test
Flexibility - no rupture or cracking	ASTM D522/D522M Mandrel Bend Test

2.1.2 Bridging Encapsulant

Requirement	Test Standard
Flame Spread - 25, Smoke Emission - 50	ASTM E84
Life Expectancy - 20 years	ASTM C732 Accelerated Aging Test
Permeability - Minimum 0.4 perms	ASTM E96/E96M
Fire Resistance - Negligible affect on fire resistance rating over 3 hour test (Classified by UL for use over fibrous and cementitious sprayed fireproofing)	ASTM E119
Impact Resistance - Minimum 43 in/lb	ASTM D2794 Gardner Impact Test
Flexibility - no rupture or cracking	ASTM D522/D522M Mandrel Bend Test

2.1.3 Penetrating Encapsulant

Requirement	Test Standard
Flame Spread - 25, Smoke Emission - 50	ASTM E84

Requirement	Test Standard
Life Expectancy - 20 years	ASTM C732 Accelerated Aging Test
Permeability - Minimum 0.4 perms	ASTM E96/E96M
Cohesion/Adhesion Test - 50 pounds of force/foot	ASTM E119
Fire Resistance - Negligible affect on fire resistance rating over 3 hour test (Classified by UL for use over fibrous and cementitious sprayed fireproofing)	ASTM E119
Impact Resistance - Minimum 43 in/lb	ASTM D2794 Gardner Impact Test
Flexibility - no rupture or cracking	ASTM D522/D522M Mandrel Bend Test

2.1.4 Lock-down Encapsulant

Requirement	Test Standard
Flame Spread - 25, Smoke Emission - 50	ASTM E84
Life Expectancy - 20 years	ASTM C732 Accelerated Aging Test
Permeability - Minimum 0.4 perms	ASTM E96/E96M
Fire Resistance - Negligible affect on fire resistance rating over 3 hour test (Tested with fireproofing over encapsulant applied directly to steel member)	ASTM E119
Bond Strength: 100 pounds of force/foot	ASTM E736
(Tests compatibility with cementitious and fibrous fireproofing)	

PART 3 EXECUTION

3.1 EQUIPMENT

At all times, provide the Contracting Officer or the Contracting Officer's

Representative, with at least one complete sets of personal protective equipment as required for entry to and inspection of the asbestos control area. Provide equivalent training to the Contracting Officer or a designated representative as provided to Contractor employees in the use of the required personal protective equipment. Provide manufacturer's certificate of compliance for all equipment used to contain airborne asbestos fibers.

3.1.1 Respirators

Select respirators from those approved by the National Institute for Occupational Safety and Health (NIOSH), Department of Health and Human Services.

3.1.1.1 Respirators for Handling Asbestos

Provide personnel engaged in pre-cleaning, cleanup, handling, and removal of asbestos materials with respiratory protection as indicated in 29 CFR 1926.1101 and 29 CFR 1926.103.

3.1.2 Exterior Whole Body Protection

3.1.2.1 Outer Protective Clothing

Provide personnel exposed to asbestos with disposable "non-breathable," whole body outer protective clothing, head coverings, gloves, and foot coverings. Provide disposable plastic or rubber gloves to protect hands. Cloth gloves may be worn inside the plastic or rubber gloves for comfort, but shall not be used alone. Make sleeves secure at the wrists, make foot coverings secure at the ankles, and make clothing secure at the neck by the use of tape.

3.1.2.2 Work Clothing

Provide cloth work clothes for wear under the outer protective clothing and foot coverings and either dispose of or properly decontaminate them as recommended by the PQP after each use.

3.1.2.3 Personal Decontamination Unit

Provide a temporary, negative pressure unit with a separate decontamination locker room and clean locker room with a shower that complies with 29 CFR 1926.51(f)(4)(ii) through (V) in between for personnel required to wear whole body protective clothing. Provide two separate lockers for each asbestos worker, one in each locker room. Keep street clothing and street shoes in the clean locker. HEPA vacuum and remove asbestos contaminated disposable protective clothing while still wearing respirators at the boundary of the asbestos work area and seal in impermeable bags or containers for disposal. HEPA vacuum and remove asbestos contaminated reusable protective clothing while still wearing respirators at the boundary of the asbestos work area, seal in two impermeable bags, label outer bag as asbestos contaminated waste, and transport for decontamination.

Do not wear work clothing between home and work. Locate showers between the decontamination locker room and the clean locker room and require that all employees shower before changing into street clothes. Collect used shower water and filter with approved water filtration equipment to remove asbestos contamination. Dispose of filters and residue as asbestos waste. Discharge clean water to the sanitary system. Dispose of asbestos contaminated work clothing as asbestos contaminated waste or properly

decontaminate as specified in the Contractor's Asbestos Hazard Abatement Plan. Decontamination units shall be physically attached to the asbestos control area. Build both a personnel decontamination unit and an equipment decontamination unit onto and integral with each asbestos control area.

3.1.2.4 Decontamination of Reusable Outer Protective Clothing

When reusable outer protective clothing is used, transport the double bagged clothing to a previously notified commercial/industrial decontamination facility for decontamination. Perform non-destructive testing to determine the effectiveness of asbestos decontamination. If representative sampling is used, ensure the statistical validity of the sampling results. If representative sampling is used, reject any entire batch in which any of the pieces exceed 40 fibers per square millimeter. Inspect reusable protective clothing prior to use to ensure that it will provide adequate protection and is not or is not about to become ripped, torn, deteriorated, or damaged, and that it is not visibly contaminated. Notify, in writing, all personnel involved in the decontamination of reusable outer protective clothing as indicated in 29 CFR 1926.1101.

3.1.2.5 Eye Protection

Provide goggles to personnel engaged in asbestos abatement operations when the use of a full face respirator is not required.

3.1.3 Warning Signs and Labels

Provide bilingual warning signs printed in English and Spanish at all approaches to asbestos control areas. Locate signs at such a distance that personnel may read the sign and take the necessary protective steps required before entering the area. Provide labels and affix to all asbestos materials, scrap, waste, debris, and other products contaminated with asbestos.

3.1.3.1 Warning Sign

Provide vertical format conforming to 29 CFR 1926.200, and 29 CFR 1926.1101 minimum 20 by 14 inches displaying the following legend in the lower panel:

Legend	Notation
Danger	one inch Sans Serif Gothic or Block
Asbestos	one inch Sans Serif Gothic or Block
Cancer and Lung Disease Hazard	1/4 inch Sans Serif Gothic or Block
Authorized Personnel Only	1/4 inch Sans Serif Gothic or Block

Legend	Notation
Respirators and Protective Clothing are Required in this Area	1/4 inch Sans Serif Gothic or Block

Spacing between lines shall be at least equal to the height of the upper of any two lines.

3.1.3.2 Warning Labels

Provide labels conforming to 29 CFR 1926.1101 of sufficient size to be clearly legible, displaying the following legend:

DANGER
CONTAINS ASBESTOS FIBERS
AVOID CREATING DUST
CANCER AND LUNG DISEASE HAZARD
BREATHING ASBESTOS DUST MAY CAUSE SERIOUS BODILY HARM

3.1.4 Local Exhaust System

Provide a local exhaust system in the asbestos control area in accordance with ASSE Z9.2 and 29 CFR 1926.1101 and NC Dept of Administration (NCDA), State Construction Office (SCO), Division 1, Section 01513 that will provide at least four air changes per hour inside of the negative pressure enclosure. Local exhaust equipment shall be operated 24 hours per day, until the asbestos control area is removed and shall be leak proof to the filter and equipped with HEPA filters. Maintain a minimum pressure differential in the control area of minus 0.02 inch of water column relative to adjacent, unsealed areas. Provide continuous 24-hour per day monitoring of the pressure differential with a pressure differential automatic recording instrument. In no case shall the building ventilation system be used as the local exhaust system for the asbestos control area. Filters on exhaust equipment shall conform to ASSE Z9.2 and UL 586. The local exhaust system shall terminate out of doors and remote from any public access or ventilation system intakes.

3.1.5 Tools

Vacuums shall be leak proof to the filter and equipped with HEPA filters. Filters on vacuums shall conform to ASSE Z9.2 and UL 586. Do not use power tools to remove asbestos containing materials unless the tool is equipped with effective, integral HEPA filtered exhaust ventilation systems. Remove all residual asbestos from reusable tools prior to storage or reuse.

3.1.6 Rental Equipment

If rental equipment is to be used, furnish written notification to the rental agency concerning the intended use of the equipment and the possibility of asbestos contamination of the equipment.

3.1.7 Glovebags

Submit written manufacturers proof that glovebags will not break down under expected temperatures and conditions.

3.2 WORK PROCEDURE

Perform asbestos related work in accordance with 29 CFR 1926.1101, 40 CFR 61-SUBPART M, NCDA, SCO, Division 2, Section 02080 and as specified herein. Use wet removal procedures and glovebags during regulated friable removals, as specified herein. Personnel shall wear and utilize protective clothing and equipment as specified herein. Eating, smoking, drinking, chewing gum, tobacco, or applying cosmetics shall not be permitted in the asbestos work or control areas. Personnel of other trades not engaged in the removal of asbestos containing material shall not be exposed at any time to airborne concentrations of asbestos unless all the personnel protection and training provisions of this specification are complied with by the trade personnel. Shut down the building heating, ventilating, and air conditioning system, cap the openings to the system, and provide temporary ventilation prior to the commencement of asbestos work. Disconnect electrical service when wet removal is performed and provide temporary electrical service with verifiable ground fault circuit interrupter (GFCI) protection prior to the use of any water or encapsulant. If an asbestos fiber release or spill occurs outside of the asbestos control area, stop work immediately, correct the condition to the satisfaction of the Contracting Officer including clearance sampling, prior to resumption of work.

3.2.1 Protection of Existing Work to Remain

Perform work without damage or contamination of adjacent work. Where such work is damaged or contaminated as verified by the Contracting Officer using visual inspection or sample analysis, it shall be restored to its original condition or decontaminated by the Contractor at no expense to the Government as deemed appropriate by the Contracting Officer. This includes inadvertent spill of dirt, dust, or debris in which it is reasonable to conclude that asbestos may exist. When these spills occur, stop work immediately. Then clean up the spill. When satisfactory visual inspection and air sampling results are obtained from the PQP work may proceed at the discretion of the Contracting Officer.

3.2.2 Furnishings

Furniture and moveable equipment will be removed from the area of work by the Government before asbestos work begins.

3.2.3 Precleaning

Wet wipe and HEPA vacuum all surfaces potentially contaminated with asbestos prior to establishment of an enclosure.

3.2.4 Asbestos Control Area Requirements

3.2.4.1 Glovebag

The construction of a negative pressure enclosure is infeasible for the removal of pipe insulation and fittings. Use alternate techniques as indicated in 29 CFR 1926.1101 and NCDA, SCO, Section 02080. Establish designated limits for the asbestos regulated area with the use of rope or

other continuous barriers, and maintain all other requirements for asbestos control areas. The PQP shall conduct personal samples of each worker engaged in asbestos handling (removal, disposal, transport and other associated work) throughout the duration of the project. If the quantity of airborne asbestos fibers monitored at the breathing zone of the workers at any time exceeds background or 0.01 fibers per cubic centimeter whichever is greater, stop work, evacuate personnel in adjacent areas or provide personnel with approved protective equipment at the discretion of the Contracting Officer. This sampling may be duplicated by the Government at the discretion of the Contracting Officer. If the air sampling results obtained by the Government differ from those obtained by the Contractor, the Government will determine which results predominate. If adjacent areas are contaminated as determined by the Contracting Officer, clean the contaminated areas, monitor, and visually inspect the area as specified herein.

3.2.5 Removal Procedures

Wet asbestos material with a fine spray of amended water during removal, cutting, or other handling so as to reduce the emission of airborne fibers. Remove material and immediately place in 6 mil plastic disposal bags. Remove asbestos containing material in a gradual manner, with continuous application of the amended water or wetting agent in such a manner that no asbestos material is disturbed prior to being adequately wetted. Where unusual circumstances prohibit the use of 6 mil plastic bags, submit an alternate proposal for containment of asbestos fibers to the Contracting Officer for approval. For example, in the case where both piping and insulation are to be removed, the Contractor may elect to wet the insulation, wrap the pipes and insulation in plastic and remove the pipe by sections. Asbestos containing material shall be containerized while wet. At no time shall asbestos material be allowed to accumulate or become dry. Lower and otherwise handle asbestos containing material as indicated in 40 CFR 61-SUBPART M.

3.2.5.1 Sealing Contaminated Items Designated for Disposal

Remove contaminated architectural, mechanical, and electrical appurtenances such as venetian blinds, full-height partitions, carpeting, duct work, pipes and fittings, radiators, light fixtures, conduit, panels, and other contaminated items designated for removal by completely coating the items with an asbestos lock-down encapsulant at the demolition site before removing the items from the asbestos control area. These items need not be vacuumed. The asbestos lock-down encapsulant shall be tinted a contrasting color. It shall be spray-applied by airless method. Thoroughness of sealing operation shall be visually gauged by the extent of colored coating on exposed surfaces. Lock-down encapsulants shall comply with the performance requirements specified herein.

3.2.5.2 Exposed Pipe Insulation Edges

Contain edges of asbestos insulation to remain that are exposed by a removal operation. Wet and cut the rough ends true and square with sharp tools and then encapsulate the edges with a 1/4 inch thick layer of non-asbestos containing insulating cement troweled to a smooth hard finish. When cement is dry, lag the end with a layer of non-asbestos lagging cloth, overlapping the existing ends by at least 4 inches. When insulating cement and cloth is an impractical method of sealing a raw edge of asbestos, take appropriate steps to seal the raw edges as approved by the Contracting Officer.

3.2.6 Air Sampling

Sampling of airborne concentrations of asbestos fibers shall be performed in accordance with 29 CFR 1926.1101 and as specified herein. Sampling performed in accordance with 29 CFR 1926.1101 shall be performed by the PQP. Sampling performed for environmental and quality control reasons shall not be performed by the PQP hired by the abatement contractor, and shall be performed by the PQP hired by the General Contractor. Unless otherwise specified, use NIOSH Method 7400 for sampling and analysis. Monitoring may be duplicated by the Government at the discretion of the Contracting Officer. If the air sampling results obtained by the Government differ from those results obtained by the Contractor, the Government will determine which results predominate.

3.2.6.1 Sampling Prior to Asbestos Work

Provide area air sampling and establish the baseline one day prior to the masking and sealing operations for each removal site. Establish the background by performing area sampling in similar but uncontaminated sites in the building.

3.2.6.2 Sampling During Asbestos Work

The PQP shall provide personal and area sampling as indicated in 29 CFR 1926.1101 and governing environmental regulations. In addition, provided the same type of work is being performed, provide area sampling during each work shift, close to the work inside the enclosure, outside the glove bag, and at the exhaust opening of the local exhaust system. If sampling outside the enclosure shows airborne levels have exceeded background or 0.01 fibers per cubic centimeter, whichever is greater, stop all work, correct the condition(s) causing the increase, and notify the Contracting Officer immediately. Where alternate methods are used, perform personal and area air sampling at locations and frequencies that will accurately characterize the evolving airborne asbestos levels.

3.2.6.3 Sampling After Final Clean-Up (Clearance Sampling)

Provide area sampling of asbestos fibers using aggressive clearance air sampling techniques as defined in NCDA, SCO, Division 1, Section 01714 and the EPA 560/5-85-024 and establish an airborne asbestos concentration of less than 0.01 fibers per cubic centimeter after final clean-up but before removal of the enclosure or the asbestos work control area. After final cleanup and the asbestos control area is dry but prior to clearance sampling, the PQP shall perform a visual inspection in accordance with ASTM E1368 to ensure that the asbestos control and work area is free of any accumulations of dirt, dust, or debris. Prepare a written report signed and dated by the PQP documenting that the asbestos control area is free of dust, dirt, and debris and all waste has been removed. Collect at least five (5) samples inside each containment. Use phase contrast microscopy (PCM) and NIOSH 7400 Method to analyze clearance samples and report the results in accordance with current NIOSH criteria. The asbestos fiber counts from these samples shall be less than 0.01 fibers per cubic centimeter or be not greater than the background, whichever is greater. Should any of the final samples indicate a higher value, the Contractor shall take appropriate actions to re-clean the area and shall repeat the sampling and PCM analysis at the Contractor's expense.

3.2.7 Lock-Down

Prior to removal of plastic barriers and glove bags and after pre-clearance clean up of gross contamination, the PQP shall conduct a visual inspection of all areas affected by the removal in accordance with ASTM E1368. Inspect for any visible fibers, and to ensure that encapsulants were applied evenly and appropriately. A post removal (lock-down) encapsulant shall then be spray applied to ceiling, walls, floors and other areas exposed in the removal area. The exposed area shall include but not be limited to plastic barriers, furnishings and articles to be discarded as well as dirty change room, air locks for bag removal and decontamination chambers.

3.2.8 Site Inspection

While performing asbestos engineering control work, the Contractor shall be subject to on-site inspection by the Contracting Officer who may be assisted by or represented by safety or industrial hygiene personnel. If the work is found to be in violation of this specification, the Contracting Officer or his representative will issue a stop work order to be in effect immediately and until the violation is resolved. All related costs including standby time required to resolve the violation shall be at the Contractor's expense.

3.3 CLEAN-UP AND DISPOSAL

3.3.1 Housekeeping

Essential parts of asbestos dust control are housekeeping and clean-up procedures. Maintain surfaces of the asbestos control area free of accumulations of asbestos fibers. Give meticulous attention to restricting the spread of dust and debris; keep waste from being distributed over the general area. Use HEPA filtered vacuum cleaners. DO NOT BLOW DOWN THE SPACE WITH COMPRESSED AIR. When asbestos removal is complete, all asbestos waste is removed from the work-site, and final clean-up is completed, the Contracting Officer will attest that the area is safe before the signs can be removed. After final clean-up and acceptable airborne concentrations are attained but before the HEPA unit is turned off and the enclosure removed, remove all pre-filters on the building HVAC system and provide new pre-filters. Dispose of filters as asbestos contaminated materials. Reestablish HVAC mechanical, and electrical systems in proper working order. The Contracting Officer will visually inspect all surfaces within the enclosure for residual material or accumulated dust or debris. The Contractor shall re-clean all areas showing dust or residual materials. If re-cleaning is required, air sample and establish an acceptable asbestos airborne concentration after re-cleaning. The Contracting Officer must agree that the area is safe in writing before unrestricted entry will be permitted. The Government shall have the option to perform monitoring to determine if the areas are safe before entry is permitted.

3.3.2 Title to Materials

All waste materials, except as specified otherwise, shall become the property of the Contractor and shall be disposed of as specified in applicable local, State, and Federal regulations and herein.

3.3.3 Disposal of Asbestos

3.3.3.1 Procedure for Disposal

Collect asbestos waste, asbestos contaminated water, scrap, debris, bags, containers, equipment, and asbestos contaminated clothing which may produce airborne concentrations of asbestos fibers and place in sealed fiber-proof, waterproof, non-returnable containers (e.g. double plastic bags 6 mils thick, cartons, drums or cans). Wastes within the containers must be adequately wet in accordance with 40 CFR 61-SUBPART M. Affix a warning and Department of Transportation (DOT) label to each container including the bags or use at least 6 mils thick bags with the approved warnings and DOT labeling preprinted on the bag. The name of the waste generator and the location at which the waste was generated shall be clearly indicated on the outside of each container. Prevent contamination of the transport vehicle (especially if the transport vehicle is a rented truck likely to be used in the future for non-asbestos purposes). These precautions include lining the vehicle cargo area with plastic sheeting (similar to work area enclosure) and thorough cleaning of the cargo area after transport and unloading of asbestos debris is complete. Dispose of waste asbestos material at an Environmental Protection Agency (EPA) or State-approved asbestos landfill off Government property. For temporary storage, store sealed impermeable bags in asbestos waste drums or skids. An area for interim storage of asbestos waste-containing drums or skids will be assigned by the Contracting Officer or his authorized representative. Procedure for hauling and disposal shall comply with 40 CFR 61-SUBPART M, State, regional, and local standards. Sealed plastic bags may be dumped from drums into the burial site unless the bags have been broken or damaged. Damaged bags shall remain in the drum and the entire contaminated drum shall be buried. Uncontaminated drums may be recycled. Workers unloading the sealed drums shall wear appropriate respirators and personal protective equipment when handling asbestos materials at the disposal site.

3.3.3.2 Asbestos Disposal Quantity Report

Direct the PQP to record and report, to the Contracting Officer, the amount of asbestos containing material removed and released for disposal. Deliver the report for the previous day at the beginning of each day shift with amounts of material removed during the previous day reported in linear feet or square feet as described initially in this specification and in cubic feet for the amount of asbestos containing material released for disposal.

-- End of Section --

SECTION 02 83 13.00 20

LEAD IN CONSTRUCTION
08/11

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN INDUSTRIAL HYGIENE ASSOCIATION (AIHA)

AIHA Z88.6	(2006) Respiratory Protection - Respirator Use-Physical Qualifications for Personnel

STATE OF NORTH CAROLINA ADMINISTRATIVE CODE (NCAC)

10A NCAC 41C.0800	Lead-Based Paint Hazard Management Program

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT (HUD)

HUD 6780	(1995; Errata Aug 1996;Rev Ch. 7 - 1997) Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1926.103	Respiratory Protection
29 CFR 1926.21	Safety Training and Education
29 CFR 1926.33	Access to Employee Exposure and Medical Records
29 CFR 1926.55	Gases, Vapors, Fumes, Dusts, and Mists
29 CFR 1926.59	Hazard Communication
29 CFR 1926.62	Lead
29 CFR 1926.65	Hazardous Waste Operations and Emergency Response
40 CFR 260	Hazardous Waste Management System: General
40 CFR 261	Identification and Listing of Hazardous Waste
40 CFR 262	Standards Applicable to Generators of Hazardous Waste
40 CFR 263	Standards Applicable to Transporters of Hazardous Waste
40 CFR 264	Standards for Owners and Operators of

	Hazardous Waste Treatment, Storage, and Disposal Facilities
40 CFR 265	Interim Status Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities
40 CFR 268	Land Disposal Restrictions
40 CFR 745	Lead-Based Paint Poisoning Prevention in Certain Residential Structures
49 CFR 172	Hazardous Materials Table, Special Provisions, Hazardous Materials Communications, Emergency Response Information, and Training Requirements
49 CFR 178	Specifications for Packagings

UNDERWRITERS LABORATORIES (UL)

UL 586	(2009) Standard for High-Efficiency Particulate, Air Filter Units

1.2 DEFINITIONS

1.2.1 Action Level

Employee exposure, without regard to use of respirators, to an airborne concentration of lead of 30 micrograms per cubic meter of air averaged over an 8 hour period.

1.2.2 Area Sampling

Sampling of lead concentrations within the lead control area and inside the physical boundaries which is representative of the airborne lead concentrations but is not collected in the breathing zone of personnel (approximately 5 to 6 feet above the floor).

1.2.3 Competent Person (CP)

As used in this section, refers to a person employed by the Contractor who is trained in the recognition and control of lead hazards in accordance with current federal, State, and local regulations and has the authority to take prompt corrective actions to control the lead hazard. A Certified Industrial Hygienist (CIH) certified by the American Board of Industrial Hygiene or a Certified Safety Professional (CSP) certified by the Board of Certified Safety Professionals is the best choice.

1.2.4 Contaminated Room

Refers to a room for removal of contaminated personal protective equipment (PPE).

1.2.5 Decontamination Shower Facility

That facility that encompasses a clean clothing storage room, and a contaminated clothing storage and disposal rooms, with a shower facility in between.

1.2.6 High Efficiency Particulate Arrestor (HEPA) Filter Equipment

HEPA filtered vacuuming equipment with a UL 586 filter system capable of collecting and retaining lead-contaminated particulate. A high efficiency particulate filter demonstrates at least 99.97 percent efficiency against 0.3 micron or larger size particles.

1.2.7 Lead

Metallic lead, inorganic lead compounds, and organic lead soaps. Excludes other forms of organic lead compounds.

1.2.8 Lead Control Area

A system of control methods to prevent the spread of lead dust, paint chips or debris to adjacent areas that may include temporary containment, floor or ground cover protection, physical boundaries, and warning signs to prevent unauthorized entry of personnel. HEPA filtered local exhaust equipment may be used as engineering controls to further reduce personnel exposures or building/outdoor environmental contamination.

1.2.9 Lead Permissible Exposure Limit (PEL)

Fifty micrograms per cubic meter of air as an 8 hour time weighted average as determined by 29 CFR 1926.62. If an employee is exposed for more than eight hours in a work day, the PEL shall be determined by the following formula:

PEL (micrograms/cubic meter of air) = 400/No. hrs worked per day

1.2.10 Material Containing Lead/Paint with Lead (MCL/PWL)

Any material, including paint, which contains lead as determined by the testing laboratory using a valid test method. The requirements of this section does not apply if no detectable levels of lead are found using a quantitative method for analyzing paint or MCL using laboratory instruments with specified limits of detection (usually 0.01 percent). An X-Ray Fluorescence (XRF) instrument is not considered a valid test method.

1.2.11 Personal Sampling

Sampling of airborne lead concentrations within the breathing zone of an employee to determine the 8 hour time weighted average concentration in accordance with 29 CFR 1926.62. Samples shall be representative of the employees' work tasks. Breathing zone shall be considered an area within a hemisphere, forward of the shoulders, with a radius of 6 to 9 inches and centered at the nose or mouth of an employee.

1.2.12 Physical Boundary

Area physically roped or partitioned off around lead control area to limit unauthorized entry of personnel.

1.3 DESCRIPTION

1.3.1 Description of Work

During surface preparation or removal of paint from any of the following

surfaces in the proposed work area in Building B133:

Building No./ Sample No.	Paint Color	Material Description
B133-L01	Green	Rooftop Metal Fresh Air Intakes
B133-L02	Beige	Masonite Wall Boards in Penthouses
B133-L03	Silver	Penthouse Louvers
B133-L04	Yellow	Masonite Wall Boards in Penthouses
B133-L05	Blue	Masonite Wall Boards in Penthouses
B133-L06	Yellow	Metal Penthouse Roof Access Ladder
B133-L07	Beige	Penthouse Wood Trusses/Ceiling
B133-L09	White	Masonite Wall Boards in Penthouses
B133-L12	Yellow	Metal Supports for Exterior HVAC Equipment
B133-L13	White	Wood Interior Truss System
B133-L14	Yellow	Wood Interior Truss System
B133-L15	Red	Floor Paint
B133-L16	White	Floor Paint
B133-L17	White	Brick Walls

These samples were collected August 31, 2009 and October 1, 2009. These painted surfaces are currently in fair condition.

Construction activities impacting PWL or material containing lead which are covered by this specification include the demolition and/or removal of material containing lead in fair condition, located in and around the roof penthouses and the roof truss system, and as indicated on the drawings.

Prior to any torch cutting, burning or welding, components coated with PWL shall be chemically stripped down to the substrate. Any components coated with PWL that will be replaced shall be removed intact as a component. Prior to re-painting, components coated with PWL in fair or poor condition shall be hand-scraped of loose and flaking paint and primed. Prior to component removal or hand scraping, polyethylene sheeting shall be placed under and adjacent to the PWL surfaces to capture loose paint chips. All PWL waste shalll be disposed in accordance with EPA and NC regulations.

1.3.2 Coordination with Other Work

The contractor shall coordinate with work being performed in adjacent areas. Coordination procedures shall be explained in the Plan and shall describe how the Contractor will prevent lead exposure to other contractors and/or Government personnel performing work unrelated to lead activities.

1.4 SUBMITTALS

The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Occupational and Environmental Assessment Data Report (if objective data is used to justify excluding the initial occupational exposure assessment)

Lead Compliance Plan including CP approval (signature, date, and certification number)

Competent Person qualifications

Training Certification of workers and supervisors

lead waste management plan

written evidence that TSD is approved for lead disposal

Certification of Medical Examinations

SD-06 Test Reports

sampling results

Occupational and Environmental Assessment Data Report

SD-07 Certificates

Testing laboratory qualifications

Occupant Notification

Third party consultant qualifications

Clearance Certification

SD-11 Closeout Submittals

Completed and signed hazardous waste manifest from treatment or disposal facility

Waste turn-in documents or weight tickets for non-hazardous wastes that are disposed of at sanitary or construction and demolition landfills

1.5 QUALITY ASSURANCE

1.5.1 Qualifications

1.5.1.1 Competent Person (CP)

Submit name, address, and telephone number of the CP selected to perform responsibilities specified in paragraph entitled "Competent Person (CP) Responsibilities." Provide documented construction project-related experience with implementation of OSHA's Lead in Construction standard (29 CFR 1926.62) which shows ability to assess occupational and environmental exposure to lead, experience with the use of respirators, personal protective equipment and other exposure reduction methods to protect employee health. Submit proper documentation that the CP is trained licensed and certified in accordance with federal, State and local laws. The competent person shall be a licensed lead-based paint abatement Supervisor/Project Designer in the State of North Carolina.

1.5.1.2 Training Certification

Submit a certificate for each worker and supervisor, signed and dated by the accredited training provider, stating that the employee has received the required lead training specified in 29 CFR 1926.62(l) and is certified to perform or supervise deleading, lead removal or demolition activities in the state of North Carolina.

1.5.1.3 Testing Laboratory

Submit the name, address, and telephone number of the testing laboratory selected to perform the air and wipe analysis, testing, and reporting of airborne concentrations of lead. Use a laboratory participating in the EPA National Lead Laboratory Accreditation Program (NLLAP) by being accredited by either the American Association for Laboratory Accreditation (A2LA) or the American Industrial Hygiene Association (AIHA) and that is successfully participating in the Environmental Lead Proficiency Analytical Testing (ELPAT) program to perform sample analysis. Laboratories selected to perform blood lead analysis shall be OSHA approved.

1.5.1.4 Third Party Consultant Qualifications

Submit the name, address and telephone number of the third party consultant selected to perform the wipe sampling for determining concentrations of lead in dust. Submit proper documentation that the consultant is trained and certified as an inspector technician or inspector/risk assessor by the USEPA authorized State (or local) certification and accreditation program.

1.5.2 Requirements

1.5.2.1 Competent Person (CP) Responsibilities

a. Verify training meets all federal, State, and local requirements.

b. Review and approve Lead Compliance Plan for conformance to the applicable referenced standards.

c. Continuously inspect PWL or MCL work for conformance with the approved plan.

d. Perform (or oversee performance of) air sampling. Recommend upgrades or downgrades (whichever is appropriate based on exposure) on the use of PPE (respirators included) and engineering controls.

e. Ensure work is performed in strict accordance with specifications at all times.

f. Control work to prevent hazardous exposure to human beings and to the environment at all times.

g. Supervise final cleaning of the lead control area, take clearance wipe samples if necessary; review clearance sample results and make recommendations for further cleaning.

h. Certify the conditions of the work as called for elsewhere in this specification.

1.5.2.2 Lead Compliance Plan

Submit a detailed job-specific plan of the work procedures to be used in the disturbance of PWL or MCL. The plan shall include a sketch showing the location, size, and details of lead control areas, critical barriers, physical boundaries, location and details of decontamination facilities, viewing ports, and mechanical ventilation system. Include a description of equipment and materials, work practices, controls and job responsibilities for each activity from which lead is emitted. Include in the plan, eating,

drinking, smoking, hygiene facilities and sanitary procedures, interface of trades, sequencing of lead related work, collected waste water and dust containing lead and debris, air sampling, respirators, personal protective equipment, and a detailed description of the method of containment of the operation to ensure that lead is not released outside of the lead control area. Include site preparation, cleanup and clearance procedures. Include occupational and environmental sampling, training and strategy, sampling and analysis strategy and methodology, frequency of sampling, duration of sampling, and qualifications of sampling personnel in the air sampling portion of the plan. Include a description of arrangements made among contractors on multicontractor worksites to inform affected employees and to clarify responsibilities to control exposures.

The plan shall be developed by a certified planner/project designer in the State of North Carolina.

In occupied buildings, the plan shall also include an occupant protection program that describes the measures that will be taken during the work to notify and protect the building occupants.

1.5.2.3 Occupational and Environmental Assessment Data Report

If initial monitoring is necessary, submit occupational and environmental sampling results to the Contracting Officer within three working days of collection, signed by the testing laboratory employee performing the analysis, the employee that performed the sampling, and the CP.

In order to reduce the full implementation of 29 CFR 1926.62, the Contractor shall provide documentation. Submit a report that supports the determination to reduce full implementation of the requirements of 29 CFR 1926.62 and supporting the Lead Compliance Plan.

a. The initial monitoring shall represent each job classification, or if working conditions are similar to previous jobs by the same employer, provide previously collected exposure data that can be used to estimate worker exposures per 29 CFR 1926.62. The data shall represent the worker's regular daily exposure to lead for stated work.

b. Submit worker exposure data gathered during the task based trigger operations of 29 CFR 1926.62 with a complete process description. This includes manual demolition, manual scraping, manual sanding, heat gun, power tool cleaning, rivet busting, cleanup of dry expendable abrasives, abrasive blast enclosure removal, abrasive blasting, welding, cutting and torch burning where lead containing coatings are present.

c. The initial assessment shall determine the requirement for further monitoring and the need to fully implement the control and protective requirements including the lead compliance plan per 29 CFR 1926.62.

1.5.2.4 Medical Examinations

Initial medical surveillance as required by 29 CFR 1926.62 shall be made available to all employees exposed to lead at any time (1 day) above the action level. Full medical surveillance shall be made available to all employees on an annual basis who are or may be exposed to lead in excess of the action level for more than 30 days a year or as required by 29 CFR 1926.62. Adequate records shall show that employees meet the medical surveillance requirements of 29 CFR 1926.33, 29 CFR 1926.62 and 29 CFR

1926.103. Provide medical surveillance to all personnel exposed to lead as indicated in 29 CFR 1926.62. Maintain complete and accurate medical records of employees for the duration of employment plus 30 years.

1.5.2.5 Training

Train each employee performing work that disturbs lead, who performs MCL/PWL disposal, and air sampling operations prior to the time of initial job assignment and annually thereafter, in accordance with 29 CFR 1926.21, 29 CFR 1926.62, and State (10A NCAC 41C.0800) and local regulations where appropriate.

1.5.2.6 Respiratory Protection Program

a. Provide each employee required to wear a respirator a respirator fit test at the time of initial fitting and at least annually thereafter as required by 29 CFR 1926.62.

b. Establish and implement a respiratory protection program as required by AIHA Z88.6, 29 CFR 1926.103, 29 CFR 1926.62, and 29 CFR 1926.55.

1.5.2.7 Hazard Communication Program

Establish and implement a Hazard Communication Program as required by 29 CFR 1926.59.

1.5.2.8 Lead Waste Management

The Lead Waste Management Plan shall comply with applicable requirements of federal, State, and local hazardous waste regulations. and address:

a. Identification and classification of wastes associated with the work.

b. Estimated quantities of wastes to be generated and disposed of.

c. Names and qualifications of each contractor that will be transporting, storing, treating, and disposing of the wastes. Include the facility location, operator and a 24-hour point of contact. Furnish two copies of USEPA, State and local hazardous waste permits, manifests and USEPA Identification numbers.

d. Names and qualifications (experience and training) of personnel who will be working on-site with hazardous wastes.

e. List of waste handling equipment to be used in performing the work, to include cleaning, volume reduction, and transport equipment.

f. Spill prevention, containment, and cleanup contingency measures including a health and safety plan to be implemented in accordance with 29 CFR 1926.65.

g. Work plan and schedule for waste containment, removal and disposal. Proper containment of the waste includes using acceptable waste containers (e.g., 55-gallon drums) as well as proper marking/labeling of the containers. Wastes shall be cleaned up and containerized daily.

h. Include any process that may alter or treat waste rendering a hazardous waste non hazardous.

i. Unit cost for hazardous waste disposal according to this plan.

1.5.2.9 Environmental, Safety and Health Compliance

In addition to the detailed requirements of this specification, comply with laws, ordinances, rules, and regulations of federal, State, and local authorities regarding lead. Comply with the applicable requirements of the current issue of 29 CFR 1926.62. Submit matters regarding interpretation of standards to the Contracting Officer for resolution before starting work. Where specification requirements and the referenced documents vary, the most stringent requirement shall apply.

Licensing in the state of North Carolina is required.

1.5.3 Pre-Construction Conference

Along with the CP, meet with the Contracting Officer to discuss in detail the Lead Waste Management Plan and the Lead Compliance Plan, including procedures and precautions for the work.

1.6 EQUIPMENT

1.6.1 Respirators

Furnish appropriate respirators approved by the National Institute for Occupational Safety and Health (NIOSH), Department of Health and Human Services, for use in atmospheres containing lead dust, fume and mist. Respirators shall comply with the requirements of 29 CFR 1926.62.

1.6.2 Special Protective Clothing

Furnish personnel who will be exposed to lead-contaminated dust with proper disposable protective whole body clothing, head covering, gloves, eye, and foot coverings as required by 29 CFR 1926.62. Furnish proper disposable plastic or rubber gloves to protect hands. Reduce the level of protection only after obtaining approval from the CP.

1.6.3 Rental Equipment Notification

If rental equipment is to be used during PWL or MCL handling and disposal, notify the rental agency in writing concerning the intended use of the equipment.

1.6.4 Vacuum Filters

UL 586 labeled HEPA filters.

1.6.5 Equipment for Government Personnel

Furnish the Contracting Officer with two complete sets of personal protective equipment (PPE) daily, as required herein, for entry into and inspection of the lead removal work within the lead controlled area. Personal protective equipment shall include disposable whole body covering, including appropriate foot, head, eye, and hand protection. PPE shall remain the property of the Contractor. The Government will provide respiratory protection for the Contracting Officer.

1.7 PROJECT/SITE CONDITIONS

1.7.1 Protection of Existing Work to Remain

Perform work without damage or contamination of adjacent areas. Where existing work is damaged or contaminated, restore work to its original condition or better as determined by the Contracting Officer.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.1 PREPARATION

3.1.1 Protection

3.1.1.1 Notification

a. Notify the Contracting Officer 20 days prior to the start of any lead work.

b. Occupant Notification

Submit occupant written acknowledgment of the delivery of lead hazard information pamphlet (EPA 747-K-99-001 "Protect Your Family From Lead in Your Home") prior to commencing the renovation work for each affected unit using language provided in 40 CFR 745 Subpart E.

3.1.1.2 Lead Control Area

a. Physical Boundary - Provide physical boundaries around the lead control area by roping off the area designated in the work plan or providing curtains, portable partitions or other enclosures to ensure that lead will not escape outside of the lead control area.

b. Warning Signs - Provide warning signs at approaches to lead control areas. Locate signs at such a distance that personnel may read the sign and take the necessary precautions before entering the area. Signs shall comply with the requirements of 29 CFR 1926.62.

3.1.1.3 Furnishings

The Government will remove furniture and equipment from the building before lead work begins.

3.1.1.4 Heating, Ventilating and Air Conditioning (HVAC) Systems

Shut down, lock out, and isolate HVAC systems that supply, exhaust, or pass through the lead control areas. Seal intake and exhaust vents in the lead control area with 6 mil plastic sheet and tape. Seal seams in HVAC components that pass through the lead control area. Provide temporary HVAC system for areas in which HVAC has been shut down outside the lead control area.

3.1.1.5 Decontamination Shower Facility

Provide clean and contaminated change rooms and shower facilities in accordance with this specification and 29 CFR 1926.62.

3.1.1.6 Eye Wash Station

Where eyes may be exposed to injurious corrosive materials, suitable facilities for quick drenching or flushing of the eyes shall be provided within the work area.

3.1.1.7 Mechanical Ventilation System

a. To the extent feasible, use local exhaust ventilation or other collection systems, approved by the CP. Local exhaust ventilation systems shall be evaluated and maintained in accordance with 29 CFR 1926.62.

b. Vent local exhaust outside the building and away from building ventilation intakes or ensure system is connected to HEPA filters.

c. Use locally exhausted, power actuated tools or manual hand tools.

3.1.1.8 Personnel Protection

Personnel shall wear and use protective clothing and equipment as specified herein. Eating, smoking, or drinking or application of cosmetics is not permitted in the lead control area. No one will be permitted in the lead control area unless they have been appropriately trained and provided with protective equipment.

3.2 ERECTION

3.2.1 Lead Control Area Requirements

Establish a lead control area by completely establishing barriers and physical boundaries around the area or structure where PWL or MCL removal operations will be performed.

3.3 APPLICATION

3.3.1 Lead Work

Perform lead work in accordance with approved Lead Compliance Plan. Use procedures and equipment required to limit occupational exposure and environmental contamination with lead when the work is performed in accordance with 29 CFR 1926.62 or 40 CFR 745, and as specified herein. Dispose of all PWL or MCL and associated waste in compliance with federal, State, and local requirements.

3.3.2 Paint with Lead or Material Containing Lead Removal

Manual or power sanding or grinding of lead surfaces or materials is not permitted unless tools are equipped with HEPA attachments or wet methods. The dry sanding or grinding of surfaces that contain lead is prohibited. Provide methodology for removing lead in the Lead Compliance Plan. Select lead removal processes to minimize contamination of work areas outside the control area with lead-contaminated dust or other lead-contaminated debris or waste and to ensure that unprotected personnel are not exposed to

hazardous concentrations of lead. Describe this removal process in the Lead Compliance Plan.

3.3.2.1 Paint with Lead or Material Containing Lead - Indoor Removal

Perform manual or mechanical removal in the lead control areas using enclosures, barriers or containments and powered locally exhausted tools. Collect residue debris for disposal in accordance with federal, State, and local requirements.

3.3.2.2 Paint with Lead or Material Containing Lead - Outdoor Removal

Perform outdoor removal as indicated in federal, State, and local regulations and in the Lead Compliance Plan. The worksite preparation (barriers or containments) shall be job dependent and presented in the Lead Compliance Plan.

3.3.3 Personnel Exiting Procedures

Whenever personnel exit the lead-controlled area, they shall perform the following procedures and shall not leave the work place wearing any clothing or equipment worn in the control area:

a. Vacuum all clothing before entering the contaminated change room.

b. Remove protective clothing in the contaminated change room, and place them in an approved impermeable disposal bag.

c. Shower.

d. Wash hands and face at the site, don appropriate disposable or uncontaminated reusable clothing, move to an appropriate shower facility, shower.

e. Change to clean clothes prior to leaving the clean clothes storage area.

3.4 FIELD QUALITY CONTROL

3.4.1 Tests

3.4.1.1 Air and Wipe Sampling

Conduct sampling for lead in accordance with 29 CFR 1926.62 and as specified herein. Air and wipe sampling shall be directed or performed by the CP.

a. The CP shall be on the job site directing the air and wipe sampling and inspecting the PWL or MCL removal work to ensure that the requirements of the contract have been satisfied during the entire PWL or MCL operation.

b. Collect personal air samples on employees who are anticipated to have the greatest risk of exposure as determined by the CP. In addition, collect air samples on at least twenty-five percent of the work crew or a minimum of two employees, whichever is greater, during each work shift.

c. Submit results of air samples, signed by the CP, within 72 hours after the air samples are taken.

d. Conduct area air sampling daily, on each shift in which lead-based paint removal operations are performed, in areas immediately adjacent to the lead control area. Sufficient area monitoring shall be conducted to ensure unprotected personnel are not exposed at or above 30 micrograms per cubic meter of air. If 30 micrograms per cubic meter of air is reached or exceeded, stop work, correct the conditions(s) causing the increased levels. Notify the Contracting Officer immediately. Determine if condition(s) require any further change in work methods. Removal work shall resume only after the CP and the Contracting Officer give approval.

e. Before any work begins, a third party consultant shall collect and analyze baseline wipe samples in accordance with methods defined by federal, State, and local standards inside and outside of the physical boundary to assess the degree of dust contamination in the facility prior to lead disturbance or removal.

3.4.1.2 Sampling After Removal

After the visual inspection, collect wipe samples according to the HUD protocol contained in HUD 6780 to determine the lead content of settled dust in micrograms per square meter foot of surface area.

3.5 CLEANING AND DISPOSAL

3.5.1 Cleanup

Maintain surfaces of the lead control area free of accumulations of dust and debris. Restrict the spread of dust and debris; keep waste from being distributed over the work area. Do not dry sweep or use pressurized air to clean up the area. At the end of each shift and when the lead operation has been completed, clean the controlled area of visible contamination by vacuuming with a HEPA filtered vacuum cleaner, wet mopping the area and wet wiping the area as indicated by the Lead Compliance Plan. Reclean areas showing dust or debris. After visible dust and debris is removed, wet wipe and HEPA vacuum all surfaces in the controlled area. If adjacent areas become contaminated at any time during the work, clean, visually inspect, and then wipe sample all contaminated areas. The CP shall then certify in writing that the area has been cleaned of lead contamination before clearance testing.

3.5.1.1 Clearance Certification

The CP shall certify in writing that air samples collected outside the lead control area during paint removal operations are less than 30 micrograms per cubic meter of air; the respiratory protection used for the employees was adequate; the work procedures were performed in accordance with 29 CFR 1926.62; and that there were no visible accumulations of material and dust containing lead left in the work site. Do not remove the lead control area or roped off boundary and warning signs prior to the Contracting Officer's acknowledgement of receipt of the CP certification.

The third party consultant shall certify surface wipe sample results collected inside and outside the work area are less than 200 micrograms per square foot on floors or horizontal surfaces.

3.5.2 Disposal

a. All material, whether hazardous or non-hazardous shall be disposed in accordance with all laws and provisions and all federal, State or local regulations. Ensure all waste is properly characterized. The result of each waste characterization (TCLP for RCRA materials) will dictate disposal requirements.

b. Contractor is responsible for segregation of waste. Collect lead-contaminated waste, scrap, debris, bags, containers, equipment, and lead-contaminated clothing that may produce airborne concentrations of lead particles. Label the containers in accordance with 29 CFR 1926.62 and 40 CFR 261.

c. Dispose of lead-contaminated material classified as hazardous waste at an EPA or State approved hazardous waste treatment, storage, or disposal facility off Government property.

d. Store waste materials in U.S. Department of Transportation (49 CFR 178) approved 55 gallon drums. Properly label each drum to identify the type of waste (49 CFR 172) and the date the drum was filled. For hazardous waste, the collection drum requires marking/labeling in accordance with 40 CFR 262 during the accumulation/collection timeframe. The Contracting Officer or an authorized representative will assign an area for interim storage of waste-containing drums. Do not store hazardous waste drums in interim storage longer than 90 calendar days from the date affixed to each drum.

e. Handle, store, transport, and dispose lead or lead-contaminated waste in accordance with 40 CFR 260, 40 CFR 261, 40 CFR 262, 40 CFR 263, 40 CFR 264, and 40 CFR 265. Comply with land disposal restriction notification requirements as required by 40 CFR 268.

3.5.2.1 Disposal Documentation

Submit written evidence to demonstrate the hazardous waste treatment, storage, or disposal facility (TSD) is approved for lead disposal by the EPA, State or local regulatory agencies. Submit one copy of the completed hazardous waste manifest, signed and dated by the initial transporter in accordance with 40 CFR 262. Contractor shall provide a certificate that the waste was accepted by the disposal facility. Provide turn-in documents or weight tickets for non-hazardous waste disposal.

3.5.2.2 Payment for Hazardous Waste

Payment for disposal of hazardous and non-hazardous waste will not be made until a signed copy of the manifest from the treatment or disposal facility certifying the amount of lead-containing materials or non-hazardous waste delivered is returned and a copy is furnished to the Government.

-- End of Section --

SECTION 05 12 00

STRUCTURAL STEEL
05/14

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)

AISC 303	(2010) Code of Standard Practice for Steel Buildings and Bridges
AISC 325	(2011) Steel Construction Manual
AISC 326	(2009) Detailing for Steel Construction
AISC 341	(2010) Seismic Provisions for Structural Steel Buildings
AISC 360	(2010) Specification for Structural Steel Buildings

AMERICAN WELDING SOCIETY (AWS)

AWS A2.4	(2012) Standard Symbols for Welding, Brazing and Nondestructive Examination
AWS D1.1/D1.1M	(2010; Errata 2011) Structural Welding Code - Steel

ASME INTERNATIONAL (ASME)

ASME B46.1	(2009) Surface Texture, Surface Roughness, Waviness and Lay

ASTM INTERNATIONAL (ASTM)

ASTM A143/A143M	(2007) Standard Practice for Safeguarding Against Embrittlement of Hot-Dip Galvanized Structural Steel Products and Procedure for Detecting Embrittlement
ASTM A153/A153M	(2009) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A29/A29M	(2013) Standard Specification for General Requirements for Steel Bars, Carbon and Alloy, Hot-Wrought
ASTM A307	(2012) Standard Specification for Carbon Steel Bolts and Studs, 60 000 PSI Tensile

	Strength
ASTM A325	(2010; E 2013) Standard Specification for Structural Bolts, Steel, Heat Treated, 120/105 ksi Minimum Tensile Strength
ASTM A36/A36M	(2012) Standard Specification for Carbon Structural Steel
ASTM A490	(2012) Standard Specification for Structural Bolts, Alloy Steel, Heat Treated, 150 ksi Minimum Tensile Strength
ASTM A500/A500M	(2013) Standard Specification for Cold-Formed Welded and Seamless Carbon Steel Structural Tubing in Rounds and Shapes
ASTM A53/A53M	(2012) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A563	(2007a) Standard Specification for Carbon and Alloy Steel Nuts
ASTM A563M	(2007; R 2013) Standard Specification for Carbon and Alloy Steel Nuts (Metric)
ASTM A6/A6M	(2013a) Standard Specification for General Requirements for Rolled Structural Steel Bars, Plates, Shapes, and Sheet Piling
ASTM A780/A780M	(2009) Standard Practice for Repair of Damaged and Uncoated Areas of Hot-Dip Galvanized Coatings
ASTM A992/A992M	(2011) Standard Specification for Structural Steel Shapes
ASTM B695	(2004; R 2009) Standard Specification for Coatings of Zinc Mechanically Deposited on Iron and Steel
ASTM C1107/C1107M	(2013) Standard Specification for Packaged Dry, Hydraulic-Cement Grout (Nonshrink)
ASTM C827/C827M	(2010) Change in Height at Early Ages of Cylindrical Specimens from Cementitious Mixtures
ASTM F1852	(2011) Standard Specification for "Twist Off" Type Tension Control Structural Bolt/Nut/Washer Assemblies, Steel, Heat Treated, 120/105 ksi Minimum Tensile Strength
ASTM F2329	(2013) Zinc Coating, Hot-Dip, Requirements for Application to Carbon and Alloy Steel Bolts, Screws, Washers, Nuts, and Special

	Threaded Fasteners
ASTM F436	(2011) Hardened Steel Washers
ASTM F844	(2007a; R 2013) Washers, Steel, Plain (Flat), Unhardened for General Use
ASTM F959	(2013) Compressible-Washer-Type Direct Tension Indicators for Use with Structural Fasteners

U.S. DEPARTMENT OF DEFENSE (DOD)

UFC 3-301-01	(2013) Structural Engineering
UFC 3-310-04	(2013) Seismic Design for Buildings

1.2 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Erection Drawings

SD-02 Shop Drawings

Fabrication drawings including description of connections

SD-03 Product Data

Welding electrodes and rods

Direct Tension Indicator Washers

Non-Shrink Grout

Tension control bolts

SD-06 Test Reports

Bolts, nuts, and washers

Weld Inspection Reports

Direct Tension Indicator Washer Inspection Reports

Bolt Testing Reports

Embrittlement Test Reports

SD-07 Certificates

Steel

Bolts, nuts, and washers

Galvanizing

AISC Fabrication Plant Quality Certification

Welding procedures and qualifications

Welding electrodes and rods

1.3 AISC QUALITY CERTIFICATION

Work must be fabricated in an AISC Certified Fabrication Plant, Category Std. Submit AISC fabrication plant quality certification.

1.4 QUALITY ASSURANCE

1.4.1 Preconstruction Submittals

1.4.1.1 Erection Drawings

Submit for record purposes. Indicate the sequence of erection, temporary shoring and bracing. The erection drawings must conform to AISC 303.

1.4.2 Fabrication Drawing Requirements

Submit fabrication drawings for approval prior to fabrication. Prepare in accordance with AISC 326 and AISC 325. Fabrication drawings must not be reproductions of contract drawings. Include complete information for the fabrication and erection of the structure's components, including the location, type, and size of bolts, welds, member sizes and lengths, connection details, blocks, copes, and cuts. Use AWS A2.4 standard welding symbols. Shoring and temporary bracing must be designed and sealed by a registered professional engineer and submitted for record purposes, with calculations, as part of the drawings. Any deviations from the details shown on the contract drawings must be clearly highlighted on the fabrication drawings. Explain the reasons for any deviations from the contract drawings.

1.4.3 Certifications

1.4.3.1 Welding Procedures and Qualifications

Prior to welding, submit certification for each welder stating the type of welding and positions qualified for, the code and procedure qualified under, date qualified, and the firm and individual certifying the qualification tests. If the qualification date of the welding operator is more than one-year old, the welding operator's qualification certificate must be accompanied by a current certificate by the welder attesting to the fact that he has been engaged in welding since the date of certification, with no break in welding service greater than 6 months.

Conform to all requirements specified in AWS D1.1/D1.1M.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

Provide the structural steel system, including galvanizing, complete and ready for use. Structural steel systems including design, materials, installation, workmanship, fabrication, assembly, erection, inspection, quality control, and testing must be provided in accordance with AISC 360,

AISC 341, UFC 3-301-01 and UFC 3-310-04 except as modified in this contract.

2.2 STEEL

2.2.1 Structural Steel

Wide flange and WT shapes, ASTM A992/A992M. Angles, Channels and Plates, ASTM A36/A36M.

2.2.2 Structural Steel Tubing

ASTM A500/A500M, Grade B.

2.2.3 Steel Pipe

ASTM A53/A53M, Type E or S, Grade B, weight class STD (Standard).

2.3 BOLTS, NUTS, AND WASHERS

Submit the certified manufacturer's mill reports which clearly show the applicable ASTM mechanical and chemical requirements together with the actual test results for the supplied fasteners.

2.3.1 Common Grade Bolts

2.3.1.1 Bolts

ASTM A307, Grade A. The bolt heads and the nuts of the supplied fasteners must be marked with the manufacturer's identification mark, the strength grade and type specified by ASTM specifications.

2.3.1.2 Nuts

ASTM A563M, Grade A, heavy hex style.

2.3.1.3 Washers

ASTM F844.

2.3.2 High-Strength Bolts

2.3.2.1 Bolts

ASTM A325, Type 1 ASTM A490, Type 1 or 2.

2.3.2.2 Nuts

ASTM A563, Grade and Style as specified in the applicable ASTM bolt standard.

2.3.2.3 Direct Tension Indicator Washers

ASTM F959. Provide ASTM B695, Class 50, Type 1 galvanizing.

2.3.2.4 Washers

ASTM F436, plain carbon steel.

2.3.3 Tension Control Bolts

ASTM F1852, Type 1, heavy-hex head assemblies consisting of steel structural bolts with splined ends, heavy-hex carbon steel nuts, and hardened carbon steel washers. Assembly finish must be mechanically deposited zinc coating.

2.4 STRUCTURAL STEEL ACCESSORIES

2.4.1 Welding Electrodes and Rods

AWS D1.1/D1.1M.

2.4.2 Non-Shrink Grout

ASTM C1107/C1107M, with no ASTM C827/C827M shrinkage. Grout must be nonmetallic.

2.4.3 Welded Shear Stud Connectors

ASTM A29/A29M, Type B. AWS D1.1/D1.1M.

2.5 GALVANIZING

ASTM F2329 for threaded parts or ASTM A153/A153M for structural steel members, as applicable, unless specified otherwise galvanize after fabrication where practicable. All steel, grating, bolts, nuts and washers shall be galvanized.

2.6 FABRICATION

Fabrication must be in accordance with the applicable provisions of AISC 325. Fabrication and assembly must be done in the shop to the greatest extent possible. Punch, subpunch and ream, or drill bolt holes perpendicular to the surface of the member.

Compression joints depending on contact bearing must have a surface roughness not in excess of 500 micro inch as determined by ASME B46.1, and ends must be square within the tolerances for milled ends specified in ASTM A6/A6M.

Shop splices of members between field splices will be permitted only where indicated on the Contract Drawings. Splices not indicated require the approval of the Contracting Officer.

Erection of platform in the field shall utilize bolted connections to greatest extent possible.

2.6.1 Markings

Prior to erection, members must be identified by a painted erection mark. Connecting parts assembled in the shop for reaming holes in field connections must be match marked with scratch and notch marks. Do not locate erection markings on areas to be welded. Do not locate match markings in areas that will decrease member strength or cause stress concentrations. Affix embossed tags to hot-dipped galvanized members.

2.7 DRAINAGE HOLES

Adequate drainage holes must be drilled to eliminate water traps. Hole diameter must be 1/2 inch and location must be indicated on the detail drawings. Hole size and location must not affect the structural integrity.

PART 3 EXECUTION

3.1 ERECTION

a. Erection of structural steel must be in accordance with the applicable provisions of AISC 325.

After final positioning of steel members, provide full bearing under base plates and bearing plates using nonshrink grout. Place nonshrink grout in accordance with the manufacturer's instructions.

3.1.1 STORAGE

Material must be stored out of contact with the ground in such manner and location as will minimize deterioration.

3.2 CONNECTIONS

Except as modified in this section, connections not detailed must be designed in accordance with AISC 360. Build connections into existing work. Do not tighten anchor bolts set in concrete with impact torque wrenches. Holes must not be cut or enlarged by burning. Bolts, nuts, and washers must be clean of dirt and rust, and lubricated immediately prior to installation.

3.2.1 Common Grade Bolts

ASTM A307 bolts must be tightened to a "snug tight" fit. "Snug tight" is the tightness that exists when plies in a joint are in firm contact. If firm contact of joint plies cannot be obtained with a few impacts of an impact wrench, or the full effort of a man using a spud wrench, contact the Contracting Officer for further instructions.

3.2.2 High-Strength Bolts

Provide direct tension indicator washers in all ASTM A325 and ASTM A490 bolted connections. Bolts must be installed in connection holes and initially brought to a snug tight fit. After the initial tightening procedure, bolts must then be fully tensioned, progressing from the most rigid part of a connection to the free edges.

3.2.2.1 Installation of Direct Tension Indicator Washers (DTIW)

Where possible, the DTIW must be installed under the bolt head and the nut must be tightened. If the DTIW is installed adjacent to the turned element, provide a flat washer between the DTIW and nut when the nut is turned for tightening, and between the DTIW and bolt head when the bolt head is turned for tightening. In addition to the LIW, provide flat washers under both the bolt head and nut when ASTM A490 bolts are used.

3.2.3 Tension Control Bolts

Bolts must be installed in connection holes and initially brought to a snug

tight fit. After the initial tightening procedure, bolts must then be fully tensioned, progressing from the most rigid part of a connection to the free edges.

3.3 GAS CUTTING

Use of gas-cutting torch in the field for correcting fabrication errors will not be permitted on any major member in the structural framing. Use of a gas cutting torch will be permitted on minor members not under stress only after approval has been obtained from the Contracting Officer.

3.4 WELDING

Welding must be in accordance with AWS D1.1/D1.1M. Grind exposed welds smooth as indicated. Provide AWS D1.1/D1.1M qualified welders, welding operators, and tackers.

Develop and submit the Welding Procedure Specifications (WPS) for all welding, including welding done using prequalified procedures. Prequalified procedures may be submitted for information only; however, procedures that are not prequalified must be submitted for approval.

3.4.1 Removal of Temporary Welds, Run-Off Plates, and Backing Strips

Remove only from finished areas.

3.5 GALVANIZING REPAIR

Repair damage to galvanized coatings using ASTM A780/A780M zinc rich paint for galvanizing damaged by handling, transporting, cutting, welding, or bolting. Do not heat surfaces to which repair paint has been applied.

3.6 FIELD QUALITY CONTROL

Perform field tests, and provide labor, equipment, and incidentals required for testing. The Contracting Officer must be notified in writing of defective welds, bolts, nuts, and washers within 7 working days of the date of the inspection.

3.6.1 Welds

3.6.1.1 Visual Inspection

AWS D1.1/D1.1M. Furnish the services of AWS-certified welding inspectors for fabrication and erection inspection and testing and verification inspections.

Inspect proper preparation, size, gaging location, and acceptability of welds; identification marking; operation and current characteristics of welding sets in use. Submit weld inspection Reports.

3.6.2 Direct Tension Indicator Washers

3.6.2.1 Direct Tension Indicator Washer Compression

Direct tension indicator washers must be tested in place to verify that they have been compressed sufficiently to provide the 0.015 inch gap when the direct tension indicator washer is placed under the bolt head and the nut is tightened, and to provide the 0.005 inch gap when the direct tension

indicator washer is placed under the turned element, as required by ASTM F959. Submit direct tension indicator washer inspection reports.

3.6.3 High-Strength Bolts

3.6.3.1 Testing Bolt, Nut, and Washer Assemblies

Test a minimum of 3 bolt, nut, and washer assemblies from each mill certificate batch in a tension measuring device at the job site prior to the beginning of bolting start-up. Demonstrate that the bolts and nuts, when used together, can develop tension not less than the provisions specified in AISC 360, depending on bolt size and grade. The bolt tension must be developed by tightening the nut. A representative of the manufacturer or supplier must be present to ensure that the fasteners are properly used, and to demonstrate that the fastener assemblies supplied satisfy the specified requirements. Submit bolt testing reports.

3.6.3.2 Inspection

Inspection procedures must be in accordance with AISC 360. Confirm and report to the Contracting Officer that the materials meet the project specification and that they are properly stored. Confirm that the faying surfaces have been properly prepared before the connections are assembled. Observe the specified job site testing and calibration, and confirm that the procedure to be used provides the required tension. Monitor the work to ensure the testing procedures are routinely followed on joints that are specified to be fully tensioned.

Inspect calibration of torque wrenches for high-strength bolts.

3.6.3.3 Testing

The Government has the option to perform nondestructive tests on 5 percent of the installed bolts to verify compliance with pre-load bolt tension requirements. Provide the required access for the Government to perform the tests. The nondestructive testing will be done in-place using an ultrasonic measuring device or any other device capable of determining in-place pre-load bolt tension. The test locations must be selected by the Contracting Officer. If more than 10 percent of the bolts tested contain defects identified by testing, then all bolts used from the batch from which the tested bolts were taken, must be tested at the Contractor's expense. Retest new bolts after installation at the Contractor's expense.

3.6.4 Testing for Embrittlement

ASTM A143/A143M for steel products hot-dip galvanized after fabrication. Submit embrittlement test reports.

-- End of Section --

SECTION 05 50 13

MISCELLANEOUS METAL FABRICATIONS
05/10

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)

AISC 303	(2010) Code of Standard Practice for Steel Buildings and Bridges

AMERICAN WELDING SOCIETY (AWS)

AWS D1.1/D1.1M	(2010; Errata 2011) Structural Welding Code - Steel

ASME INTERNATIONAL (ASME)

ASME B18.2.1	(2012; Errata 2013) Square and Hex Bolts and Screws (Inch Series)
ASME B18.21.1	(2009) Washers: Helical Spring-Lock, Tooth Lock, and Plain Washers (Inch Series)
ASME B18.6.2	(1998; R 2010) Slotted Head Cap Screws, Square Head Set Screws, and Slotted Headless Set Screws: Inch Series
ASME B18.6.3	(2013) Machine Screws, Tapping Screws, and Machine Drive Screws (Inch Series)

ASTM INTERNATIONAL (ASTM)

ASTM A123/A123M	(2013) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A153/A153M	(2009) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A307	(2012) Standard Specification for Carbon Steel Bolts and Studs, 60 000 PSI Tensile Strength
ASTM A36/A36M	(2012) Standard Specification for Carbon Structural Steel
ASTM A475	(2003a; E 2009; R 2009) Standard Specification for Zinc-Coated Steel Wire

	Strand
ASTM A653/A653M	(2013) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM A780/A780M	(2009) Standard Practice for Repair of Damaged and Uncoated Areas of Hot-Dip Galvanized Coatings
ASTM A924/A924M	(2013) Standard Specification for General Requirements for Steel Sheet, Metallic-Coated by the Hot-Dip Process
ASTM C1513	(2013) Standard Specification for Steel Tapping Screws for Cold-Formed Steel Framing Connections
ASTM D1187/D1187M	(1997; E 2011; R 2011) Asphalt-Base Emulsions for Use as Protective Coatings for Metal
ASTM E488/E488M	(2010) Standard Test Methods for Strength of Anchors in Concrete and Masonry Elements

MASTER PAINTERS INSTITUTE (MPI)

MPI 79	(Oct 2009) Alkyd Anti-Corrosive Metal Primer

NATIONAL ASSOCIATION OF ARCHITECTURAL METAL MANUFACTURERS (NAAMM)

NAAMM MBG 531	(2009) Metal Bar Grating Manual

1.2 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Floor gratings and roof walkways, installation drawings

Angles and plates, installation drawings

Submit fabrication drawings showing layout(s), connections to structural system, and anchoring details as specified in AISC 303.

Submit templates, erection and installation drawings indicating thickness, type, grade, class of metal, and dimensions. Show construction details, reinforcement, anchorage, and installation with relation to the building construction.

SD-03 Product Data

Floor gratings and roof walkways

1.3 QUALIFICATION OF WELDERS

Qualify welders in accordance with AWS D1.1/D1.1M. Use procedures, materials, and equipment of the type required for the work.

1.4 DELIVERY, STORAGE, AND PROTECTION

Protect from corrosion, deformation, and other types of damage. Store items in an enclosed area free from contact with soil and weather. Remove and replace damaged items with new items.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Structural Carbon Steel

ASTM A36/A36M.

2.1.2 Gratings

a. Metal bar type grating NAAMM MBG 531.

2.1.3 Anchor Bolts

ASTM A307. Where exposed, shall be of the same material, color, and finish as the metal to which applied.

2.1.3.1 Adhesive Anchors

Provide 5/8 in. (minimum) diameter adhesive anchors. Minimum concrete embedment shall be 5 in. Design values listed shall be as tested according to ASTM E488/E488M.

a. Minimum allowable pullout value shall be 5200 lb.

b. Minimum allowable shear value shall be 3700 lb.

2.1.3.2 Lag Screws and Bolts

ASME B18.2.1, type and grade best suited for the purpose.

2.1.3.3 Screws

ASME B18.2.1, ASME B18.6.2, ASME B18.6.3 and ASTM C1513.

2.1.3.4 Washers

Provide plain washers to conform to ASME B18.21.1. Provide beveled washers for American Standard beams and channels, square or rectangular, tapered in thickness, and smooth. Provide lock washers to conform to ASME B18.21.1.

2.2 FABRICATION FINISHES

2.2.1 Galvanizing

Hot-dip galvanize items specified to be zinc-coated, after fabrication where practicable. Galvanizing: ASTM A123/A123M, ASTM A153/A153M,

ASTM A653/A653M or ASTM A924/A924M, G90, as applicable.

2.2.2 Galvanize

Anchor bolts, grating fasteners, washers, and parts or devices necessary for proper installation, unless indicated otherwise.

2.2.3 Repair of Zinc-Coated Surfaces

Repair damaged surfaces with galvanizing repair method and paint conforming to ASTM A780/A780M or by application of stick or thick paste material specifically designed for repair of galvanizing, as approved by Contracting Officer. Clean areas to be repaired and remove slag from welds. Heat surfaces to which stick or paste material is applied, with a torch to a temperature sufficient to melt the metallics in stick or paste; spread molten material uniformly over surfaces to be coated and wipe off excess material.

2.2.4 Nonferrous Metal Surfaces

Protect by plating, anodic, or organic coatings.

2.3 FLOOR GRATINGS AND ROOF WALKWAYS

Design steel grating in accordance with NAAMM MBG 531 for bar type grating or manufacturer's charts for plank grating. Galvanize steel floor gratings.

a. Design floor gratings to support a live load of 100 pounds per square foot for the spans indicated, with maximum deflection of L/240.

b. NAAMM MBG 531, band edges of grating with bars of the same size as the bearing bars. Weld banding in accordance with the manufacturer's standard for trim unless otherwise indicated. Design tops of bearing bars, cross or intermediate bars to be in the same plane and match grating finish.

c. Attach gratings to structural members with welded-on anchors. d. Slip resistance requirements must exceed both wet and dry a static coefficient of friction of 0.5.

2.4 MISCELLANEOUS PLATES AND SHAPES

Provide angles and plates, ASTM A36/A36M, as indicated. Galvanize according to ASTM A123/A123M.

2.5 GUY CABLES

Guy cables shall be prestretched, galvanized wire rope of the sizes indicated. Wire rope shall conform to ASTM A475, high strength grade with Class A coating. Guys shall have a factory attached clevis top-end fitting; a factory attached open-bridge strand socket bottom-end fitting; and be complete with oval eye, threaded anchor rods. Fittings and accessories shall be hot-dip galvanized.

PART 3 EXECUTION

3.1 GENERAL INSTALLATION REQUIREMENTS

Install items at locations indicated, according to manufacturer's

instructions. Verify all measurements and take all field measurements necessary before fabrication. Exposed fastenings shall be compatible materials, shall generally match in color and finish, and harmonize with the material to which fastenings are applied. Include materials and parts necessary to complete each item, even though such work is not definitely shown or specified. Poor matching of holes for fasteners shall be cause for rejection. Conceal fastenings where practicable. Thickness of metal and details of assembly and supports shall provide strength and stiffness. Form joints exposed to the weather shall be formed to exclude water. Items listed below require additional procedures.

3.2 WORKMANSHIP

Provide miscellaneous metalwork that is well formed to shape and size, with sharp lines and angles and true curves. Drilling and punching shall produce clean true lines and surfaces. Provide continuous welding along the entire area of contact except where tack welding is permitted. Do not tack weld exposed connections of work in place and ground smooth. Provide a smooth finish on exposed surfaces of work in place and unless otherwise approved, flush exposed riveting. Mill joints where tight fits are required. Corner joints shall be coped or mitered, well formed, and in true alignment. Accurately set work to established lines and elevations and securely fastened in place. Install in accordance with manufacturer's installation instructions and approved drawings, cuts, and details.

3.3 ANCHORAGE, FASTENINGS, AND CONNECTIONS

Provide anchorage where necessary for fastening miscellaneous metal items securely in place. Include for anchorage not otherwise specified or indicated slotted inserts, expansion shields, and powder-driven fasteners, when approved for concrete; through bolts, lag bolts, and screws for wood. Do not use wood plugs in any material. Provide non-ferrous attachments for non-ferrous metal. Make exposed fastenings of compatible materials, generally matching in color and finish, to which fastenings are applied. Conceal fastenings where practicable.

3.4 BUILT-IN WORK

Form for anchorage metal work built-in with concrete or masonry, or provide with suitable anchoring devices as indicated or as required. Furnish metal work in ample time for securing in place as the work progresses.

3.5 WELDING

Perform welding, welding inspection, and corrective welding, in accordance with AWS D1.1/D1.1M. Use continuous welds on all exposed connections. Grind visible welds smooth in the finished installation.

3.6 FINISHES

3.6.1 Dissimilar Materials

Where dissimilar metals are in contact, protect surfaces with a coat conforming to MPI 79 to prevent galvanic or corrosive action. Where aluminum is in contact with concrete, plaster, mortar, masonry, wood, or absorptive materials subject to wetting, protect with ASTM D1187/D1187M, asphalt-base emulsion.

3.6.2 Field Preparation

Remove rust preventive coating just prior to field erection, using a remover approved by the rust preventive manufacturer. Surfaces, when assembled, shall be free of rust, grease, dirt and other foreign matter.

3.6.3 Environmental Conditions

Do not clean or paint surface when damp or exposed to foggy or rainy weather, when metallic surface temperature is less than 5 degrees F above the dew point of the surrounding air, or when surface temperature is below 45 degrees F or over 95 degrees F, unless approved by the Contracting Officer.

-- End of Section --

SECTION 05 52 00

METAL RAILINGS
02/11

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN WELDING SOCIETY (AWS)

AWS D1.1/D1.1M	(2010; Errata 2011) Structural Welding Code - Steel

ASTM INTERNATIONAL (ASTM)

ASTM A123/A123M	(2013) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A283/A283M	(2013) Standard Specification for Low and Intermediate Tensile Strength Carbon Steel Plates
ASTM A36/A36M	(2012) Standard Specification for Carbon Structural Steel
ASTM A53/A53M	(2012) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A575	(1996; E 2013; R 2013) Standard Specification for Steel Bars, Carbon, Merchant Quality, M-Grades

NATIONAL ASSOCIATION OF ARCHITECTURAL METAL MANUFACTURERS (NAAMM)

NAAMM AMP 521	(2001) Pipe Railing Manual

1.2 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Fabrication Drawings

Iron and Steel Hardware

Steel Shapes, Plates, Bars and Strips

SD-03 Product Data

Structural Steel Plates, Shapes, and Bars

Hot-Rolled Carbon Steel Bars

Protective Coating

Steel Railings

SD-07 Certificates

Welding Procedures

Welder Qualification

SD-08 Manufacturer's Instructions

Installation Instructions

1.3 QUALITY ASSURANCE

1.3.1 Welding Procedures

Submit welding procedures testing in accordance with AWS D1.1/D1.1M made in the presence of the Contracting Officer and by an approved testing laboratory at the Contractor's expense.

1.3.2 Welder Qualification

Submit certified welder qualification by tests in accordance with AWS D1.1/D1.1M, or under an equivalent approved qualification test. In addition be performed on test pieces in positions and with clearances equivalent to those actually encountered. If a test weld fails to meet requirements, make an immediate retest of two test welds and ensure each test weld passes. Failure in the immediate retest will require that the welder be retested after further practice or training and make a complete set of test welds.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

Provide complete, detailed fabrication and installation drawings for all iron and steel hardware, and for all steel shapes, plates, bars and strips used in accordance with the design specifications referenced in this section.

Pre-assemble items in the shop to the greatest extent possible. Disassemble units only to the extent necessary for shipping and handling. Clearly mark units for reassembly and coordinated installation.

For the fabrication of work exposed to view, use only materials that are smooth and free of surface blemishes, including pitting, seam marks, roller marks, rolled trade names, and roughness. Remove blemishes by grinding, or by welding and grinding, prior to cleaning, treating, and application of surface finishes, including zinc coatings.

2.2 GENERAL FABRICATION

Provide railings and guardrails detail plans and elevations at not less than

1 inch to 1 foot. Provide details of sections and connections at not less than 3 inches to 1 foot. Also detail setting drawings, diagrams, templates for installation of anchorages, including concrete inserts, anchor bolts, and miscellaneous metal items having integral anchors.

Use materials of size and thicknesses indicated or, if not indicated, of required size and thickness to produce adequate strength and durability in finished product for intended use. Work materials to dimensions indicated on approved detail drawings, using proven details of fabrication and support. Use type of materials indicated or specified for the various components of work.

Form exposed work true to line and level with accurate angles and surfaces and straight sharp edges. Ensure all exposed edges are eased to a radius of approximately 1/32 inch. Bend metal corners to the smallest radius possible without causing grain separation or otherwise impairing the work.

Weld corners and seams continuously and in accordance with the recommendations of AWS D1.1/D1.1M. Grind exposed welds smooth and flush to match and blend with adjoining surfaces.

Form exposed connections with hairline joints that are flush and smooth, using concealed fasteners wherever possible. Use exposed fasteners of the type indicated or, if not indicated, use Phillips flathead (countersunk) screws or bolts.

Provide anchorage of the type indicated and coordinated with the supporting structure. Fabricate anchoring devices and space as indicated and as required to provide adequate support for the intended use of the work.

Use hot-rolled steel bars for work fabricated from bar stock unless work is indicated or specified to be fabricated from cold-finished or cold-rolled stock.

2.3 STRUCTURAL STEEL PLATES, SHAPES AND BARS

Provide structural-size shapes and plates, except plates to be bent or cold-formed, conforming to ASTM A36/A36M, unless otherwise noted.

Provide steel plates, to be bent or cold-formed,conforming to ASTM A283/A283M, Grade C.

Provide steel bars and bar-size shapes conforming to ASTM A36/A36M, unless otherwise noted.

2.4 HOT-ROLLED CARBON STEEL BARS

Provide bars and bar-size shapes conforming to ASTM A575, grade as selected by the fabricator.

2.5 STEEL PIPE

Provide pipe conforming to ASTM A53/A53M, type as selected, Grade B; galvanized; Extra-Strong.

2.6 PROTECTIVE COATING

Provide hot dipped galvanized steelwork as indicated in accordance with ASTM A123/A123M. Touch up abraded surfaces and cut ends of galvanized

members with zinc-dust, zinc-oxide primer, or an approved galvanizing repair compound.

2.7 STEEL RAILINGS

Design railing to resist a concentrated load of 250 lbs in any direction at any point of the top of the rail or 20 lbs per foot applied horizontally to top of the rail, whichever is more severe. NAAMM AMP 521, provide the same size rail and post. Provide pipe collars of the same material and finish as the handrail and posts.

2.7.1 Steel Guardrails

Provide steel pipe conforming to ASTM A53/A53M. Provide steel railings of 1 1/2 inches nominal size, hot-dip galvanized.

a. Fabrication: Joint posts, rail, and corners by one of the following methods:

(1) Flush-type rail fittings of commercial standard, welded and ground smooth with railing splice locks secured with 3/8 inch hexagonal-recessed-head setscrews.

(2) Mitered and welded joints made by fitting post to top rail and intermediate rail to post, mitering corners, groove welding joints, and grinding smooth. Butt railing splices and reinforce them by a tight fitting interior sleeve not less than 6 inches long.

(3) Railings may be bent at corners in lieu of jointing, provided bends are made in suitable jigs and the pipe is not crushed.

b. Provide removable sections as indicated.

Provide kickplates between railing posts where indicated, and consist of 1/8-inch steel flat bars not less than 4 inches high unless otherwise indicated. Secure kickplates as indicated.

Provide galvanized railings, including pipe, fittings, brackets, fasteners, and other ferrous metal components.

PART 3 EXECUTION

3.1 INSTALLATION INSTRUCTIONS

Submit manufacturer's fabrication drawings and installation instructions for the following products to be used in the fabrication of steel:

a. Steel railings and guardrails

Provide complete, detailed fabrication and installation drawings for all iron and steel hardware, and for all steel shapes, plates, bars and strips used in accordance with the design specifications referenced in this section.

3.2 PREPARATION

Adjust railings prior to securing in place to ensure proper matching at butting joints and correct alignment throughout their length. Space posts

not more than 4 feet on center. Plumb posts in each direction. Secure posts and rail ends to building construction as follows:

Anchor posts by means of pipe sleeves where indicated. Provide sleeves of galvanized, standard weight, steel pipe, not less than 6 inches long, and having an inside diameter not less than 1/2-inch greater than the outside diameter of the inserted pipe post.

3.3 FIELD WELDING

Ensure procedures of manual shielded metal arc welding, appearance and quality of welds made, and methods used in correcting welding work comply with AWS D1.1/D1.1M.

-- End of Section --

SECTION 06 10 00

ROUGH CARPENTRY
02/12

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN INSTITUTE OF TIMBER CONSTRUCTION (AITC)

AITC TCM	(2004; Errata 2010) Timber Construction Manual, 5th Edition

AMERICAN LUMBER STANDARDS COMMITTEE (ALSC)

ALSC PS 20	(2010) American Softwood Lumber Standard

AMERICAN WOOD COUNCIL (AWC)

AWC NDS	(2012) National Design Specification (NDS) for Wood Construction
AWC WFCM	(2012) Wood Frame Construction Manual for One- and Two-Family Dwellings

AMERICAN WOOD PROTECTION ASSOCIATION (AWPA)

AWPA BOOK	(2012) AWPA Book of Standards
AWPA M2	(2011) Standard for Inspection of Treated Wood Products
AWPA M6	(2013) Brands Used on Preservative Treated Materials
AWPA P5	(2007) Standard for Waterborne Preservatives

APA - THE ENGINEERED WOOD ASSOCIATION (APA)

APA E30	(2011) Engineered Wood Construction Guide
APA EWS T300	(2007) Technical Note: Glulam Connection Details
APA L870	(2010) Voluntary Product Standard, PS 1-09, Structural Plywood

ASME INTERNATIONAL (ASME)

ASME B18.2.1	(2012; Errata 2013) Square and Hex Bolts and Screws (Inch Series)

ASME B18.2.2	(2010) Nuts for General Applications: Machine Screw Nuts, Hex, Square, Hex Flange, and Coupling Nuts (Inch Series)
ASME B18.5.2.1M	(2006; R 2011) Metric Round Head Short Square Neck Bolts
ASME B18.5.2.2M	(1982; R 2010) Metric Round Head Square Neck Bolts
ASME B18.6.1	(1981; R 2008) Wood Screws (Inch Series)

ASTM INTERNATIONAL (ASTM)

ASTM A153/A153M	(2009) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A307	(2012) Standard Specification for Carbon Steel Bolts and Studs, 60 000 PSI Tensile Strength
ASTM A653/A653M	(2013) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM F1667	(2013) Driven Fasteners: Nails, Spikes, and Staples
ASTM F547	(2006; R 2012) Nails for Use with Wood and Wood-Base Materials

FM GLOBAL (FM)

FM 4435	(2013) Roof Perimeter Flashing

INTERNATIONAL CODE COUNCIL (ICC)

ICC IBC	(2012) International Building Code

TRUSS PLATE INSTITUTE (TPI)

TPI 1	(2007; R 2006) National Design Standard for Metal Plate Connected Wood Truss Construction; Commentary and Appendices

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

CID A-A-1923	(Rev A; Notice 2) Shield, Expansion (Lag, Machine and Externally Threaded Wedge Bolt Anchors)
CID A-A-1924	(Rev A; Notice 2) Shield, Expansion (Self Drilling Tubular Expansion Shell Bolt Anchors
CID A-A-1925	(Rev A; Notice 2) Shield Expansion (Nail Anchors)

FS UU-B-790 (Rev A; Am 1; Notice 1) Building Paper, Vegetable Fiber: (Kraft, Waterproofed, Water Repellent and Fire Resistant)

1.2 SUBMITTALS

The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-06 Test Reports

Preservative-treated lumber and plywood

SD-07 Certificates

Certificates of grade

Manufacturer's certificates (approved by an American Lumber Standards approved agency) attesting that lumber and material not normally grade marked meet the specified requirements. Certificate of Inspection for grade marked material by an American Lumber Standards Committee (ALSC) recognized inspection agency prior to shipment.

Preservative treatment

1.3 DELIVERY AND STORAGE

Deliver materials to the site in an undamaged condition. Store, protect, handle, and install prefabricated structural elements in accordance with manufacturer's instructions and as specified. Store materials off the ground to provide proper ventilation, with drainage to avoid standing water, and protection against ground moisture and dampness. Store materials with a moisture barrier at both the ground level and as a cover forming a well ventilated enclosure. Adhere to requirements for stacking, lifting, bracing, cutting, notching, and special fastening requirements. Remove defective and damaged materials and provide new materials. Store separated reusable wood waste convenient to cutting station and area of work.

1.4 GRADING AND MARKING

1.4.1 Lumber

Mark each piece of framing and board lumber or each bundle of small pieces of lumber with the grade mark of a recognized association or independent inspection agency. Such association or agency shall be certified by the Board of Review, American Lumber Standards Committee, to grade the species used. Surfaces that are to be exposed to view shall not bear grademarks, stamps, or any type of identifying mark. Hammer marking will be permitted on timbers when all surfaces will be exposed to view.

1.4.2 Plywood

Mark each sheet with the mark of a recognized association or independent inspection agency that maintains continuing control over the quality of the plywood. The mark shall identify the plywood by species group or span rating, exposure durability classification, grade, and compliance with

APA L870.Surfaces that are to be exposed to view shall not bear grademarks or other types of identifying marks.

1.4.3 Preservative-Treated Lumber and Plywood

The Contractor shall be responsible for the quality of treated wood products. Each treated piece shall be inspected in accordance with AWPA M2 and permanently marked or branded, by the producer, in accordance with AWPA M6. The Contractor shall provide Contracting Officer's Representative (COR) with the inspection report of an approved independent inspection agency that offered products comply with applicable AWPA Standards. The appropriate Quality Mark on each piece will be accepted, in lieu of inspection reports, as evidence of compliance with applicable AWPA treatment standards.

1.5 SIZES AND SURFACING

ALSC PS 20 for dressed sizes of yard and structural lumber. Lumber shall be surfaced four sides. Size references, unless otherwise specified, are nominal sizes, and actual sizes shall be within manufacturing tolerances allowed by the standard under which the product is produced. Other measurements are IP or SI standard.

1.6 MOISTURE CONTENT

Air-dry or kiln-dry lumber. Kiln-dry treated lumber after treatment. Maximum moisture content of wood products shall be as follows at the time of delivery to the job site:

a. Framing lumber and board, 19 percent maximum

b. Timbers 5 inches and thicker, 25 percent maximum

c. Materials other than lumber; moisture content shall be in accordance with standard under which the product is produced

1.7 PRESERVATIVE TREATMENT

Treat wood products with waterborne wood preservatives conforming to AWPA P5. Pressure treatment of wood products shall conform to the requirements of AWPA BOOK Use Category System Standards U1 and T1. Pressure-treated wood products shall not contain arsenic, chromium, or other agents classified as carcinogenic, probably carcinogenic, or possibly carcinogenic to humans (compounds in Groups 1, 2A, or 2B) by the International Agency for Research on Cancer (IARC), Lyon, France. Pressure-treated wood products shall not exceed the limits of the U.S. EPA's Toxic Characteristic Leaching Procedure (TCLP), and shall not be classified as hazardous waste. Submit certification from treating plant stating chemicals and process used and net amount of preservatives retained are in conformance with specified standards.

a. 0.25 pcf intended for above ground use.

1.8 QUALITY ASSURANCE

1.8.1 Certificates of Grade

Submit certificates attesting that products meet the grade requirements specified in lieu of grade markings where appearance is important and grade

marks will deface material.

1.8.2 Humidity Requirements

Sequence work to minimize use of temporary HVAC to dry out building and control humidity.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Virgin Lumber

Lumber fabricated from old growth timber is not permitted. Avoid companies who buy, sell, or use old growth timber in their operations, when possible.

2.2 LUMBER

2.2.1 Structural Lumber

Unless otherwise indicated all lumber shall be Southern Pine No.2. Design of members and fastenings shall conform to AITC TCM. Other stress graded or dimensioned items such as blocking, carriages, and studs shall be standard or No. 2 grade except that studs may be Stud grade.

2.3 PLYWOOD

APA L870.

2.3.1 Roof Sheathing

2.3.1.1 Plywood

Structural I, exposure 1, and a minimum thickness of 3/4 inch.

2.4 OTHER MATERIALS

2.4.1 Building Paper

FS UU-B-790, Type I, Grade D, Style 1.

2.4.2 Miscellaneous Wood Members

2.4.2.1 Nonstress Graded Members

Members shall include bridging, corner bracing, furring, grounds, and nailing strips. Members shall be in accordance with TABLE I for the species used. Sizes shall be as follows unless otherwise shown:

Member	Size inch
Bridging	1 x 3 or 1 x 4 for use between members 2 x 12 and smaller; 2 x 4 for use between members larger than 2 x 12.

2.4.2.2 Blocking

Blocking shall be southern pine number 2 grade.

2.5 ROUGH HARDWARE

Unless otherwise indicated or specified, rough hardware shall be of the type and size necessary for the project requirements. Sizes, types, and spacing of fastenings of manufactured building materials shall be as recommended by the product manufacturer unless otherwise indicated or specified. Rough hardware exposed to the weather or embedded in or in contact with preservative treated wood, exterior masonry, or concrete walls or slabs shall be hot-dip zinc-coated in accordance with ASTM A153/A153M.

2.5.1 Bolts, Nuts, Studs, and Rivets

ASME B18.2.1, ASME B18.5.2.1M, ASME B18.5.2.2M and ASME B18.2.2.

2.5.2 Anchor Bolts

ASTM A307, size as indicated, complete with nuts and washers.

2.5.3 Expansion Shields

CID A-A-1923, CID A-A-1924, and CID A-A-1925. Except as shown otherwise, maximum size of devices shall be 3/8 inch.

2.5.4 Lag Screws and Lag Bolts

ASME B18.2.1.

2.5.5 Wood Screws

ASME B18.6.1.

2.5.6 Nails

ASTM F547, size and type best suited for purpose. For sheathing and subflooring, length of nails shall be sufficient to extend 1 inch into supports. In general, 8-penny or larger nails shall be used for nailing through 1 inch thick lumber and for toe nailing 2 inch thick lumber; 16-penny or larger nails shall be used for nailing through 2 inch thick lumber. Nails used with treated lumber and sheathing shall be hot-dipped galvanized in accordance with ASTM A153/A153M. Nailing shall be in accordance with the recommended nailing schedule contained in AWC WFCM. Where detailed nailing requirements are not specified, nail size and spacing shall be sufficient to develop an adequate strength for the connection. The connection's strength shall be verified against the nail capacity tables in AWC NDS. Reasonable judgment backed by experience shall ensure that the designed connection will not cause the wood to split. If a load situation exceeds a reasonable limit for nails, a specialized connector shall be used.

2.5.7 Wire Nails

ASTM F1667.

2.5.8 Timber Connectors

Unless otherwise specified, timber connectors shall be in accordance with TPI 1, APA EWS T300 or AITC TCM.

2.5.9 Clip Angles

Steel, 3/16 inch thick, size as indicated; or zinc-coated steel or iron commercial clips designed for connecting wood members.

2.5.10 Joist Hangers

Steel or iron, zinc coated, sized to fit the supported member, of sufficient strength to develop the full strength of the supported member in accordance with ICC IBC, and furnished complete with any special nails required.

2.5.11 Metal Framing Anchors

Construct anchors to the configuration shown using hot dip zinc-coated steel conforming to ASTM A653/A653M, G90. Except where otherwise shown, Steel shall be not lighter than 18 gage. Special nails supplied by the manufacturer shall be used for all nailing.

2.5.12 Panel Edge Clips

Extruded aluminum or galvanized steel, H-shaped clips to prevent differential deflection of roof sheathing.

PART 3 EXECUTION

3.1 INSTALLATION

Conform to AWC WFCM and install in accordance with the National Association of Home Builders (NAHB) Advanced Framing Techniques: Optimum Value Engineering, unless otherwise indicated or specified. Select lumber sizes to minimize waste. Fit framing lumber and other rough carpentry, set accurately to the required lines and levels, and secure in place in a rigid manner. o not splice framing members between bearing points. Set joists, rafters, and purlins with their crown edge up. Frame members for the passage of pipes, conduits, and ducts. Provide adequate support as appropriate to the application, climate, and modulus of elasticity of the product. Do not cut or bore structural members for the passage of ducts or pipes without approval. Reinforce all members damaged by such cutting or boring by means of specially formed and approved sheet metal or bar steel shapes, or remove and provide new, as approved. Provide as necessary for the proper completion of the work all framing members not indicated or specified. Spiking and nailing not indicated or specified otherwise shall be in accordance with the Nailing Schedule contained in ICC IBC; perform bolting in an approved manner. Spikes, nails, and bolts shall be drawn up tight.

3.1.1 Roof Framing or Rafters

Tops of supports or rafters shall form a true plane. Rafters shall have full and solid bearing on plates. Rafters shall be spiked to beams with no less than three 8-penny nails. Rafters shall be braced to prevent movement until permanent bracing, decking or sheathing is installed. Openings in roof shall be framed with headers and trimmers. Unless otherwise

indicated, headers carrying more than two rafters and trimmers supporting headers carrying more than one rafter shall be double.

3.1.2 Bridging

Provide bridging or blocking for roof rafters. Locate bridging or blocking as indicated and as specified herein. Provide bridging or blocking for spans greater than 6 feet, but do not exceed 8 feet maximum spacing between rows of bridging or blocking. Install rows of bridging or blocking uniformly.

3.1.3 Plywood Roof Sheathing

Install with the grain of the outer plies or long dimension at right angles to supports. Stagger end joints and locate over the centerlines of supports. Allow 1/8 inch spacing at panel ends and 1/4 inch at panel edges. Nail panels with 8-penny common nails or 6-penny annular rings or screw-type nails spaced 6 inches o.c. at supported edges and 12 inches o.c. at intermediate bearings. Do not use staples in roof sheathing. Where the support spacing exceeds the maximum span for an unsupported edge, provide adequate blocking, tongue-and-groove edges, or panel edge clips, in accordance with APA E30.

3.2 MISCELLANEOUS

3.2.1 Wood Roof Nailers, Edge Strips, and Cants

Provide sizes and configurations indicated or specified and anchored securely to continuous construction.

3.2.1.1 Roof Edge Strips and Nailers

Provide around openings through roof, and where roofs abut walls, curbs, and other vertical surfaces. Except where indicated otherwise, nailers shall be 6 inches wide and the same thickness as the insulation. Anchor nailers securely to underlying construction. Anchor perimeter nailers in accordance with FM 4435.

3.2.2 Wood Blocking

Provide proper sizes and shapes at proper locations for the installation and attachment of wood and other finish materials, fixtures, equipment, and items indicated or specified.

3.2.3 Temporary Closures

Provide with hinged doors and padlocks and install during construction at exterior doorways and other ground level openings that are not otherwise closed. Cover windows and other unprotected openings with polyethylene or other approved material, stretched on wood frames. Provide dustproof barrier partitions to isolate areas as directed.

3.2.4 Bridging and Blocking

Wood bridging shall have ends accurately cut to afford firm contact and shall be nailed at each end with two nails.

3.3 INSTALLATION OF TIMBER CONNECTORS

Installation of timber connectors shall conform to applicable requirements of AWC NDS.

3.4 WASTE MANAGEMENT

Clearly separate damaged wood and other scrap lumber for acceptable alternative uses on site, including bracing, blocking, cripples, ties, and shims.

Separate treated, stained, painted, and contaminated wood and place in designated area for hazardous materials. Dispose of according to local regulations. Do not leave any wood, shavings, sawdust, or other wood waste buried in fill or on the ground. Prevent sawdust and wood shavings from entering the storm drainage system.Do not burn scrap lumber that has been pressure treated, or lumber that is less than one year old.

-- End of Section --

SECTION 07 22 00

ROOF AND DECK INSULATION
11/08

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C 1289	(2008) Standard Specification for Faced Rigid Cellular Polyisocyanurate Thermal Insulation Board
ASTM C 208	(2008a) Cellulosic Fiber Insulating Board
ASTM C 726	(2005e1) Mineral Fiber Roof Insulation Board
ASTM D 226	(2006) Standard Specification for Asphalt-Saturated Organic Felt Used in Roofing and Waterproofing
ASTM E 84	(2009a) Standard Test Method for Surface Burning Characteristics of Building Materials

FM GLOBAL (FM)

FM P7825	(2005) Approval Guide
FM P9513	(2002) Specialist Data Book Set for Roofing Contractors; contains 1-22 (2001), 1-28 (2002), 1-29 (2002), 1-28R/1-29R (1998), 1-30 (2000), 1-31 (2000), 1-32 (2000), 1-33 (2000), 1-34 (2001), 1-49 (2000), 1-52 (2000), 1-54 (2001)

UNDERWRITERS LABORATORIES (UL)

UL Bld Mat Dir	(2012) Building Materials Directory

1.2 SUBMITTALS

The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

SD-03 Product Data

Fasteners

Insulation

SD-06 Test Reports

Flame spread and smoke developed ratings

Submit in accordance with ASTM E 84.

SD-07 Certificates

Installer qualifications

SD-08 Manufacturer's Instructions

Nails and fasteners

Roof insulation, including field of roof and perimeter attachment requirements.

1.3 MANUFACTURER'S CERTIFICATE

Submit certificate from the insulation manufacturer attesting that the installer has the proper qualifications for installing tapered roof insulation systems.

Certificate attesting that the expanded perlite or polyisocyanurate insulation contains recovered material and showing estimated percent of recovered material. Certificates of compliance for felt materials.

1.4 QUALITY ASSURANCE

1.4.1 Insulation on Combustible Decks

Roof insulation shall have a flame spread rating not greater than 75 and a smoke developed rating not greater than 150, exclusive of covering, when tested in accordance with ASTM E 84. Insulation bearing the UL label and listed in the UL Bld Mat Dir as meeting the flame spread and smoke developed ratings will be accepted in lieu of copies of test reports. Compliance with flame spread and smoke developed ratings will not be required when insulation has been tested as part of a roof construction assembly of the type used for this project and the construction is listed as fire-classified in the UL Bld Mat Dir or listed as Class I roof deck construction in the FM P7825. Insulation tested as part of a roof construction assembly shall bear UL or FM labels attesting to the ratings specified herein.

1.5 DELIVERY, STORAGE, AND HANDLING

1.5.1 Delivery

Deliver materials to site in manufacturer's unopened and undamaged standard commercial containers bearing the following legible information:

a. Name of manufacturer;

b. Brand designation;

c. Specification number, type, and class, as applicable, where

materials are covered by a referenced specification; and

Deliver materials in sufficient quantity to allow continuity of the work.

1.5.2 Storage and Handling

Store and handle materials in a manner to protect from damage, exposure to open flame or other ignition sources, and from wetting, condensation or moisture absorption. Store in an enclosed building or trailer that provides a dry, adequately ventilated environment. Store felt rolls on ends. For the 24 hours immediately before application of felts, store felts in an area maintained at a temperature no lower than 50 degrees F above grade and having ventilation around all sides. Replace damaged material with new material.

1.6 ENVIRONMENTAL CONDITIONS

Do not install roof insulation during inclement weather or when air temperature is below 40 degrees F and interior humidity is 45 percent or greater, or when there is visible ice, frost, or moisture on the roof deck.

PART 2 PRODUCTS

2.1 INSULATION

2.1.1 Insulation Types

Roof insulation shall be one or an assembly of a maximum of three of the following materials and compatible with attachment methods for the specified insulation and roof membrane:

a. Polyisocyanurate Board: ASTM C 1289 Type II, fibrous felt or glass mat membrane both sides, except minimum compressive strength shall be 20 pounds per square inch (psi).

ASTM C 208 Type II, Grade 1 or 2, roof insulating board, treated with sizing, wax or bituminous impregnation. Bituminous impregnation shall be limited to 4 percent by weight when used over steel decks. Maximum board size: 4 feet by 4 feet.

2.1.2 Mineral-Fiber Insulation Board

ASTM C 726.

2.1.3 Recovered Materials

Provide thermal insulation materials containing recycled materials to the extent practical. The required minimum recycled material content for the listed materials are:

Polyisocyanurate/polyurethane: 9 percent recovered material

2.1.4 Insulation Thickness

As necessary to provide a thermal resistance (R value) of 18.5 ((2) 1-1/2" rigid)). Thickness shall be based on the "R" value for aged insulation.

2.1.5 Cants and Tapered Edge Strips

Provide preformed cants and tapered edge strips of the same material as the roof insulation; or, when roof insulation material is unavailable, provide pressure-preservative treated wood, wood fiberboard, or rigid perlite board cants and edge strips as recommended by the roofing manufacturer, unless otherwise indicated. Face of cant strips shall have incline of 45 degrees and vertical height of 4 inches. Taper edge strips at a rate of one to 1 1/2 inch per foot down to approximately 1/8 inch thick.

2.2 SHEATHING PAPER FOR WOOD DECKS

Rosin-sized building paper or unsaturated felt weighing not less than 5 pounds per 100 square feet.

2.3 MOISTURE CONTROL

2.3.1 Organic Roofing

ASTM D 226, Type I.

2.4 FASTENERS

Flush-driven through flat round or hexagonal steel or plastic plates. Steel plates shall be zinc-coated, flat round not less than 1 3/8 inch diameter or hexagonal not less than 28 gage. Plastic plates shall be high-density, molded thermoplastic with smooth top surface, reinforcing ribs and not less than 3 inches in diameter. Fastener head shall recess fully into the plastic plate after it is driven. Plates shall be formed to prevent dishing. Do not use bell-or cup-shaped plates.

2.4.1 Roofing Nails for Wood Decks

Barbed 11 gage, zinc-coated nails with 7/16 to 5/8 inch diameter heads or annular ring shank, square head, one-piece composite nails. Nails shall be long enough to penetrate wood deck at least 5/8 inch but shall not protrude through underside of decking.

2.4.2 Fasteners for Plywood Decks

Annular ring shank, square head, one-piece composite nails long enough to penetrate into plywood decks approximately 1/2 inch but not protrude through underside of decking.

PART 3 EXECUTION

3.1 EXAMINATION AND PREPARATION

3.1.1 Surface Inspection

Surfaces shall be clean, smooth, and dry. Check roof deck surfaces, including surfaces sloped to roof drains and outlets, for defects before starting work.

The Contractorand Contracting Officer will inspect and approve the surfaces immediately before starting installation. Prior to installing insulation, perform the following:

a. Examine wood decks to ascertain that deck boards have been

properly nailed and that exposed nail heads have been set.

3.1.2 Surface Preparation

Correct defects and inaccuracies in roof deck surface to eliminate poor drainage and hollow or low spots and perform the following:

a. Install wood nailers the same thickness as insulation at eaves, edges, curbs, walls, and roof openings for securing cant strips, , and flashing flanges. Space nailers in accordance with approved shop drawings.

b. Fill or cover cracks or knot holes larger than 1/2 inch in diameter in wood decks as necessary to form an unyielding surface.

3.2 INSULATION INSTALLATION

Apply insulation in two layers with staggered joints when total required thickness of insulation exceeds 1/2 inch. Lay insulation so that continuous longitudinal joints are perpendicular to direction of felts for the built-up roofing, and end joints of each course are staggered with those of adjoining courses. When using multiple layers of insulation, joints of each succeeding layer shall be parallel and offset in both directions with respect to layer below. Keep insulation 1/2 inch clear of vertical surfaces penetrating and projecting from roof surface.

3.2.1 Installation Using Only Mechanical Fasteners

Secure total thickness of insulation with penetrating type fasteners.

3.2.2 Special Precautions for Installation of Foam Insulation

3.2.2.1 Polyisocyanurate Insulation

Where polyisocyanurate foam board insulation is provided, install 1/2 inch thick wood fiberboard, glass mat gypsum roof board, or 3/4 inch thick expanded perlite board insulation over top surface of foam board insulation. Stagger joints of insulation with respect to foam board insulation below.

3.2.3 Cant Strips

Where indicated, provide cant strips at intersections of roof with walls, parapets, and curbs extending above roof. Wood cant strips shall bear on and be anchored to wood blocking. Fit cant strips flush against vertical surfaces. Where possible, nail cant strips to adjoining surfaces. Where cant strips are installed against non-nailable materials, install in an approved adhesive.

3.2.4 Tapered Edge Strips

Where indicated, provide edge strips in the right angle formed by junction of roof and wood nailing strips that extend above level of roof. Install edge strips flush against vertical surfaces of wood nailing strips. Where possible, nail edge strips to adjoining surfaces.

3.3 PROTECTION

3.3.1 Protection of Applied Insulation

Completely cover each day's installation of insulation with the finished roofing on same day. Do not permit phased construction. Protect open spaces between insulation and parapets or other walls and spaces at curbs, scuttles, and expansion joints, until permanent roofing and flashing are applied. Do not permit storing, walking, wheeling, or trucking directly on insulation or on roofed surfaces. Provide smooth, clean board or plank walkways, runways, and platforms near supports, as necessary, to distribute weight . Exposed edges of the insulation shall be protected by cutoffs at the end of each work day or whenever precipitation is imminent. Cutoffs shall be 2 layers of bituminous-saturated felt set in plastic bituminous cement or single ply set in roof cement. Fill all profile voids in cut-offs to prevent entrapping of moisture into the area below the membrane. Cutoffs shall be removed when work is resumed.

3.3.2 Damaged Work and Materials

Restore work and materials that become damaged during construction to original condition or replace with new materials.

3.4 INSPECTION

The Contractor shall establish and maintain an inspection procedure to assure compliance of the installed roof insulation with the contract requirements. Any work found not to be in compliance with the contract shall be promptly removed and replaced or corrected in an approved manner. Quality control shall include, but not be limited to, the following:

a. Observation of environmental conditions; number and skill level of insulation workers; start and end time of work.

b. Verification of certification, listing or label compliance with FM P9513.

c. Verification of proper storage and handling of insulation and vapor retarder materials before, during, and after installation.

d. Inspection of vapor retarder application, including edge envelopes and mechanical fastening.

e. Inspection of mechanical fasteners; type, number, length, and spacing.

f. Coordination with other materials, cants, sleepers, and nailing strips.

g. Inspection of insulation joint orientation and laps between layers, joint width and bearing of edges of insulation on deck.

h. Installation of cutoffs and proper joining of work on subsequent days.

i. Continuation of complete roofing system installation to cover insulation installed same day.

-- End of Section --

SECTION 07 52 00

MODIFIED BITUMINOUS MEMBRANE ROOFING
11/08

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI/SPRI ES-1	(2003) Wind Design Standard for Edge Systems Used with Low Slope Roof Systems

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)

ASCE 7	(2005; Supp 1) Minimum Design Loads for Buildings and Other Structures

AMERICAN SOCIETY OF SAFETY ENGINEERS (ASSE/SAFE)

ASSE/SAFE A10.24	(2006) Roofing - Safety Requirements of Low-Sloped Roofs

ASPHALT ROOFING MANUFACTURER'S ASSOCIATION (ARMA)

ARMA 410BUR88	(2001) Manual of Roof Maintenance and Repair
ARMA 460LSR97	(2002) NRCA/MRCA Repair Manual for Low Slope Membrane Roof Systems
ARMA PMBRG98	(1998) Quality Control Guideline for the Application of Polymer Modified Bitumen Roofing

ASTM INTERNATIONAL (ASTM)

ASTM D 4073	(2006) Standard Test Method for Tensile-Tear Strength of Bituminous Roofing Membranes
ASTM D 41	(2005) Asphalt Primer Used in Roofing, Dampproofing, and Waterproofing
ASTM D 4586	(2007) Asphalt Roof Cement, Asbestos-Free
ASTM D 5147	(2007b) Standard Test Methods for Sampling and Testing Modified Bituminous Sheet Material
ASTM D 6164	(2005e1) Styrene Butadiene Styrene (SBS) Modified Bituminous Sheet Materials Using

	Polyester Reinforcements
ASTM E 108	(2007a) Fire Tests of Roof Coverings

FM GLOBAL (FM)

FM 4470	(1986; R 1992) Class I Roof Covers
FM P7825	(2005) Approval Guide
FM P7825c	(2005) Approval Guide Building Materials

NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)

NRCA Details	(2003) NRCA Roof Perimeter Flashing Systems Construction Details for Class 1 Roof Construction
NRCA RWM	(2003) Roofing and Waterproofing Manual

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

SMACNA Arch. Manual	(2006) Architectural Sheet Metal Manual

UNDERWRITERS LABORATORIES (UL)

UL 790	(2004; Rev thru Oct 2008) Test Methods for Fire Tests of Roof Coverings
UL RMSD	(2008) Roofing Materials and Systems Directory

1.2 DESCRIPTION OF ROOF MEMBRANE SYSTEM

Minimum two-ply SBS modified bitumen roof membrane consisting of modified bitumen base sheet and cap sheet installed over existing wood and plywood roof deck. Modified bitumen roof membrane shall be mechanically fastened with self adhesive lap seams and cap sheet set in cold applied adhesive.

Review the demolition and the new roof plans. The project includes isolated tearoff as well as isolated new roofing system.

All work must follow the NRCA RWM guidelines and standards stated within this Section.

1.3 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Roof plan drawing depicting wind loads and boundaries of enhanced perimeter and corner attachments of roof system components, as applicable

SD-03 Product Data

Cold Adhesive Applied Modified Bitumen Cap Sheet

Cold-Applied Membrane Adhesive Primer

Modified Bitumen Roof Cement

Modified Bitumen Sheets

Pre-Manufactured Accessories

Fasteners And Plates

Sample Warranty certificate

Submit all data required by Section 07 22 00 ROOF AND DECK INSULATION, together with requirements of this section. Include in data written acceptance by the roof membrane manufacturer of the products and accessories provided. Products must be as listed in the applicable wind uplift and fire rating classification listings, unless approved otherwise by the Contracting Officer.

SD-05 Design Data

Wind Uplift CalculationsProvide Engineering calculations, signed, sealed, and dated by a qualified Engineer validating the wind resistance per ASCE 7, ASTM D 4073, and ANSI/SPRI ES-1 of non-rated roof system.

SD-07 Certificates

Provide evidence that products used within this specification are manufactured in the United States.

Qualification of Manufacturer

Certify that the manufacturer of the modified bitumen membrane meets requirements specified under paragraph entitled "Qualification of Manufacturer."

Qualification of Applicator

Certify that the applicator meets requirements specified under paragraph entitled "Qualification of Applicator."

Qualification of Engineer of Record

Certify that the Engineer of Record is fully qualified, competent, and currently licensed to practice in the project jurisdiction.

Wind Uplift Resistance classification, as applicable

Fire Resistance classification

Submit the roof system assembly wind uplift and fire rating classification listings.

SD-08 Manufacturer's Instructions

Modified Bitumen Membrane Application

Flashing

Cold Adhesive Applied Modified Bitumen Cap Sheet

Base Sheet attachment, including pattern and frequency of mechanical attachments required in field of roof, corners, and perimeters to provide for the specified wind resistance.

Primer

Modified Bitumen Roof Cement

Fasteners

Cold Weather Installation

Include detailed application instructions and standard manufacturer drawings altered as required by these specifications. Explicitly identify in writing, differences between manufacturer's instructions and the specified requirements.

SD-11 Closeout Submittals

Warranty

Information Card

Instructions To Government Personnel

Include copies of Material Safety Data Sheets for maintenance/repair materials.

Submit 20 year "No-Dollar-Limit" warranty for labor and materials.

1.4 QUALITY ASSURANCE

1.4.1 Qualification of Manufacturer

Modified bitumen sheet roofing system manufacturer must have a minimum of 5 years experience in manufacturing modified bitumen roofing products.

1.4.2 Qualification of Applicator

Roofing system applicator must be approved, authorized, or licensed in writing by the modified bitumen sheet roofing system manufacturer and have a minimum of three years experience as an approved, authorized, or licensed applicator with that manufacturer and be approved at a level capable of providing the specified warranty. The applicator must supply the names, locations and client contact information of five projects of similar size and scope that the applicator has constructed using the manufacturer's roofing products submitted for this project within the previous three years.

1.4.3 Qualification of Engineer of Record

Engineer of Record must be currently licensed within the jurisdiction of the project.

1.4.4 Fire Resistance

Complete roof covering assembly must:

a. Be Class A or B rated in accordance with ASTM E 108, FM 4470, or UL 790; and

b. Be listed as part of Fire-Classified roof deck construction in UL RMSD, or Class I roof deck construction in FM P7825.

FM or UL approved components of the roof covering assembly must bear the appropriate FM or UL label.

1.4.5 Wind Uplift Resistance

Complete roof covering assembly, including insulation, must be rated Class 1-90 in accordance with FM P7825 and ASTM D 4073 capable of withstanding an uplift pressure of 45 psf. Non-rated systems must not be installed. Base all Wind uplift calculationson a design wind speed of 100 mph in accordance with ASCE 7, ASTM D 4073, or applicable building code requirements.

1.4.6 Preroofing Conference

After approval of submittals and before performing roofing and insulation system installation work, hold a preroofing conference to review the following:

a. Drawings, including Roof Plan, specifications and submittals related to the roof work

   Field inspection and verification of all existing conditions, including all fire safety issues, existing structure, and existing materials, including concealed combustibles, which may require additional protection during installation.

b. Roof system components installation

c. Procedure for the roof manufacturer's technical representative's onsite inspection and acceptance of the roof structure, and roofing substrate, the name of the manufacturer's technical representatives, the frequency of the onsite visits, distribution of copies of the inspection reports from the manufacturer's technical representatives to roof manufacturer

d. Contractor's plan for coordination of the work of the various trades involved in providing the roofing system and other components secured to the roofing

e. Quality control, (ARMA PMBRG98) plan for the roof system installation

f. Safety requirements

Coordinate preroofing conference scheduling with the Contracting Officer. The conference must be attended by the Contractor, the Contracting Officer's designated personnel, and personnel directly responsible for the installation of roofing and insulation, flashing and sheet metal work, mechanical, other trades interfacing with the roof work, designated safety personnel trained to enforce and comply with ASSE/SAFE A10.24, and representative of the roofing materials manufacturer. Before beginning roofing work, provide a copy of meeting notes and action items to all attending parties. Note action items requiring resolution prior to start of roof work.

1.5 DELIVERY, STORAGE, AND HANDLING

1.5.1 Delivery

Deliver materials in manufacturers' original unopened containers and rolls with labels intact and legible. Mark and remove wet or damaged materials from the site. Where materials are covered by a referenced specification, the container must bear the specification number, type, and class, as applicable. Deliver materials in sufficient quantity to allow work to proceed without interruption.

1.5.2 Storage

Protect materials against moisture absorption and contamination or other damage. Avoid crushing or crinkling of roll materials. Store roll materials on end on clean raised platforms or pallets one level high in dry locations with adequate ventilation, such as an enclosed building or closed trailer. Do not store roll materials in buildings under construction until concrete, mortar, and plaster work is finished and dry. Maintain roll materials at temperatures above 50 degrees F for 24 hours immediately before application. Do not store materials outdoors unless approved by the Contracting Officer. Completely cover felts stored outdoors, on and off roof, with waterproof canvas protective covering. Do not use polyethylene sheet as a covering. Tie covering securely to pallets to make completely weatherproof. Provide sufficient ventilation to prevent condensation. Do not store more materials on roof than can be installed the same day and remove unused materials at end of each days work. Distribute materials temporarily stored on roof to stay within live load limits of the roof construction.

Maintain a minimum distance of 35 foot for all stored flammable materials, including materials covered with shrink wraps, craft paper and/or tarps from all torch/welding applications.

Immediately remove wet, contaminated or otherwise damaged or unsuitable materials from the site. Damaged materials may be marked by the Contracting Officer.

1.5.3 Handling

Prevent damage to edges and ends of roll materials. Do not install damaged materials in the work. Select and operate material handling equipment to prevent damage to materials or applied roofing.

1.6 ENVIRONMENTAL REQUIREMENTS

Do not install roofing system when air temperature is below 40 degrees F, during any form of precipitation, including fog, or when there is ice,

frost, moisture, or any other visible dampness on the roof deck. Follow manufacturer's printed instructions for Cold Weather Installation.

1.7 SEQUENCING

Coordinate the work with other trades to ensure that components which are to be secured to or stripped into the roofing system are available and that permanent flashing and counter flashing, per NRCA Details, and are installed as the work progresses. Ensure temporary protection measures are in place to preclude moisture intrusion or damage to installed materials. Application of roofing must immediately follow application of insulation as a continuous operation. Coordinate roofing operations with insulation work so that all roof insulation applied each day is covered with roof membrane installation the same day.

1.8 WARRANTY

Provide roof system material and workmanship warranties meeting specified requirements. Provide revision or amendment to standard membrane manufacturer warranty as required to comply with the specified requirements.

Note; Building 133 has an existing recently installed new roof. This project is primarily a number of 'patches/repairs' to coordinate with new mechanical equipment and the structure that will support the mechanical equipment. The warranty for this project shall match/meet the warranty of the existing recently installed roof.

1.8.1 Roof Membrane Manufacturer Warranty

Furnish the roof membrane manufacturer's 20-year no dollar limit roof system materials and installation workmanship warranty, including flashing, insulation in compliance with , and accessories necessary for a watertight roof system construction. Provide warranty directly to the Government and commence warranty effective date at time of Government's acceptance of the roof work. The warranty must state that:

a. If within the warranty period the roof system, as installed for its intended use in the normal climatic and environmental conditions of the facility, becomes non-watertight, shows evidence of moisture intrusion within the assembly, blisters, splits, tears, delaminates, separates at the seams, or shows evidence of excessive weathering due to defective materials or installation workmanship, the repair or replacement of the defective and damaged materials of the roof system assembly and correction of defective workmanship are the responsibility of the roof membrane manufacturer. All costs associated with the repair or replacement work are the responsibility of the roof membrane manufacturer.

b. When the manufacturer or his approved applicator fail to perform the repairs within 72 hours of notification, emergency temporary repairs performed by others does not void the warranty.

c. Damage to the roofing system caused by sustained winds having a velocity of 100 mphor
less is covered by the warranty.

d. Upon completion of installation, and acceptance by the Contracting Officer and Roofing System Engineer of Record, the manufacturer must supply the appropriate warranty to the Owner.

e. Installer must submit a minimum two year warranty to the membrane manufacturer from the date of acceptance, with a copy to the Contracting Officer and Roofing System Engineer of Record.

1.8.2 Roofing System Installer Warranty

The roof system installer must warrant for a period of not less than two years that the roof system, as installed, is free from defects in installation workmanship, to include the roof membrane, flashing, insulation, accessories, attachments, and sheet metal installation integral to a complete watertight roof system assembly. Make warranty directly to the Government. Correction of defective workmanship and replacement of damaged or affected materials are the responsibility of the roof system installer. All costs associated with the repair or replacement work are the responsibility of the installer.

1.8.3 Continuance of Warranty

Repair or replacement work, ARMA 410BUR88, ARMA 460LSR97 that becomes necessary within the warranty period must be approved, as required, and accomplished in a manner so as to restore the integrity of the roof system assembly and validity of the roof membrane manufacturer warranty for the remainder of the manufacturer warranty period.

1.9 CONFORMANCE AND COMPATIBILITY

The entire roofing and flashing system must be in accordance with specified and indicated requirements, including fire and wind resistance (ANSI/SPRI ES-1) requirements. Work not specifically addressed and any deviation from specified requirements must be in general accordance with recommendations of the NRCA Roofing and Waterproofing Manual, membrane manufacturer published recommendations and details, and compatible with surrounding components and construction. Submit any deviation from specified or indicated requirements to the Contracting Officer for approval prior to installation.

PART 2 PRODUCTS

2.1 MODIFIED BITUMEN SHEETS

Furnish a combination of specified materials that comprise the modified bitumen manufacturer's standard system of the number and type of plies specified. Materials provided must be suitable for the service and climatic conditions of the installation. Modified bitumen sheets must be watertight and visually free of pinholes, particles of foreign matter, non-dispersed raw material, factory splices, or other conditions that might affect serviceability. Polymer modifier must comply with ARMA PMBRG98 and be uniformly dispersed throughout the sheet. Edges of sheet must be straight and flat.

a. SBS Base Sheet: ASTM D 6164, Type I, Grade S, minimum 112 thick.
b. SBS Cap Sheet: ASTM D 6164; Type I, Grade G, minimum (160 mils) thick at selvage edge, and as required to provide specified fire safety rating.

2.2 BASE FLASHING MEMBRANE

Membrane manufacturer's standard, minimum two-ply modified bitumen membrane flashing system compatible with the roof membrane specified and as recommended in membrane manufacturer's published literature. Flashing membranes must meet or exceed the properties of the material standards specified for the modified bitumen base and cap sheet, except that flashing membrane thickness must be as recommended by the membrane manufacturer. Flashing sheets shall both be installed in cold adhesive or self-adhered base flashing with cold adhesive cap flashing.

2.3 COLD-APPLIED MEMBRANE ADHESIVE

Membrane manufacturer's recommended cold process adhesive for application of the membrane plies.2.4 MEMBRANE SURFACING

Provide modified bitumen roof membrane cap sheet with factory-applied granule surfacing of light color as selected from membrane manufacturer's standard colors.

2.5 PRIMER

ASTM D 41, or other primer compatible with the application and as approved in writing by the modified bitumen membrane manufacturer.

2.6 MODIFIED BITUMEN ROOF CEMENT

ASTM D 4586, Type II for vertical surfaces, Type I for horizontal surfaces, compatible with the modified bitumen roof membrane and as recommended by the modified bitumen membrane manufacturer.

2.7 CANT AND TAPERED EDGE STRIPS

Cant strips must be minimum 1-1/2 inch thick and provide for minimum 5 inch face and 3-1/2 inch vertical height when installed at 45 degree face angle, except where clearance restricts height to lesser dimension. Taper edge strips at a rate of one to 1-1/2 inch per foot to a minimum of 1/8 inch of thickness. Provide kiln-dried preservative-treated wood cants at base of wood nailers set on edge and wood curbing and where otherwise indicated.

2.8 FASTENERS AND PLATES

Provide coated, corrosion-resistant fasteners as recommended by the modified bitumen sheet manufacturer's printed instructions and meeting the requirements of FM 4470 and FM P7825c for Class I roof deck construction and the wind uplift resistance specified. For fastening of membrane or felts to wood materials, provide fasteners driven through 1 inch diameter metal discs, or one piece composite fasteners with heads not less than 1 inch in diameter or 1 inch square with rounded or 45 degree tapered corners.

2.8.1 Masonry or Concrete Walls and Vertical Surfaces

Use hardened steel nails or screws with flat heads, diamond shaped points, and mechanically deformed shanks not less than 1 inch long for securing felts, modified bitumen sheets, metal items, and accessories to masonry or concrete walls and vertical surfaces. Use power-driven fastenersonly when approved in writing by the Contracting Officer.

2.8.2 Metal Plates

Provide flat corrosion-resistant round stress plates as recommended by the modified bitumen sheet manufacturer's printed instructions and meeting the requirements of FM 4470; not less than 2 inch in diameter. Form discs to prevent dishing or cupping.

2.9 PRE-MANUFACTURED ACCESSORIES

Pre-manufactured accessories must be manufacturer's standard for intended purpose, compatible with the membrane roof system and approved for use by the modified bitumen membrane manufacturer.

2.9.1 Pre-fabricated Curbs

Provide 18 gauge G90 galvanized curbs with minimum 4 inch flange for attachment to roof nailers. Curbs must be minimum height of 10 inch above the finished roof membrane surface.

2.10 ROOF INSULATION BELOW MODIFIED BITUMEN MEMBRANE SYSTEM

Insulation must be compatible with the roof membrane, approved by the membrane manufacturer and as specified in UFGS Section 07 22 00 ROOF AND DECK INSULATION.

PART 3 EXECUTION

3.1 EXAMINATION

Ensure that the following conditions exist prior to application of the roofing materials:

a. Drains, curbs, cants, roof penetrating components, and equipment supports are in place.

b. Surfaces are rigid, clean, dry, smooth, and free from cracks, holes, and sharp changes in elevation. Joints in the substrate are sealed to prevent dripping of bitumen into building or down exterior walls.

c. The plane of the substrate does not vary more than 1/4 inchwithin an area 10 by 10 foot when checked with a 10 foot straight edge placed anywhere on the substrate.

d. Substrate is sloped as indicated to provide positive drainage.

e. Walls and vertical surfaces are constructed to receive counter flashing, and will permit mechanical fastening of the base flashing materials.

f. Treated wood nailers are in place on non-nailable surfaces, to permit nailing of base flashing at minimum height of 8 inch above finished roofing surface.

g. Treated wood nailers are fastened in place at eaves, gable ends, openings, and intersections with vertical surfaces for securing of membrane, edging strips, attachment flanges of sheet metal, and

roof fixtures. Surface-applied nailers are the same thickness as the roof insulation.

h. Cants are securely fastened in place in the angles formed by walls and other vertical surfaces. The angle of the cant is 45 degrees and the height of the vertical leg is not less than 3-1/2 inch.

i. Insulation boards are installed smoothly and evenly, and are not broken, cracked, or curled. There are no gaps in insulation board joints exceeding 1/4 inch in width. Insulation is being roofed over on the same day the insulation is installed.

3.2 PREPARATION

3.2.1 Protection of Property

3.2.1.1 Protective Coverings

Install protective coverings at paving and building walls adjacent to hoists prior to starting the work. Lap protective coverings not less than 6 inch, secure against wind, and vent to prevent collection of moisture on covered surfaces. Keep protective coverings in place for the duration of the roofing work.

3.2.2 Equipment

3.2.2.1 Mechanical Application Devices

Mount mechanical application devices on pneumatic-tired wheels. Use devices designed and maintained to operate without damaging the insulation, roofing membrane, or structural components.

3.2.3 Priming of Surfaces

Prime all surfaces to be in contact with adhered membrane materials. Apply primer at the rate of 0.75 gallon per 100 sq. ft. or as recommended by modified bitumen sheet manufacturer's printed instructions to promote adhesion of membrane materials. Allow primer to dry prior to application of membrane materials to primed surface.

3.2.3.1 Priming of Concrete and Masonry Surfaces

After surface dryness requirements have been met, coat concrete and masonry surfaces which are to receive membrane materials uniformly with primer.

3.2.3.2 Priming of Metal Surfaces

Prime flanges of metal components to be embedded into the roof system prior to setting in bituminous materials or stripping into roofing system.

3.2.4 Membrane Preparation

Unroll modified bitumen membrane materials and allow to relax a minimum of

30 minutes prior to installation. In cold weather, adhere to membrane manufacturer's additional recommendations for pre-installation membrane handling and preparation. Inspect for damage, pinholes, particles of foreign matter, non-dispersed raw material, factory splices, or other conditions that might affect serviceability. Edges of seams must be straight and flat so that they may be seamed to one another without forming fish mouths or wrinkles. Discard damaged or defective materials.

3.2.5 Substrate Preparation

Apply membrane to clean, dry surfaces only. Don not apply membrane to surfaces that have been wet by rain or frozen precipitation within the previous 12 hours. Provide cleaning and artificial drying with heated blowers or torches as necessary to ensure clean, dry surface prior to membrane application.

3.3 APPLICATION

Apply roofing materials as specified herein unless approved otherwise by the Contracting Officer. Keep roofing materials dry before and during application. Complete application of roofing in a continuous operation. Begin and apply only as much roofing in one day as can be completed that same day. Maintain specified temperatures for asphalt. Provide temporary roofing and flashing as specified herein prior to application of permanent roofing system.

3.3.1 Phased Membrane Construction

Phased membrane construction will be allowed if approved by the membrane manufacturer. If cap sheet installation is delayed, thoroughly clean the applied membrane material surface and dry immediately prior to cap sheet installation. Priming of the applied membrane surface may be required at the discretion of the Contracting Officer prior to cap sheet installation.

3.3.2 Application Method

3.3.2.1 Mechanically-Fastened with Self-Adhesive Lap Seams and Cold Adhesive Applied Modified Bitumen Cap Sheet

Fasten base sheet with mechanical fasteners in conformance with specified wind resistance requirements and membrane manufacturer's printed instructions. Ensure substrate membrane surfaces are warmed naturally. Apply uniform positive pressure to ensure membrane is adhered and all laps are sealed. Form laps over the granules of the receiving sheet according to manufacturer's printed instructions to form a uniform compound surface. Roll all lap areas with a weighted roller immediately after forming lap. Inspect and ensure that all lap areas are fully sealed.

3.3.2.2 Cold Adhesive Applied Modified Bitumen Cap Sheet

Apply cold adhesive with airless sprayer or 1/4 inch saw-toothed rubber squeegee to prepared surfaces in accordance with membrane manufacturer's application instructions. Fully cover substrate with adhesive. Roll or lay membrane in adhesive in accordance with manufacturer's recommendations and within the time limitations of adhesive application. Broom the membrane to ensure full contact with adhesive. Seal laps with adhesive or by heat fusing with torch or hot air welder as required by membrane

manufacturer. Minimize traffic on installed membrane during the adhesive cure and set time.

3.3.3 Modified Bitumen Membrane Application

Ensure proper sheet alignment prior to installation. Apply membrane layers perpendicular to slope of roof in shingle fashion to shed water, including application on areas of tapered insulation that change slope direction. Bucking or backwater laps are prohibited. Fully adhere membrane sheets to underlying substrate materials. Provide minimum 3 inch side laps and minimum 6 inch end laps and as otherwise required by membrane manufacturer. Stagger end laps minimum 36 inch. Offset side laps between membrane layers a minimum of 12 inch. Offset end laps between membrane layers a minimum of 36 inch. Install all membrane layers the same workday, unless supported otherwise by roof membrane manufacturer application instructions and approved by the Contracting Officer. Provide tight smooth laminations of each membrane layer without wrinkles, ridges, buckles, kinks, fishmouths, or voids. Ensure full membrane adhesion and full lap seals. Rework to seal any open laps prior to application of subsequent membrane layers. The completed membrane application must be free of surface abrasions, air pockets, blisters, ridges, wrinkles, buckles, kinks, fishmouths, voids, or open seams.

3.3.3.1 Cap Sheet Installation

Underlying applied membrane must be inspected and repaired free of damage, holes, puncture, gouges, abrasions, and any other defects, and free of moisture, loose materials, debris, sediments, dust, and any other conditions required by the membrane manufacturer prior to cap sheet installation. Do not apply cap sheet if rain or frozen precipitation has occurred within the previous 24 hours. Align cap membrane and apply by the specified method with the proper side and end lap widths. Apply cap sheet in accordance with the modified bitumen membrane manufacturer's printed instructions. Cut at a 45 degree angle across selvage edge of cap membrane to be overlapped in end lap areas prior to applying overlapping cap membrane. Apply matching granules in any areas of adhesive bleed out while the adhesive is still tacky. Minimize traffic on newly installed cap sheet membrane.

3.3.4 Membrane Flashing

Apply two-ply modified bitumen strip flashing and sheet flashing in the angles formed where the roof deck abuts walls, curbs, ventilators, pipes, and other vertical surfaces, and where necessary to make the work watertight. Apply membrane flashing in accordance with the roof membrane manufacturers printed instructions and as specified. Cut at a 45 degree angle across terminating end lap area of cap membrane prior to applying adjacent overlapping cap membrane. Press flashing into place to ensure full adhesion and avoid bridging. Ensure full lap seal in all lap areas. Mechanically fasten top edge of modified bituminous base flashing 150 mm (6 inches) on center through minimum 1 inch diameter tin caps with fasteners of sufficient length to embed minimum one inch into attachment substrate. Apply matching granules in any areas of adhesive bleed out while the adhesive is still tacky. Apply membrane liner over top of exposed nailers and blocking and to overlap top edge of base flashing installation at curbs, parapet walls, expansion joints and as otherwise indicated to serve as waterproof lining under sheet metal flashing components. Metal flashing per SMACNA Arch. Manual guidelines and standards is specified under UFGS Section 07 60 00 FLASHING AND SHEET METAL. Do not set metal flashing in

hot asphalt.

3.3.4.1 Membrane Strip Flashing

Set primed flanges of metal flashing in full bed of modified bituminous cement material and securely fasten through to attachment substrate. Strip-in with membrane flashing so that strip extends not less than 4 inch beyond outer edge of flange. Where multiple membrane stripping plies are installed, extend each additional stripping ply minimum 4 inch beyond edge of previous ply.

3.3.4.2 Membrane Flashing at Roof Drain

Flashing for roof drains, is specified in UFGS Section 07 60 00 FLASHING AND SHEET METAL. Extend membrane sheets to edge of drain bowl opening at the roof drain deck flange in accordance with membrane manufacturer's printed application instructions. Securely clamp membrane sheets and metal roof drain flashing and strip flashing in the flashing clamping ring. Secure clamps so that sheets and metal flashing are free from wrinkles and folds. Trim stripping must be flush with inside of clamping ring.

3.3.4.3 Pre-fabricated Curbs

Securely anchor prefabricated curbs to nailer or other base substrate and flash with modified bitumen membrane.

3.3.4.4 Set-On Accessories

Where pipe or conduit blocking, supports and similar roof accessories are set on the membrane, adhere walkpad material to bottom of accessories prior to setting on roofing membrane. Specific method of installing set-on accessories must permit normal movement due to expansion, contraction, vibration, and similar occurrences without damaging roofing membrane. Do not mechanically secure set-on accessories through roofing membrane into roof deck substrate.

3.3.5 Correction of Deficiencies

Where any form of deficiency is found, additional measures will be taken as deemed necessary by the Contracting Officer to determine the extent of the deficiency and corrective actions must be performed as directed by the Contracting Officer.

3.3.6 Clean Up

Remove debris, scraps, containers and other rubbish and trash resulting from installation of the roofing system from job site each day.

3.4 PROTECTION OF APPLIED ROOFING

At the end of the day's work and when precipitation is imminent, protect applied modified bitumen roofing system from water intrusion.

3.4.1 Water Cutoffs

Straighten insulation line using loose-laid cut insulation sheets and seal the terminated edge of modified bitumen roofing system in an effective manner. Remove the water cut-offs to expose the insulation when resuming work, and remove the insulation sheets used for fill-in.

3.4.2 Temporary Flashing for Permanent Roofing

Provide temporary flashing at drains, curbs, walls and other penetrations and terminations of roofing sheets until permanent flashing can be applied. Remove temporary flashing before applying permanent flashing.

3.4.3 Temporary Walkways, Runways, and Platforms

Do not permit storing, walking, wheeling, and trucking directly on applied roofing materials. Provide temporary walkways, runways, and platforms of smooth clean boards, mats or planks as necessary to avoid damage to applied roofing materials, and to distribute weight to conform to live load limits of roof construction. Use rubber-tired equipment for roofing work.

3.5 FIELD QUALITY CONTROL

Perform field tests in the presence of the Contracting Officer. Notify the Contracting Officer one day before performing tests.

3.5.1 Construction Monitoring

During progress of the roof work, Contractor must make visual inspections as necessary to ensure compliance with specified parameters. Additionally, verify the following:

a. Materials comply with the specified requirements.

b. Materials are not installed in adverse weather conditions.

All materials are properly stored, handled and protected from moisture or other damages.

c. Equipment is in working order. Metering devices are accurate.

d. Substrates are in acceptable condition, in compliance with specification, prior to application of subsequent materials.

(1) Nailers and blocking are provided where and as needed.

Insulation substrate is smooth, properly secured to its substrate, and without excessive gaps prior to membrane application.

(2) The proper number, type, and spacing of fasteners are installed.

The proper number and types of plies are installed, with the specified overlaps.

Applied membrane surface is inspected, cleaned, dry, and repaired as necessary prior to cap sheet installation.

(3) Lap areas of all plies are completely sealed.

Membrane is fully adhered without ridges, wrinkles, kinks, fishmouths, or other voids or delaminations.

Installer adheres to specified and detailed application parameters.

Associated flashing and sheet metal are installed in a timely manner in accord with the specified requirements.

Temporary protection measures are in place at the end of each work shift.

3.5.1.1 Manufacturer's Inspection

Manufacturer's technical representative must visit the site a minimum of three times during the installation for purposes of reviewing materials installation practices and adequacy of work in place. Inspections must occur during the first 20 squares of membrane installation, at mid-point of the installation, and at substantial completion, at a minimum. Additional inspections must not exceed one for each 100 squares of total roof area with the exception that follow-up inspections of previously noted deficiencies or application errors must be performed as requested by the Contracting Officer. After each inspection, submit a report, signed by the manufacturer's technical representative to the Contracting Officer within 3 working days. Note in the report overall quality of work, deficiencies and any other concerns, and recommended corrective action.

3.5.2 Samples of Roofing

Take samples per ASTM D 5147, sized 4-inch by 40-inch cut across width of modified bitumen sheets as directed by the Contracting Officer. Cut samples will be examined by the Contracting Officer for specified number of plies, proper lap width, complete lap seal, full uniform adhesive compound application and adhesion, full bond between plies, harmful foreign materials, presence of moisture, and wet insulation. Where cuts are not retained by the Contracting Officer or disposed, set cut strip back in cut area in bed of modified bitumen cement. Repair area of cut with new minimum two-ply modified bitumen membrane patch.

3.6 INSTRUCTIONS TO GOVERNMENT PERSONNEL

Furnish written and verbal instructions on proper maintenance procedures to designated Government personnel. Furnish instructions by a competent representative of the modified bitumen membrane manufacturer and include a minimum of 4 hours on maintenance and emergency repair of the membrane. Include a demonstration of membrane repair, and give sources of required special tools. Furnish information on safety requirements during maintenance and emergency repair operations.

3.7 INFORMATION CARD

For each roof, furnish a typewritten information card for facility Records and a card laminated in plastic and framed for interior display at roof access point, or a photoengraved 0.039 inch thick aluminum card for exterior display. Card must be 8 1/2 by 11 inch minimum. Information card must identify facility name and number; location; contract number; approximate roof area; detailed roof system description, including deck type, membrane, number of plies, method of application, manufacturer, insulation and cover board system and thickness; presence of tapered insulation for primary drainage, presence of vapor barrier material; date of completion; installing contractor identification and contact

information; membrane manufacturer warranty expiration, warranty reference number, and contact information. The card must be a minimum size of 8 1/2 by 11 inch. Install card at roof top or access location as directed by the Contracting Officer and provide a paper copy to the Contracting Officer.

-- End of Section --

SECTION 07 60 00

FLASHING AND SHEET METAL
08/08

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN WELDING SOCIETY (AWS)

AWS D1.2/D1.2M	(2008) Structural Welding Code - Aluminum

ASTM INTERNATIONAL (ASTM)

ASTM A 167	(1999; R 2009) Standard Specification for Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet, and Strip
ASTM A 308/A 308M	(2006) Standard Specification for Steel Sheet, Terne (Lead-Tin Alloy) Coated by the Hot Dip Process
ASTM A 653/A 653M	(2009) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM B 101	(2007) Standard Specification for Lead-Coated Copper Sheet and Strip for Building Construction
ASTM B 209	(2007) Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate
ASTM B 221	(2008) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes
ASTM B 32	(2008) Standard Specification for Solder Metal
ASTM B 370	(2009) Standard Specification for Copper Sheet and Strip for Building Construction
ASTM B 69	(2008) Standard Specification for Rolled Zinc
ASTM D 1784	(2008) Standard Specification for Rigid Poly(Vinyl Chloride) (PVC) Compounds and Chlorinated Poly(Vinyl Chloride) (CPVC) Compounds

ASTM D 226	(2006) Standard Specification for Asphalt-Saturated Organic Felt Used in Roofing and Waterproofing
ASTM D 41	(2005) Asphalt Primer Used in Roofing, Dampproofing, and Waterproofing
ASTM D 4586	(2007) Asphalt Roof Cement, Asbestos-Free

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

SMACNA 1793	(2006) Architectural Sheet Metal Manual, Sixth Edition, Second Printing

1.2 GENERAL REQUIREMENTS

Finished sheet metalwork will form a weathertight construction without waves, warps, buckles, fastening stresses or distortion, which allows for expansion and contraction. Sheet metal mechanic is responsible for cutting, fitting, drilling, and other operations in connection with sheet metal required to accommodate the work of other trades. Coordinate installation of sheet metal items used in conjunction with roofing with roofing work to permit continuous roofing operations.

1.3 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Gravel stops and fascias

Flashing at roof penetrations

Indicate thicknesses, dimensions, fastenings and anchoring methods, expansion joints, and other provisions necessary for thermal expansion and contraction. Scaled manufacturer's catalog data may be submitted for factory fabricated items.

SD-11 Closeout Submittals

Quality Control Plan

Submit for sheet metal work in accordance with paragraph entitled "Field Quality Control."

1.4 DELIVERY, HANDLING, AND STORAGE

Package and protect materials during shipment. Uncrate and inspect materials for damage, dampness, and wet-storage stains upon delivery to the job site. Remove from the site and replace damaged materials that cannot be restored to like-new condition. Handle sheet metal items to avoid damage to surfaces, edges, and ends. Store materials in dry, weather-tight, ventilated areas until immediately before installation.

PART 2 PRODUCTS

2.1 MATERIALS

Do not use lead, lead-coated metal, or galvanized steel. Use any metal listed by SMACNA Arch. Manual for a particular item, unless otherwise specified or indicated. Conform to the requirements specified and to the thicknesses and configurations established in SMACNA Arch. Manual for the materials. Different items need not be of the same metal, except that if copper is selected for any exposed item, all exposed items must be copper.

Furnish sheet metal items in 8 to 10 foot lengths. Single pieces less than 8 feet long may be used to connect to factory-fabricated inside and outside corners, and at ends of runs. Factory fabricate corner pieces with minimum 12 inch legs. Provide accessories and other items essential to complete the sheet metal installation. Provide accessories made of the same or compatible materials as the items to which they are applied. Fabricate sheet metal items of the materials specified below and to the gage, thickness, or weight shown in Table I at the end of this section. Provide sheet metal items with mill finish unless specified otherwise. Where more than one material is listed for a particular item in Table I, each is acceptable and may be used except as follows:

2.1.1 Exposed Sheet Metal Items

Must be of the same material. Consider the following as exposed sheet metal: gutters, including hangers; downspouts; gravel stops and fascias; cap, valley, steeped, base, and eave flashings and related accessories.

2.1.2 Drainage

Do not use copper for an exposed item if drainage from that item will pass over exposed masonry, stonework or other metal surfaces. In addition to the metals listed in Table I, lead-coated copper may be used for such items.

2.1.3 Copper, Sheet and Strip

ASTM B 370, cold-rolled temper, H 00 (standard).

2.1.4 Lead-Coated Copper Sheet

ASTM B 101.

2.1.5 Lead Sheet

Minimum weight 4 pounds per square foot.

2.1.6 Steel Sheet, Zinc-Coated (Galvanized)

ASTM A 653/A 653M.

2.1.7 Zinc Sheet and Strip

ASTM B 69, Type I, a minimum of 0.024 inch thick.

2.1.8 Stainless Steel

ASTM A 167, Type 302 or 304, 2D Finish, fully annealed, dead-soft temper.

2.1.9 Terne-Coated Steel

Minimum of 14 by 20 inch with minimum of 40 pound coating per double base box. ASTM A 308/A 308M.

2.1.10 Aluminum Alloy Sheet and Plate

ASTM B 209, anodized clear form alloy, and temper appropriate for use.

2.1.10.1 Alclad

When fabricated of aluminum, fabricate the items Alclad 3003, Alclad 3004, Alclad 3005, clad on one side unless otherwise indicated.

a. Gutters, downspouts, and hangers

b. Gravel stops and fascias

c. Flashing

2.1.11 Aluminum Alloy, Extruded Bars, Rods, Shapes, and Tubes

ASTM B 221.

2.1.12 Solder

ASTM B 32, 95-5 tin-antimony.

2.1.13 Polyvinyl Chloride Reglet

ASTM D 1784, Type II, Grade 1, Class 14333-D, 0.075 inch minimum thickness.

2.1.14 Bituminous Plastic Cement

ASTM D 4586, Type I.

2.1.15 Roofing Felt

ASTM D 226 Type I .

2.1.16 Asphalt Primer

ASTM D 41.

2.1.17 Fasteners

Use the same metal or a metal compatible with the item fastened. Use stainless steel fasteners to fasten dissimilar materials.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Workmanship

Make lines and angles sharp and true. Free exposed surfaces from visible wave, warp, buckle, and tool marks. Fold back exposed edges neatly to form a 1/2 inch hem on the concealed side. Make sheet metal exposed to the

weather watertight with provisions for expansion and contraction.

Make surfaces to receive sheet metal plumb and true, clean, even, smooth, dry, and free of defects and projections. For installation of items not shown in detail or not covered by specifications conform to the applicable requirements of SMACNA 1793, Architectural Sheet Metal Manual. Provide sheet metal flashing in the angles formed where roof decks abut walls, curbs, ventilators, pipes, or other vertical surfaces and wherever indicated and necessary to make the work watertight. Join sheet metal items together as shown in Table II.

3.1.2 Nailing

Confine nailing of sheet metal generally to sheet metal having a maximum width of 18 inch. Confine nailing of flashing to one edge only. Space nails evenly not over 3 inch on center and approximately 1/2 inch from edge unless otherwise specified or indicated. Face nailing will not be permitted. Where sheet metal is applied to other than wood surfaces, include in shop drawings, the locations for sleepers and nailing strips required to secure the work.

3.1.3 Cleats

Provide cleats for sheet metal 18 inch and over in width. Space cleats evenly not over 12 inch on center unless otherwise specified or indicated. Unless otherwise specified, provide cleats of 2 inch wide by 3 inch long and of the same material and thickness as the sheet metal being installed. Secure one end of the cleat with two nails and the cleat folded back over the nailheads. Lock the other end into the seam. Pretin cleats for soldered seams.

3.1.4 Bolts, Rivets, and Screws

Install bolts, rivets, and screws where indicated or required. Provide compatible washers where required to protect surface of sheet metal and to provide a watertight connection. Provide mechanically formed joints in aluminum sheets 0.040 inch or less in thickness.

3.1.5 Seams

Straight and uniform in width and height with no solder showing on the face.

3.1.5.1 Flat-lock Seams

Finish not less than 3/4 inch wide.

3.1.5.2 Lap Seams

Finish soldered seams not less than one inch wide. Overlap seams not soldered, not less than 3 inch.

3.1.5.3 Loose-Lock Expansion Seams

Not less than 3 inch wide; provide minimum one inch movement within the joint. Completely fill the joints with the specified sealant, applied at not less than 1/8 inch thick bed.

3.1.5.4 Standing Seams

Not less than one inch high, double locked without solder.

3.1.5.5 Flat Seams

Make seams in the direction of the flow.

3.1.6 Soldering

Where soldering is specified, apply to copper, terne-coated stainless steel, zinc-coated steel, and stainless steel items. Pretin edges of sheet metal before soldering is begun. Seal the joints in aluminum sheets of 0.040 inch or less in thickness with specified sealants. Do not solder aluminum.

3.1.6.1 Edges

Scrape or wire-brush the edges of lead-coated material to be soldered to produce a bright surface. Flux brush the seams in before soldering. Treat with soldering acid flux the edges of stainless steel to be pretinned. Seal the joints in aluminum sheets of 0.040 inch or less in thickness with specified sealants. Do not solder aluminum.

3.1.7 Welding and Mechanical Fastening

Use welding for aluminum of thickness greater than 0.040 inch. Aluminum 0.040 inch or less in thickness must be butted and the space backed with formed flashing plate; or lock joined, mechanically fastened, and filled with sealant as recommended by the aluminum manufacturer.

3.1.7.1 Welding of Aluminum

Use welding of the inert gas, shield-arc type. For procedures, appearance and quality of welds, and the methods used in correcting welding work, conform to AWS D1.2/D1.2M.

3.1.7.2 Mechanical Fastening of Aluminum

Use No. 12, aluminum alloy, sheet metal screws or other suitable aluminum alloy or stainless steel fasteners. Drive fasteners in holes made with a No. 26 drill in securing side laps, end laps, and flashings. Space fasteners 12 inch maximum on center. Where end lap fasteners are required to improve closure, locate the end lap fasteners not more than 2 inch from the end of the overlapping sheet.

3.1.8 Protection from Contact with Dissimilar Materials

3.1.8.1 Copper or Copper-bearing Alloys

Paint with heavy-bodied bituminous paint surfaces in contact with dissimilar metal, or separate the surfaces by means of moistureproof building felts.

3.1.8.2 Aluminum

Do not allow aluminum surfaces in direct contact with other metals except stainless steel, zinc, or zinc coating. Where aluminum contacts another metal, paint the dissimilar metal with a primer followed by two coats of

aluminum paint. Where drainage from a dissimilar metal passes over aluminum, paint the dissimilar metal with a non-lead pigmented paint.

3.1.8.3 Metal Surfaces

Paint surfaces in contact with mortar, concrete, or other masonry materials with alkali-resistant coatings such as heavy-bodied bituminous paint.

3.1.8.4 Wood or Other Absorptive Materials

Paint surfaces that may become repeatedly wet and in contact with metal with two coats of aluminum paint or a coat of heavy-bodied bituminous paint.

3.1.9 Expansion and Contraction

Provide expansion and contraction joints at not more than 32 foot intervals for aluminum and at not more than 40 foot intervals for other metals. Provide an additional joint where the distance between the last expansion joint and the end of the continuous run is more than half the required interval. Space joints evenly. Join extruded aluminum gravel stops and fascias by expansion and contraction joints spaced not more than 12 feet apart.

3.1.10 Gravel Stops and Fascias

Prefabricate in the shapes and sizes indicated and in lengths not less that 8 feet. Extend flange at least 4 inch onto roofing. Provide prefabricated, mitered corners internal and external corners. Install gravel stops and fascias after all plies of the roofing membrane have been applied, but before the flood coat of bitumen is applied. Prime roof flange of gravel stops and fascias on both sides with an asphalt primer. After primer has dried, set flange on roofing membrane and strip-in.Nail flange securely to wood nailer with large-head, barbed-shank roofing nails 1.5 inch long spaced not more than 3 inch on center, in two staggered rows.

3.1.10.1 Edge Strip

Hook the lower edge of fascias at least 3/4 inch over a continuous strip of the same material bent outward at an angle not more than 45 degrees to form a drip. Nail hook strip to a wood nailer at 6 inchmaximum on center. Where fastening is made to concrete or masonry, use screws spaced 12 inch on center driven in expansion shields set in the concrete or masonry. Where horizontal wood nailers are slotted to provide for insulation venting, install strips to prevent obstruction of vent slots. Where necessary, install strips over 1/16 inch thick compatible spacer or washers.

3.1.10.2 Joints

Leave open the section ends of gravel stops and fascias 1/4 inch and backed with a formed flashing plate, mechanically fastened in place and lapping each section end a minimum of 4 inch set laps in plastic cement. Face nailing will not be permitted. Install prefabricated aluminum gravel stops and fascias in accordance with the manufacturer's printed instructions and details.

3.1.11 Flashing at Roof Penetrations and Equipment Supports

Provide metal flashing for all pipes, ducts, and conduits projecting through the roof surface and for equipment supports, guy wire anchors, and

similar items supported by or attached to the roof deck.

3.1.12 Single Pipe Vents

See Table I, footnote (d). Set flange of sleeve in bituminous plastic cement and nail 3 inch on center. Bend the top of sleeve over and extend down into the vent pipe a minimum of 2 inch. For long runs or long rises above the deck, where it is impractical to cover the vent pipe with lead, use a two-piece formed metal housing. Set metal housing with a metal sleeve having a 4 inch roof flange in bituminous plastic cement and nailed 3 inch on center. Extend sleeve a minimum of8 inch above the roof deck and lapped a minimum of 3 inch by a metal hood secured to the vent pipe by a draw band. Seal the area of hood in contact with vent pipe with an approved sealant.

3.2 PAINTING

Field-paint sheet metal for separation of dissimilar materials.

3.2.1 Aluminum Surfaces

Shall be solvent cleaned and given one coat of zinc-molybdate primer and one coat of aluminum paint.

3.3 CLEANING

Clean exposed sheet metal work at completion of installation. Remove grease and oil films, handling marks, contamination from steel wool, fittings and drilling debris, and scrub-clean. Free the exposed metal surfaces of dents, creases, waves, scratch marks, and solder or weld marks.

3.4 REPAIRS TO FINISH

Scratches, abrasions, and minor surface defects of finish may be repaired in accordance with the manufacturer's printed instructions and as approved. Repair damaged surfaces caused by scratches, blemishes, and variations of color and surface texture. Replace items which cannot be repaired.

3.5 FIELD QUALITY CONTROL

Establish and maintain a Quality Control Plan for sheet metal used in conjunction with roofing to assure compliance of the installed sheet metalwork with the contract requirements. Remove work that is not in compliance with the contract and replace or correct. Include quality control, but not be limited to, the following:

a. Observation of environmental conditions; number and skill level of sheet metal workers; condition of substrate.

b. Verification that specified material is provided and installed.

c. Inspection of sheet metalwork, for proper size(s) and thickness(es), fastening and joining, and proper installation.

3.5.1 Procedure

Submit for approval prior to start of roofing work. Include a checklist of points to be observed. Document the actual quality control observations and inspections. Furnish a copy of the documentation to the Contracting

Officer at the end of each day.

TABLE I. SHEET METAL WEIGHTS, THICKNESSES, AND GAGES

Sheet Metal Items	Copper, Ounces Per Square Foot	Aluminum, Inch	Stainless Steel, Inch	Terne-Coated Steel, Inch	Zinc-Coated Steel, U.S. Std. Gage
Building Expansion Joints Cover.....	16	.032	.015	.015	24
Flashings:					
Roof drain.....	16(b)				
Pipe vent sleeve(d)					
Gravel stops and fascias:					

-- End of Section --

SECTION 07 92 00

JOINT SEALANTS
01/07

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C 920	(2008) Standard Specification for Elastomeric Joint Sealants

1.2 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Sealants

Primers

Bond breakers

Backstops

Manufacturer's descriptive data including storage requirements, shelf life, curing time, instructions for mixing and application, and primer data (if required). Provide a copy of the Material Safety Data Sheet for each solvent, primer or sealant material.

SD-07 Certificates

Sealant

Certificates of compliance stating that the materials conform to the specified requirements.

1.3 ENVIRONMENTAL CONDITIONS

Apply sealant when the ambient temperature is between 40 and 90 degrees F.

1.4 DELIVERY AND STORAGE

Deliver materials to the job site in unopened manufacturers' external shipping containers, with brand names, date of manufacture, color, and material designation clearly marked thereon. Lable elastomeric sealant containers to identify type, class, grade, and use. Carefully handle and store materials to prevent inclusion of foreign materials or subjection to sustained temperatures exceeding 90 degrees F or less than 0 degrees F.

1.5 QUALITY ASSURANCE

1.5.1 Compatibility with Substrate

Verify that each of the sealants are compatible for use with joint substrates.

1.5.2 Joint Tolerance

Provide joint tolerances in accordance with manufacturer's printed instructions.

1.6 SPECIAL WARRANTY

Guarantee sealant joint against failure of sealant and against water penetration through each sealed joint for five years.

PART 2 PRODUCTS

2.1 SEALANTS

Provide sealant that has been tested and found suitable for the substrates to which it will be applied.

2.1.1 Exterior Sealant

For joints in vertical surfaces, provide ASTM C 920, Type S or M, Grade NS, Class 25, Use NT. For joints in horizontal surfaces, provide ASTM C 920, Type S or M, Grade P, Class 25, Use T. Provide location(s) and color(s) of sealant as follows:

	LOCATION	COLOR
a.	Joints and recesses formed where frames and subsills of windows, doors, louvers, and vents adjoin masonry, concrete, or metal frames. Use sealant at both exterior and interior surfaces of exterior wall penetrations.	As selected
b.	Expansion and control joints.	As selected_____
c.	Voids where items pass through exterior walls.	Match adjacent_____ surface color
d.	Metal reglets, where flashing is inserted into masonry joints, and where flashing is penetrated by coping dowels.	As selected_____
e.	Metal-to-metal joints where sealant is indicated or specified.	As selected_____

2.2 PRIMERS

Provide a nonstaining, quick-drying type and consistency recommended by the sealant manufacturer for the particular application.

2.3 BOND BREAKERS

Provide the type and consistency recommended by the sealant manufacturer to prevent adhesion of the sealant to backing or to bottom of the joint.

2.4 BACKSTOPS

Provide glass fiber roving or neoprene, butyl, polyurethane, or polyethylene foams free from oil or other staining elements as recommended by sealant manufacturer. Provide 25 to 33 percent oversized backing for closed cell and 40 to 50 percent oversized backing for open cell material, unless otherwise indicated. Make backstop material compatible with sealant. Do not use oakum and other types of absorptive materials as backstops.

2.5 CLEANING SOLVENTS

Provide type(s) recommended by the sealant manufacturer except for aluminum and bronze surfaces that will be in contact with sealant.

PART 3 EXECUTION

3.1 SURFACE PREPARATION

Clean surfaces from dirt frost, moisture, grease, oil, wax, lacquer, paint, or other foreign matter that would tend to destroy or impair adhesion. Remove oil and grease with solvent. Surfaces must be wiped dry with clean cloths. When resealing an existing joint, remove existing calk or sealant prior to applying new sealant. For surface types not listed below, contact sealant manufacturer for specific recommendations.

3.1.1 Steel Surfaces

Remove loose mill scale by sandblasting or, if sandblasting is impractical or would damage finish work, scraping and wire brushing. Remove protective coatings by sandblasting or using a residue-free solvent.

3.1.2 Aluminum or Bronze Surfaces

Remove temporary protective coatings from surfaces that will be in contact with sealant. When masking tape is used as a protective coating, remove tape and any residual adhesive just prior to sealant application. For removing protective coatings and final cleaning, use nonstaining solvents recommended by the manufacturer of the item(s) containing aluminum or bronze surfaces.

3.1.3 Concrete and Masonry Surfaces

Where surfaces have been treated with curing compounds, oil, or other such materials, remove materials by sandblasting or wire brushing. Laitance, remove efflorescence and loose mortar from the joint cavity.

3.2 SEALANT PREPARATION

Do not add liquids, solvents, or powders to the sealant. Mix multicomponent elastomeric sealants in accordance with manufacturer's instructions.

3.3 APPLICATION

3.3.1 Joint Width-To-Depth Ratios

a. Acceptable Ratios:

JOINT WIDTH	JOINT DEPTH	
	Minimum	Maximum
For metal, glass, or other nonporous surfaces:		
1/4 inch (minimum)	1/4 inch	1/4 inch
over 1/4 inch	1/2 of width	Equal to width
For wood, concrete, masonry, stone, :		
1/4 inch (minimum)	1/4 inch	1/4 inch
Over 1/4 inch to 1/2 inch	1/4 inch	Equal to width
Over 1/2 inch to 2 inch	1/2 inch	5/8 inch
Over 2 inch.	(As recommended by sealant manufacturer)	

b. Unacceptable Ratios: Where joints of acceptable width-to-depth ratios have not been provided, clean out joints to acceptable depths and grind or cut to acceptable widths without damage to the adjoining work. Grinding is not required on metal surfaces.

3.3.2 Masking Tape

Place masking tape on the finish surface on one or both sides of a joint cavity to protect adjacent finish surfaces from primer or sealant smears. Remove masking tape within 10 minutes after joint has been filled and tooled.

3.3.3 Backstops

Install backstops dry and free of tears or holes. Tightly pack the back or bottom of joint cavities with backstop material to provide a joint of the depth specified. Install backstops in the following locations:

a. Where indicated.

b. Where backstop is not indicated but joint cavities exceed the acceptable maximum depths specified in paragraph entitled, "Joint Width-to-Depth Ratios".

3.3.4 Primer

Immediately prior to application of the sealant, clean out loose particles from joints. Where recommended by sealant manufacturer, apply primer to joints in concrete masonry units, wood, and other porous surfaces in accordance with sealant manufacturer's instructions. Do not apply primer to exposed finish surfaces.

3.3.5 Bond Breaker

Provide bond breakers to the back or bottom of joint cavities, as recommended by the sealant manufacturer for each type of joint and sealant used, to prevent sealant from adhering to these surfaces. Carefully apply the bond breaker to avoid contamination of adjoining surfaces or breaking bond with surfaces other than those covered by the bond breaker.

3.3.6 Sealants

Provide a sealant compatible with the material(s) to which it is applied. Do not use a sealant that has exceeded shelf life or has jelled and can not be discharged in a continuous flow from the gun. Apply the sealant in accordance with the manufacturer's printed instructions with a gun having a nozzle that fits the joint width. Force sealant into joints to fill the joints solidly without air pockets. Tool sealant after application to ensure adhesion. Make sealant uniformly smooth and free of wrinkles. Upon completion of sealant application, roughen partially filled or unfilled joints, apply sealant, and tool smooth as specified. Apply sealer over the sealant when and as specified by the sealant manufacturer.

3.4 PROTECTION AND CLEANING

3.4.1 Protection

Protect areas adjacent to joints from sealant smears. Masking tape may be used for this purpose if removed 5 to 10 minutes after the joint is filled.

3.4.2 Final Cleaning

Upon completion of sealant application, remove remaining smears and stains and leave the work in a clean and neat condition.

a. Masonry and Other Porous Surfaces: Immediately scrape off fresh sealant that has been smeared on masonry and rub clean with a solvent as recommended by the sealant manufacturer. Allow excess sealant to cure for 24 hour then remove by wire brushing or sanding.

b. Metal and Other Non-Porous Surfaces: Remove excess sealant with a solvent-moistened cloth.

-- End of Section --

SECTION 09 90 00

PAINTS AND COATINGS
02/10

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN CONFERENCE OF GOVERNMENTAL INDUSTRIAL HYGIENISTS (ACGIH)

ACGIH 0100Doc	(2005) Documentation of the Threshold Limit Values and Biological Exposure Indices

ASME INTERNATIONAL (ASME)

ASME A13.1	(2007; R 2013) Scheme for the Identification of Piping Systems

ASTM INTERNATIONAL (ASTM)

ASTM D 2092	(1995; R 2001e1) Standard Guide for Preparation of Zinc-Coated (Galvanized) Steel Surfaces for Painting
ASTM D 235	(2002; R 2008) Mineral Spirits (Petroleum Spirits) (Hydrocarbon Dry Cleaning Solvent)
ASTM D 4214	(2007) Standard Test Method for Evaluating the Degree of Chalking of Exterior Paint Films
ASTM D 4444	(2008) Use and Calibration of Hand-Held Moisture Meters
ASTM D 523	(2008) Standard Test Method for Specular Gloss

MASTER PAINTERS INSTITUTE (MPI)

MPI 107	(Oct 2009) Rust Inhibitive Primer (Water-Based)
MPI 134	(Oct 2009) Galvanized Primer (Waterbased)
MPI 147	(Oct 2009) Institutional Low Odor / VOC Interior Latex, Semi-Gloss, MPI Gloss Level 5
MPI 163	(Oct 2009) Exterior W.B. Light Industrial Coating, Semi-Gloss, MPI Gloss Level 5
MPI 23	(Oct 2009) Surface Tolerant Metal Primer

MPI 39	(Oct 2009) Interior Latex-Based Wood Primer
MPI 47	(Oct 2009) Interior Alkyd, Semi-Gloss, MPI Gloss Level 5
MPI 79	(Oct 2009) Alkyd Anti-Corrosive Metal Primer
MPI 94	(Oct 2009) Exterior Alkyd, Semi-Gloss, MPI Gloss Level 5

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS SP-01	(2000) Environmentally Preferable Product Specification for Architectural and Anti-Corrosive Paints

THE SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC PA 1	(2000; E 2004) Shop, Field, and Maintenance Painting
SSPC PA Guide 3	(1982; E 1995) A Guide to Safety in Paint Application
SSPC SP 1	(1982; E 2004) Solvent Cleaning
SSPC SP 10	(2007) Near-White Blast Cleaning
SSPC SP 12	(2002) Surface Preparation and Cleaning of Metals by Waterjetting Prior to Recoating
SSPC SP 2	(1982; E 2004) Hand Tool Cleaning
SSPC SP 3	(2004; E 2004) Power Tool Cleaning
SSPC SP 6	(2007) Commercial Blast Cleaning
SSPC SP 7	(2007) Brush-Off Blast Cleaning
SSPC VIS 1	(2002; E 2004) Guide and Reference Photographs for Steel Surfaces Prepared by Dry Abrasive Blast Cleaning
SSPC VIS 3	(2004) Visual Standard for Power-and Hand-Tool Cleaned Steel
SSPC VIS 4	(1998; E 2000; E 2004) Guide and Reference Photographs for Steel Surfaces Prepared by Waterjetting

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2008; Errata 1-2010; Changes 1-3 2010; Changes 4-6 2011; Change 7 2012) Safety and Health Requirements Manual

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

FED-STD-313	(Rev D; Am 1) Material Safety Data, Transportation Data and Disposal Data for Hazardous Materials Furnished to Government Activities

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.1000	Air Contaminants

1.2 SUBMITTALS

The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

The current MPI, "Approved Product List" which lists paint by brand, label, product name and product code as of the date of contract award, will be used to determine compliance with the submittal requirements of this specification. The Contractor may choose to use a subsequent MPI "Approved Product List", however, only one list may be used for the entire contract and each coating system is to be from a single manufacturer. All coats on a particular substrate must be from a single manufacturer. No variation from the MPI Approved Products List is acceptable.

Samples of specified materials may be taken and tested for compliance with specification requirements.

In keeping with the intent of Executive Order 13101, "Greening the Government through Waste Prevention, Recycling, and Federal Acquisition", products certified by SCS as meeting SCS SP-01 shall be given preferential consideration over registered products. Products that are registered shall be given preferential consideration over products not carrying any EPP designation.

SD-02 Shop Drawings

Piping identification

SD-03 Product Data

Local/Regional Materials

Materials

Coating

Manufacturer's Technical Data Sheets

Indicate VOC content.

SD-04 Samples

Color

Submit manufacturer's samples of paint colors. Cross reference color samples to color scheme as indicated.

SD-07 Certificates

Applicator's qualifications

Qualification Testing laboratory for coatings

SD-08 Manufacturer's Instructions

Application instructions

Mixing

Detailed mixing instructions, minimum and maximum application temperature and humidity, potlife, and curing and drying times between coats.

Manufacturer's Material Safety Data Sheets

Submit manufacturer's Material Safety Data Sheets for coatings, solvents, and other potentially hazardous materials, as defined in FED-STD-313.

SD-10 Operation and Maintenance Data

Coatings:

Preprinted cleaning and maintenance instructions for all coating systems shall be provided.

1.3 APPLICATOR'S QUALIFICATIONS

1.3.1 Contractor Qualification

Submit the name, address, telephone number, FAX number, and e-mail address of the contractor that will be performing all surface preparation and coating application. Submit evidence that key personnel have successfully performed surface preparation and application of coatings on a minimum of three similar projects within the past three years. List information by individual and include the following:

a. Name of individual and proposed position for this work.

b. Information about each previous assignment including:

Position or responsibility

Employer (if other than the Contractor)

Name of facility owner

Mailing address, telephone number, and telex number (if non-US) of facility owner

Name of individual in facility owner's organization who can be contacted as a reference

Location, size and description of structure

Dates work was carried out

Description of work carried out on structure

1.4 QUALITY ASSURANCE

1.4.1 Field Samples and Tests

The Contracting Officer may choose up to two coatings that have been delivered to the site to be tested at no cost to the Government. Take samples of each chosen product as specified in the paragraph "Sampling Procedures." Test each chosen product as specified in the paragraph "Testing Procedure." Products which do not conform, shall be removed from the job site and replaced with new products that conform to the referenced specification. Testing of replacement products that failed initial testing shall be at no cost to the Government.

1.4.1.1 Sampling Procedure

The Contracting Officer will select paint at random from the products that have been delivered to the job site for sample testing. The Contractor shall provide one quart samples of the selected paint materials. The samples shall be taken in the presence of the Contracting Officer, and labeled, identifying each sample. Provide labels in accordance with the paragraph "Packaging, Labeling, and Storage" of this specification.

1.4.1.2 Testing Procedure

Provide Batch Quality Conformance Testing for specified products, as defined by and performed by MPI. As an alternative to Batch Quality Conformance Testing, the Contractor may provide Qualification Testing for specified products above to the appropriate MPI product specification, using the third-party laboratory approved under the paragraph "Qualification Testing" laboratory for coatings. The qualification testing lab report shall include the backup data and summary of the test results. The summary shall list all of the reference specification requirements and the result of each test. The summary shall clearly indicate whether the tested paint meets each test requirement. Note that Qualification Testing may take 4 to 6 weeks to perform, due to the extent of testing required.

Submit name, address, telephone number, FAX number, and e-mail address of the independent third party laboratory selected to perform testing of coating samples for compliance with specification requirements. Submit documentation that laboratory is regularly engaged in testing of paint samples for conformance with specifications, and that employees performing testing are qualified. If the Contractor chooses MPI to perform the Batch Quality Conformance testing, the above submittal information is not required, only a letter is required from the Contractor stating that MPI will perform the testing.

1.5 REGULATORY REQUIREMENTS

1.5.1 Environmental Protection

In addition to requirements specified elsewhere for environmental protection, provide coating materials that conform to the restrictions of the local Air Pollution Control District and regional jurisdiction. Notify Contracting Officer of any paint specified herein which fails to

conform.

1.5.2 Lead Content

Do not use coatings having a lead content over 0.06 percent by weight of nonvolatile content.

1.5.3 Chromate Content

Do not use coatings containing zinc-chromate or strontium-chromate.

1.5.4 Asbestos Content

Materials shall not contain asbestos.

1.5.5 Mercury Content

Materials shall not contain mercury or mercury compounds.

1.5.6 Silica

Abrasive blast media shall not contain free crystalline silica.

1.5.7 Human Carcinogens

Materials shall not contain ACGIH 0100Doc and ACGIH 0100Doc confirmed human carcinogens (A1) or suspected human carcinogens (A2).

1.6 PACKAGING, LABELING, AND STORAGE

Paints shall be in sealed containers that legibly show the contract specification number, designation name, formula or specification number, batch number, color, quantity, date of manufacture, manufacturer's formulation number, manufacturer's directions including any warnings and special precautions, and name and address of manufacturer. Pigmented paints shall be furnished in containers not larger than 5 gallons. Paints and thinners shall be stored in accordance with the manufacturer's written directions, and as a minimum, stored off the ground, under cover, with sufficient ventilation to prevent the buildup of flammable vapors, and at temperatures between 40 to 95 degrees F. Do not store paint, polyurethane, varnish, or wood stain products with materials that have a high capacity to adsorb VOC emissions. Do not store paint, polyurethane, varnish, or wood stain products in occupied spaces.

1.7 SAFETY AND HEALTH

Apply coating materials using safety methods and equipment in accordance with the following:

Work shall comply with applicable Federal, State, and local laws and regulations, and with the ACCIDENT PREVENTION PLAN, including the Activity Hazard Analysis as specified in Section 01 35 26 GOVERNMENT SAFETY REQUIREMENTS and in Appendix A of EM 385-1-1. The Activity Hazard Analysis shall include analyses of the potential impact of painting operations on painting personnel and on others involved in and adjacent to the work zone.

1.7.1 Safety Methods Used During Coating Application

Comply with the requirements of SSPC PA Guide 3.

1.7.2 Toxic Materials

To protect personnel from overexposure to toxic materials, conform to the most stringent guidance of:

a. The applicable manufacturer's Material Safety Data Sheets (MSDS) or local regulation.

b. 29 CFR 1910.1000.

c. ACGIH 0100Doc, threshold limit values.

1.8 ENVIRONMENTAL CONDITIONS

Comply, at minimum, with manufacturer recommendations for space ventilation during and after installation.

1.8.1 Coatings

Do not apply coating when air or substrate conditions are:

a. Less than 5 degrees F above dew point;

b. Below 50 degrees F or over 95 degrees F, unless specifically pre-approved by the Contracting Officer and the product manufacturer. Under no circumstances shall application conditions exceed manufacturer recommendations.

1.9 SUSTAINABLE DESIGN REQUIREMENTS

1.9.1 Local/Regional Materials

Use materials or products extracted, harvested, or recovered, as well as manufactured, within a 500 mile radius from the project site, if available from a minimum of three sources.

1.10 SCHEDULING

Allow paint, polyurethane, varnish, and wood stain installations to cure prior to the installation of materials that adsorb VOCs, including.

1.11 COLOR SELECTION

Colors of finish coats shall be as indicated or specified. Where not indicated or specified, colors shall be selected by the Contracting Officer. Manufacturers' names and color identification are used for the purpose of color identification only. Named products are acceptable for use only if they conform to specified requirements. Products of other manufacturers are acceptable if the colors approximate colors indicated and the product conforms to specified requirements.

Tint each coat progressively darker to enable confirmation of the number of coats.

1.12 LOCATION AND SURFACE TYPE TO BE PAINTED

1.12.1 Painting Included

Where a space or surface is indicated to be painted, include the following unless indicated otherwise.

a. Surfaces behind portable objects and surface mounted articles readily detachable by removal of fasteners, such as screws and bolts.

b. New factory finished surfaces that require identification or color coding and factory finished surfaces that are damaged during performance of the work.

c. Existing coated surfaces that are damaged during performance of the work.

1.12.1.1 Interior Painting

Includes new surfaces, existing uncoated surfaces, and existing coated surfaces of the buildings and appurtenances as indicated and existing coated surfaces made bare by cleaning operations. Where a space or surface is indicated to be painted, include the following items, unless indicated otherwise.

a. Exposed columns, girders, beams, joists, and metal deck; and

b. Other contiguous surfaces.

1.12.2 Painting Excluded

Do not paint the following unless indicated otherwise.

a. Surfaces concealed and made inaccessible by panelboards, fixed ductwork, machinery, and equipment fixed in place.

b. Surfaces in concealed spaces. Concealed spaces are defined as enclosed spaces above suspended ceilings, furred spaces, attic spaces, crawl spaces, elevator shafts and chases.

c. Steel to be embedded in concrete.

d. Copper, stainless steel, aluminum, brass, and lead except existing coated surfaces.

e. Hardware, fittings, and other factory finished items.

1.12.3 Mechanical and Electrical Painting

Includes field coating of interior and exterior new and existing surfaces.

a. Where a space or surface is indicated to be painted, include the following items unless indicated otherwise.

(1) Exposed piping, conduit, and ductwork;

(2) Supports, hangers, air grilles, and registers;

(3) Miscellaneous metalwork and insulation coverings

1.12.3.1 Fire Extinguishing Sprinkler Systems

Clean, pretreat, prime, and paint new fire extinguishing sprinkler systems including valves, piping, conduit, hangers, supports, miscellaneous metalwork, and accessories. Apply coatings to clean, dry surfaces, using clean brushes. Clean the surfaces to remove dust, dirt, rust, and loose mill scale. Immediately after cleaning, provide the metal surfaces with one coat primer per schedules. Shield sprinkler heads with protective covering while painting is in progress. Upon completion of painting, remove protective covering from sprinkler heads. Remove sprinkler heads which have been painted and replace with new sprinkler heads. Provide primed surfaces with the following:

a. Piping in Unfinished Areas: Provide primed surfaces with one coat of red alkyd gloss enamel applied to a minimum dry film thickness of 1.0 mil in attic spaces, spaces above suspended ceilings, crawl spaces, pipe chases, mechanical equipment room, and spaces where walls or ceiling are not painted or not constructed of a prefinished material. In lieu of red enamel finish coat, provide piping with 2 inch wide red enamel bands or self-adhering red plastic bands spaced at maximum of 20 foot intervals.

b. Piping in Finished Areas: Provide primed surfaces with two coats of paint to match adjacent surfaces, except provide valves and operating accessories with one coat of red alkyd gloss enamel applied to a minimum dry film thickness of 1.0 mil. Provide piping with 2 inch wide red enamel bands or self-adhering red plastic bands spaced at maximum of 20 foot intervals throughout the piping systems.

1.12.4 Definitions and Abbreviations

1.12.4.1 Qualification Testing

Qualification testing is the performance of all test requirements listed in the product specification. This testing is accomplished by MPI to qualify each product for the MPI Approved Product List, and may also be accomplished by Contractor's third party testing lab if an alternative to Batch Quality Conformance Testing by MPI is desired.

1.12.4.2 Batch Quality Conformance Testing

Batch quality conformance testing determines that the product provided is the same as the product qualified to the appropriate product specification. This testing shall only be accomplished by MPI testing lab.

1.12.4.3 Coating

A film or thin layer applied to a base material called a substrate. A coating may be a metal, alloy, paint, or solid/liquid suspensions on various substrates (metals, plastics, wood, paper, leather, cloth, etc.). They may be applied by electrolysis, vapor deposition, vacuum, or mechanical means such as brushing, spraying, calendaring, and roller coating. A coating may be applied for aesthetic or protective purposes or both. The term "coating" as used herein includes emulsions, enamels,

stains, varnishes, sealers, epoxies, and other coatings, whether used as primer, intermediate, or finish coat. The terms paint and coating are used interchangeably.

1.12.4.4 DFT or dft

Dry film thickness, the film thickness of the fully cured, dry paint or coating.

1.12.4.5 DSD

Degree of Surface Degradation, the MPI system of defining degree of surface degradation. Five (5) levels are generically defined under the Assessment sections in the MPI Maintenance Repainting Manual.

1.12.4.6 EPP

Environmentally Preferred Products, a standard for determining environmental preferability in support of Executive Order 13101.

1.12.4.7 EXT

MPI short term designation for an exterior coating system.

1.12.4.8 INT

MPI short term designation for an interior coating system.

1.12.4.9 micron / microns

The metric measurement for 0.001 mm or one/one-thousandth of a millimeter.

1.12.4.10 mil / mils

The English measurement for 0.001 in or one/one-thousandth of an inch, equal to 25.4 microns or 0.0254 mm.

1.12.4.11 mm

The metric measurement for millimeter, 0.001 meter or one/one-thousandth of a meter.

1.12.4.12 MPI Gloss Levels

MPI system of defining gloss. Seven (7) gloss levels (G1 to G7) are generically defined under the Evaluation sections of the MPI Manuals. Traditionally, Flat refers to G1/G2, Eggshell refers to G3, Semigloss refers to G5, and Gloss refers to G6.

Gloss levels are defined by MPI as follows:

Gloss Level	Description	Units @ 60 degrees	Units @ 85 degrees
G1	Matte or Flat	0 to 5	10 max
G2	Velvet	0 to 10	10 to 35
G3	Eggshell	10 to 25	10 to 35
G4	Satin	20 to 35	35 min
G5	Semi-Gloss	35 to 70	

G6	Gloss	70 to 85
G7	High Gloss	

Gloss is tested in accordance with ASTM D 523. Historically, the Government has used Flat (G1 / G2), Eggshell (G3), Semi-Gloss (G5), and Gloss (G6).

1.12.4.13 MPI System Number

The MPI coating system number in each Division found in either the MPI Architectural Painting Specification Manual or the Maintenance Repainting Manual and defined as an exterior (EXT/REX) or interior system (INT/RIN). The Division number follows the CSI Master Format.

1.12.4.14 Paint

See Coating definition.

1.12.4.15 REX

MPI short term designation for an exterior coating system used in repainting projects or over existing coating systems.

1.12.4.16 RIN

MPI short term designation for an interior coating system used in repainting projects or over existing coating systems.

PART 2 PRODUCTS

2.1 MATERIALS

Conform to the coating specifications and standards referenced in PART 3. Submit manufacturer's technical data sheets for specified coatings and solvents.

PART 3 EXECUTION

3.1 PROTECTION OF AREAS AND SPACES NOT TO BE PAINTED

Prior to surface preparation and coating applications, remove, mask, or otherwise protect, hardware, hardware accessories, machined surfaces, radiator covers, plates, lighting fixtures, public and private property, and other such items not to be coated that are in contact with surfaces to be coated. Following completion of painting, workmen skilled in the trades involved shall reinstall removed items. Restore surfaces contaminated by coating materials, to original condition and repair damaged items.

3.2 SURFACE PREPARATION

Remove dirt, splinters, loose particles, grease, oil, disintegrated coatings, and other foreign matter and substances deleterious to coating performance as specified for each substrate before application of paint or surface treatments. Oil and grease shall be removed prior to mechanical cleaning. Cleaning shall be programmed so that dust and other contaminants will not fall on wet, newly painted surfaces. Exposed ferrous metals such as nail heads on or in contact with surfaces to be painted with water-thinned paints, shall be spot-primed with a suitable

corrosion-inhibitive primer capable of preventing flash rusting and compatible with the coating specified for the adjacent areas.

3.2.1 Additional Requirements for Preparation of Surfaces With Existing Coatings

Before application of coatings, perform the following on surfaces covered by soundly-adhered coatings, defined as those which cannot be removed with a putty knife:

a. Test existing finishes for lead before sanding, scraping, or removing. If lead is present, refer to paragraph Toxic Materials.

b. Wipe previously painted surfaces to receive solvent-based coatings, except stucco and similarly rough surfaces clean with a clean, dry cloth saturated with mineral spirits, ASTM D 235. Allow surface to dry. Wiping shall immediately precede the application of the first coat of any coating, unless specified otherwise.

c. Sand existing glossy surfaces to be painted to reduce gloss. Brush, and wipe clean with a damp cloth to remove dust.

d. The requirements specified are minimum. Comply also with the application instructions of the paint manufacturer.

e. Previously painted surfaces damaged during construction shall be thoroughly cleaned of all grease, dirt, dust or other foreign matter.

f. Blistering, cracking, flaking and peeling or other deteriorated coatings shall be removed.

g. Chalk shall be removed so that when tested in accordance with ASTM D 4214, the chalk resistance rating is no less than 8.

h. Slick surfaces shall be roughened. Damaged areas such as, but not limited to, nail holes, cracks, chips, and spalls shall be repaired with suitable material to match adjacent undamaged areas.

i. Edges of chipped paint shall be feather edged and sanded smooth.

j. Rusty metal surfaces shall be cleaned as per SSPC requirements. Solvent, mechanical, or chemical cleaning methods shall be used to provide surfaces suitable for painting.

k. New, proposed coatings shall be compatible with existing coatings.

3.2.2 Existing Coated Surfaces with Minor Defects

Sand, spackle, and treat minor defects to render them smooth. Minor defects are defined as scratches, nicks, cracks, gouges, spalls, alligatoring, chalking, and irregularities due to partial peeling of previous coatings. Remove chalking by sanding so that when tested in accordance with ASTM D 4214, the chalk rating is not less than 8.

3.2.3 Removal of Existing Coatings

Remove existing coatings from the following surfaces:

a. Surfaces containing large areas of minor defects;

b. Surfaces containing more than 20 percent peeling area; and

c. Surfaces designated by the Contracting Officer, such as surfaces where rust shows through existing coatings.

3.2.4 Substrate Repair

a. Repair substrate surface damaged during coating removal;

b. Sand edges of adjacent soundly-adhered existing coatings so they are tapered as smooth as practical to areas involved with coating removal; and

c. Clean and prime the substrate as specified.

3.3 PREPARATION OF METAL SURFACES

3.3.1 Existing and New Ferrous Surfaces

a. Ferrous Surfaces including Shop-coated Surfaces and Small Areas That Contain Rust, Mill Scale and Other Foreign Substances: Solvent clean or detergent wash in accordance with SSPC SP 1 to remove oil and grease. Where shop coat is missing or damaged, clean according to SSPC SP 2. Shop-coated ferrous surfaces shall be protected from corrosion by treating and touching up corroded areas immediately upon detection.

b. Surfaces With More Than 20 Percent Rust, Mill Scale, and Other Foreign Substances: Clean entire surface in accordance with SSPC SP 6/SSPC SP 12 WJ-3.

3.3.2 Final Ferrous Surface Condition:

For tool cleaned surfaces, the requirements are stated in SSPC SP 2 and SSPC SP 3. As a visual reference, cleaned surfaces shall be similar to photographs in SSPC VIS 3.

For abrasive blast cleaned surfaces, the requirements are stated in SSPC SP 7, SSPC SP 6, and SSPC SP 10. As a visual reference, cleaned surfaces shall be similar to photographs in SSPC VIS 1.

For waterjet cleaned surfaces, the requirements are stated in SSPC SP 12. As a visual reference, cleaned surfaces shall be similar to photographs in SSPC VIS 4.

3.3.3 Galvanized Surfaces

a. New or Existing Galvanized Surfaces With Only Dirt and Zinc Oxidation Products: Clean with solvent, or non-alkaline detergent solution in accordance with SSPC SP 1. If the galvanized metal has been passivated or stabilized, the coating shall be completely removed by brush-off abrasive blast. New galvanized steel to be coated shall not be "passivated" or "stabilized" If the absence of hexavalent stain inhibitors is not documented, test as described in ASTM D 2092, Appendix X2, and remove by one of the

methods described therein.

3.3.4 Non-Ferrous Metallic Surfaces

Aluminum and aluminum-alloy, lead, copper, and other nonferrous metal surfaces.

a. Surface Cleaning: Solvent clean in accordance with SSPC SP 1 and wash with mild non-alkaline detergent to remove dirt and water soluble contaminants.

3.4 PREPARATION OF CONCRETE AND CEMENTITIOUS SURFACE

3.5 PREPARATION OF WOOD AND PLYWOOD SURFACES

3.5.1 New , Existing Uncoated, and Existing Coated Plywood and Wood Surfaces, Except Floors:

a. Wood surfaces shall be cleaned of foreign matter.

Surface Cleaning: Surfaces shall be free from dust and other deleterious substances and in a condition approved by the Contracting Officer prior to receiving paint or other finish. Do not use water to clean uncoated wood. Scrape to remove loose coatings. Lightly sand to roughen the entire area of previously enamel-coated wood surfaces.

b. Removal of Fungus and Mold: Wash existing coated surfaces with a solution composed of 3 ounces (2/3 cup) trisodium phosphate, 1 ounce (1/3 cup) household detergent, 1 quart 5 percent sodium hypochlorite solution and 3 quarts of warm water. Rinse thoroughly with fresh water.

c. Moisture content of the wood shall not exceed 12 percent as measured by a moisture meter in accordance with ASTM D 4444, Method A, unless otherwise authorized.

d. Wood surfaces adjacent to surfaces to receive water-thinned paints shall be primed and/or touched up before applying water-thinned paints.

e. Cracks and Nailheads: Set and putty stop nailheads and putty cracks after the prime coat has dried.

f. Cosmetic Repair of Minor Defects:

(1) Knots and Resinous Wood : Prior to application of coating, cover knots and stains with two or more coats of 3-pound-cut shellac varnish, plasticized with 5 ounces of castor oil per gallon. Scrape away existing coatings from knotty areas, and sand before treating. Prime before applying any putty over shellacked area.

(2) Open Joints and Other Openings: Fill with whiting putty, linseed oil putty. Sand smooth after putty has dried.

(3) Checking: Where checking of the wood is present, sand the surface, wipe and apply a coat of pigmented orange shellac. Allow to dry before paint is applied.

3.5.2 Interior Wood Surfaces, Stain Finish

Interior wood surfaces to receive stain shall be sanded. Oak and other open-grain wood to receive stain shall be given a coat of wood filler not less than 8 hours before the application of stain; excess filler shall be removed and the surface sanded smooth.

3.6 APPLICATION

3.6.1 Coating Application

Painting practices shall comply with applicable federal, state and local laws enacted to insure compliance with Federal Clean Air Standards. Apply coating materials in accordance with SSPC PA 1. SSPC PA 1 methods are applicable to all substrates, except as modified herein.

At the time of application, paint shall show no signs of deterioration. Uniform suspension of pigments shall be maintained during application.

Unless otherwise specified or recommended by the paint manufacturer, paint may be applied by brush, roller, or spray. Use trigger operated spray nozzles for water hoses. Rollers for applying paints and enamels shall be of a type designed for the coating to be applied and the surface to be coated. Wear protective clothing and respirators when applying oil-based paints or using spray equipment with any paints.

Paints, except water-thinned types, shall be applied only to surfaces that are completely free of moisture as determined by sight or touch.

Thoroughly work coating materials into joints, crevices, and open spaces. Special attention shall be given to insure that all edges, corners, crevices, welds, and rivets receive a film thickness equal to that of adjacent painted surfaces.

Each coat of paint shall be applied so dry film shall be of uniform thickness and free from runs, drops, ridges, waves, pinholes or other voids, laps, brush marks, and variations in color, texture, and finish. Hiding shall be complete.

Touch up damaged coatings before applying subsequent coats. Interior areas shall be broom clean and dust free before and during the application of coating material.

Apply paint to new fire extinguishing sprinkler systems including valves, piping, conduit, hangers, supports, miscellaneous metal work, and accessories. Shield sprinkler heads with protective coverings while painting is in progress. Remove sprinkler heads which have been painted and replace with new sprinkler heads. For piping in unfinished spaces, provide primed surfaces with one coat of red alkyd gloss enamel to a minimum dry film thickness of 1.0 mil. Unfinished spaces include attic spaces, spaces above suspended ceilings, crawl spaces, pipe chases, mechanical equipment room, and space where walls or ceiling are not painted or not constructed of a prefinished material. For piping in finished areas, provide prime surfaces with two coats of paint to match adjacent surfaces, except provide valves and operating accessories with one coat of red alkyd gloss enamel. Upon completion of painting, remove protective covering from sprinkler heads.

a. Drying Time: Allow time between coats, as recommended by the coating manufacturer, to permit thorough drying, but not to present topcoat adhesion problems. Provide each coat in specified condition to receive next coat.

b. Primers, and Intermediate Coats: Do not allow primers or intermediate coats to dry more than 30 days, or longer than recommended by manufacturer, before applying subsequent coats. Follow manufacturer's recommendations for surface preparation if primers or intermediate coats are allowed to dry longer than recommended by manufacturers of subsequent coatings. Each coat shall cover surface of preceding coat or surface completely, and there shall be a visually perceptible difference in shades of successive coats.

c. Finished Surfaces: Provide finished surfaces free from runs, drops, ridges, waves, laps, brush marks, and variations in colors.

d. Thermosetting Paints: Topcoats over thermosetting paints (epoxies and urethanes) should be applied within the overcoating window recommended by the manufacturer.

3.6.2 Mixing and Thinning of Paints

Reduce paints to proper consistency by adding fresh paint, except when thinning is mandatory to suit surface, temperature, weather conditions, application methods, or for the type of paint being used. Obtain written permission from the Contracting Officer to use thinners. The written permission shall include quantities and types of thinners to use.

When thinning is allowed, paints shall be thinned immediately prior to application with not more than 1 pint of suitable thinner per gallon. The use of thinner shall not relieve the Contractor from obtaining complete hiding, full film thickness, or required gloss. Thinning shall not cause the paint to exceed limits on volatile organic compounds. Paints of different manufacturers shall not be mixed.

3.6.3 Two-Component Systems

Two-component systems shall be mixed in accordance with manufacturer's instructions. Any thinning of the first coat to ensure proper penetration and sealing shall be as recommended by the manufacturer for each type of substrate.

3.6.4 Coating Systems

a. Systems by Substrates: Apply coatings that conform to the respective specifications listed in the following Tables:

Table

Division 5. Exterior Metal, Ferrous and Non-Ferrous Paint Table
Division 5. Interior Metal, Ferrous and Non-Ferrous Paint Table
Division 6. Interior Wood Paint Table

b. Minimum Dry Film Thickness (DFT): Apply paints, primers, varnishes, enamels, undercoats, and other coatings to a minimum dry film thickness of 1.5 mil each coat unless specified otherwise

in the Tables. Coating thickness where specified, refers to the minimum dry film thickness.

c. Coatings for Surfaces Not Specified Otherwise: Coat surfaces which have not been specified, the same as surfaces having similar conditions of exposure.

d. Existing Surfaces Damaged During Performance of the Work, Including New Patches In Existing Surfaces: Coat surfaces with the following:

(1) One coat of primer.

(2) One coat of undercoat or intermediate coat.

(3) One topcoat to match adjacent surfaces.

e. Existing Coated Surfaces To Be Painted: Apply coatings conforming to the respective specifications listed in the Tables herein, except that pretreatments, sealers and fillers need not be provided on surfaces where existing coatings are soundly adhered and in good condition. Do not omit undercoats or primers.

3.7 COATING SYSTEMS FOR METAL

Apply coatings of Tables in Division 5 for Exterior and Interior.

a. Apply specified ferrous metal primer on the same day that surface is cleaned, to surfaces that meet all specified surface preparation requirements at time of application.

b. Inaccessible Surfaces: Prior to erection, use one coat of specified primer on metal surfaces that will be inaccessible after erection.

c. Shop-primed Surfaces: Touch up exposed substrates and damaged coatings to protect from rusting prior to applying field primer.

d. Surface Previously Coated with Epoxy or Urethane: Apply MPI 101, 1.5 mils DFT immediately prior to application of epoxy or urethane coatings.

e. Pipes and Tubing: The semitransparent film applied to some pipes and tubing at the mill is not to be considered a shop coat, but shall be overcoated with the specified ferrous-metal primer prior to application of finish coats.

f. Exposed Nails, Screws, Fasteners, and Miscellaneous Ferrous Surfaces. On surfaces to be coated with water thinned coatings, spot prime exposed nails and other ferrous metal with latex primer MPI 107.

3.8 COATING SYSTEMS FOR WOOD AND PLYWOOD

a. Apply coatings of Tables in Division 6 for Exterior and Interior.

b. Prior to erection, apply two coats of specified primer to treat and prime wood and plywood surfaces which will be inaccessible after erection.

c. Apply stains in accordance with manufacturer's printed instructions.

3.9 PIPING IDENTIFICATION

Piping Identification, Including Surfaces In Concealed Spaces: Provide in accordance with ASME A13.1. Place vinyl self-adhesive labels in clearly visible locations.

3.10 INSPECTION AND ACCEPTANCE

In addition to meeting previously specified requirements, demonstrate mobility of moving components, including swinging and sliding doors, cabinets, and windows with operable sash, for inspection by the Contracting Officer. Perform this demonstration after appropriate curing and drying times of coatings have elapsed and prior to invoicing for final payment.

3.11 WASTE MANAGEMENT

As specified in the Waste Management Plan and as follows. Do not use kerosene or any such organic solvents to clean up water based paints. Properly dispose of paints or solvents in designated containers. Close and seal partially used containers of paint to maintain quality as necessary for reuse. Store in protected, well-ventilated, fire-safe area at moderate temperature. Place materials defined as hazardous or toxic waste in designated containers. Coordinate with manufacturer for take-back program. Set aside scrap to be returned to manufacturer for recycling into new product. When such a service is not available, local recyclers shall be sought after to reclaim the materials. Set aside extra paint for future color matches or reuse by the Government.

3.12 PAINT TABLES

3.12.1 EXTERIOR PAINT TABLES

DIVISION 5: EXTERIOR METAL, FERROUS AND NON-FERROUS PAINT TABLE

STEEL / FERROUS SURFACES

A. New Steel that has been hand or power tool cleaned to SSPC SP 2 or SSPC SP 3

1. Alkyd
New; MPI EXT 5.1Q-G5 (Semigloss) Existing; MPI REX 5.1D-G5

Primer:	Intermediate:	Topcoat:
MPI 23	MPI 94	MPI 94

System DFT: 5.25 mils

B. Existing steel that has been spot-blasted to SSPC SP 6:

1. Surface previously coated with alkyd or latex:

Waterborne Light Industrial Coating
MPI REX 5.1C-G5 (Semigloss)

Spot Primer:	Intermediate:	Topcoat:
MPI 79	MPI 163	MPI 163

System DFT: 5 mils

STEEL / FERROUS SURFACES

A. Galvanized surfaces with slight coating deterioration; little or no rusting:

1. Waterborne Light Industrial Coating
MPI REX 5.3J-G5 (Semigloss)

Primer:	Intermediate:	Topcoat:
MPI 134	N/A	MPI 163

System DFT: 4.5 mils

3.12.2 INTERIOR PAINT TABLES

DIVISION 5: INTERIOR METAL, FERROUS AND NON-FERROUS PAINT TABLE

INTERIOR STEEL / FERROUS SURFACES

A. Metal, Mechanical, Electrical, Fire extinguishing sprinkler systems including valves, conduit, hangers, supports,Surfaces adjacent to painted surfaces (Match surrounding finish), and miscellaneous metal items not otherwise specified except floors, hot metal surfaces, and new prefinished equipment:

1.

MPI INT 5.1E-G5 (Semigloss)

Primer:	Intermediate:	Topcoat:
MPI 79	MPI 47	MPI 47

System DFT: 5.25 mils

DIVISION 6: INTERIOR WOOD PAINT TABLE

A. New and Existing, uncoated Wood and plywood not otherwise specified:

1.

New; MPI INT 6.3V-G5 (Semigloss)

Primer:	Intermediate:	Topcoat:
MPI 39	MPI 147	MPI 147

System DFT: 4 mils

B. Existing, previously painted Wood and plywood not otherwise specified:

1.Existing; MPI RIN 6.4D-G5 (Semigloss)

Primer:	Intermediate:	Topcoat:
MPI 39	MPI 147	MPI 147

System DFT: 4 mils

-- End of Section --

SECTION 23 00 00

AIR SUPPLY, DISTRIBUTION, VENTILATION, AND EXHAUST SYSTEMS
08/10

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AIR MOVEMENT AND CONTROL ASSOCIATION INTERNATIONAL (AMCA)

AMCA 201	(2002; R 2011) Fans and Systems
AMCA 210	(2007) Laboratory Methods of Testing Fans for Aerodynamic Performance Rating
AMCA 300	(2008) Reverberant Room Method for Sound Testing of Fans
AMCA 301	(1990; INT 2007) Methods for Calculating Fan Sound Ratings from Laboratory Test Data
AMCA 500-D	(2012) Laboratory Methods of Testing Dampers for Rating

AIR-CONDITIONING, HEATING AND REFRIGERATION INSTITUTE (AHRI)

AHRI 260 I-P	(2012) Sound Rating of Ducted Air Moving and Conditioning Equipment
AHRI 410	(2001; Addendum 1 2002; Addendum 2 2005; Addendum 3 2011) Forced-Circulation Air-Cooling and Air-Heating Coils
AHRI 430	(2009) Central-Station Air-Handling Units
AHRI Guideline D	(1996) Application and Installation of Central Station Air-Handling Units

AMERICAN BEARING MANUFACTURERS ASSOCIATION (ABMA)

ABMA 11	(1990; R 2008) Load Ratings and Fatigue Life for Roller Bearings
ABMA 9	(1990; ERTA 2012; S 2013) Load Ratings and Fatigue Life for Ball Bearings

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE 52.2	(2012; Errata 2013) Method of Testing General Ventilation Air-Cleaning Devices for Removal Efficiency by Particle Size

ASHRAE 62.1	(2010; Errata 2011; INT 3 2012; INT 4 2012; INT 5 2013) Ventilation for Acceptable Indoor Air Quality
ASHRAE 68	(1997) Laboratory Method of Testing to Determine the Sound Power In a Duct
ASHRAE 70	(2006; R 2011) Method of Testing for Rating the Performance of Air Outlets and Inlets
ASHRAE 90.1 - IP	(2010; Errata 1-4 2011; INT 1-12 2011; Addenda A, B, C, G, H, J, K, O, P, S, Y, Z, BZ, CG, CI and DS 2012; Errata 5-9 2012; INT 13-16 2012; Errata 10-12 2013; INT 17-18 2013) Energy Standard for Buildings Except Low-Rise Residential Buildings

ASME INTERNATIONAL (ASME)

ASME A13.1	(2007; R 2013) Scheme for the Identification of Piping Systems

ASTM INTERNATIONAL (ASTM)

ASTM A123/A123M	(2013) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A167	(1999; R 2009) Standard Specification for Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet, and Strip
ASTM A924/A924M	(2013) Standard Specification for General Requirements for Steel Sheet, Metallic-Coated by the Hot-Dip Process
ASTM B117	(2011) Standard Practice for Operating Salt Spray (Fog) Apparatus
ASTM B766	(1986; R 2008) Standard Specification for Electrodeposited Coatings of Cadmium
ASTM C1071	(2012) Standard Specification for Fibrous Glass Duct Lining Insulation (Thermal and Sound Absorbing Material)
ASTM D1654	(2008) Evaluation of Painted or Coated Specimens Subjected to Corrosive Environments
ASTM D3359	(2009; E 2010; R 2010) Measuring Adhesion by Tape Test
ASTM D520	(2000; R 2011) Zinc Dust Pigment

ASTM E2016	(2011) Standard Specification for Industrial Woven Wire Cloth

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA MG 1	(2011; Errata 2012) Motors and Generators
NEMA MG 10	(2001; R 2007) Energy Management Guide for Selection and Use of Fixed Frequency Medium AC Squirrel-Cage Polyphase Induction Motors

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 90A	(2012) Standard for the Installation of Air Conditioning and Ventilating Systems

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

SMACNA 1966	(2005) HVAC Duct Construction Standards Metal and Flexible, 3rd Edition

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

40 CFR 82	Protection of Stratospheric Ozone

UNDERWRITERS LABORATORIES (UL)

UL 6	(2007; reprint Nov 2010) Electrical Rigid Metal Conduit-Steel
UL 705	(2004; Reprint Dec 2013) Standard for Power Ventilators
UL 900	(2004; Reprint Feb 2012) Standard for Air Filter Units
UL Bld Mat Dir	(2012) Building Materials Directory

1.2 SYSTEM DESCRIPTION

Furnish ductwork, piping offsets, fittings, and accessories as required to provide a complete installation. Coordinate the work of the different trades to avoid interference between piping, equipment, structural, and electrical work. Provide complete, in place, all necessary offsets in piping and ductwork, and all fittings, and other components, required to install the work as indicated and specified.

1.2.1 Mechanical Equipment Identification

The number of charts and diagrams shall be equal to or greater than the number of mechanical equipment rooms. Where more than one chart or diagram per space is required, mount these in edge pivoted, swinging leaf, extruded aluminum frame holders which open to 170 degrees.

1.2.1.1 Charts

Provide chart listing of equipment by designation numbers and capacities

such as flow rates, pressure and temperature differences, heating and cooling capacities, horsepower, pipe sizes, and voltage and current characteristics.

1.2.1.2 Diagrams

Submit proposed diagrams, at least 2 weeks prior to start of related testing. provide neat mechanical drawings provided with extruded aluminum frame under 1/8-inch glass or laminated plastic, system diagrams that show the layout of equipment, piping, and ductwork, and typed condensed operation manuals explaining preventative maintenance procedures, methods of checking the system for normal, safe operation, and procedures for safely starting and stopping the system. After approval, post these items where directed.

1.2.2 Service Labeling

Label equipment, including fans, air handlers, terminal units, etc. with labels made of self-sticking, plastic film designed for permanent installation. Labels shall be in accordance with the typical examples below:

SERVICE	LABEL AND TAG DESIGNATION
Air handling unit Number	AHU
Control and instrument air	CONTROL AND INSTR.

Identify similar services with different temperatures or pressures. Where pressures could exceed 125 pounds per square inch, gage, include the maximum system pressure in the label. Label and arrow piping in accordance with the following:

a. Each point of entry and exit of pipe passing through walls.

b. Each change in direction, i.e., elbows, tees.

c. In congested or hidden areas and at all access panels at each point required to clarify service or indicated hazard.

d. In long straight runs, locate labels at distances within eyesight of each other not to exceed 75 feet. All labels shall be visible and legible from the primary service and operating area.

For Bare or Insulated Pipes	
for Outside Diameters of	Lettering
1/2 thru 1-3/8 inch	1/2 inch
1-1/2 thru 2-3/8 inch	3/4 inch
2-1/2 inch and larger	1-1/4 inch

1.2.3 Color Coding

Color coding of all piping systems shall be in accordance with ASME A13.1.

1.3 SUBMITTALS

Submit the following in accordance with SUBMITTAL PROCEDURES:

SD-03 Product Data

Diffusers

Air Vents, Penthouses, and Goosenecks
Air Handling Units

Diagrams

SD-06 Test Reports

Performance Tests

SD-08 Manufacturer's Instructions

Manufacturer's Installation Instructions
Operation and Maintenance Training

SD-10 Operation and Maintenance Data

Air Handling Units

1.4 QUALITY ASSURANCE

Except as otherwise specified, approval of materials and equipment is based on manufacturer's published data.

a. Where materials and equipment are specified to conform to the standards of the Underwriters Laboratories, the label of or listing with reexamination in UL Bld Mat Dir, and UL 6 is acceptable as sufficient evidence that the items conform to Underwriters Laboratories requirements. In lieu of such label or listing, submit a written certificate from any nationally recognized testing agency, adequately equipped and competent to perform such services, stating that the items have been tested and that the units conform to the specified requirements. Outline methods of testing used by the specified agencies.

b. Where materials or equipment are specified to be constructed or tested, or both, in accordance with the standards of the ASTM International (ASTM), the ASME International (ASME), or other standards, a manufacturer's certificate of compliance of each item is acceptable as proof of compliance.

c. Conformance to such agency requirements does not relieve the item from compliance with other requirements of these specifications.

1.4.1 Prevention of Corrosion

Protect metallic materials against corrosion. Manufacturer shall provide rust-inhibiting treatment and standard finish for the equipment enclosures. Do not use aluminum in contact with earth, and where connected to dissimilar metal. Protect aluminum by approved fittings, barrier

material, or treatment. Ferrous parts such as anchors, bolts, braces, boxes, bodies, clamps, fittings, guards, nuts, pins, rods, shims, thimbles, washers, and miscellaneous parts not of corrosion-resistant steel or nonferrous materials shall be hot-dip galvanized in accordance with ASTM A123/A123M for exterior locations and cadmium-plated in conformance with ASTM B766 for interior locations.

1.4.2 Asbestos Prohibition

Do not use asbestos and asbestos-containing products.

1.4.3 Ozone Depleting Substances Used as Refrigerants

Minimize releases of Ozone Depleting Substances (ODS) during repair, maintenance, servicing or disposal of appliances containing ODS's by complying with all applicable sections of 40 CFR 82 Part 82 Subpart F.

1.4.4 Use of Ozone Depleting Substances, Other than Refrigerants

The use of Class I or Class II ODS's listed as nonessential in 40 CFR 82 Part 82.66 Subpart C is prohibited. These prohibited materials and uses include:

a. Any plastic party spray streamer or noise horn which is propelled by a chlorofluorocarbon

b. Any cleaning fluid for electronic and photographic equipment which contains a chlorofluorocarbon; including liquid packaging, solvent wipes, solvent sprays, and gas sprays.

c. Any plastic flexible or packaging foam product which is manufactured with or contains a chlorofluorocarbon, including, open cell foam, open cell rigid polyurethane poured foam, closed cell extruded polystyrene sheet foam, closed cell polyethylene foam and closed cell polypropylene foam except for flexible or packaging foam used in coaxial cabling.

d. Any aerosol product or other pressurized dispenser which contains a chlorofluorocarbon, except for those listed in 40 CFR 82 Part 82.66 Subpart C.

Request a waiver if a facility requirement dictates that a prohibited material is necessary to achieve project goals. Submit the waiver request in writing to the Contracting Officer. The waiver will be evaluated and dispositioned.

1.5 DELIVERY, STORAGE, AND HANDLING

Protect stored equipment at the jobsite from the weather, humidity and temperature variations, dirt and dust, or other contaminants. Additionally, cap or plug all pipes until installed.

PART 2 PRODUCTS

2.1 IDENTIFICATION PLATES

In addition to standard manufacturer's identification plates, provide engraved laminated phenolic identification plates for each piece of mechanical equipment. Identification plates are to designate the function of the equipment. Submit designation with the shop drawings.

Identification plates shall be three layers, black-white-black, engraved to show white letters on black background. Letters shall be upper case. Identification plates 1-1/2-inches high and smaller shall be 1/16-inch thick, with engraved lettering 1/8-inch high; identification plates larger than 1-1/2-inches high shall be 1/8-inch thick, with engraved lettering of suitable height. Identification plates 1-1/2-inches high and larger shall have beveled edges. Install identification plates using a compatible adhesive.

2.2 EQUIPMENT GUARDS AND ACCESS

Fully enclose or guard belts, pulleys, chains, gears, couplings, projecting setscrews, keys, and other rotating parts exposed to personnel contact according to OSHA requirements. Properly guard or cover with insulation of a type specified, high temperature equipment and piping exposed to contact by personnel or where it creates a potential fire hazard.

2.3 ELECTRICAL WORK

a. Provide motors, controllers, integral disconnects, contactors, and controls with their respective pieces of equipment, except controllers indicated as part of motor control centers. Provide electrical equipment, including motors and wiring, as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Provide manual or automatic control and protective or signal devices required for the operation specified and control wiring required for controls and devices specified, but not shown. For packaged equipment, include manufacturer provided controllers with the required monitors and timed restart.

b. For polyphase motors, provide squirrel-cage medium induction motors, including motors that are part of a system , and that meet the efficiency ratings for premium efficiency motors in accordance with NEMA MG 1. Select premium efficiency polyphase motors in accordance with NEMA MG 10.

c. Provide motors in accordance with NEMA MG 1 and of sufficient size to drive the load at the specified capacity without exceeding the nameplate rating of the motor. Provide motors rated for continuous duty with the enclosure specified. Provide motor duty that allows for maximum frequency start-stop operation and minimum encountered interval between start and stop. Provide motor torque capable of accelerating the connected load within 20 seconds with 80 percent of the rated voltage maintained at motor terminals during one starting period. Provide motor starters complete with thermal overload protection and other necessary appurtenances. Fit motor bearings with grease supply fittings and grease relief to outside of the enclosure.

2.4 PAINTING

Paint equipment units in accordance with approved equipment manufacturer's standards unless specified otherwise. Field retouch only if approved. Otherwise, return equipment to the factory for refinishing.

2.5 INDOOR AIR QUALITY

Provide equipment and components that comply with the requirements of ASHRAE 62.1 unless more stringent requirements are specified herein.

2.6 DUCT SYSTEMS

2.6.1 Metal Ductwork

Provide metal ductwork construction, including all fittings and components, that complies with SMACNA 1966, as supplemented and modified by this specification.

a. Provide radius type elbows with a centerline radius of 1.5 times the width or diameter of the duct where space permits. Otherwise, elbows having a minimum radius equal to the width or diameter of the duct or square elbows with factory fabricated turning vanes are allowed.

b. Provide ductwork that meets the requirements of Seal Class A

c. Provide sealants that conform to fire hazard classification specified in Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS and are suitable for the range of air distribution and ambient temperatures to which it is exposed. Do not use pressure sensitive tape as a sealant.

d. Make spiral lock seam duct, and flat oval with duct sealant and lock with not less than 3 equally spaced drive screws or other approved methods indicated in SMACNA 1966. Apply the sealant to the exposed male part of the fitting collar so that the sealer is on the inside of the joint and fully protected by the metal of the duct fitting. Apply one brush coat of the sealant over the outside of the joint to at least 2 inch band width covering all screw heads and joint gap. Dents in the male portion of the slip fitting collar are not acceptable. Fabricate outdoor air intake ducts and plenums with watertight soldered or brazed joints and seams.

2.6.2 Air Supply and Exhaust Air Dampers

Where aoutdoor air supply exhaust air dampers are required they shall have a maximum leakage raete when tested in accordance with AMCA 500-D as required by ASHRAE 90.1 - IP, including maximum Damper Leakage for:

a. Climate Zones 1,2,6,7,8 the maximum damper leakage at 1 inch w.g. for motoroized dampers is 4 cfm per square foot of damper area and non-motorized dampers are not allowed.

b. All other Climate Zones the maximum damer leakage at 1.0 inch w.g. is 10 cfm per square foot and for non-motorized dampers is 20 cfm per square foot of damper area

Dampers smaller that 24 inches in either direction may have leakage of 40 cfm per square foot

2.6.3 Air Deflectors and Branch Connections

Provide air deflectos at all duct mounted supply outlets, at takeoff or extensions collars to supply outlets, at duct breanch takeoff connections, and at 90 degress elbows, as well as at locations as indicated on the drawings or therwise specified. Conical branch connections or 45 degree entry connections are allowed in lieu of deflectors for branch connections. Furnish all air deflectors, except those installed in 90 degress elbows, with an approved means of adjustment, Provide easily accessible means for adjustment inside the duct or from an adjustment with sturdy lock on the face of the duct. When installed on the ducts to be

thermally insulated, provide external adjustments with stand-off mounting brackets, integral with adjustment device, ro provide clearance between the duct surface and the adjustment device not less than the thickness of the thermal insulation. Provide factory-fabricated air deflectors consisting of curved turning vanes or louver blades designed to provide uniform air distribution and change of direction with minimum turbulence or pressure loss. Provide factory or field assembled air deflectors. Make adjustment from the face of the diffuser or by position adjustment and lock external to the duct. Provide stand-off brackets on insulated ducts as described herein. Provide fixed air deflectos, also called turning vanes, in 90 degree elbows.

2.6.4 Diffusers, Registers, and Grilles

Provide factory-fabricated units of steel that distribute the specified quantity of air evenly over space intended without causing noticeable drafts, air movement faster than 50 fpm in occupied zone, or dead spots anywhere in the conditioned area. Provide outlets for diffusion, spread, throw, and noise level as required for specified performance. Certify performance according to ASHRAE 70. Provide sound rated and certified inlets and outlets according to ASHRAE 70. Provide sound power level as indicated. Provide diffusers and registers with volume damper with accessible operator, unless otherwise indicated; or if standard with the manufacturer, an automatically controlled device is acceptable. Provide opposed blade type volume dampers for all diffusers and registers.

2.6.4.1 Diffusers

Provide diffuser types indicated. For connecting the duct to diffuser, provide duct collar that is airtight and does not interfere with volume controller.

2.6.5 Air Vents, Penthouses, and Goosenecks

Fabricate air vents, penthouses, and goosenecks from galvanized steel sheets with galvanized structural shapes. Provide sheet metal thickness, reinforcement, and fabrication that conform to SMACNA 1966. Accurately fit and secure louver blades to frames. Fold or bead edges of louver blades for rigidity and baffle these edges to exclude driving rain. Provide air vents, penthouses, and goosenecks with bird screen.

2.6.6 Bird Screens and Frames

Provide bird screens that conform to ASTM E2016, No. 2 mesh, aluminum or stainless steel. Provide "medium-light" rated aluminum screens. Provide "light" rated stainless steel screens. Provide removable type frames fabricated from either stainless steel or extruded aluminum.

2.7 AIR SYSTEMS EQUIPMENT

2.7.1 Fans

Test and rate fans according to AMCA 210. Calculate system effect on air moving devices in accordance with AMCA 201 where installed ductwork differs from that indicated on drawings. Install air moving devices to minimize fan system effect. Where system effect is unavoidable, determine the most effective way to accommodate the inefficiencies caused by system effect on the installed air moving device. The sound power level of the fans shall not exceed 85 dBA when tested according to AMCA 300 and rated in accordance

with AMCA 301. Provide all fans with an AMCA seal. Connect fans to the motors either directly or indirectly with V-belt drive. Use V-belt drives designed for not less than 150 percent of the connected driving capacity. Provide variable pitch motor sheaves for 15 hp and below, and fixed pitch as defined by AHRI Guideline D (A fixed-pitch sheave is provided on both the fan shaft and the motor shaft. This is a non-adjustable speed drive.). Select variable pitch sheaves to drive the fan at a speed which can produce the specified capacity when set at the approximate midpoint of the sheave adjustment. When fixed pitch sheaves are furnished, provide a replaceable sheave when needed to achieve system air balance. Provide motors for V-belt drives with adjustable rails or bases. Provide removable metal guards for all exposed V-belt drives, and provide speed-test openings at the center of all rotating shafts. Provide fans with personnel screens or guards on both suction and supply ends, except that the screens need not be provided, unless otherwise indicated, where ducts are connected to the fan. Provide fan and motor assemblies with vibration-isolation supports or mountings as indicated. Use vibration-isolation units that are standard products with published loading ratings. Select each fan to produce the capacity required at the fan static pressure indicated. Provide sound power level as indicated. Obtain the sound power level values according to AMCA 300. Provide standard AMCA arrangement, rotation, and discharge as indicated. Provide power ventilators that conform to UL 705 and have a UL label.

2.7.2 Coils

Provide fin-and-tube type coils constructed of seamless copper tubes and aluminum or copper fins mechanically bonded or soldered to the tubes. Provide copper tube wall thickness that is a minimum of 0.024 inches. Provide aluminum fins that are 0.0055 inch minimum thickness. Provide copper fins that are 0.0045 inch minimum thickness. Provide casing and tube support sheets that are not lighter than 16 gauge galvanized steel, formed to provide structural strength. When required, provide multiple tube supports to prevent tube sag. Test each coil at the factory under water at not less than 400 psi air pressure and make suitable for 200 psi working pressure and 300 degrees F operating temperature unless otherwise stated. Mount coils for counterflow service. Rate and certify coils to meet the requirements of AHRI 410.

2.7.2.1 Water Coils

Install water coils with a pitch of not less than 1/8 inch/foot of the tube length toward the drain end. Use headers constructed of cast iron, welded steel or copper. Furnish each coil with a plugged vent and drain connection extending through the unit casing. Provide removable water coils with drain pans.

2.7.2.2 Steam Heating Coils

Construct steam coils from cast semisteel, welded steel or copper headers, and copper tubes. Construct headers from cast iron, welded steel or copper. Provide each coil with a field or factory installed vacuum breaker. Provide single-tube type coils with tubes not less than 1/2 inch outside diameter, except for steam preheat coils. Provide supply headers that distribute steam evenly to all tubes at the indicated steam pressure. Factory test coils to ensure that, when supplied with a uniform face velocity, temperature across the leaving side is uniform with a maximum variation of no more than 5 percent.

2.7.3 Corrosion Protection for Coastal Installations

Mechanical equipment with casing exterior factory painted shall be able to withstand a salt spray tect in accordance with ASTM B117 for a minimum of 500 consecutive hours.

2.7.4 Air Filters

List air filters according to requirements of UL 900.

2.7.4.1 Extended Surface Pleated Panel Filters

Provide 2 inch depth, sectional, disposable type filters of the size indicated with a MERV of 8 when tested according to ASHRAE 52.2. Provide initial resistance at 500 fpm that does not exceed 0.36 inches water gauge. Provide UL Class 2 filters, and nonwoven cotton and synthetic fiber mat media. Attach a wire support grid bonded to the media to a moisture resistant fiberboard frame. Bond all four edges of the filter media to the inside of the frame to prevent air bypass and increase rigidity.

2.7.4.2 Holding Frames

Fabricate frames from not lighter than 16 gauge sheet steel with rust-inhibitor coating. Equip each holding frame with suitable filter holding devices. Provide gasketed holding frame seats. Make all joints airtight.

2.7.4.3 Filter Gauges

Provide dial type filter gauges, diaphragm actuated draft for all filter stations, including those filters which are furnished as integral parts of factory fabricated air handling units. Gauges shall be at least 3-7/8 inches in diameter, with white dials with black figures, and graduated in 0.01 inch of water, with a minimum range of 1 inch of water beyond the specified final resistance for the filter bank on which each gauge is applied. Provide each gauge with a screw operated zero adjustment and two static pressure tips with integral compression fittings, two molded plastic vent valves, two 5 foot minimum lengths of 1/4 inch diameter aluminum tubing, and all hardware and accessories for gauge mounting.

2.8 AIR HANDLING UNITS

2.8.1 Factory-Fabricated Air Handling Units

Provide single-zone draw-through type units as indicated. Units shall include fans, coils, airtight insulated casing, prefilters, adjustable V-belt drives, belt guards for externally mounted motors, access sections where indicated, mixing box vibration-isolators, and appurtenances required for specified operation. Provide vibration isolators as indicated. Physical dimensions of each air handling unit shall be suitable to fit space allotted to the unit with the capacity indicated. Provide air handling unit that is rated in accordance with AHRI 430 and AHRI certified for cooling.

2.8.1.1 Casings

Provide the following:

a. Casing sections 2 inch double wall type, constructed of a minimum 18

gauge galvanized steel, or 18 gauge corrosion-resisting sheet steel conforming to ASTM A167, Type 304.Inner casing of double-wall units that are a minimum 20 gauge solid galvanized steel or corrosion-resisting sheet steel conforming to ASTM A167, Type 304. Design and construct casing with an integral insulated structural galvanized steel frame such that exterior panels are non-load bearing.

b. Individually removable exterior panels with standard tools. Removal shall not affect the structural integrity of the unit. Furnish casings with access sections, according to paragraph AIR HANDLING UNITS, inspection doors, and access doors, all capable of opening a minimum of 90 degrees, as indicated.

c. Insulated, fully gasketed, double-wall type inspection and access doors, of a minimum 18 gauge outer and 20 gauge inner panels made of either galvanized steel or corrosion-resisting sheet steel conforming to ASTM A167, Type 304. Doors shall be rigid and provided with heavy duty hinges and latches. Inspection doors shall be a minimum 12 inches wide by 12 inches high. Access doors shall be a minimum 24 inches wide, the full height of the unit casing or a minimum of 6 foot, whichever is less.

d. Double-wall insulated type drain pan (thickness equal to exterior casing) constructed of 16 gauge galvanized steel, conforming to ASHRAE 62.1. Construct drain pans water tight, treated to prevent corrosion, and designed for positive condensate drainage. Construct drain pan to allow for easy visual inspection, including underneath the coil without removal of the coil and to allow complete and easy physical cleaning of the pan underneath the coil without removal of the coil. Coils shall be individually removable from the casing.

e. Casing insulation that conforms to NFPA 90A. Single-wall casing sections handling conditioned air shall be insulated with not less than 1 inch thick, 1-1/2 pound density coated fibrous glass material having a thermal conductivity not greater than 0.23 Btu/hr-sf-F. Double-wall casing sections handling conditioned air shall be insulated with not less than 2 inches of the same insulation specified for single-wall casings. Foil-faced insulation is not an acceptable substitute for use with double wall casing. Double wall insulation shall be completely sealed by inner and outer panels.

f. Factory applied fibrous glass insulation that conforms to ASTM C1071, except that the minimum thickness and density requirements do not apply, and that meets the requirements of NFPA 90A. Make air handling unit casing insulation uniform over the entire casing. Foil-faced insulation is not an acceptable substitute for use on double-wall access doors and inspections doors and casing sections.

g. A latched and hinged inspection door, in the fan and coil sections. Plus additional inspection doors, access doors and access sections where indicated.

2.8.1.2 Heating and Cooling Coils

Provide coils as specified in paragraph AIR SYSTEMS EQUIPMENT.

2.8.1.3 Air Filters

Provide air filters as specified in paragraph AIR SYSTEMS EQUIPMENT for

types and thickness indicated.

2.8.1.4 Fans

Provide the following:

a. Fan bearings that are sealed against dust and dirt and are precision self-aligning ball or roller type, with L50 rated bearing life at not less than 200,000 hours as defined by ABMA 9 and ABMA 11. Bearings shall be permanently lubricated or lubricated type with lubrication fittings readily accessible at the drive side of the unit. Support bearings by structural shapes, or die formed sheet structural members, or support plates securely attached to the unit casing. Do not fasten bearings directly to the unit sheet metal casing. Furnish fans and scrolls with coating indicated.

b. Fans that are driven by a unit-mounted, or a floor-mounted motor connected to fans by V-belt drive. Belt drives shall be designed for not less than a 1.3 service factor based on motor nameplate rating.

c. Motor sheaves that are variable pitch for 25 hp and below and fixed pitch above 25 hp as defined by AHRI Guideline D. Where fixed sheaves are required, the use of variable pitch sheaves is allowed during air balance, but replace them with an appropriate fixed sheave after air balance is completed. Select variable pitch sheaves to drive the fan at a speed that produces the specified capacity when set at the approximate midpoint of the sheave adjustment. Furnish motors for V-belt drives with adjustable bases, and with totally enclosed enclosures.

d. Motor starters of across-the-line type with watertight enclosure. Select unit fan or fans to produce the required capacity at the fan static pressure with sound power level as indicated. Obtain the sound power level values according to AMCA 300, ASHRAE 68, or AHRI 260 I-P.

2.8.1.5 Access Sections and Filter/Mixing Boxes

Provide access sections where indicated and furnish with access doors as shown. Construct access sections and filter/mixing boxes in a manner identical to the remainder of the unit casing and equip with access doors. Design mixing boxes to minimize air stratification and to promote thorough mixing of the air streams.

2.9 FACTORY PAINTING

Factory paint new equipment, which are not of galvanized construction. Paint with a corrosion resisting paint finish according to ASTM A123/A123M or ASTM A924/A924M. Clean, phosphatize and coat internal and external ferrous metal surfaces with a paint finish which has been tested according to ASTM B117, ASTM D1654, and ASTM D3359. Submit evidence of satisfactory paint performance for a minimum of 125 hours for units to be installed indoors and 500 hours for units to be installed outdoors. Provide rating of failure at the scribe mark that is not less than 6, average creepage not greater than 1/8 inch. Provide rating of the inscribed area that is not less than 10, no failure. On units constructed of galvanized steel that have been welded, provide a final shop docket of zinc-rich protective paint on exterior surfaces of welds or welds that have burned through from the interior according to ASTM D520 Type I.

2.10 SUPPLEMENTAL COMPONENTS/SERVICES

2.10.1 Chilled, Condenser, or Dual Service Water Piping

The requirements for chilled, condenser, or dual service water piping and accessories are specified in Section 23 05 15 COMMOM PIPING FOR HVAC

2.10.2 Water or Steam Heating System Accessories

The requirements for water or steam heating accessories such as expansion tanks and steam traps are specified in Section 23 22 26.00 20 STEAM SYSTEM AND TERMINAL UNITS.

2.10.3 Condensate Drain Lines

Provide and install condensate drainage for each item of equipment that generates condensate in accordance with Section 23 05 15 COMMON PIPING FOR HVAC except as modified herein.

2.10.4 Insulation

The requirements for shop and field applied insulation are specified in Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS.

2.10.5 Controls

The requirements for controls are specified in 23 09 23.13 20 BACnet DIRECT DIGITAL CONTROL SYSTEMS FOR HVAC.

PART 3 EXECUTION

3.1 EXAMINATION

After becoming familiar with all details of the work, verify all dimensions in the field, and advise the Contracting Officer of any discrepancy before performing the work.

3.2 INSTALLATION

a. Install materials and equipment in accordance with the requirements of the contract drawings and approved manufacturer's installation instructions. Accomplish installation by workers skilled in this type of work. Perform installation so that there is no degradation of the designed fire ratings of walls, partitions, ceilings, and floors.

b. No installation is permitted to block or otherwise impede access to any existing machine or system. Install all hinged doors to swing open a minimum of 120 degrees. Provide an area in front of all access doors that clears a minimum of 3 feet. In front of all access doors to electrical circuits, clear the area the minimum distance to energized circuits as specified in OSHA Standards, part 1910.333 (Electrical-Safety Related work practices).

c. Except as otherwise indicated, install emergency switches and alarms in conspicuous locations. Mount all indicators, to include gauges, meters, and alarms in order to be easily visible by people in the area.

3.2.1 Condensate Drain Lines

Provide water seals in the condensate drain from all units. Provide a depth of each seal of 2 inches plus the number of inches, measured in water gauge, of the total static pressure rating of the unit to which the drain is connected. Provide water seals that are constructed of 2 tees and an appropriate U-bend with the open end of each tee plugged. Provide pipe cap or plug cleanouts where indicated.

3.2.2 Equipment and Installation

Provide frames and supports for air handling units and other similar items requiring supports.

3.2.3 Metal Ductwork

Install according to SMACNA 1966 unless otherwise indicated. Install duct supports for sheet metal ductwork according to SMACNA 1966, unless otherwise specified. Do not use friction beam clamps indicated in SMACNA 1966. Anchor risers on high velocity ducts in the center of the vertical run to allow ends of riser to move due to thermal expansion. Erect supports on the risers that allow free vertical movement of the duct. Attach supports only to structural framing members and concrete slabs. Do not anchor supports to metal decking unless a means is provided and approved for preventing the anchor from puncturing the metal decking. Where supports are required between structural framing members, provide suitable intermediate metal framing. Where C-clamps are used, provide retainer clips.

3.2.4 Dust Control

To prevent the accumulation of dust, debris and foreign material during construction, perform temporary dust control protection. Protect the distribution system (supply and return) with temporary seal-offs at all inlets and outlets at the end of each day's work. Keep temporary protection in place until system is ready for startup.

3.2.5 Insulation

Provide thickness and application of insulation materials for ductwork, piping, and equipment according to Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS.

3.2.6 Duct Test Holes

Provide holes with closures or threaded holes with plugs in ducts and plenums as indicated or where necessary for the use of pitot tube in balancing the air system. Plug insulated duct at the duct surface, patched over with insulation and then marked to indicate location of test hole if needed for future use.

3.2.7 Power Roof Ventilator Mounting

Provide foamed 1/2 inch thick, closed-cell, flexible elastomer insulation to cover width of roof curb mounting flange. Where wood nailers are used, predrill holes for fasteners.

3.2.8 Power Transmission Components Adjustment

Test V-belts and sheaves for proper alignment and tension prior to operation and after 72 hours of operation at final speed. Uniformly load belts on drive side to prevent bouncing. Make alignment of direct driven couplings to within 50 percent of manufacturer's maximum allowable range of misalignment.

3.3 CUTTING AND PATCHING

Install work in such a manner and at such time that a minimum of cutting and patching of the building structure is required.

3.4 CLEANING

Thoroughly clean surfaces of piping and equipment that have become covered with dirt, plaster, or other material during handling and construction before such surfaces are prepared for final finish painting or are enclosed within the building structure. Before final acceptance, clean mechanical equipment, including piping, ducting, and fixtures, and free from dirt, grease, and finger marks. When the work area is in an occupied space such as office, laboratory, warehouse, or production area, protect all furniture and equipment from dirt and debris. Incorporate housekeeping for field construction work which leaves all furniture and equipment in the affected area free of construction generated dust and debris; and, all floor surfaces vacuum-swept clean.

3.5 FIELD PAINTING OF MECHANICAL EQUIPMENT

Clean, pretreat, prime and paint metal surfaces; except aluminum surfaces need not be painted. Apply coatings to clean dry surfaces. Clean the surfaces to remove dust, dirt, rust, oil and grease by wire brushing and solvent degreasing prior to application of paint, except clean to bare metal on metal surfaces subject to temperatures in excess of 120 degrees F. Where more than one coat of paint is specified, apply the second coat after the preceding coat is thoroughly dry. Lightly sand damaged painting and retouch before applying the succeeding coat. Provide aluminum or light gray finish coat.

3.5.1 Temperatures less than 120 degrees F

Immediately after cleaning, apply one coat of pretreatment primer applied to a minimum dry film thickness of 0.3 mil, one coat of primer applied to a minimum dry film thickness of one mil; and two coats of enamel applied to a minimum dry film thickness of one mil per coat to metal surfaces subject to temperatures less than 120 degrees F.

3.6 IDENTIFICATION SYSTEMS

Provide identification tags made of brass, engraved laminated plastic, or engraved anodized aluminum, indicating service and item number on all valves and dampers. Provide tags that are 1-3/8 inch minimum diameter with stamped or engraved markings. Make indentations black for reading clarity. Attach tags to valves with No. 12 AWG 0.0808-inch diameter corrosion-resistant steel wire, copper wire, chrome-plated beaded chain or plastic straps designed for that purpose.

3.7 TESTING, ADJUSTING, AND BALANCING

The requirements for testing, adjusting, and balancing are specified in Section 23 05 93 TESTING, ADJUSTING AND BALANCING FOR HVAC. Begin testing, adjusting, and balancing only when the air supply and distribution, including controls, has been completed, with the exception of performance tests.

3.8 PERFORMANCE TESTS

After testing, adjusting, and balancing is complete as specified, test each system as a whole to see that all items perform as integral parts of the system and temperatures and conditions are evenly controlled throughout the building. Record the testing during the applicable season. Make corrections and adjustments as necessary to produce the conditions indicated or specified. Conduct capacity tests and general operating tests by an experienced engineer. Provide tests that cover a period of not less than 7 days for each system and demonstrate that the entire system is functioning according to the specifications. Make coincidental chart recordings at points indicated on the drawings for the duration of the time period and record the temperature at space thermostats or space sensors, the humidity at space humidistats or space sensors and the ambient temperature and humidity in a shaded and weather protected area.

3.9 OPERATION AND MAINTENANCE

3.9.1 Operation And Maintenance Training

Conduct a training course for the members of the operating staff as designated by the Contracting Officer. Make the training period consist of a total of 16 hours of normal working time and start it after all work specified herein is functionally completed and the Performance Tests have been approved. Conduct field instruction that covers all of the items contained in the Operation and Maintenance Manuals as well as demonstrations of routine maintenance operations. Notify the Contracting Officer at least 14 days prior to conducting the training course.

-- End of Section --

SECTION 23 03 00.00 20

BASIC MECHANICAL MATERIALS AND METHODS
08/10

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM B117	(2011) Standard Practice for Operating Salt Spray (Fog) Apparatus

1.2 RELATED REQUIREMENTS

This section applies to all sections of Divisions: 21, FIRE SUPPRESSION and 23, HEATING, VENTILATING, AND AIR CONDITIONING of this project specification, unless specified otherwise in the individual section.

1.3 QUALITY ASSURANCE

1.3.1 Material and Equipment Qualifications

Provide materials and equipment that are standard products of manufacturers regularly engaged in the manufacture of such products, which are of a similar material, design and workmanship. Standard products shall have been in satisfactory commercial or industrial use for 2 years prior to bid opening. The 2-year use shall include applications of equipment and materials under similar circumstances and of similar size. The product shall have been for sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2 year period.

1.3.2 Alternative Qualifications

Products having less than a two-year field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturer's factory or laboratory tests, can be shown.

1.3.3 Service Support

The equipment items shall be supported by service organizations. Submit a certified list of qualified permanent service organizations for support of the equipment which includes their addresses and qualifications. These service organizations shall be reasonably convenient to the equipment installation and able to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

1.3.4 Manufacturer's Nameplate

Each item of equipment shall have a nameplate bearing the manufacturer's name, address, model number, and serial number securely affixed in a conspicuous place; the nameplate of the distributing agent will not be

acceptable.

1.3.5 Modification of References

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "shall" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction", or words of similar meaning, to mean the Contracting Officer.

1.3.5.1 Definitions

For the International Code Council (ICC) Codes referenced in the contract documents, advisory provisions shall be considered mandatory, the word "should" shall be interpreted as "shall." Reference to the "code official" shall be interpreted to mean the "Contracting Officer." For Navy owned property, references to the "owner" shall be interpreted to mean the "Contracting Officer." For leased facilities, references to the "owner" shall be interpreted to mean the "lessor." References to the "permit holder" shall be interpreted to mean the "Contractor."

1.3.5.2 Administrative Interpretations

For ICC Codes referenced in the contract documents, the provisions of Chapter 1, "Administrator," do not apply. These administrative requirements are covered by the applicable Federal Acquisition Regulations (FAR) included in this contract and by the authority granted to the Officer in Charge of Construction to administer the construction of this project. References in the ICC Codes to sections of Chapter 1, shall be applied appropriately by the Contracting Officer as authorized by his administrative cognizance and the FAR.

1.4 DELIVERY, STORAGE, AND HANDLING

Handle, store, and protect equipment and materials to prevent damage before and during installation in accordance with the manufacturer's recommendations, and as approved by the Contracting Officer. Replace damaged or defective items.

1.5 ELECTRICAL REQUIREMENTS

Furnish motors, controllers, disconnects and contactors with their respective pieces of equipment. Motors, controllers, disconnects and contactors shall conform to and have electrical connections provided under Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Furnish internal wiring for components of packaged equipment as an integral part of the equipment. Extended voltage range motors will not be permitted. Controllers and contactors shall have a maximum of 120 volt control circuits, and shall have auxiliary contacts for use with the controls furnished. When motors and equipment furnished are larger than sizes indicated, the cost of additional electrical service and related work shall be included under the section that specified that motor or equipment. Power wiring and conduit for field installed equipment shall be provided under and conform to the requirements of Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM.

1.6 INSTRUCTION TO GOVERNMENT PERSONNEL

When specified in other sections, furnish the services of competent

instructors to give full instruction to the designated Government personnel in the adjustment, operation, and maintenance, including pertinent safety requirements, of the specified equipment or system. Instructors shall be thoroughly familiar with all parts of the installation and shall be trained in operating theory as well as practical operation and maintenance work.

Instruction shall be given during the first regular work week after the equipment or system has been accepted and turned over to the Government for regular operation. The number of man-days (8 hours per day) of instruction furnished shall be as specified in the individual section. When more than 4 man-days of instruction are specified, use approximately half of the time for classroom instruction. Use other time for instruction with the equipment or system.

When significant changes or modifications in the equipment or system are made under the terms of the contract, provide additional instruction to acquaint the operating personnel with the changes or modifications.

1.7 ACCESSIBILITY

Install all work so that parts requiring periodic inspection, operation, maintenance, and repair are readily accessible. Install concealed valves, expansion joints, controls, dampers, and equipment requiring access, in locations freely accessible through access doors.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

3.1 PAINTING OF NEW EQUIPMENT

New equipment painting shall be factory applied or shop applied, and shall be as specified herein, and provided under each individual section.

3.1.1 Factory Painting Systems

Manufacturer's standard factory painting systems may be provided subject to certification that the factory painting system applied will withstand 125 hours in a salt-spray fog test, except that equipment located outdoors shall withstand 500 hours in a salt-spray fog test. Salt-spray fog test shall be in accordance with ASTM B117, and for that test the acceptance criteria shall be as follows: immediately after completion of the test, the paint shall show no signs of blistering, wrinkling, or cracking, and no loss of adhesion; and the specimen shall show no signs of rust creepage beyond 0.125 inch on either side of the scratch mark.

The film thickness of the factory painting system applied on the equipment shall not be less than the film thickness used on the test specimen. If manufacturer's standard factory painting system is being proposed for use on surfaces subject to temperatures above 120 degrees F, the factory painting system shall be designed for the temperature service.

3.1.2 Shop Painting Systems for Metal Surfaces

Clean, pretreat, prime and paint metal surfaces; except aluminum surfaces need not be painted. Apply coatings to clean dry surfaces. Clean the surfaces to remove dust, dirt, rust, oil and grease by wire brushing and

solvent degreasing prior to application of paint, except metal surfaces subject to temperatures in excess of 120 degrees F shall be cleaned to bare metal.

Where more than one coat of paint is specified, apply the second coat after the preceding coat is thoroughly dry. Lightly sand damaged painting and retouch before applying the succeeding coat. Color of finish coat shall be aluminum or light gray.

a. Temperatures Less Than 120 Degrees F: Immediately after cleaning, the metal surfaces subject to temperatures less than 120 degrees F shall receive one coat of pretreatment primer applied to a minimum dry film thickness of 0.3 mil, one coat of primer applied to a minimum dry film thickness of 1 mil; and two coats of enamel applied to a minimum dry film thickness of 1 mil per coat.

-- End of Section --

SECTION 23 05 15

COMMON PIPING FOR HVAC
02/14

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)

AISC 325	(2011) Steel Construction Manual

AMERICAN WELDING SOCIETY (AWS)

AWS A5.8/A5.8M	(2011; Amendment 2012) Specification for Filler Metals for Brazing and Braze Welding
AWS WHB-2.9	(2004) Welding Handbook; Volume 2, Welding Processes, Part 1

ASME INTERNATIONAL (ASME)

ASME A112.19.2/CSA B45.1	(2013) Standard for Vitreous China Plumbing Fixtures and Hydraulic Requirements for Water Closets and Urinals
ASME B16.1	(2010) Gray Iron Pipe Flanges and Flanged Fittings Classes 25, 125, and 250
ASME B16.11	(2011) Forged Fittings, Socket-Welding and Threaded
ASME B16.22	(2013) Standard for Wrought Copper and Copper Alloy Solder Joint Pressure Fittings
ASME B16.25	(2012) Standard for Buttwelding Ends
ASME B16.3	(2011) Malleable Iron Threaded Fittings, Classes 150 and 300
ASME B16.39	(2009) Standard for Malleable Iron Threaded Pipe Unions; Classes 150, 250, and 300
ASME B16.4	(2011) Standard for Gray Iron Threaded Fittings; Classes 125 and 250
ASME B16.5	(2013) Pipe Flanges and Flanged Fittings: NPS 1/2 Through NPS 24 Metric/Inch Standard
ASME B16.9	(2012) Standard for Factory-Made Wrought Steel Buttwelding Fittings

ASME B31.3	(2012) Process Piping
ASME B36.10M	(2004; R 2010) Standard for Welded and Seamless Wrought Steel Pipe
ASME B40.100	(2013) Pressure Gauges and Gauge Attachments
ASME BPVC SEC IX	(2010) BPVC Section IX-Welding and Brazing Qualifications

ASTM INTERNATIONAL (ASTM)

ASTM A105/A105M	(2013) Standard Specification for Carbon Steel Forgings for Piping Applications
ASTM A126	(2004; R 2009) Standard Specification for Gray Iron Castings for Valves, Flanges, and Pipe Fittings
ASTM A197/A197M	(2000; R 2011) Standard Specification for Cupola Malleable Iron
ASTM A234/A234M	(2013; E 2014) Standard Specification for Piping Fittings of Wrought Carbon Steel and Alloy Steel for Moderate and High Temperature Service
ASTM A276	(2013a) Standard Specification for Stainless Steel Bars and Shapes
ASTM A278/A278M	(2001; R 2011) Standard Specification for Gray Iron Castings for Pressure-Containing Parts for Temperatures Up to 650 degrees F (350 degrees C)
ASTM A307	(2012) Standard Specification for Carbon Steel Bolts and Studs, 60 000 PSI Tensile Strength
ASTM A53/A53M	(2012) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A563	(2007a) Standard Specification for Carbon and Alloy Steel Nuts
ASTM A6/A6M	(2013a) Standard Specification for General Requirements for Rolled Structural Steel Bars, Plates, Shapes, and Sheet Piling
ASTM B117	(2011) Standard Practice for Operating Salt Spray (Fog) Apparatus
ASTM B32	(2008) Standard Specification for Solder Metal
ASTM B370	(2012) Standard Specification for Copper Sheet and Strip for Building Construction

ASTM B62	(2009) Standard Specification for Composition Bronze or Ounce Metal Castings
ASTM B749	(2003; R 2009) Standard Specification for Lead and Lead Alloy Strip, Sheet and Plate Products
ASTM B88	(2009) Standard Specification for Seamless Copper Water Tube
ASTM C920	(2011) Standard Specification for Elastomeric Joint Sealants
ASTM E1	(2013) Standard Specification for ASTM Liquid-in-Glass Thermometers
ASTM E84	(2013a) Standard Test Method for Surface Burning Characteristics of Building Materials
ASTM F104	(2011) Standard Classification System for Nonmetallic Gasket Materials
ASTM F2389	(2010) Standard Specification for Pressure-rated Polypropylene (PP) Piping Systems

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

MSS SP-58	(2009) Pipe Hangers and Supports - Materials, Design and Manufacture, Selection, Application, and Installation
MSS SP-67	(2011) Butterfly Valves
MSS SP-72	(2010a) Ball Valves with Flanged or Butt-Welding Ends for General Service

NSF INTERNATIONAL (NSF)

NSF/ANSI 14	(2014) Plastics Piping System Components and Related Materials

1.2 GENERAL REQUIREMENTS

Section 23 00 00 AIR SUPPLY, DISTRIBUTION, VENTILATION, AND EXHAUST SYSTEMS applies to work specified in this section

Submit Records of Existing Conditions consisting of the results of Contractor's survey of work area conditions and features of existing structures and facilities within and adjacent to the jobsite. Commencement of work constitutes acceptance of the existing conditions.

Submit Material, Equipment, and Fixture Lists for pipes, valves and specialties including manufacturer's style or catalog numbers, specification and drawing reference numbers, warranty information, and fabrication site information. Provide a complete list of construction

equipment to be used.

Submit Manufacturer's Standard Color Charts for pipes, valves and specialties showing the manufacturer's recommended color and finish selections.

Include with Listing of Product Installations for piping systems identification of at least 5 units, similar to those proposed for use, that have been in successful service for a minimum period of 5 years. Include in the list purchaser, address of installation, service organization, and date of installation.

Submit Record Drawings for pipes, valves and accessories providing current factual information including deviations and amendments to the drawings, and concealed and visible changes in the work.

Submit Connection Diagrams for pipes, valves and specialties indicating the relations and connections of devices and apparatus by showing the general physical layout of all controls, the interconnection of one system (or portion of system) with another, and internal tubing, wiring, and other devices.

1.3 SUBMITTALS

Submit the following in accordance with SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Material, Equipment, and Fixture Lists

SD-02 Shop Drawings

Record Drawings

Connection Diagrams

Installation Drawings

SD-03 Product Data

Pipe and Fittings

Piping Specialties

SD-04 Samples

Manufacturer's Standard Color Charts

SD-05 Design Data

Pipe and Fittings

Piping Specialties

SD-06 Test Reports

Hydrostatic Tests

Air Tests

Valve-Operating Tests

Drainage Tests

System Operation Tests

SD-07 Certificates

List of Qualified Permanent Service OrganizationsListing of Product Installations

Records of Existing Conditions

SD-10 Operation and Maintenance Data

Operation and Maintenance Manuals

1.4 QUALITY ASSURANCE

1.4.1 Material and Equipment Qualifications

Provide materials and equipment that are standard products of manufacturers regularly engaged in the manufacture of such products, which are of a similar material, design and workmanship. Provide standard products in satisfactory commercial or industrial use for 2 years prior to bid opening. The 2-year use includes applications of equipment and materials under similar circumstances and of similar size. Ensure the product has been for sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2 year period.

1.4.2 Alternative Qualifications

Products having less than a two-year field service record are acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturer's factory or laboratory tests, can be shown.

1.4.3 Service Support

Ensure the equipment items are supported by service organizations. Submit a certified list of qualified permanent service organizations for support of the equipment which includes their addresses and qualifications. Select service organizations that are reasonably convenient to the equipment installation and able to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

1.4.4 Manufacturer's Nameplate

Provide a nameplate on each item of equipment bearing the manufacturer's name, address, model number, and serial number securely affixed in a

conspicuous place; the nameplate of the distributing agent is not acceptable.

1.4.5 Modification of References

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "shall" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction," or words of similar meaning, to mean the Contracting Officer.

1.4.5.1 Definitions

For the International Code Council (ICC) Codes referenced in the contract documents, advisory provisions are considered mandatory, the word "should" is interpreted as "shall." Reference to the "code official" is interpreted to mean the "Contracting Officer." For Navy owned property, interpret references to the "owner" to mean the "Contracting Officer." For leased facilities, references to the "owner" is interpreted to mean the "lessor." References to the "permit holder" are interpreted to mean the "Contractor."

1.4.5.2 Administrative Interpretations

For ICC Codes referenced in the contract documents, the provisions of Chapter 1, "Administrator," do not apply. These administrative requirements are covered by the applicable Federal Acquisition Regulations (FAR) included in this contract and by the authority granted to the Officer in Charge of Construction to administer the construction of this project. References in the ICC Codes to sections of Chapter 1, are applied as appropriate by the Contracting Officer and as authorized by his administrative cognizance and the FAR.

1.5 DELIVERY, STORAGE, AND HANDLING

Handle, store, and protect equipment and materials to prevent damage before and during installation in accordance with the manufacturer's recommendations, and as approved by the Contracting Officer. Replace damaged or defective items.

1.6 ELECTRICAL REQUIREMENTS

Furnish motors, controllers, disconnects and contactors with their respective pieces of equipment. Ensure motors, controllers, disconnects and contactors conform to and have electrical connections provided under Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Furnish internal wiring for components of packaged equipment as an integral part of the equipment. Extended voltage range motors is not permitted. Provide controllers and contactors with a maximum of 120 volt control circuits, and auxiliary contacts for use with the controls furnished. When motors and equipment furnished are larger than sizes indicated, include the cost of additional electrical service and related work under the section that specified that motor or equipment. Provide power wiring and conduit for field installed equipment under and conform to the requirements of Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM.

1.7 INSTRUCTION TO GOVERNMENT PERSONNEL

When specified in other sections, furnish the services of competent instructors to give full instruction to the designated Government personnel

in the adjustment, operation, and maintenance, including pertinent safety requirements, of the specified equipment or system. Provide instructors thoroughly familiar with all parts of the installation and trained in operating theory as well as practical operation and maintenance work.

Give instruction during the first regular work week after the equipment or system has been accepted and turned over to the Government for regular operation. The number of man-days (8 hours per day) of instruction furnished is as specified in the individual section. When more than 4 man-days of instruction are specified, use approximately half of the time for classroom instruction. Use other time for instruction with the equipment or system.

When significant changes or modifications in the equipment or system are made under the terms of the contract, provide additional instruction to acquaint the operating personnel with the changes or modifications.

1.8 ACCESSIBILITY

Install all work so that parts requiring periodic inspection, operation, maintenance, and repair are readily accessible.

PART 2 PRODUCTS

2.1 PIPE AND FITTINGS

Submit equipment and performance data for pipe and fittings consisting of corrosion resistance, life expectancy, gage tolerances, and grade line analysis. Submit design analysis and calculations consisting of surface resistance, rates of flow, head losses, inlet and outlet design, required radius of bend, and pressure calculations. Also include in data pipe size, shape, and dimensions, as well as temperature ratings, vibration and thrust limitations minimum burst pressures, shut-off and non-shock pressures and weld characteristics.

2.1.1 Chilled Water Service Type BCS, Black Carbon Steel

Ensure pipe 1/8 through 12 inches is Schedule 40 black carbon steel, conforming to ASTM A53/A53M.

Ensure pipe 1/8 through 10 inches is Schedule 40 seamless conforming to ASTM A53/A53M, Type S (seamless). Grade A should be used for permissible field bending, in both cases.

Ensure fittings 2 inches and under are 150-pounds per square inch, gage (psig) working steam pressure (wsp) banded black malleable iron screwed, conforming to ASTM A197/A197M and ASME B16.3.

Ensure unions 2 inches and under are 250 pounds per square inch, wsp female, screwed, black malleable iron with brass-to-iron seat, and ground joint, conforming to ASME B16.39.

Ensure fittings 2-1/2 inches and over are Steel butt weld, conforming to ASTM A234/A234M and ASME B16.9 to match pipe wall thickness.

Ensure flanges 2-1/2 inches and over are 150-pound forged-steel conforming to ASME B16.5, welding neck to match pipe wall thickness.

2.1.2 Steam and Steam Condensate Service Type BCS-125, 125-psi Service

Ensure pipe 1/8 through 1-1/2 inches is Schedule 40 steam, Schedule 80 condensate, furnace butt weld, black carbon steel, conforming to ASTM A53/A53M, Type F (furnace butt welded, continuous welded) and ASME B36.10M.

Ensure pipe 2 through 10 inches is Schedule 40 steam, Schedule 80 condensate, seamless black carbon steel, conforming to ASTM A53/A53M Type S (seamless) and ASME B36.10M.

Ensure fittings 2 inches and under are 125-psig wsp, cast iron, screwed end, conforming to ASTM A126 Class A and ASME B16.4.

Ensure fittings 2-1/2 inches and over are wall thickness to match pipe, long radius butt weld, black carbon steel, conforming to ASTM A234/A234M, Grade WPB and ASME B16.9.

Ensure couplings 2 inches and under are commercial standard weight for Schedule 40 pipe and commercial extra heavy weight for Schedule 80 pipe, black carbon steel where threaded, and 2,000-or 3,000-psi wog forged carbon steel, conforming to ASTM A105/A105M and ASME B16.11, where welded.

Ensure flanges 2-1/2 inches and over are 150-pound, forged carbon-steel welding neck, with raised face or flat face and concentric serrated finish, conforming to ASTM A105/A105M and ASME B16.5.

2.1.3 Air Conditioning Condensate Service Type CPR, Copper

2.1.3.1 Type CPR-A, Copper Above Ground

Ensure tubing 2 inches and under is seamless copper tubing, conforming to ASTM B88, Type L (hard-drawn for all horizontal and all exposed vertical lines, annealed for concealed vertical lines).

Ensure fittings 2 inches and under are 150-psig wsp wrought-copper solder joint fittings conforming to ASME B16.22.

Ensure unions 2 inches and under are 150-psig wsp wrought-copper solder joint, conforming to ASME B16.22.

Provide brazing rod with Classification BCuP-5, conforming to AWS A5.8/A5.8M.

Use solder, alloy Sb-5, conforming to ASTM B32.

2.1.4 Polypropylene Pipe

Pipe is manufactured from a PP-R resin meeting the short-term properties and long-term strength requirements of ASTM F2389 Pipe is made in a three layer extrusion process. Piping contains a fiber layer (faser) to restrict thermal expansion. Pipe complies with the rated pressure requirements of ASTM F 2389 Ensure layers are incorporated in the pipe wall to limit thermal expansion to 2 1/4-inches per 100 F per 100-ft. If the hydronic system includes ferrous components, an oxygen barrier is required in pipe wall.

Ensure pipe is certified by NSF International as complying with NSF/ANSI 14, and ASTM F2389

Ensure pipe wrap or insulation meets the requirements of ASTM E84. Ensure the system has a Flame Spread Classification of less than 25 and Smoke Development rating of less than 50.

Where pipe is exposed to direct UV light for more than 30 days, provide a Factory applied, UV-resistant coating or alternative UV protection.

2.2 PIPING SPECIALTIES

Submit equipment and performance data for piping specialties consisting of corrosion resistance, life expectancy, gage tolerances, and grade line analysis. Submit design analysis and calculations consisting of surface resistance, rates of flow, head losses, inlet and outlet design, required radius of bend, and pressure calculations. Also include in data pipe size, shape, and dimensions, as well as temperature ratings, vibration and thrust limitations minimum burst pressures, shut-off and non-shock pressures and weld characteristics.

2.2.1 Air Vents

Provide automatic air vents on pumps, mains, and where indicated using ball-float construction. Ensure the vent inlet is not less than 3/4-inch ips and the outlet not less than 1/4-inch ips. Orifice size is 1/8 inch. Provide corrosion-resistant steel trim conforming to ASTM A276. Ensure vent discharges air at any pressure up to 150 psi. Ensure outlet is copper tube routed.

2.2.2 Dielectric Connections

Electrically insulate dissimlar pipe metals from each other by couplings, unions, or flanges commercially manufactured for that purpose and rated for the service pressure and temperature.

2.2.3 Pressure Gages

Ensure pressure gages conform to ASME B40.100 and to requirements specified herein. Pressure-gage size is 3-1/2 inches nominal diameter. Ensure case is corrosion-resistant steel, conforming to any of the AISI 300 series of ASTM A6/A6M, with an ASM No. 4 standard commercial polish or better. Equip gages with adjustable red marking pointer and damper-screw adjustment in inlet connection. Align service-pressure reading at midpoint of gage range. Ensure all gages are Grade B or better and be equipped with gage isolators.

Fit steam gages with black steel syphons and steam service pressure-rated gage cocks or valves.

2.2.4 Sight-Flow Indicators

Construct sight-flow indicators for pressure service on 3-inch ips and smaller of bronze with specially treated single- or double-glass sight windows and have a bronze, nylon, or tetrafluoroethylene rotating flow indicator mounted on an AISI Type 304 corrosion-resistant steel shaft. Body may have screwed or flanged end. Provide pressure- and temperature-rated assembly for the applied service. Flapper flow-type indicators are not acceptable.

2.2.5 Sleeve Couplings

Sleeve couplings for plain-end pipe consist of one steel middle ring, two steel followers, two chloroprene or Buna-N elastomer gaskets, and the necessary steel bolts and nuts.

2.2.6 Thermometers

Ensure thermometers conform to ASTM E1, except for being filled with a red organic liquid. Provide an industrial pattern armored glass thermometer, (well-threaded and seal-welded). Ensure thermometers installed 6 feet or higher above the floor have an adjustable angle body. Ensure scale is not less than 7 inches long and the case face is manufactured from manufacturer's standard polished aluminum or AISI 300 series polished corrosion-resistant steel. Thermometer range is 0 to 300 degrees F. Provide thermometers with nonferrous separable wells. Provide lagging extension to accommodate insulation thickness.

2.2.7 Line Strainers, Water Service

Install Y-type strainers with removable basket. Ensure strainers in sizes 2-inch ips and smaller have screwed ends; in sizes 2-1/2-inch ipsand larger, strainers have flanged ends. Ensure body working-pressure rating exceeds maximum service pressure of installed system by at least 50 percent. Ensure body has cast-in arrows to indicate direction of flow. Ensure all strainer bodies fitted with screwed screen retainers have straight threads and gasketed with nonferrous metal. For strainer bodies 2-1/2-inches and larger, fitted with bolted-on screen retainers, provide offset blowdown holes. Fit all strainers larger than 2-1/2-inches with manufacturer's standard ball-type blowdown valve. Ensure body material is cast iron conforming to Class 30 ASTM A278/A278M. Where system material is nonferrous, use nonferrous metal for the metal strainer body material.

Ensure minimum free-hole area of strainer element is equal to not less than 3.4 times the internal area of connecting piping. Strainer screens perforation size is not to exceed 0.045-inch. Ensure strainer screens have finished ends fitted to machined screen chamber surfaces to preclude bypass flow. Strainer element material is AISI Type 304 corrosion-resistant steel.

2.2.8 Line Strainers, Steam Service

Install Type Y strainers with removable strainer element.

Use flanged body end connections for all valves larger than 2 inches, unless butt weld ends are specified. Use screwed weld for sizes 2 inches and under to suit specified piping system end connection and maintenance requirements or be welded.

Body working steam pressure rating is the same as the primary valve rating for system in which strainer is installed, except where welded end materials requirements result in higher pressure ratings. Ensure body has integral cast or forged arrows to indicate direction of flow. Provide strainer bodies with blowdown valves that have discharge end plugged with a solid metal plug. Make closure assembly with tetrafluoroethylene tape. Ensure bodies fitted with bolted-on screen retainers have offset blowdown holes.

Body materials are cast iron conforming to ASTM A126, Class B, for service pressures 125-psi wsp and less.

Ensure minimum free-hole area of strainer element is equal to not less than 3.4 times the internal area of connecting piping. Strainer screens perforation size is not to exceed 0.020 inch or equivalent wire mesh. Strainer screens have finished ends fitted to machined screen chamber surfaces to preclude bypass flow. Strainer element material is AISI Type 304 corrosion-resistant steel and fitted with backup screens where necessary to prevent collapse.

2.3 VALVES

2.3.1 Ball and Butterfly Valves

Ensure ball valves conform to MSS SP-72 for Figure 1A, 1 piece body 1B, vertically split body 1C, top entry 1D, three piece body and are rated for service at not less than 175 psig at 200 degrees F. For valve bodies in sizes 2 inches and smaller, use screwed-end connection-type constructed of Class A copper alloy. For valve bodies in sizes 2-1/2 inches and larger, use flanged-end connection type, constructed of Class D material. Balls and stems of valves 2 inches and smaller are manufacturer's standard with hard chrome plating finish. Balls and stems of valves 2-1/2 inches and larger are manufacturer's standard Class C corrosion-resistant steel alloy with hard chrome plating. Balls of valves 6 inches and larger may be Class D with 900 Brinell hard chrome plating. Ensure valves are suitable for flow from either direction and seal equally tight in either direction. Valves with ball seals held in place by spring washers are not acceptable. Ensure all valves have adjustable packing glands. Seats and seals are fabricated from tetrafluoroethylene.

Ensure butterfly valves conform to MSS SP-67and are the wafer type for mounting between specified flanges. Ensure valves are rated for 150-psig shutoff and nonshock working pressure. Select bodies of cast ferrous metal conforming to ASTM A126, Class B, and to ASME B16.1 for body wall thickness. Seats and seals are fabricated from resilient elastomer designed for field removal and replacement.

2.3.2 Drain, Vent, and Gage Cocks

Provide T-head drain, vent, and gage cocks, ground key type, with washer and screw, constructed of polished ASTM B62 bronze, and rated 125-psi wsp. Ensure end connections are rated for specified service pressure.

Ensure pump vent cocks, and where spray control is required, are UL umbrella-hood type, constructed of manufacturer's standard polished brass. Ensure cocks are 1/2-inch ips male, end threaded, and rated at not less than 125 psi at 225 degrees F.

2.3.3 Standard Check Valves (SCV)

Ensure standard check valves in sizes 2 inches and smaller are 125-psi swing check valves except as otherwise specified. Provide lift checks where indicated. Ensure swing-check pins are nonferrous and suitably hard for the service. Select composition type discs. Ensure the swing-check angle of closure is manufacturer's standard unless a specific angle is needed.

Use cast iron, bronze trim, swing type check valves in sizes 2-1/2 inches and larger. Ensure valve bodies are cast iron, conforming to ASTM A126, Class A and valve ends are flanged in conformance with ASME B16.1.

Swing-check pin is AISI Type or approved equal corrosion-resistant steel. Angle of closure is manufacturer's standard unless a specific angle is needed. Ensure valves have bolted and gasketed covers.

Provide check valves with lever-weighted, positive-closure devices and valve ends are flanged.

2.4 MISCELLANEOUS MATERIALS

2.4.1 Bolting

Ensure flange and general purpose bolting is hex-head and conforms to ASTM A307, Grade B (bolts, for flanged joints in piping systems where one or both flanges are cast iron). Heavy hex-nuts conform to ASTM A563. Square-head bolts and nuts are not acceptable. Ensure threads are coarse-thread series.

2.4.2 Elastomer Caulk

Use two-component polysulfide- or polyurethane-base elastomer caulking material, conforming to ASTM C920.

2.4.3 Escutcheons

Manufacture escutcheons from nonferrous metals and chrome-plated except when AISI 300 series corrosion-resistant steel is provided. Ensure metals and finish conforms to ASME A112.19.2/CSA B45.1.

Use one-piece escutcheons where mounted on chrome-plated pipe or tubing, and one-piece of split-pattern type elsewhere. Ensure all escutcheons have provisions consisting of setscrews for maintaining a fixed position against a surface.

2.4.4 Flashing

Ensure sheetlead conforms to ASTM B749, UNS Alloy Number L50049 (intended for use in laboratories and shops in general application) .

Ensure sheet copper conforms to ASTM B370 and be not less than 16 ounces per square foot weight.

2.4.5 Flange Gaskets

Provide compressed non-asbestos sheets, conforming to ASTM F104, coated on both sides with graphite or similar lubricant, with nitrile composition, binder rated to 750 degrees F.

2.5 SUPPORTING ELEMENTS

Provide all necessary piping systems and equipment supporting elements, including but not limited to: building structure attachments; supplementary steel; hanger rods, stanchions, and fixtures; vertical pipe attachments; horizontal pipe attachments; anchors; guides; and spring-cushion, variable, or constant supports. Ensure supporting elements are suitable for stresses imposed by systems pressures and temperatures and natural and other external forces normal to this facility without damage to supporting element system or to work being supported.

Ensure supporting elements conform to requirements of ASME B31.3, and

MSS SP-58, except as noted.

Ensure attachments welded to pipe are made of materials identical to that of pipe or materials accepted as permissible raw materials by referenced code or standard specification.

Ensure supporting elements exposed to weather are hot-dip galvanized or stainless steel. Select materials of such a nature that their apparent and latent-strength characteristics are not reduced due to galvanizing process. Electroplate supporting elements in contact with copper tubing with copper.

Type designations specified herein are based on MSS SP-58. Provide support elements, except for supplementary steel, that are cataloged, load rated, commercially manufactured products.

2.5.1 Building Structure Attachments

2.5.1.1 Beam Clamps

Ensure beam clamps are center-loading MSS SP-58 Type 21.

When it is not possible to use center-loading beam clamps, eccentric-loading beam clamps, MSS SP-58 Type 19 may be used for piping sizes 2 inches and less and for piping sizes 2 through 10 inches provided two counterbalancing clamps are used per point of pipe support. Where more than one rod is used per point of pipe support, determine rod diameter in accordance with referenced standards.

2.5.1.2 C-Clamps

Do not use C-clamps.

2.5.2 Horizontal Pipe Attachments

2.5.2.1 Single Pipes

Support piping in sizes to and including 2-inch ips by MSS SP-58 Type 6 solid malleable iron pipe rings, except that, use split-band-type rings in sizes up to 1-inch ips.

Support piping in sizes through 8-inch ips inclusive by MSS SP-58 Type 1 attachments.

Use MSS SP-58 Type 1 and Type 6 assemblies on vapor-sealed insulated piping and have an inside diameter larger than pipe being supported to provide adequate clearance during pipe movement.

Where thermal movement of a point in a piping system 4 inches and larger would cause a hanger rod to deflect more than 4 degrees from the vertical or where a horizontal point movement exceeds 1/2 inch, use MSS SP-58 Type 44 through 46 pipe rolls.

Support piping in sizes larger than 8-inch ips with MSS SP-58 Type 44 through 46 pipe rolls.

Use MSS SP-58 Type 40 shields on all insulated piping. Ensure area of the supporting surface is such that compression deformation of insulated surfaces does not occur. Roll away longitudinal and transverse shield

edges from the insulation.

Provide insulated piping without vapor barrier on roll supports with MSS SP-58 Type 39 saddles.

2.5.2.2 Parallel Pipes

Use trapeze hangers fabricated from structural steel shapes, with U-bolts, in congested areas and where multiple pipe runs occur. Ensure structural steel shapes conform to supplementary steel requirements.

2.5.3 Vertical Pipe Attachments

Ensure vertical pipe attachments are MSS SP-58 Type 8.

Include complete fabrication and attachment details of any spring supports in shop drawings.

2.5.4 Hanger Rods and Fixtures

Use only circular cross section rod hangers to connect building structure attachments to pipe support devices. Use pipe, straps, or bars of equivalent strength for hangers only where approved by the Contracting Officer.

Provide turnbuckles, swing eyes, and clevises as required by support system to accommodate temperature change, pipe accessibility, and adjustment for load and pitch. Rod couplings are not acceptable.

2.5.5 Supplementary Steel

Where it is necessary to frame structural members between existing members or where structural members are used in lieu of commercially rated supports, design and fabricate such supplementary steel in accordance with AISC 325.

PART 3 EXECUTION

3.1 PIPE INSTALLATION

Submit certificates for pipes, valves and specialties showing conformance with test requirements as contained in the reference standards contained in this section.

Provide test reports for Hydrostatic Tests, Air Tests, Valve-Operating Tests, Drainage Tests, and System Operation Tests, in compliance with referenced standards contained within this section.

Fabricate and install piping systems in accordance with ASME B31.3, MSS SP-58, and AWS WHB-2.9.

Submit Installation Drawings for pipes, valves and specialties. Drawings include the manufacturer's design and construction calculations, forces required to obtain rated axial, lateral, or angular movements, installation criteria, anchor and guide requirements for equipment, and equipment room layout and design. Ensure drawings specifically advise on procedures to be followed and provisions required to protect expansion joints during specified hydrostatic testing operations.

Ensure connections between steel piping and copper piping are electrically isolated from each other with dielectric couplings (or unions) rated for the service.

Make final connections to equipment with unions provided every 100 feet of straight run. Provide unions in the line downstream of screwed- and welded-end valves.

Ream all pipe ends before joint connections are made.

Make screwed joints with specified joint compound with not more than three threads showing after joint is made up.

Apply joint compounds to the male thread only and exercise care to prevent compound from reaching the unthreaded interior of the pipe.

Provide screwed unions, welded unions, or bolted flanges wherever required to permit convenient removal of equipment, valves, and piping accessories from the piping system for maintenance.

Securely support piping systems with due allowance for thrust forces, thermal expansion and contraction. Do not subject the system to mechanical, chemical, vibrational or other damage as specified in ASME B31.3.

Ensure field welded joints conform to the requirements of the AWS WHB-2.9, ASME B31.3, and ASME BPVC SEC IX.

Make piping systems butt weld joints with backing rings. Use compatible backing ring materials with materials being joined. Ensure joint configuration conforms to ASME B16.25.

For polyropylene pipe, make fusion-weld joints in accordance with the pipe and fitting manufacturer's specifications and product standards. Use fusion-weld tooling, welding machines, and electrofusion devices specified by the pipe and fittings manufacturer. Prior to joining, prepare the pipe and fittings in accordance with ASTM F2389 and the manufacturer's specifications. Ensure joint preparation, setting and alignment, fusion process, cooling times and working pressure are in accordance with the pipe and fitting manufacturer's specifications.

Accomplish preheat and postheat treatment of welds in accordance with ASME BPVC SEC IX and ASME B31.3.

3.2 VALVES

Provide valves in piping mains and all branches and at equipment where indicated and as specified.

Provide valves to permit isolation of branch piping and each equipment item from the balance of the system.

Provide riser and downcomer drains above piping shutoff valves in piping 2-1/2 inches and larger. Tap and fit shutoff valve body with a 1/2-inch plugged globe valve.

Provide valves unavoidably located in furred or other normally inaccessible places with access panels adequately sized for the location and located so that concealed items may be serviced, maintained, or replaced.

3.3 SUPPORTING ELEMENTS INSTALLATION

Provide supporting elements in accordance with the referenced codes and standards.

Support piping from building structure. Do not support piping from roof deck or from other pipe.

Run piping parallel with the lines of the building. Space and install piping and components so that a threaded pipe fitting may be removed between adjacent pipes and so that there is no less than 1/2 inch of clear space between the finished surface and other work and between the finished surface of parallel adjacent piping. Arrange hangars on different adjacent service lines running parallel with each other in line with each other and parallel to the lines of the building.

Install piping support elements at intervals specified hereinafter, at locations not more than 3 feet from the ends of each runout, and not over 1 foot from each change in direction of piping.

Base load rating for all pipe-hanger supports on insulated weight of lines filled with water and forces imposed. Deflection per span is not exceed slope gradient of pipe. Ensure supports are in accordance with the following minimum rod size and maximum allowable hanger spacing for specified pipe. For concentrated loads such as valves, reduce the allowable span proportionately:

PIPE SIZE INCHES	ROD SIZE INCHES	STEEL PIPE FEET	COPPER PIPE FEET
1 and smaller	3/8	8	6
1-1/4 to 1-1/2	3/8	10	8
2	3/8	10	8
2-1/2 to 3-1/2	1/2	12	12
4 to 5	5/8	16	14
6	3/4	16	16
8 to 12	7/8	20	20
14 to 18	1	20	20
20 and over	1-1/4	20	20

Provide vibration isolation supports where needed. Refer to Section 23 05 48.00 40 VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT where A/C equipment and piping is installed.

Support vertical risers independently of connected horizontal piping, whenever practicable, with fixed or spring supports at the base and at intervals to accommodate system range of thermal conditions. Ensure risers have guides for lateral stability. For risers subject to expansion, provide only one rigid support at a point approximately one-third down from the top. Place clamps under fittings unless otherwise specified. Support carbon-steel pipe at each floor and at not more than 15-foot intervals for

pipe 2 inches and smaller and at not more than 20-foot intervals for pipe 2-1/2 inches and larger.

3.4 OPERATION AND MAINTENANCE

Provide Operation and Maintenance Manuals consistent with manufacturer's standard brochures, schematics, printed instructions, general operating procedures and safety precautions. Submit test data that is clear and readily legible.

3.5 PAINTING OF NEW EQUIPMENT

Factory or shop apply new equipment painting, as specified herein, and provided under each individual section.

3.5.1 Factory Painting Systems

Manufacturer's standard factory painting systems may be provided subject to certification that the factory painting system applied withstands 125 hours in a salt-spray fog test, except that equipment located outdoors withstand 500 hours in a salt-spray fog test. Conduct salt-spray fog test is in accordance with ASTM B117, and for that test the acceptance criteria is as follows: immediately after completion of the test, the inspected paint shows no signs of blistering, wrinkling, or cracking, and no loss of adhesion; and the specimen shows no signs of rust creepage beyond 0.125 inch on either side of the scratch mark.

Ensure the film thickness of the factory painting system applied on the equipment is not less than the film thickness used on the test specimen. If manufacturer's standard factory painting system is being proposed for use on surfaces subject to temperatures above 120 degrees F, design the factory painting system for the temperature service.

3.5.2 Shop Painting Systems for Metal Surfaces

Clean, pretreat, prime and paint metal surfaces; except aluminum surfaces need not be painted. Apply coatings to clean dry surfaces. Clean the surfaces to remove dust, dirt, rust, oil and grease by wire brushing and solvent degreasing prior to application of paint, except clean to bare metal, surfaces subject to temperatures in excess of 120 degrees F.

Where more than one coat of paint is specified, apply the second coat after the preceding coat is thoroughly dry. Lightly sand damaged painting and retouch before applying the succeeding coat. Selected color of finish coat is aluminum or light gray.

a. Temperatures Less Than 120 Degrees F: Immediately after cleaning, the metal surfaces subject to temperatures less than 120 degrees F receives one coat of pretreatment primer applied to a minimum dry film thickness of 0.3 mil, one coat of primer applied to a minimum dry film thickness of one mil; and two coats of enamel applied to a minimum dry film thickness of one mil per coat.

b. Temperatures Between 120 and 400 Degrees F: Metal surfaces subject to temperatures between 120 and 400 degrees F Receives two coats of 400 degrees F heat-resisting enamel applied to a total minimum thickness of 2 mils.

-- End of Section --

SECTION 23 05 48.00 40

VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT
02/11

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ACOUSTICAL SOCIETY OF AMERICA (ASA)

ASA S2.71	(1983; R 2006) Guide to the Evaluation of Human Exposure to Vibration in Buildings

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE HVAC APP IP HDBK	(2011) HVAC Applications Handbook, I-P Edition

NATIONAL ENVIRONMENTAL BALANCING BUREAU (NEBB)

NEBB PROCEDURAL STANDARDS	(2005) Procedural Standards for TAB (Testing, Adjusting and Balancing) Environmental Systems

1.2 ADMINISTRATIVE REQUIREMENTS

Section 23 00 00 AIR SUPPLY, DISTRIBUTION, VENTILATION, AND EXHAUST SYSTEMS applies to work specified in this section to the extent applicable.

Section 23 05 15 COMMON PIPING FOR HVAC applies to work specified in this section to the extent applicable.

Ensure all vibration-control apparatus is the product of a single manufacturing source, where possible. Human exposure levels should be considered using ASA S2.71 and NEBB PROCEDURAL STANDARDS.

Scheduled isolation mounting is in inches and is a minimum static deflection.

Spans referred to in Part 2, "Vibration-Isolation Systems Application," means longest bay dimension.

Determine exact mounting sizes and number of isolators by the isolator manufacturer based on equipment that will be installed. Check equipment revolutions per minute (rpm) and spring deflections to verify that resonance cannot occur.

Within ten working days of Contract Award, submit equipment and performance data for vibration isolator systems including equipment base design; inertia-block mass relative to support equipment weight; spring loads and free, operating, and solid heights of spring; spring diameters; nonmetallic isolator loading and deflection; disturbing frequency; natural

frequency of mounts; deflection of working member; and anticipated amount of physical movement at the reference points.

1.3 SUBMITTALS

Submit the following in accordance with SUBMITTAL PROCEDURES:

SD-03 Product Data

Equipment and Performance Data

Isolators

PART 2 PRODUCTS

2.1 TYPE OF VIBRATION-ISOLATION PROVISIONS

Design for vibration isolation using ASHRAE HVAC APP IP HDBK, Chapter 48, as applicable to the following sections.

2.1.1 Materials

Ensure rubber is natural rubber and elastomer is chloroprene. Shore A durometer measurement of both materials and range between 40 and 60.

Inorganic materials such as precompressed, high-density, fibrous glass encased in a resilient moisture-impervious membrane may be used in lieu of specified natural rubber and elastomers. Where this substitution is made, ensure specified deflections are modified by the manufacturing source to accommodate physical characteristics of inorganic materials and to provide equal or better vibration isolation.

Ensure weather-exposed metal vibration-isolator parts are corrosion protected. Chloroprene coat springs.

2.1.2 Mountings

Provide the following mountings:

Type B: Double rubber-in-shear with molded-in steel reinforcement in top and bottom. Maximum deflections up to 0.50 inch are allowed.

Type C: Free-standing laterally stable open-spring type for deflections over 0.50 inch, with built-in bearing and leveling provisions, 0.25-inch thick Type A base elastomer pads, and accessories. Ensure outside diameter of each spring is equal to or greater than 0.9 times the operating height of the spring under rated load.

2.1.3 Bases

Provide the following bases:

Type U: Unit isolators without rails, structural-steel bases, or inertia blocks.

Configure rectangular inertia bases to accommodate equipment supported.

Ensure minimum thickness of inertia base, in addition to providing

suitable mass, is sufficient to provide stiffness to maintain equipment manufacturer's recommended alignment and duty efficiency of power-transmission components, and is sufficient to result in base deflection at midpoint of unsupported span of not more than 1/1,440th of the span between isolators. Verify minimum thickness, the preceding requirements not withstanding, is 8 percent of the longest base dimension.

2.2 VIBRATION-ISOLATION SYSTEMS APPLICATION

Vibration isolation design per ASHRAE HVAC APP IP HDBK, Chapter 37.

2.2.1 Low-Pressure AHU Locations

Vibration-isolation provisions apply to floor-mounted Air Moving and Conditioning Association Class A packaged central-station units.

TYPE EQUIPMENT	BASEMENT BELOW-GRADE PROVISIONS*	ON\ABOVE GRADE 20-FOOT FLOOR-SPAN PROVISIONS*	ON\ABOVE GRADE 30-FOOT FLOOR-SPAN PROVISIONS*	ON\ABOVE GRADE 40-FOOT FLOOR-SPAN PROVISIONS*
Through 5 hp	B-U-0.35	C-U-1.0	C-U-1.0	C-U-1.0
7-1/2 hp and over 250 to 500 rpm	B-U-0.35	C-U-1.75	C-U-1.75	C-U-1.75
500 rpm	B-U-0.35	C-U-1.0	C-U-1.5	

*TYPE OF MOUNTING, BASE, AND MINIMUM DEFLECTION IN INCHES

2.3 PIPE AND DUCT VIBRATION ISOLATION

Type G: Provide isolators with in-series contained steel springs and preformed fibrous-glass or chloroprene-elastomer elements for connecting to building-structure attachments. Load devices by supported system during operating conditions to produce a minimum spring and elastomer static deflection of 1 inch and 3/8 inch, respectively.

Type H: Provide isolators with contained chloroprene-elastomer elements for connecting to building-structure attachments. Load devices by supported system during operating conditions to produce a minimum elastomer static deflection of 3/8 inch.

Type J: Provide isolators with elastomers mounted on floor-supported columns or directly on the floor. Load devices by supported system during operating conditions to produce a minimum elastomer static deflection of 3/8 inch.

PART 3 EXECUTION

3.1 INSTALLATION

Install equipment in accordance with manufacturer's recommendations.

-- End of Section --

SECTION 23 05 48

VIBRATION AND SEISMIC CONTROLS FOR HVAC PIPING AND EQUIPMENT
08/08

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ACOUSTICAL SOCIETY OF AMERICA (ASA)

ASA S2.71	(1983; R 2006) Guide to the Evaluation of Human Exposure to Vibration in Buildings

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE HVAC APP IP HDBK	(2007) HVAC Applications Handbook, I-P Edition

NATIONAL ENVIRONMENTAL BALANCING BUREAU (NEBB)

NEBB PROCEDURAL STANDARDS	(2005) Procedural Standards for TAB (Testing, Adjusting and Balancing) Environmental Systems

1.2 GENERAL REQUIREMENTS

Section 23 00 00 AIR SUPPLY, DISTRIBUTION, VENTILATION, AND EXHAUST SYSTEMS applies to work specified in this section to the extent applicable.

Section 23 05 15 COMMON PIPING FOR HVAC applies to work specified in this section to the extent applicable.

All vibration-control apparatus must be the product of a single manufacturing source, where possible. Human exposure levels should be considered using ASA S2.71 and NEBB PROCEDURAL STANDARDS.

Scheduled isolation mounting is in inches and is a minimum static deflection.

Spans referred to in Part 2, "Vibration-Isolation Systems Application," must mean longest bay dimension.

Determine exact mounting sizes and number of isolators by the isolator manufacturer based on equipment that will be installed. Check equipment revolutions per minute (rpm) and spring deflections to verify that resonance cannot occur.

Equipment and Performance Data for vibration isolator systems must include equipment base design; inertia-block mass relative to support equipment weight; spring loads and free, operating, and solid heights of spring; spring diameters; nonmetallic isolator loading and deflection; disturbing frequency; natural frequency of mounts; deflection of working member; and

anticipated amount of physical movement at the reference points.

1.3 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Submit Equipment and Performance Data in accordance with paragraph entitled, "General Requirements," of this section.

Submit Manufacturer's catalog data for the following items:

Mountings
Bases
Isolators

PART 2 PRODUCTS

2.1 TYPE OF VIBRATION-ISOLATION PROVISIONS

Design for vibration isolation using ASHRAE HVAC APP IP HDBK, Chapter 37, as applicable to the following sections.

2.1.1 Materials

Rubber must be natural rubber. Elastomer must be chloroprene. Shore A durometer measurement of both materials and range between 40 and 60.

Inorganic materials such as precompressed, high-density, fibrous glass encased in a resilient moisture-impervious membrane may be used in lieu of specified natural rubber and elastomers. Where this substitution is made, specified deflections must be modified by the manufacturing source to accommodate physical characteristics of inorganic materials and to provide equal or better vibration isolation.

Weather-exposed metal vibration-isolator parts must be corrosion protected. Chloroprene coat springs.

2.1.2 Mountings

Mountings must be:

Type B: Double elastomer-in-shear with molded-in steel reinforcement in top and bottom. Maximum deflections up to 0.50 inch are allowed.

Type C: Free-standing laterally stable open-spring type for deflections over 0.50 inch, with built-in bearing and leveling provisions, 0.25-inch thick Type A base elastomer pads, and accessories. Outside diameter of each spring must be equal to or greater than 0.9 times the operating height of the spring under rated load.

2.1.3 Bases

Bases must be:

Type U: Unit isolators without rails, structural-steel bases, or

inertia blocks.

Configuration of inertia bases must be rectangular to accommodate equipment supported.

Minimum thickness of inertia base, in addition to providing suitable mass, must be sufficient to provide stiffness to maintain equipment manufacturer's recommended alignment and duty efficiency of power-transmission components. Minimum thickness must be sufficient to result in base deflection at midpoint of unsupported span of not more than 1/1,440th of the span between isolators. Minimum thickness, the preceding requirements not withstanding, must be 8 percent of the longest base dimension.

2.2 VIBRATION-ISOLATION SYSTEMS APPLICATION

Vibration isolation design per ASHRAE HVAC APP IP HDBK, Chapter 37.

2.2.1 Low-Pressure AHU Locations

Vibration-isolation provisions apply to floor-mounted Air Moving and Conditioning Association Class A packaged central-station units.

TYPE EQUIPMENT	BASEMENT BELOW-GRADE PROVISIONS*	ON GRADE 20-FOOT FLOOR-SPAN PROVISIONS*	ON GRADE 30-FOOT FLOOR-SPAN PROVISIONS*	ON GRADE 40-FOOT FLOOR-SPAN PROVISIONS*
Through 5 hp	B-U-0.35	C-U-1.0	C-U-1.0	C-U-1.0
7-1/2 hp and over 250 to 500 rpm	B-U-0.35	C-U-1.75	C-U-1.75	C-U-1.75
500 rpm	B-U-0.35	C-U-1.0	C-U-1.5	

*TYPE OF MOUNTING, BASE, AND MINIMUM DEFLECTION IN INCHES

2.3 PIPE AND DUCT VIBRATION ISOLATION

Type G: Isolators must be devices with in-series contained steel springs and preformed fibrous-glass or chloroprene-elastomer elements for connecting to building-structure attachments. Load devices by supported system during operating conditions to produce a minimum spring and elastomer static deflection of 1 inch and 3/8 inch, respectively.

Type H: Isolators must be devices with contained chloroprene-elastomer elements for connecting to building-structure attachments. Load devices by supported system during operating conditions to produce a minimum elastomer static deflection of 3/8 inch.

Type J: Isolators must be devices with elastomers mounted on floor-supported columns or directly on the floor. Load devices by supported system during operating conditions to produce a minimum elastomer static deflection of 3/8 inch.

PART 3 EXECUTION

3.1 INSTALLATION

Install equipment in accordance with manufacturer's recommendations.

3.2 TESTS AND REPORTS

Not Used.

-- End of Section --

SECTION 23 05 93

TESTING, ADJUSTING, AND BALANCING FOR HVAC
08/09

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ACOUSTICAL SOCIETY OF AMERICA (ASA)

ASA S1.11	(2004; Errata 2005; R 2009) Specification for Octave- Band and Fractional-Octave-Band Analog and Digital Filters (ASA 65)
ASA S1.4	(1983; Amendment 1985; R 2006) Specification for Sound Level Meters (ASA 47)

AIR MOVEMENT AND CONTROL ASSOCIATION INTERNATIONAL (AMCA)

AMCA 203	(1990; R 2011) Field Performance Measurements of Fan Systems

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE HVAC APP IP HDBK	(2011) HVAC Applications Handbook, I-P Edition

ASSOCIATED AIR BALANCE COUNCIL (AABC)

AABC MN-1	(2002; 6th ed) National Standards for Total System Balance
AABC MN-4	(1996) Test and Balance Procedures

NATIONAL ENVIRONMENTAL BALANCING BUREAU (NEBB)

NEBB MASV	(2006) Procedural Standards for Measurements and Assessment of Sound and Vibration
NEBB PROCEDURAL STANDARDS	(2005) Procedural Standards for TAB (Testing, Adjusting and Balancing) Environmental Systems

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

SMACNA 1780	(2002) HVAC Systems - Testing, Adjusting and Balancing, 3rd Edition

SMACNA 1858	(2004) HVAC Sound And Vibration Manual - First Edition
SMACNA 1972 CD	(2012) HVAC Air Duct Leakage Test Manual - 2nd Edition

1.2 DEFINITIONS

a. AABC: Associated Air Balance Council.

b. COTR: Contracting Officer's Technical Representative.

c. DALT: Duct air leakage test

d. DALT'd: Duct air leakage tested

e. HVAC: Heating, ventilating, and air conditioning; or heating, ventilating, and cooling.

f. NEBB: National Environmental Balancing Bureau

g. Out-of-tolerance data: Pertains only to field acceptance testing of Final DALT or TAB report. When applied to DALT work, this phase means "a leakage rate measured during DALT field acceptance testing which exceeds the leakage raete allowed by SMACNA Leak Test manual for an indicated duct construction and sealant class." "a leakage rate measured during DALT field acceptance testing which exceeds the leakage rate allwed by Appendix D REQUIREMENTS FOR DUCT AIR LEAK TESTING." When applied to TAB work this phase means "a measurement taken during TAB field acceptance testing which does not fall within the range of plus 5 to minus 5 percent of the original measurement reported on the TAB Report for a specific parameter."

h. Season of maximum heating load: The time of year when the outdoor temperature at the project site remains within plus or minus 30 degrees Fahrenheit of the project site's winter outdoor design temperature, throughout the period of TAB data recording.

i. Season of maximum cooling load: The time of year when the outdoor temperature at the project site remains within plus or minus 5 degrees Fahrenheit of the project site's summer outdoor design temperature, throughout the period of TAB data recording.

j. Season 1, Season 2: Depending upon when the project HVAC is completed and ready for TAB, Season 1 is defined, thereby defining Season 2. Season 1 could be the season of maximum heating load, or the season of maximum cooling load.

k. Sound measurements terminology: Defined in AABC MN-1, NEBB MASV, or SMACNA 1858 (TABB).

l. TAB: Testing, adjusting, and balancing (of HVAC systems).

m. TAB'd: HVAC Testing/Adjusting/Balancing procedures performed.

n. TAB Agency: TAB Firm

o. TAB team field leader: TAB team field leader

p. TAB team supervisor: TAB team engineer.

q. TAB team technicians: TAB team assistants.

r. TABB: Testing Adjusting and Balancing Bureau.

1.2.1 Similar Terms

In some instances, terminology differs between the Contract and the TAB Standard primarily because the intent of this Section is to use the industry standards specified, along with additional requirements listed herein to produce optimal results.

The following table of similar terms is provided for clarification only. Contract requirements take precedent over the corresponding AABC, NEBB, or TABB requirements where differences exist.

SIMILAR TERMS			
Contract Term	AABC Term	NEBB Term	TABB Term
TAB Standard	National Standards for Testing and Balancing Heating, Ventilating, and Air Conditioning Systems	Procedural Standards for Testing, Adjusting and Balancing of Environmental Systems	International Standards for Environmental Systems Balance
TAB Specialist	TAB Engineer	TAB Supervisor	TAB Supervisor
Systems Readiness Check	Construction Phase Inspection	Field Readiness Check & Preliminary Field Procedures	Field Readiness Check & Prelim. Field Procedures

1.3 WORK DESCRIPTION

The work includes duct air leakage testing (DALT) and testing, adjusting, and balancing (TAB) of new heating, ventilating, and cooling (HVAC) air and water distribution systems including ducts, and piping which are located within, on, under, between, and adjacent to buildings.

Perform TAB in accordance with the requirements of the TAB procedural standard recommended by the TAB trade association that approved the TAB Firm's qualifications. Comply with requirements of AABC MN-1, NEBB PROCEDURAL STANDARDS, or SMACNA 1780 (TABB) as supplemented and modified by this specification section. All recommendations and suggested practices contained in the TAB procedural standards are considered mandatory.

Conduct DALT and TAB of the indicated existing systems and equipment and submit the specified DALT and TAB reports for approval. Conduct DALT testing in compliance with the requirements specified in SMACNA 1972 CD,

except as supplemented and modified by this section. Conduct DALT and TAB work in accordance with the requirements of this section.

1.3.1 Air Distribution Systems

Test, adjust, and balance systems (TAB) in compliance with this section. Obtain Contracting Officer's written approval before applying insulation to exterior of air distribution systems as specified under Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS.

1.3.2 Water Distribution Systems

TAB systems in compliance with this section. Obtain Contracting Officer's written approval before applying insulation to water distribution systems as specified under Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS. At Contractor's option and with Contracting Officer's written approval, the piping systems may be insulated before systems are TAB'd.

Terminate piping insulation immediately adjacent to each flow control valve, automatic control valve, or device. Seal the ends of pipe insulation and the space between ends of pipe insulation and piping, with waterproof vapor barrier coating.

After completion of work under this section, insulate the flow control valves and devices as specified under Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS.

1.4 SUBMITTALS

Submit the following in accordance with SUBMITTAL PROCEDURES:

SD-07 Certificates

Independent TAB agency and personnel qualifications

Advance notice of Pre-Final DALT field work

Completed Pre-Final DALT Work Checklist

Advance Notice of Season 1 TAB Field Work

Completed Season 1 Pre-TAB Work Checklist

Advance Notice of Season 2 TAB Field Work

Completed Season 2 Pre-TAB Work Checklist

1.5 QUALITY ASSURANCE

1.5.1 Independent TAB Agency and Personnel Qualifications

To secure approval for the proposed agency, submit information certifying that the TAB agency is a first tier subcontractor who is not affiliated with any other company participating in work on this contract, including design, furnishing equipment, or construction. Further, submit the

following, for the agency, to Contracting Officer for approval:

a. Independent AABC or NEBB or TABB TAB agency:

TAB agency: AABC registration number and expiration date of current certification; or NEBB certification number and expiration date of current certification; or TABB certification number and expiration date of current certification.

TAB team supervisor: Name and copy of AABC or NEBB or TABB TAB supervisor certificate and expiration date of current certification.

TAB team field leader: Name and documented evidence that the team field leader has satisfactorily performed full-time supervision of TAB work in the field for not less than 3 years immediately preceding this contract's bid opening date.

TAB team field technicians: Names and documented evidence that each field technician has satisfactorily assisted a TAB team field leader in performance of TAB work in the field for not less than one year immediately preceding this contract's bid opening date.

Current certificates: Registrations and certifications are current, and valid for the duration of this contract. Renew Certifications which expire prior to completion of the TAB work, in a timely manner so that there is no lapse in registration or certification. TAB agency or TAB team personnel without a current registration or current certification are not to perform TAB work on this contract.

b. TAB Team Members: TAB team approved to accomplish work on this contract are full-time employees of the TAB agency. No other personnel is allowed to do TAB work on this contract.

c. Replacement of TAB team members: Replacement of members may occur if each new member complies with the applicable personnel qualifications and each is approved by the Contracting Officer.

1.5.2 TAB Standard

Perform TAB in accordance with the requirements of the standard under which the TAB Firm's qualifications are approved, i.e., AABC MN-1, NEBB PROCEDURAL STANDARDS, or SMACNA 1780 unless otherwise specified herein. All recommendations and suggested practices contained in the TAB Standard are considered mandatory. Use the provisions of the TAB Standard, including checklists, report forms, etc., as nearly as practical, to satisfy the Contract requirements. Use the TAB Standard for all aspects of TAB, including qualifications for the TAB Firm and Specialist and calibration of TAB instruments. Where the instrument manufacturer calibration recommendations are more stringent than those listed in the TAB Standard, adhere to the manufacturer's recommendations.

All quality assurance provisions of the TAB Standard such as performance guarantees are part of this contract. For systems or system components not covered in the TAB Standard, TAB procedures must be developed by the TAB Specialist. Where new procedures, requirements, etc., applicable to the Contract requirements have been published or adopted by the body responsible for the TAB Standard used (AABC, NEBB, or TABB), the

requirements and recommendations contained in these procedures and requirements are considered mandatory, including the latest requirements of ASHRAE 62.1.

1.5.3 Sustainability

Contractor must submit the following as part of the Quality Control Plan for acceptance testing:

a. List all test equipment to be used, including its manufacturer,model number, calibration date, and serial number.

b. Certificates of test personnel qualifications and certifications. Provide certification of compliance with 40 CFR 82.

c. Proof of equivalency if the contractor desires to substitute a test requirement.

Perform the following PTI as an integral part of the TAB process per the most recent edition of the NASA RCBEA GUIDE:

Fans:
a. Vibration Analysis
b. Balance Test and Measurement
c. Alignment (laser preferred)
d. Lubricating Oil Test
e. Thermodynamic Performance Test

Heat Exchangers (General):
a. Hydrostatic Test
b. Airborne Ultrasonic Test
c. Thermodynamic Performance Test
d. Infrared Thermography (optional)

HVAC Ducts:
a. Operational Test
b. Ductwork Leak Testing (DALT); Pre-Final DALT report, Final DALT report

Piping Systems:
a. Vibration Analysis
b. Infrared Thermography

Steam Coils:
a. Warranty Test
b. Vibration Analysis
c. Performance Test
d. Infrared Thermography

Valves:
a. Hydrostatic Test
b. Airborne Ultrasonic Test (optional)
c. Thermodynamic Performance Test (optional)

1.5.4 Qualifications

1.5.4.1 TAB Firm

The TAB Firm must be either a member of AABC or certified by the NEBB or the TABB and certified in all categories and functions where measurements or performance are specified on the plans and specifications, including building systems commissioning.

Certification must be maintained for the entire duration of duties specified herein. If, for any reason, the firm loses subject certification during this period, the Contractor must immediately notify the Contracting Officer and submit another TAB Firm for approval. Any firm that has been the subject of disciplinary action by either the AABC, the NEBB, or the TABB within the five years preceding Contract Award is not be eligible to perform any duties related to the HVAC systems, including TAB. All work specified in this Section and in other related Sections to be performed by the TAB Firm will be considered invalid if the TAB Firm loses its certification prior to Contract completion and must be performed by an approved successor.

These TAB services are to assist the prime Contractor in performing the quality oversight for which it is responsible. The TAB Firm must be a prime subcontractor of the Contractor and be financially and corporately independent of the mechanical subcontractor, reporting directly to and paid by the Contractor.

1.5.4.2 TAB Specialist

The TAB Specialist must be either a member of AABC,an experienced technician of the Firm certified by the NEBB, or a Supervisor certified by the TABB. The certification must be maintained for the entire duration of duties specified herein. If, for any reason, the Specialist loses subject certification during this period, immediately notify the Contracting Officer and submit another TAB Specialist for approval. Any individual that has been the subject of disciplinary action by either the AABC, the NEBB, or the TABB within the five years preceding Contract Award is not eligible to perform any duties related to the HVAC systems, including TAB. All work specified in this Section and in other related Sections performed by the TAB Specialist will be considered invalid if the TAB Specialist loses its certification prior to Contract completion and must be performed by the approved successor.

1.5.4.3 TAB Specialist Responsibilities

TAB Specialist responsibilities include all TAB work specified herein and in related sections under his direct guidance. The TAB specialist is required to be onsite on a daily basis to direct TAB efforts.

1.5.4.4 TAB Related HVAC Submittals

The TAB Specialist must prepare a list of the submittals from the Contract Submittal Register that relate to the successful accomplishment of all HVAC TAB. Accompany the submittals identified on this list with a letter of approval signed and dated by the TAB Specialist when submitted to the Government. Ensure that the location and details of ports, terminals, connections, etc., necessary to perform TAB are identified on the submittals.

1.5.5 Responsibilities

The Contractor is responsible for ensuring compliance with the requirements of this section. The following delineation of specific work responsibilities is specified to facilitate TAB execution of the various work efforts by personnel from separate organizations. This breakdown of specific duties is specified to facilitate adherence to the schedule listed in paragraph entitled "TAB Submittal and Work Schedule."

1.5.5.1 Contractor

a. TAB personnel: Ensure that the DALT work and the TAB work is accomplished by a group meeting the requirements specified in paragraph entitled "TAB Personnel Qualification Requirements."

b. Pre-DALT/TAB meeting: Attend the meeting with the TAB Supervisor, and ensure that a representative is present for the sheetmetal contractor, mechanical contractor, electrical contractor, and automatic temperature controls contractor.

c. HVAC documentation: Furnish one complete set of the following HVAC-related documentation to the TAB agency:
(1) Contract drawings and specifications

(2) Approved submittal data for equipment

(3) Construction work schedule

(4) Up-to-date revisions and change orders for the previously listed items

d. Submittal and work schedules: Ensure that the schedule for submittals and work required by this section and specified in paragraph entitled "TAB Submittal and Work Schedule," is met.

e. Coordination of supporting personnel:

Provide the technical personnel, such as factory representatives or HVAC controls installer required by the TAB field team to support the DALT and the TAB field measurement work.

Provide equipment mechanics to operate HVAC equipment and ductwork mechanics to provide the field designated test ports to enable TAB field team to accomplish the DALT and the TAB field measurement work. Ensure these support personnel are present at the times required by the TAB team, and cause no delay in the DALT and the TAB field work.

Conversely, ensure that the HVAC controls installer has required support from the TAB team field leader to complete the controls check out.

f. Deficiencies: Ensure that the TAB Agency supervisor submits all Design/Construction deficiency notifications directly to the Contracting officer within 3 days after the deficiency is encountered. Further, ensure that all such notification submittals are complete with explanation, including documentation, detailing deficiencies.

g. Prerequisite HVAC work: Complete check out and debugging of HVAC equipment, ducts, and controls prior to the TAB engineer arriving at the project site to begin the TAB work. Debugging includes searching for and eliminating malfunctioning elements in the HVAC system installations, and verifying all adjustable devices are functioning as designed. Include as prerequisite work items, the deficiencies pointed out by the TAB team supervisor in the design review report.

h. Prior to the TAB field team's arrival, ensure completion of the applicable inspections and work items listed in the TAB team supervisor's pre-field engineering report. Do not allow the TAB team to commence TAB field work until all of the following are completed.

(1) HVAC system installations are fully complete.

(2) HVAC prerequisite checkout work lists specified in the paragraph "Pre-Field TAB Engineering Report" are completed, submitted, and approved. Ensure that the TAB Agency gets a copy of the approved prerequisite HVAC work checklist.

(3) DALT field checks for all systems are completed.

(4) HVAC system filters are clean for both Season 1 and Season 2 TAB field work.

i. Advance notice: Furnish to the Contracting Officer with advance written notice for the commencement of the DALT field work and for the commencement of the TAB field work.

j. Insulation work: For required DALT work , ensure that insulation is not installed on ducts to be DALT'd until DALT work on the subject ducts is complete. Later, ensure that openings in duct and machinery insulation coverings for TAB test ports are marked, closed and sealed.

1.5.5.2 TAB Agency

Provide the services of a TAB team which complies with the requirements of paragraph entitled "Independent TAB Agency Personnel Qualifications". The work to be performed by the TAB agency is limited to testing, adjusting, and balancing of HVAC air and water systems to satisfy the requirements of this specification section.

1.5.5.3 TAB Supervisor

a. Overall management: Supervise and manage the overall TAB team work effort, including preliminary and technical DALT and TAB procedures and TAB team field work.

b. Pre-DALT/TAB meeting: Attend meeting with Contractor.

c. Design review report: Review project specifications and accompanying drawings to verify that the air systems and water systems are designed in such a way that the TAB engineer can accomplish the work in compliance with the requirements of this section. Verify the presence and location of permanently installed test ports and other devices needed, including gauge cocks, thermometer wells, flow control devices,

circuit setters, balancing valves, and manual volume dampers.

d. Support required: Specify the technical support personnel required from the Contractor other than the TAB agency; such as factory representatives for temperature controls or for complex equipment. Inform the Contractor in writing of the support personnel needed and when they are needed. Furnish the notice as soon as the need is anticipated, either with the design review report, or the pre-field engineering report, the during the DALT or TAB field work.

e. Pre-field DALT preliminary notification: Monitor the completion of the duct installation of each system and provide the necessary written notification to the Contracting Officer.

f. Pre-field engineering report: Utilizing the following HVAC-related documentation; contract drawings and specifications, approved submittal data for equipment, up-to-date revisions and change orders; prepare this report.

g. Prerequisite HVAC work checklist: Ensure the Contractor gets a copy of this checklist at the same time as the pre-field engineering report is submitted.

h. Technical assistance for DALT work.

(1) Technical assistance: Provide immediate technical assistance to TAB field team.

(2) DALT field visit: Near the end of the DALT field work effort, visit the contract site to inspect the HVAC installation and the progress of the DALT field work. Conduct a site visit to the extent necessary to verify correct procedures are being implemented and to confirm the accuracy of the Pre-final DALT Report data which has been reported. Also, perform sufficient evaluation to allow the TAB supervisor to issue certification of the final report. Conduct the site visit full-time for a minimum of two 8 hour workdays duration.

i. Final DALT report: Certify the DALT report. This certification includes the following work:

(1) Review: Review the Pre-final DALT report data. From these field reports, prepare the Certified Final DALT report.

(2) TAB Verification: Verify adherence, by the TAB field team, to the procedures specified in this section.

j. Technical Assistance for TAB Work: Provide immediate technical assistance to the TAB field team for the TAB work.

(1) TAB field visit: At the midpoint of the Season 1 and Season 2 TAB field work effort, visit the contract site to inspect the HVAC installation and the progress of the TAB field work. Conduct site visit full-time for a minimum of two 8 hour workdays duration.

(2) TAB field visit: Near the end of the TAB field work effort, visit the contract site to inspect the HVAC installation and the progress of the TAB field work. Conduct site visit full-time for

a minimum of two 8 hour workdays duration.
Review the TAB final report data and certify the TAB final report.

k. Certified TAB report: Certify the TAB report. This certification includes the following work:

(1) Review: Review the TAB field data report. From this field report, prepare the certified TAB report.

(2) Verification: Verify adherence, by the TAB field team, to the TAB plan prescribed by the pre-field engineering report and verify adherence to the procedures specified in this section.

l. Design/Construction deficiencies: Within 3 working days after the TAB Agency has encountered any design or construction deficiencies, the TAB Supervisor must submit written notification directly to the Contracting Officer, with a separate copy to the Contractor, of all such deficiencies. Provide in this submittal a complete explanation, including supporting documentation, detailing deficiencies. Where deficiencies are encountered that are believed to adversely impact successful completion of TAB, the TAB Agency must issue notice and request direction in the notification submittal.

m. TAB Field Check: The TAB team supervisor must attend and supervise Season 1 and Season 2 TAB field check.

1.5.5.4 TAB Team Field Leader

Text

a. Field manager: Manage, in the field, the accomplishment of the work specified in Part 3, "Execution."

b. Full time: Be present at the contract site when DALT field work or TAB field work is being performed by the TAB team; ensure day-to-day TAB team work accomplishments are in compliance with this section.

c. Prerequisite HVAC work: Do not bring the TAB team to the contract site until a copy of the prerequisite HVAC Checklist, with all work items certified by the Contractor to be working as designed, reaches the office of the TAB Agency.

1.5.6 Test Reports

1.5.6.1 Data from DALT Field Work

Report the data for the Pre-final DALT Report and Certified Final DALT Report in compliance the following requirements:

a. Report format: Submit report data on Air Duct Leakage Test Summary Report Forms as shown on Page 6-2 of SMACNA 1972 CD. In addition, submit in the report, a marked duct shop drawing which identifies each section of duct tested with assigned node numbers for each section. Include node numbers in the completed report forms to identify each duct section. The TAB supervisor must review and certify the report.

b. The TAB supervisor must include a copy of all calculations prepared in

determining the duct surface area of each duct test section. In addition,provide the ductwork air leak testing (DALT) reports with a copy(s) of the calibration curve for each of the DALT test orifices used for testing.

c. Instruments: List the types of instruments actually used to measure the data. Include in the listing each instrument's unique identification number, calibration date, and calibration expiration date. Instruments must have been calibrated within one year of the date of use in the field. Instrument calibration must be traceable to the measuring standards of the National Institute of Standards and Technology.

d. Certification: Include the typed name of the TAB supervisor and the dated signature of the TAB supervisor.

1.5.6.2 Certified TAB Reports

Submit: TAB Report for Season 1 and TAB Report for Season 2 in the following manner:

a. Report format: Submit the completed pre-field data forms approved in the pre-field TAB Engineering Report completed by TAB field team, reviewed and certified by the TAB supervisor. Bind the report with a waterproof front and back cover. Include a table of contents identifying by page number the location of each report. Report forms and report data must be typewritten. Handwritten report forms or report data are not acceptable.

b. Temperatures: On each TAB report form reporting TAB work accomplished on HVAC thermal energy transfer equipment, include the indoor and outdoor dry bulb temperature range and indoor and outdoor wet bulb temperature range within which the TAB data was recorded. Include in the TAB report continuous time versus temperature recording data of wet and dry bulb temperatures for the rooms, or zones, as designated in the following list:

(1) Zones K, L, O, and P. Measure and compile data on a continuous basis for the period in which TAB work affecting those rooms is being done.

(2) Measure and record data only after the HVAC systems installations are complete, the systems fully balanced and the HVAC systems controls operating in fully automatic mode.

(3) Data may be compiled using direct digital controls trend logging where available. Otherwise, temporarily install calibrated time versus temperature/humidity recorders for this purpose. The HVAC systems and controls must be fully operational a minimum of 24 hours in advance of commencing data compilation. Include the specified data in the Season I and Season 2 TAB Report.

c. System Diagrams: Provide updated diagrams with final installed locations of all terminals and devices, any numbering changes, and actual test locations. Use a key numbering system on the diagram which identifies each outlet contained in the outlet airflow report sheets.

d. Static Pressure Profiles: Report static pressure profiles for air duct systems including: all new air handling units. Report static

pressure data for all supply, return, relief, exhaust and outside air ducts for the systems listed. Include the following in the static pressure report data, in addition to AABC/NEBB/TABB required data:

(1) Report supply fan, return fan, relief fan, and exhaust fan inlet and discharge static pressures.

(2) Report static pressure drop across chilled water coils and steam coils, installed in unit cabinetry or the system ductwork.

(3) Report static pressure drop across air filters, acoustic silencers, moisture eliminators, air flow straighteners, air flow measuring stations or other pressure drop producing specialty items installed in unit cabinetry, or in the system ductwork. Examples of these specialty items are smoke detectors, white sound generators, RF shielding, wave guides, security bars, blast valves, small pipes passing through ductwork, and duct mounted humidifiers.

(4) Report static pressure drop across air filters or other pressure drop producing specialty items installed in unit cabinetry, or in the system ductwork. Examples of these specialty items are smoke detectors, small pipes passing through ductwork, and duct mounted humidifiers.

Do not report static pressure drop across duct fittings provided for the sole purpose of conveying air, such as elbows, transitions, offsets, plenums, manual dampers, and branch takes-offs.

(5) Report static pressure drop across outside air and relief/exhaust air louvers.

(6) Report static pressure readings of supply air, return air, exhaust/relief air, and outside air in duct at the point where these ducts connect to each air moving unit and also at the following locations:

Main Duct: Take readings at four locations along the full length of the main duct, 25 percent, 50 percent, 75 percent, and 100 percent of the total duct length.

Floor Branch Mains: Take readings at floor branch mains served by a main duct vertical riser.

Branch Main Ducts: Take readings at branch main ducts.

e. Duct Traverses: Report duct traverses for main and branch main supply, return, exhaust, relief and outside air ducts. This includes all ducts, including those which lack 7 1/2 duct diameters upstream and 2 1/2 duct diameters downstream of straight duct unobstructed by duct fittings/offsets/elbows. The TAB Agency must evaluate and report findings on the duct traverses taken. Evaluate the suitability of the duct traverse measurement based on satisfying the qualifications for a pilot traverse plane as defined by AMCA 203, "Field Measurements", Section 8, paragraph 8.3, "Location of Traverse Plane."

f. Instruments: List the types of instruments actually used to measure the tab data. Include in the listing each instrument's unique

identification number, calibration date, and calibration expiration date.

Instrumentation, used for taking wet bulb temperature readings must provide accuracy of plus or minus 5 percent at the measured face velocities. Submit instrument manufacturer's literature to document instrument accuracy performance is in compliance with that specified.

g. Certification: Include the typed name of the TAB supervisor and the dated signature of the TAB supervisor.

h. Performance Curves: The TAB Supervisor must include, in the TAB Reports, factory pump curves and fan curves for pumps and fans TAB'd on the job.

i. Calibration Curves: The TAB Supervisor must include, in the TAB Reports, a factory calibration curve for installed flow control balancing valves, flow venturi's and flow orifices TAB'd on the job.

1.6 PROJECT/SITE CONDITIONS

1.6.1 DALT and TAB Services to Obtain Existing Conditions

Conduct DALT and TAB of the indicated existing systems and equipment and submit the specified DALT and TAB reports for approval. Conduct this DALT and TAB work in accordance with the requirements of this section.

1.7 SEQUENCING AND SCHEDULING

1.7.1 DALT and TAB Submittal and Work Schedule

Comply with additional requirements specified in Appendix C: DALT AND TAB SUBMITTAL AND WORK SCHEDULE included at the end of this section

1.7.2 Projects with Phased Construction

This specification section is structured as though the HVAC construction, and thereby the TAB work, will be completed in a single phase. When the construction is completed in phases, the DALT work and TAB work must be planned, completed, and accepted for each construction phase.

1.7.2.1 Phasing of Work

This specification section is structured as though the HVAC construction, and thereby the TAB work, is going to be completed in a single phase in spite of the fact that there will be two seasons. All elements of the TAB work are addressed on this premise. When a contract is to be completed in construction phases, including the TAB work, and the DALT work, the TAB work and DALT work must be planned for, completed and approved by the Contracting Officer with each phase. An example of this case would be one contract that requires the rehabilitation of the HVAC in each of several separated buildings. At the completion of the final phase, compile all approved reports and submit as one document.

1.7.3 DALT and TAB Submittal and Work Schedule

Submit this schedule,and TAB Schematic Drawings, adapted for this

particular contract, to the Contracting Officer (CO) for review and approval. Include with the submittal the planned calendar dates for each submittal or work item. Resubmit an updated version for CO approval every 90 calendar days days. Compliance with the following schedule is the Contractor's responsibility.

Qualify TAB Personnel: Within 45 calendar days after date of contract award, submit TAB agency and personnel qualifications.

Pre-DALT/TAB Meeting: Within 30 calendar days after the date of approval of the TAB agency and personnel, meet with the COTR.

Design Review Report: Within 60 calendar days after the date of the TAB agency personnel qualifications approval, submit design review report.

Pre-Field DALT Preliminary Notification: On completion of the duct installation for each system, notify the Contracting Officer in writing within 5 days after completion.

Ductwork Selected for DALT: Within 7 calendar days of Pre-Field DALT Preliminary Notification, the COTR will select which of the project ductwork must be DALT'd.

DALT Field Work: Within 48 hours of COTR's selection, complete DALT field work on selected.

Submit Pre-final DALT Report: Within one working day after completion of DALT field work, submit Pre-final DALT Report. Separate Pre-final DALT reports may be submitted to allow phased testing from system to system.

DALT Work Field Check: Upon approval of the Pre-final DALT Report, schedule the COTR's DALT field check work with the Contracting Officer.

Submit Final DALT Report: Within 15 calendar days after completion of successful DALT Work Field Check, submit Season 1 TAB report.

Pre-Field TAB Engineering Report: Within 30 calendar days after approval of the TAB agency Personnel Qualifications, submit the Pre-Field TAB Engineering Report.

Prerequisite HVAC Work Check Out List For Season 1 and Advanced Notice For Season 1 TAB Field Work: At a minimum of 115 calendar days prior to CCD, submit Season 1 prerequisite HVAC work check out list certified as complete, and submit advance notice of commencement of Season 1 TAB field work.

Season 1 TAB Field Work: At a minimum of 90 calendar days prior to CCD, and when the ambient temperature is within Season 1 limits, accomplish Season 1 TAB field work.

Submit Season 1 TAB Report: Within 15 calendar days after completion of Season 1 TAB field work, submit Season 1 TAB report.

Season 1 TAB Field Check: 30 calendar days after Season 1 TAB report is approved by the Contracting Officer, conduct Season 1 field check.

Complete Season 1 TAB Work: Prior to CCD, complete all TAB work except Season 2 TAB work.

Prerequisite HVAC Work Check Out List For Season 2 and Advanced Notice For Season 2 TAB Field Work: Within 150 calendar days after date of the commencement of the Season 1 TAB field work, submit the Season 2 prerequisite HVAC work check out list certified as complete and submit advance notice of commencement of Season 2 TAB field work.

Season 2 TAB Field Work: Within 180 calendar days after date of commencement of the Season 1 TAB field work and when the ambient temperature is within Season 2 limits, accomplish Season 2 TAB field work.

Submit Season 2 TAB Report: Within 15 calendar days after completion of Season 2 TAB field work, submit Season 2 TAB report.

Season 2 TAB Field Check: 30 calendar days after the Season 2 TAB report is approved by the Contracting Officer, conduct Season 2 field check.

Complete Season 2 TAB Work: Within 15 calendar days after the completion of Season 2 TAB field data check, complete all TAB work.

1.7.3.1 Design Review Report

Submit typed report describing omissions and deficiencies in the HVAC system's design that would preclude the TAB team from accomplishing the duct leakage testing work and the TAB work requirements of this section. Provide a complete explanation including supporting documentation detailing the design deficiency. State that no deficiencies are evident if that is the case.

1.7.3.2 Pre-Field DALT Preliminary Notification

Notification: On completion of the installation of each duct system indicated to be DALT'd, notify the Contracting Officer in writing within 7 calendar days after completion.

1.7.3.3 Pre-Field TAB Engineering Report

Submit report containing the following information:

a. Step-by-step TAB procedure:

(1) Strategy: Describe the method of approach to the TAB field work from start to finish. Include in this description a complete methodology for accomplishing each seasonal TAB field work session.

(2) Air System Diagrams: Use the contract drawings and duct fabrication drawings if available to provide air system diagrams in the report showing the location of all terminal outlet supply, return, exhaust and transfer registers, grilles and diffusers. Use a key numbering system on the diagrams which identifies each outlet contained in the outlet airflow report sheets. Show intended locations of all traverses and static pressure readings.

(3) Procedural steps: Delineate fully the intended procedural steps to be taken by the TAB field team to accomplish the required TAB

work of each air distribution system and each water distribution system. Include intended procedural steps for TAB work for subsystems and system components.

b. Pre-field data: Submit AABC or NEBB or SMACNA 1780 data report forms with the following pre-field information filled in:

(1) Design data obtained from system drawings, specifications, and approved submittals.

(2) Notations detailing additional data to be obtained from the contract site by the TAB field team.

(3) Designate the actual data to be measured in the TAB field work.

(4) Provide a list of the types of instruments, and the measuring range of each, which are anticipated to be used for measuring in the TAB field work. By means of a keying scheme, specify on each TAB data report form submitted, which instruments will be used for measuring each item of TAB data. If the selection of which instrument to use, is to be made in the field, specify from which instruments the choice will be made. Place the instrument key number in the blank space where the measured data would be entered.

c. Prerequisite HVAC work checkout list: Provide a list of inspections and work items which are to be completed by the Contractor. This list must be acted upon and completed by the Contractor and then submitted and approved by the Contracting Officer prior to the TAB team coming to the contract site.

At a minimum, a list of the applicable inspections and work items listed in the NEBB PROCEDURAL STANDARDS, Section III, "Preliminary TAB Procedures" under paragraphs titled, "Air Distribution System Inspection" and "Hydronic Distribution System Inspection" must be provided for each separate system to be TAB'd.

1.8 SUBCONTRACTOR SPECIAL REQUIREMENTS

Perform all work in this section in accordance with the paragraph entitled "Subcontractor Special Requirements" in Section 01 30 00 ADMINISTRATIVE REQUIREMENTS, stating that all contract requirements of this section must be accomplished directly by a first tier subcontractor. No work may be performed by a second tier subcontractor.

1.9 WARRANTY

Furnish workmanship and performance warranty for the DALT and TAB system work performed for a period not less than 2 years from the date of Government acceptance of the work; issued directly to the Government. Include provisions that if within the warranty period the system shows evidence of major performance deterioration, or is significantly out of tolerance, resulting from defective TAB or DALT workmanship, the corrective repair or replacement of the defective materials and correction of the defective workmanship is the responsibility of the TAB firm. Perform corrective action that becomes necessary because of defective materials and workmanship while system TAB and DALT is under warranty 7 days after notification, unless additional time is approved by the Contracting Officer. Failure to perform repairs within the specified period of time constitutes grounds for having the corrective action and

repairs performed by others and the cost billed to the TAB firm. The Contractor must also provide a 2 year contractor installation warranty.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

3.1 WORK DESCRIPTIONS OF PARTICIPANTS

Comply with requirements of this section as specified in Apendix A WORK DESCRIPTIONS OF PARTICIPANTS

3.2 PRE-DALT/TAB MEETING

Meet with the Contracting Officer's technical representative (COTR)to develop a mutual understanding relative to the details of the DALT work and TAB work requirements. Ensure that the TAB supervisor is present at this meeting. Requirements to be discussed include required submittals, work schedule, and field quality control.

3.3 DALT PROCEDURES

3.3.1 Instruments, Consumables and Personnel

Provide instruments, consumables and personnel required to accomplish the DALT field work. Follow the same basic procedure specified below for TAB Field Work, including maintenance and calibration of instruments, accuracy of measurements, preliminary procedures, field work, workmanship and treatment of deficiencies. Calibrate and maintain instruments in accordance with manufacturer's written procedures.

3.3.2 Advance Notice of Pre-Final DALT Field Work

On completion of the installation of each duct system indicated to be DALT'd, notify the Contracting Officer in writing prior to the COTR's duct selection field visit.

3.3.3 Ductwork To Be DALT'd

From each duct system indicated as subject to DALT, the COTR will randomly select sections of each completed duct system for testing by the Contractor's TAB Firm. The sections selected will not exceed 20 percent of the total measured linear footage of duct systems indicated as subject to DALT. Sections of duct systems subject to DALT will include 20 percent of main ducts, branch main ducts, branch ducts and plenums for supply, return, exhaust, and plenum ductwork.

It is acceptable for an entire duct system to be DALT'd instead of disassembling that system in order to DALT only the 20 percent portion specified above.

3.3.4 DALT Testing

Perform DALT on the HVAC duct sections of each system as selected by the COTR. Use the duct class, seal class, leakage class and the leak test pressure data indicated on the drawings, to comply with the procedures specified in SMACNA 1972 CD.

In spite of specifications of SMACNA 1972 CD to the contrary, DALT ductwork of construction class of 3-inch water gauge static pressure and below if indicated to be DALT'd. Complete DALT work on the COTR selected ductwork within 48 hours after the particular ductwork was selected for DALT. Separately conduct DALT work for large duct systems to enable the DALT work to be completed in 48 hours.

3.3.5 Pre-final DALT Report

After completion of the DALT work, prepare a Pre-final DALT Report meeting the additional requirements specified in Appendix B REPORTS - DALT and TAB. Data required by those data report forms shall be furnished by the TAB team. Prepare the report neatly and legibly; the Pre-final DALT report shall provide the basis for the Final DALT Report.
TAB supervisor shall review, approve and sign the Pre-Final DALT Report and submit this report within one day of completion of DALT field work. Verbally notify the COTR that the field check of the Pre-Final DALT Report data can commence.

After completion of the DALT work, prepare a Pre-final DALT Report using the reporting forms specified. TAB team to furnish data required by those data report forms. Prepare the report neatly and legibly; the Pre-final DALT report is the basis for the Final DALT Report. TAB supervisor must review and certify the Pre-final DALT Report and submit this report within one day of completion of DALT field work. Verbally notify the COTR that the field check of the Pre-final DALT Report data can commence.

3.3.6 Quality Assurance - COTR DALT Field Acceptance Testing

In the presence of the COTR and TAB team field leader, verify for accuracy Pre-final DALT Report data selected by the COTR. For each duct system, this acceptance testing shall be conducted on a maximum of 50 percent of the duct sections DALT'd.

Further, if any data on the Pre-final DALT report form for a given duct section is out-of-tolerance, then field acceptance testing shall be conducted on data for one additional duct section, preferably in the same duct system, in the presence of the COTR.

3.3.7 Additional COTR Field Acceptance Testing

If any of the duct sections checked for a given system are determined to have a leakage rate measured that exceeds the leakage rate allowed by SMACNA Leak Test Manual for an indicated duct construction class and sealant class, terminate data checking for that section. The associated Pre-final DALT Report data for the given duct system will be disapproved. Make the necessary corrections and prepare a revised Pre-final DALT Report. Reschedule a field check of the revised report data with the COTR.

3.3.8 Certified Final DALT Report

On successful completion of all field checks of the Pre-final DALT Report data for all systems, the TAB Supervisor is to assemble, review, certify and submit the Final DALT Report to the Contracting Officer for approval.

On successful completion of all field checks of the Pre-Final DALT Report data for all systems, the TAB Supervisor shall assemble, review, approve, sign and submit the Final DALT Report in compliance with Appendix B REPORTS - DALT and TAB to the Contracting Officer for approval.

3.3.9 Prerequisite for TAB Field Work

Do not commence TAB field work prior to the completion and approval, for all systems, of the Final DALT Report.

3.4 TAB PROCEDURES

3.4.1 TAB Field Work

Test, adjust, and balance the HVAC systems until measured flow rates (air and water flow) are within plus or minus 5 percent of the design flow rates as specified or indicated on the contract documents.

That is, comply with the the requirements of AABC MN-1 , or SMACNA 1780 (TABB) and SMACNA 1858 (TABB),except as supplemented and modified by this section.

Provide instruments and consumables required to accomplish the TAB work. Calibrate and maintain instruments in accordance with manufacturer's written procedures.

Test, adjust, and balance the HVAC systems until measured flow rates (air and water flow) are within plus or minus 5 percent of the design flow rates as specified or indicated on the contract documents. Conduct TAB work, including measurement accuracy, and sound measurement work in conformance with the AABC MN-1 and AABC MN-4, or NEBB TABES and NEBB MASV, or SMACNA 1780 (used by TABB) and SMACNA 1858 sound measurement procedures, except as supplemented and modified by this section. The only water flow and air flow reporting which can be deferred until the Season 2 is that data which would be affected in terms of accuracy due to outside ambient conditions.

3.4.2 Preliminary Procedures

Use the approved pre-field engineering report as instructions and procedures for accomplishing TAB field work. TAB engineer is to locate, in the field, test ports required for testing. It is the responsibility of the sheet metal contractor to provide and install test ports as required by the TAB engineer.

3.4.3 TAB Air Distribution Systems

3.4.3.1 Units With Coils

Report heating and cooling performance capacity tests for hot water, chilled water, DX and steam coils for the purpose of verifying that the coils meet the indicated design capacity. Submit the following data and calculations with the coil test reports:

a. For air handlers with capacities greater than 7.5 tons (90,000 Btu) cooling, such as factory manufactured units, central built-up units and rooftop units, conduct capacity tests in accordance with AABC MN-4, procedure 3.5, "Coil Capacity Testing."

Do not determine entering and leaving wet and dry bulb temperatures by single point measurement, but by the average of multiple readings in compliance with paragraph 3.5-5, "Procedures", (in subparagraph d.) of AABC MN-4, Procedure 3.5, "Coil Capacity Testing."

Submit part-load coil performance data from the coil manufacturer converting test conditions to design conditions; use the data for the purpose of verifying that the coils meet the indicated design capacity in compliance with AABC MN-4, Procedure 3.5, "Coil Capacity Testing," paragraph 3.5.7, "Actual Capacity Vs. Design Capacity" (in subparagraph c.).

b. For units with capacities of 7.5 tons (90,000 Btu) or less:

Determine the apparent coil capacity by calculations using single point measurement of entering and leaving wet and dry bulb temperatures; submit the calculations with the coil reports.

3.4.3.2 Air Handling Units

Air handling unit systems including fans (air handling unit fans, exhaust fans and winter ventilation fans), coils, ducts, plenums, mixing boxes, terminal units, variable air volume boxes, and air distribution devices for supply air, return air, outside air, mixed air relief air, and makeup air.

3.4.3.3 Rooftop Air Conditioning

Rooftop air conditioning systems including fans, coils, ducts, plenums, and air distribution devices for supply air, return air, and outside air.

For refrigeration compressors/condensers/condensing units/evaporators, report data as required by NEBB, AABC, and TABB standard procedures, including refrigeration operational data.

3.4.3.4 Makeup Air Units

Makeup air unit systems including fans, coils, ducts, plenums, registers, diffusers, grilles, and louvers for supply air, return air, outside air, and mixed air.

3.4.4 TAB Water Distribution Systems

3.4.4.1 Chilled Water

Chilled water systems including coils, system balance valves and flow measuring devices.

3.4.5 Sound Measurement Work

3.4.5.1 Areas To Be Sound Measured

In the following spaces, measure and record the sound power level for each octave band listed in ASHRAE HVAC APP IP HDBK Noise Criteria:

a. All HVAC mechanical rooms, including machinery spaces and other spaces containing HVAC power drivers and power driven equipment.

b. All spaces sharing a common barrier with each mechanical room, including rooms overhead, rooms on the other side of side walls, and rooms beneath the mechanical room floor.

c. AHU No. 2 System: Rooms: 133-2021, 133-2022, 133-2023

3.4.5.2 Procedure

Measure sound levels in each room, when unoccupied except for the TAB team, with all HVAC systems that would cause sound readings in the room operating in their noisiest mode. Record the sound level in each octave band. Attempt to mitigate the sound level and bring the level to within the specified ASHRAE HVAC APP IP HDBK noise criteria goals, if such mitigation is within the TAB team's control. State in the report the ASHRAE HVAC APP IP HDBK noise criteria goals. If sound level cannot be brought into compliance, provide written notice of the deficiency to the Contractor for resolution or correction.

3.4.5.3 Timing

Measure sound levels at times prescribed by AABC or NEBB or TABB.

3.4.5.4 Meters

Measure sound levels with a sound meter complying with ASA S1.4, Type 1 or 2, and an octave band filter set complying with ASA S1.11. Use measurement methods for overall sound levels and for octave band sound levels as prescribed by NEBB.

3.4.5.5 Calibration

Calibrate sound levels as prescribed by AABC or NEBB or TABB, except that calibrators emitting a sound pressure level tone of 94 dB at 1000 hertz (Hz) are also acceptable.

3.4.5.6 Background Noise Correction

Determine background noise component of room sound (noise) levels for each (of eight) octave bands as prescribed by AABC or NEBB or TABB.

3.4.6 TAB Work on Performance Tests With Seasonal Limitations

3.4.6.1 Performance Tests

Accomplish proportionate balancing TAB work on the air distribution systems and water distribution systems, in other words, accomplish adjusting and balancing of the air flows and water flows, any time during the duration of this contract, subject to the limitations specified elsewhere in this section. However, accomplish, within the following seasonal limitations, TAB work on HVAC systems which directly transfer thermal energy.

3.4.6.2 Season Of Maximum Load

Visit the contract site for at least two TAB work sessions for TAB field measurements. Visit the contract site during the season of maximum heating load and visit the contract site during the season of maximum cooling load, the goal being to TAB the operational performance of the heating systems and

cooling systems under their respective maximum outdoor environment-caused loading. During the seasonal limitations, TAB the operational performance of the heating systems and cooling systems.

3.4.6.3 Ambient Temperatures

On each tab report form used for recording data, record the outdoor and indoor ambient dry bulb temperature range and the outdoor and indoor ambient wet bulb temperature range within which the report form's data was recorded. Record these temperatures at beginning and at the end of data taking.

3.4.6.4 Sound Measurements

Comply with paragraph entitled "Sound Measurement Work," specifically, the requirement that a room must be operating in its noisiest mode at the time of sound measurements in the room. The maximum noise level measurements could depend on seasonally related heat or cooling transfer equipment.

3.4.6.5 Refrigeration Units

For refrigeration compressors/condensers/condensing units,report data as required by NEBB Form TAB 15-83, NEBB PROCEDURAL STANDARDS, including refrigeration operational data.

3.4.6.6 Coils

Report heating and cooling performance capacity tests for chilled water and steam coils for the purpose of verifying that the coils meet the indicated design capacity. Submit the following data and calculations with the coil test reports:

a. For Central station air handlers with capacities greater than 7.5 tons (90,000 Btu) cooling, such as factory manufactured units, central built-up units and rooftop units, conduct capacity tests in accordance with AABC MN-4, procedure 3.5, "Coil Capacity Testing."

   Entering and leaving wet and dry bulb temperatures are not determined by single point measurement, but by the average of multiple readings in compliance with paragraph 3.5-5, "Procedures", (in subparagraph d.) of AABC MN-4, Procedure 3.5, "Coil Capacity Testing."

   Submit part-load coil performance data from the coil manufacturer converting test conditions to design conditions; use the data for the purpose of verifying that the coils meet the indicated design capacity in compliance with AABC MN-4, Procedure 3.5, "Coil Capacity Testing," paragraph 3.5.7, "Actual Capacity Vs. Design Capacity" (in subparagraph c.).

b. For units with capacities of 7.5 tons (90,000 Btu) or less:

   Determine the apparent coil capacity by calculations using single point measurement of entering and leaving wet and dry bulb temperatures; submit the calculations with the coil reports.

3.4.7 Workmanship

Conduct TAB work on the HVAC systems until measured flow rates are within plus or minus 5 percent of the design flow rates as specified or indicated

on the contract documents. This TAB work includes adjustment of balancing valves, balancing dampers, and sheaves. Further, this TAB work includes changing out fan sheaves and pump impellers if required to obtain air and water flow rates specified or indicated. If, with these adjustments and equipment changes, the specified or indicated design flow rates cannot be attained, contact the Contracting Officer for direction.

3.4.8 Deficiencies

Strive to meet the intent of this section to maximize the performance of the equipment as designed and installed. However, if deficiencies in equipment design or installation prevent TAB work from being accomplished within the range of design values specified in the paragraph entitled "Workmanship," provide written notice as soon as possible to the Contractor and the Contracting Officer describing the deficiency and recommended correction.

Responsibility for correction of installation deficiencies is the Contractor's. If a deficiency is in equipment design, call the TAB team supervisor for technical assistance. Responsibility for reporting design deficiencies to Contractor is the TAB team supervisor's.

3.4.9 TAB Reports
Additional requirements for TAB Reports are specified in Appendix B REPORTS - DALT and TAB

After completion of the TAB field work, prepare the TAB field data for TAB supervisor's review and certification, using the reporting forms approved in the pre-field engineering report. Data required by those approved data report forms is to be furnished by the TAB team. Except as approved otherwise in writing by the Contracting Officer, the TAB work and thereby the TAB report is considered incomplete until the TAB work is accomplished to within the accuracy range specified in the paragraph entitled "Workmanship."

3.4.10 Quality Assurance - COTR TAB Field Acceptance Testing

3.4.10.1 TAB Field Acceptance Testing

During the field acceptance testing, verify, in the presence of the COTR, random selections of data (water, air quantities, air motion, sound level readings) recorded in the TAB Report. Points and areas for field acceptance testing are to be selected by the COTR. Measurement and test procedures are the same as approved for TAB work for the TAB Report.

Field acceptance testing includes verification of TAB Report data recorded for the following equipment groups:

Group 1: All air handling units (rooftop and central stations).

Group 2: 25 percent of the supply diffusers, registers, grilles associated with constant volume air handling units.

Group 3: 25 percent of the return grilles, return registers, exhaust grilles and exhaust registers.

Group 4: 25 percent of the supply fans.

Further, if any data on the TAB Report for Groups 2 through 4 is found not

to fall within the range of plus 5 to minus 5 percent of the TAB Report data, additional group data verification is required in the presence of the COTR. Verify TAB Report data for one additional piece of equipment in that group. Continue this additional group data verification until out-of-tolerance data ceases to be found.

3.4.10.2 Additional COTR TAB Field Acceptance Testing

If any of the acceptance testing measurements for a given equipment group is found not to fall within the range of plus 5 to minus 5 percent of the TAB Report data, terminate data verification for all affected data for that group. The affected data for the given group will be disapproved. Make the necessary corrections and prepare a revised TAB Report. Reschedule acceptance testing of the revised report data with the COTR.

3.4.10.3 Prerequisite for Approval

Compliance with the field acceptance testing requirements of this section is a prerequisite for the final Contracting Officer approval of the TAB Report submitted.

3.5 MARKING OF SETTINGS

Upon the final TAB work approval, permanently mark the settings of HVAC adjustment devices including valves, gauges, splitters, and dampers so that adjustment can be restored if disturbed at any time. Provide permanent markings clearly indicating the settings on the adjustment devices which result in the data reported on the submitted TAB report.

3.6 MARKING OF TEST PORTS

The TAB team is to permanently and legibly mark and identify the location points of the duct test ports. If the ducts have exterior insulation, make these markings on the exterior side of the duct insulation. Show the location of test ports on the as-built mechanical drawings with dimensions given where the test port is covered by exterior insulation.

3.7 APPENDICES

Appendix A WORK DESCRIPTIONS OF PARTICIPANTS
Appendix B REPORTS - DALT and TAB
Appendix C DALT AND TAB SUBMITTAL AND WORK SCHEDULE

Appendix A

WORK DESCRIPTIONS OF PARTICIPANTS

The Contractor is responsible for ensuring compliance with all requirements of this specification section. However, the following delineation of specific work items is provided to facilitate and co-ordinate execution of the various work efforts by personnel from separate organizations.

1. Contractor

a. HVAC documentation: Provide pertinent contract documentation to the TAB Firm, to include the following: the contract drawings and specifications; copies of the approved submittal data for all HVAC equipment, air distribution devices, and air/water measuring/balancing devices; the construction work schedule; and other applicable documents requested by the TAB Firm. Provide the TAB Firm copies of contract revisions and modifications as they occur.

b. Schedules: Ensure the requirements specified under the paragraph "DALT and TAB Schedule" are met.

c. Pre-DALT and TAB meeting: Arrange and conduct the Pre-DALT and TAB meeting. Ensure that a representative is present for the sheet metal contractor, the mechanical contractor, the electrical contractor, and the automatic temperature controls contractor.

d. Coordinate Support: Provide and coordinate support personnel required by the TAB Firm in order to accomplish the DALT and TAB field work. Support personnel may include factory representatives, HVAC controls installers, HVAC equipment mechanics, sheet metal workers, pipe fitters, and insulators. Ensure support personnel are present at the work site at the times required.

e. Correct Deficiencies: Ensure the notifications of Construction Deficiencies are provided as specified herein. Refer to the paragraph entitled "Construction Deficiencies." Correct each deficiency as soon as practical with the Contracting Officer, and submit revised schedules and other required documentation.

f. Pre-TAB Work Checklists: Complete check out and debugging of HVAC equipment, ducts, and controls prior to the TAB engineer arriving at the project site to begin the TAB work. Debugging includes searching for and eliminating malfunctioning elements in the HVAC system installations, and verifying all adjustable devices are functioning as designed. Include as pre-TAB work checklist items, the deficiencies pointed out by the TAB team supervisor in the design review report.

Prior to the TAB field team's arrival, ensure completion of the applicable inspections and work items listed in the TAB team supervisor's DALT and TAB Work Procedures Summary. Do not allow the TAB team to commence TAB field work until all of the following are completed.

g. Give Notice of Testing: Submit advance notice of TAB field work accompanied by completed prerequisite HVAC Work List

h. Insulation work: Ensure that no insulation is shall not be installed on ducts to be DALT'd until DALT work on the subject ducts is complete.

Ensure the duct and piping systems are properly insulated and vapor sealed upon the successful completion and acceptance of the DALT and TAB work.

2. TAB Team Supervisor

a. Overall management: Supervise and manage the overall TAB team work effort, including preliminary and technical DALT and TAB procedures and TAB team field work.

b. Schedule: Ensure the requirements specified under the paragraph "DALT and TAB Schedule" are met.

c. Submittals: Provide the submittals specified herein.

d. Pre-DALT/TAB meeting: Attend meeting with Contractor. Ensure TAB personnel that will be involved in the TAB work under this contract attend the meeting.

e. Design Review Report: Submit typed report describing omissions and deficiencies in the HVAC system's design that would preclude the TAB team from accomplishing the duct leakage testing work and the TAB work requirements of this section. Provide a complete explanation including supporting documentation detailing the design deficiency. State that no deficiencies are evident if that is the case.

f. Support required: Specify the technical support personnel required from the Contractor other than the TAB agency; such as factory representatives for temperature controls or for complex equipment. Inform the Contractor in writing of the support personnel needed and when they are needed. Furnish the notice as soon as the need is anticipated, either with the design review report, or the DALT and TAB Procedures Summary, the during the DALT or TAB field work.

Ensure the Contractor is properly notified and aware of all support personnel needed to perform the TAB work. Maintain communication with the Contractor regarding support personnel throughout the duration of the TAB field work, including the TAB field acceptance testing checking.

Ensure all inspections and verifications for the Pre-Final DALT and Pre-TAB Checklists are completely and successfully conducted before DALT and TAB field work is performed.

g. Advance Notice: Monitor the completion of the duct system installations and provide the Advance Notice for Pre-Final DALT field work as specified herein.

h. Technical Assistance: Provide technical assistance to the DALT and TAB field work.

i. Deficiencies Notification: Ensure the notifications of Construction Deficiencies are provided as specified herein. Comply with requirements of the paragraph entitled "Construction Deficiencies." Resolve each deficiency as soon as practical and submit revised schedules and other required documentation.

j. Procedures: Develop the required TAB procedures for systems or system components not covered in the TAB Standard.

3. TAB Team Field Leader

a. Field manager: Manage, in the field, the accomplishment of the work specified in Part 3, "Execution."

b. Full time: Be present at the contract site when DALT field work or TAB field work is being performed by the TAB team; ensure day-to-day TAB team work accomplishments are in compliance with this section.

c. Prerequisite HVAC work: Do not bring the TAB team to the contract site until a copy of the prerequisite HVAC work list, with all work items certified by the Contractor to be working as designed, reaches the office of the TAB Agency.

Appendix B

REPORTS - DALT and TAB

All submitted documentation must be typed, neat, and organized. All reports must have a waterproof front and back cover, a title page, a certification page, sequentially numbered pages throughout, and a table of contents. Tables, lists, and diagrams must be titled. Generate and submit for approval the following documentation:

1. DALT and TAB Work Execution Schedule

Submit a detailed schedule indicating the anticipated calendar date for each submittal and each portion of work required under this section. For each work entry, indicate the support personnel (such as controls provider, HVAC mechanic, etc.) that are needed to accomplish the work. Arrange schedule entries chronologically.

2. DALT and TAB Procedures Summary

Submit a detailed narrative describing all aspects of the DALT and TAB field work to be performed. Clearly distinguish between DALT information and TAB information. Include the following:

a. A list of the intended procedural steps for the DALT and TAB field work from start to finish. Indicate how each type of data measurement will be obtained. Include what Contractor support personnel are required for each step, and the tasks they need to perform.

b. A list of the project's submittals that are needed by the TAB Firm in order to meet this Contract's requirements.

c. The schematic drawings to be used in the required reports, which may include building floor plans, mechanical room plans, duct system plans, and equipment elevations. Indicate intended TAB measurement locations, including where test ports need to be provided by the Contractor.

d. The data presentation forms to be used in the report, with the preliminary information and initial design values filled in.

e. A list of DALT and TAB instruments to be used, edited for this project, to include the instrument name and description, manufacturer, model number, scale range, published accuracy, most recent calibration date, and what the instrument will be used for on this project.

f. A thorough checklist of the work items and inspections that need to be accomplished before DALT field work can be performed. The Contractor must complete, submit, and receive approval of the Completed Pre-Final DALT Work Checklist before DALT field work can be accomplished.

g. A thorough checklist of the work items and inspections that need to be accomplished before the Season 1 TAB field work can be performed. The Contractor must complete, submit, and receive approval of the Completed Season 1 Pre-TAB Work Checklist before the Season 1 TAB field work can be accomplished.

h. A thorough checklist of the work items and inspections that need to be

accomplished before the Season 2 TAB field work can be performed. The Contractor must complete, submit, and receive approval of the Completed Season 2 Pre-TAB Work Checklist before the Season 2 TAB field work can be accomplished.

i. The checklists specified above shall be individually developed and tailored specifically for the work under this contract. Refer to NEBB PROCEDURAL STANDARDS, Section III, "Preliminary TAB Procedures" under the paragraphs titled, "Air Distribution System Inspection" and "Hydronic Distribution System Inspection" for examples of items to include in the checklists.

3. Design Review Report

Submit report containing the following information:

a. Review the contract specifications and drawings to verify that the TAB work can be successfully accomplished in compliance with the requirements of this section. Verify the presence and location of permanently installed test ports and other devices needed, including gauge cocks, thermometer wells, flow control devices, circuit setters, balancing valves, and manual volume dampers.

b. Submit a typed report describing omissions and deficiencies in the HVAC system's design that would preclude the TAB team from accomplishing the DALT work and the TAB work requirements of this section. Provide a complete explanation including supporting documentation detailing the design deficiency. If no deficiencies are evident, state so in the report.

4. Pre-Final DALT Report for COTR DALT Field Checks

Report the data for the Pre-Final DALT Report meeting the following requirements:

a. Submit a copy of the approved DALT and TAB Procedures Summary: Provide notations describing how actual field procedures differed from the procedures listed.

b. Report format: Submit a comprehensive report for the DALT field work data using data presentation forms equivalent to the "Air Duct Leakage Test Summary Report Forms" located in the SMACNA 1972 CD. In addition, submit in the report, a marked duct shop drawing which identifies each section of duct tested with assigned node numbers for each section. Node numbers shall be included in the completed report forms to identify each duct section.

c. Calculations: Include a copy of all calculations prepared in determining the duct surface area of each duct test section. Include in the DALT reports copy(s) of the calibration curve for each of the DALT test orifices used for testing.

d. Instruments: List the types of instruments actually used to measure the data. Include in the listing each instrument's unique identification number, calibration date, and calibration expiration date. Instruments are to be calibrated within one year of the date of use in the field; instrument calibration is to be traceable to the measuring standards of the National Institute of Standards and Technology.

e. TAB Supervisor Approval: Include on the submitted report the typed name of the TAB supervisor and the dated signature of the TAB supervisor.

5. Final DALT Report

On successful completion of all COTR field checks of the Pre-final DALT Report data for all systems, the TABS Supervisor shall assemble, review, sign and submit the Final DALT Report to the Contracting Officer for approval.

6. TAB Reports: Submit TAB Report for Season 1 and TAB Report for Season 2 in the following manner:

a. Procedure Summary: Submit a copy of the approved DALT and TAB Procedures Summary. When applicable, provide notations describing how actual field procedures differed from the procedures listed.

b. Report format: Submit the completed data forms approved in the pre-field TAB Engineering Report completed by TAB field team, reviewed, approved and signed by the TAB supervisor. Bind the report with a waterproof front and back cover. Include a table of contents identifying by page number the location of each report. Report forms and report data shall be typewritten. Handwritten report forms or report data are not acceptable.

c. Temperatures: On each TAB report form reporting TAB work accomplished on HVAC thermal energy transfer equipment, include the indoor and outdoor dry bulb temperature range and indoor and outdoor wet bulb temperature range within which the TAB data was recorded. Include in the TAB report continuous time versus temperature recording data of wet and dry bulb temperatures for the rooms, or zones, as designated in the following list:

Zones K,L,O,P

(1) Data shall be measured and compiled on a continuous basis for the period in which TAB work affecting those rooms is being done.

(2) Data shall be measured/recorded only after the HVAC systems installations are complete, the systems fully balanced and the HVAC systems controls operating in fully automatic mode. Provide a detailed explanation wherever a final measurement did not achieve the required value.

(3) Data may be compiled using direct digital controls trend logging where available. Otherwise, the Contractor shall temporarily install calibrated time versus temperature/humidity recorders for this purpose. The HVAC systems and controls shall have been fully operational a minimum of 24 hours in advance of commencing data compilation. The specified data shall be included in the Season I TAB Report.

d. Air System Diagrams: Provided updated diagrams with final installed locations of all terminals and devices, any numbering changes, and actual test locations.

e. Air Static Pressure Profiles: Report static pressure profiles for air

duct systems including: AHU's. Report static pressure data for all supply, return, relief, exhaust and outside air ducts for the systems listed. The static pressure report data shall include, in addition to AABC or NEBB or TABB required data, the following:

(1) Report supply fan, return fan, relief fan, and exhaust fan inlet and discharge static pressures.

(2) Report static pressure drop across chilled water coils, DX coils, hot water coils, steam coils, electric resistance heating coils and heat reclaim devices installed in unit cabinetry or the system ductwork.

(3) Report static pressure drop across outside air, return air, and supply air automatic control dampers, both proportional and two-position, installed in unit cabinetry.

(4) Report static pressure drop across air filters, acoustic silencers, moisture eliminators, air flow straighteners, air flow measuring stations or other pressure drop producing specialty items installed in unit cabinetry, or in the system ductwork. Examples of these specialty items are smoke detectors, white sound generators, RF shielding, wave guides, security bars, blast valves, small pipes passing through ductwork, and duct mounted humidifiers.

Do not report static pressure drop across duct fittings provided for the sole purpose of conveying air, such as elbows, transitions, offsets, plenums, manual dampers, and branch takes-offs.

(5) Report static pressure drop across outside air and relief/exhaust air louvers.

(6) Report static pressure readings of supply air, return air, exhaust/relief air, and outside air in duct at the point where these ducts connect to each air moving unit.

f. Duct Transverses: Report duct traverses for main and branch main supply, return, exhaust, relief and outside air ducts. This shall include all ducts, including those which lack 7 1/2 duct diameters upstream and 2 1/2 duct diameters downstream of straight duct unobstructed by duct fittings/offsets/elbows. The TAB Agency shall evaluate and report findings on the duct traverses taken. Evaluate the suitability of the duct traverse measurement based on satisfying the qualifications for a pitot traverse plane as defined by AMCA 203, "Field Measurements", Section 8, paragraph 8.3, "Location of Traverse Plane".

g. Instruments: List the types of instruments actually used to measure the tab data. Include in the listing each instrument's unique identification number, calibration date, and calibration expiration date.

Instrumentation, used for taking wet bulb temperature readings shall provide accuracy of plus or minus 5 percent at the measured face velocities. Submit instrument manufacturer's literature to document instrument accuracy performance is in compliance with that specified.

h. Performance Curves: The TAB Supervisor shall include, in the TAB

Reports, factory pump curves and fan curves for pumps and fans TAB'd on the job.

i. Calibration Curves: The TAB Supervisor shall include, in the TAB Reports, a factory calibration curve for installed flow control balancing valves, flow venturis and flow orifices TAB'd on the job.

j. Data From TAB Field Work: After completion of the TAB field work, prepare the TAB field data for TAB supervisor's review and approval signature, using the reporting forms approved in the pre-field engineering report. Data required by those approved data report forms shall be furnished by the TAB team. Except as approved otherwise in writing by the Contracting Officer, the TAB work and thereby the TAB report shall be considered incomplete until the TAB work is accomplished to within the accuracy range specified in the paragraph entitled "Workmanship."

Appendix C

DALT AND TAB SUBMITTAL AND WORK SCHEDULE

Perform the following items of work in the order listed adhering to the dates schedule specified below.

Submit TAB Agency and TAB Personnel Qualifications: Within 42 calendar days after date of contract award.

Submit the DALT and TAB Work Execution Schedule: within 14 days after receipt of the TAB agency and TAB personnel qualifications approval. Revise and re-submit this schedule 28 days prior to commencement of DALT work and 28 days prior to the commencement of TAB Season 1 work and TAB Season 2 work.

Submit the DALT and TAB Work Procedures Summary: within 14 days after receipt of the initial approved DALT and TAB Work Execution Schedule.

Meet with the COTR at the Pre-DALT/TAB Meeting: Within 28 calendar days after receipt of the approved initial DALT/TAB Execution Schedule.

Submit Design Review Report: Within 56 calendar days after the receipt of the approved initial DALT and TAB Work Execution Schedule.

Advance Notice of Pre-Final DALT Field Work: After the completed installation of the HVAC duct system to be DALT'd, submit to the Contracting Officer an Advance Notice of Pre-Final DALT Field Work accompanied by the completed Pre-Final DALT Work Checklistchecklist for the subject duct system.

Ductwork Selected for DALT: Within 14 calendar days after receiving an acceptable completed Pre-Final DALT Work Checklist, the Contracting Officer's technical representative (COTR) will select the project ductwork sections to be DALT'd.

DALT Field Work: Within 48 hours of COTR's selection, complete DALT field work on selected project ductwork.

Submit Pre-Final DALT Report: Within two working days after completion of DALT field work, submit Pre-final DALT Report. Separate Pre-final DALT reports may be submitted to allow phased testing from system to system.

Quality Assurance - COTR DALT Field Checks: Upon approval of the Pre-final DALT Report, the COTR's DALT field check work shall be scheduled with the Contracting Officer.

Submit Final DALT Report: Within 14 calendar days after completion of successful DALT Work Field Check, submit Season 1 TAB report.

Advance Notice of Season 1 TAB Field Work: At a minimum of 14 calendar days prior to Season 1 TAB Field Work, submit advance notice of TAB field work accompanied by completed
Season 1 Pre-TAB Work Checklist.

Season 1 TAB Field Work: At a minimum of 84 calendar days prior to CCD, and when the ambient temperature is within Season 1 limits, accomplish Season 1 TAB field work.

Submit Season 1 TAB Report: Within 14 calendar days after completion of Season 1 TAB field work, submit initial Season 1 TAB report.

Season 1 Quality Assurance - COTR TAB Field Check: 30 calendar days after initial Season 1 TAB report is approved by the Contracting Officer, conduct Season 1 field check.

Complete Season 1 TAB Work: Prior to CCD, complete all TAB work except Season 2 TAB work and submit final.

Receive the approved TAB report: Within 21 calendar days, receive the report from Contracting Officer approved TAB report.

Advance Notice of Season 2 TAB Field Work: At a minimum of 126 calendar days after CCD, submit advance notice of Season 2 TAB field work accompanied by completed Season 2 Pre-TAB Work Checklist.

Season 2 TAB Field Work: Within 14 calendar days after date of advance notice of Season 2 TAB field work and when the ambient temperature is within Season 2 limits, accomplish Season 2 TAB field work.

Submit Season 2 TAB Report: Within 14 calendar days after completion of Season 2 TAB field work, submit Season 2 TAB report.

Season 2 Quality Assurance - COTR TAB Field Checks: 28 calendar days after the Season 2 TAB report is approved by the Contracting Officer, conduct Season 2 field check.

Complete Season 2 TAB Work: Within 14 calendar days after the completion of Season 2 TAB field data check, complete all TAB work.

Receive the approved TAB report: Within calendar 21 days, receive the report from Contracting Officer.

-- End of Section --

SECTION 23 07 00

THERMAL INSULATION FOR MECHANICAL SYSTEMS
02/13

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only. At the discretion of the Government, the manufacturer of any material supplied will be required to furnish test reports pertaining to any of the tests necessary to assure compliance with the standard or standards referenced in this specification.

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE 90.1 - IP	(2010; Errata 1-4 2011; INT 1-12 2011; Addenda A, B, C, G, H, J, K, O, P, S, Y, Z, BZ, CG, CI and DS 2012; Errata 5-9 2012; INT 13-16 2012; Errata 10-12 2013; INT 17-18 2013) Energy Standard for Buildings Except Low-Rise Residential Buildings

ASTM INTERNATIONAL (ASTM)

ASTM A167	(1999; R 2009) Standard Specification for Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet, and Strip
ASTM A240/A240M	(2013c) Standard Specification for Chromium and Chromium-Nickel Stainless Steel Plate, Sheet, and Strip for Pressure Vessels and for General Applications
ASTM A580/A580M	(2013b) Standard Specification for Stainless Steel Wire
ASTM B209	(2010) Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate
ASTM C1126	(2013a) Standard Specification for Faced or Unfaced Rigid Cellular Phenolic Thermal Insulation
ASTM C1136	(2012) Standard Specification for Flexible, Low Permeance Vapor Retarders for Thermal Insulation
ASTM C1290	(2011) Standard Specification for Flexible Fibrous Glass Blanket Insulation Used to Externally Insulate HVAC Ducts

ASTM C1710	(2011) Standard Guide for Installation of Flexible Closed Cell Preformed Insulation in Tube and Sheet Form
ASTM C195	(2007; R 2013) Standard Specification for Mineral Fiber Thermal Insulating Cement
ASTM C450	(2008) Standard Practice for Fabrication of Thermal Insulating Fitting Covers for NPS Piping, and Vessel Lagging
ASTM C533	(2013) Standard Specification for Calcium Silicate Block and Pipe Thermal Insulation
ASTM C534/C534M	(2013) Standard Specification for Preformed Flexible Elastomeric Cellular Thermal Insulation in Sheet and Tubular Form
ASTM C547	(2012) Standard Specification for Mineral Fiber Pipe Insulation
ASTM C552	(2013) Standard Specification for Cellular Glass Thermal Insulation
ASTM C585	(2010) Standard Practice for Inner and Outer Diameters of Thermal Insulation for Nominal Sizes of Pipe and Tubing
ASTM C610	(2011) Standard Specification for Molded Expanded Perlite Block and Pipe Thermal Insulation
ASTM C612	(2014) Mineral Fiber Block and Board Thermal Insulation
ASTM C795	(2008; R 2013) Standard Specification for Thermal Insulation for Use in Contact with Austenitic Stainless Steel
ASTM C920	(2011) Standard Specification for Elastomeric Joint Sealants
ASTM C921	(2010) Standard Practice for Determining the Properties of Jacketing Materials for Thermal Insulation
ASTM D2863	(2013) Measuring the Minimum Oxygen Concentration to Support Candle-Like Combustion of Plastics (Oxygen Index)
ASTM D5590	(2000; R 2010; E 2012) Standard Test Method for Determining the Resistance of Paint Films and Related Coatings to Fungal Defacement by Accelerated Four-Week Agar Plate Assay
ASTM D882	(2012) Tensile Properties of Thin Plastic Sheeting

ASTM E2231	(2009) Specimen Preparation and Mounting of Pipe and Duct Insulation Materials to Assess Surface Burning Characteristics
ASTM E84	(2013a) Standard Test Method for Surface Burning Characteristics of Building Materials
ASTM E96/E96M	(2013) Standard Test Methods for Water Vapor Transmission of Materials

FM GLOBAL (FM)

FM APP GUIDE	(updated on-line) Approval Guide http://www.approvalguide.com/

INTERNATIONAL ORGANIZATION FOR STANDARDIZATION (ISO)

ISO 2758	(2001) Paper - Determination of Bursting Strength

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

MSS SP-69	(2003; Notice 2012) Pipe Hangers and Supports - Selection and Application (ANSI Approved American National Standard)

MIDWEST INSULATION CONTRACTORS ASSOCIATION (MICA)

MICA Insulation Stds	(1999) National Commercial & Industrial Insulation Standards

U.S. DEPARTMENT OF DEFENSE (DOD)

MIL-A-24179	(1969; Rev A; Am 2 1980; Notice 1 1987) Adhesive, Flexible Unicellular-Plastic Thermal Insulation
MIL-A-3316	(1987; Rev C; Am 2 1990) Adhesives, Fire-Resistant, Thermal Insulation

UNDERWRITERS LABORATORIES (UL)

UL 723	(2008; Reprint Aug 2013) Test for Surface Burning Characteristics of Building Materials
UL 94	(2013) Standard for Tests for Flammability of Plastic Materials for Parts in Devices and Appliances

1.2 SYSTEM DESCRIPTION

1.2.1 General

Provide field-applied insulation and accessories on mechanical systems as specified herein; factory-applied insulation is specified under the piping,

duct or equipment to be insulated. Field applied insulation materials required for use on Government-furnished items as listed in the SPECIAL CONTRACT REQUIREMENTS shall be furnished and installed by the Contractor.

1.2.2 Recycled Materials

Provide thermal insulation containing recycled materials to the extent practicable, provided that the materials meet all other requirements of this section. The minimum recycled material content of the following insulation are:

Rock Wool	75 percent slag of weight
Fiberglass	20-25 percent glass cullet by weight
Rigid Foam	9 percent recovered material

1.3 SUBMITTALS

Submit the following in accordance with SUBMITTAL PROCEDURES:

Submit the three SD types, SD-02 Shop Drawings, SD-03 Product Data, and SD-08 Manufacturer's Instructions at the same time for each system.

SD-02 Shop Drawings

MICA Plates
Pipe Insulation Systems and Associated Accessories
Duct Insulation Systems and Associated Accessories

SD-03 Product Data

Pipe Insulation Systems
Duct Insulation Systems

SD-08 Manufacturer's Instructions

Pipe Insulation Systems
Duct Insulation Systems

1.4 QUALITY ASSURANCE

1.4.1 Installer Qualification

Qualified installers shall have successfully completed three or more similar type jobs within the last 5 years.

1.5 DELIVERY, STORAGE, AND HANDLING

Materials shall be delivered in the manufacturer's unopened containers. Materials delivered and placed in storage shall be provided with protection from weather, humidity, dirt, dust and other contaminants. The Contracting Officer may reject insulation material and supplies that become dirty, dusty, wet, or contaminated by some other means. Packages or standard containers of insulation, jacket material, cements, adhesives, and coatings

delivered for use, and samples required for approval shall have manufacturer's stamp or label attached giving the name of the manufacturer and brand, and a description of the material, date codes, and approximate shelf life (if applicable). Insulation packages and containers shall be asbestos free.

PART 2 PRODUCTS

2.1 STANDARD PRODUCTS

Provide materials which are the standard products of manufacturers regularly engaged in the manufacture of such products and that essentially duplicate items that have been in satisfactory use for at least 2 years prior to bid opening. Submit a complete list of materials, including manufacturer's descriptive technical literature, performance data, catalog cuts, and installation instructions. The product number, k-value, thickness and furnished accessories including adhesives, sealants and jackets for each mechanical system requiring insulation shall be included. The product data must be copyrighted, have an identifying or publication number, and shall have been published prior to the issuance date of this solicitation. Materials furnished under this section shall be submitted together in a booklet.

2.1.1 Surface Burning Characteristics

Unless otherwise specified, insulation shall have a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84. Flame spread, and smoke developed indexes, shall be determined by ASTM E84 or UL 723. Insulation shall be tested in the same density and installed thickness as the material to be used in the actual construction. Test specimens shall be prepared and mounted according to ASTM E2231.

2.2 MATERIALS

Provide insulation that meets or exceed the requirements of ASHRAE 90.1 - IP. Insulation exterior shall be cleanable, grease resistant, non-flaking and non-peeling. Materials shall be compatible and shall not contribute to corrosion, soften, or otherwise attack surfaces to which applied in either wet or dry state. Materials to be used on stainless steel surfaces shall meet ASTM C795 requirements. Calcium silicate shall not be used on chilled or cold water systems. Materials shall be asbestos free. Provide product recognized under UL 94 (if containing plastic) and listed in FM APP GUIDE.

2.2.1 Adhesives

2.2.1.1 Mineral Fiber Insulation Cement

Cement shall be in accordance with ASTM C195.

2.2.1.2 Lagging Adhesive

Lagging is the material used for thermal insulation, especially around a cylindrical object. This may include the insulation as well as the cloth/material covering the insulation. To resist mold/mildew, lagging adhesive shall meet ASTM D5590 with 0 growth rating. Lagging adhesives shall be nonflammable and fire-resistant and shall have a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84. Adhesive shall be MIL-A-3316, Class 1, pigmented

white and be suitable for bonding fibrous glass cloth to faced and unfaced fibrous glass insulation board; for bonding cotton brattice cloth to faced and unfaced fibrous glass insulation board; for sealing edges of and bonding glass tape to joints of fibrous glass board; for bonding lagging cloth to thermal insulation; or Class 2 for attaching fibrous glass insulation to metal surfaces. Lagging adhesives shall be applied in strict accordance with the manufacturer's recommendations for pipe and duct insulation.

2.2.1.3 Contact Adhesive

Adhesives may be any of, but not limited to, the neoprene based, rubber based, or elastomeric type that have a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84. The adhesive shall not adversely affect, initially or in service, the insulation to which it is applied, nor shall it cause any corrosive effect on metal to which it is applied. Any solvent dispersing medium or volatile component of the adhesive shall have no objectionable odor and shall not contain any benzene or carbon tetrachloride. The dried adhesive shall not emit nauseous, irritating, or toxic volatile matters or aerosols when the adhesive is heated to any temperature up to 212 degrees F. The dried adhesive shall be nonflammable and fire resistant. Flexible Elastomeric Adhesive: Comply with MIL-A-24179, Type II, Class I. Provide product listed in FM APP GUIDE.

2.2.2 Caulking

ASTM C920, Type S, Grade NS, Class 25, Use A.

2.2.3 Corner Angles

Nominal 0.016 inch aluminum 1 by 1 inch with factory applied kraft backing. Aluminum shall be ASTM B209, Alloy 3003, 3105, or 5005.

2.2.4 Fittings

Fabricated Fittings are the prefabricated fittings for flexible elastomeric pipe insulation systems in accordance with ASTM C1710. Together with the flexible elastomeric tubes, they provide complete system integrity for retarding heat gain and controlling condensation drip from chilled-water and refrigeration systems. Flexible elastomeric, fabricated fittings provide thermal protection (0.25 k) and condensation resistance (0.05 Water Vapor Transmission factor). For satisfactory performance, properly installed protective vapor retarder/barriers and vapor stops shall be used on high relative humidity and below ambient temperature applications to reduce movement of moisture through or around the insulation to the colder interior surface.

2.2.5 Finishing Cement

ASTM C450: Mineral fiber hydraulic-setting thermal insulating and finishing cement. All cements that may come in contact with Austenitic stainless steel must comply with ASTM C795.

2.2.6 Fibrous Glass Cloth and Glass Tape

Fibrous glass cloth, with 20X20 maximum mesh size, and glass tape shall have maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84. Tape shall be 4 inch wide

rolls. Class 3 tape shall be 4.5 ounces/square yard. Elastomeric Foam Tape: Black vapor-retarder foam tape with acrylic adhesive containing an anti-microbial additive.

2.2.7 Jackets

2.2.7.1 Aluminum Jackets

Aluminum jackets shall be corrugated, embossed or smooth sheet, 0.016 inch nominal thickness; ASTM B209, Temper H14, Temper H16, Alloy 3003, 5005, or 3105. Corrugated aluminum jacket shall not be used outdoors. . Aluminum jacket circumferential seam bands shall be 2 by 0.016 inch aluminum matching jacket material. Bands for insulation below ground shall be 3/4 by 0.020 inch thick stainless steel, or fiberglass reinforced tape. The jacket may, at the option of the Contractor, be provided with a factory fabricated Pittsburgh or "Z" type longitudinal joint. When the "Z" joint is used, the bands at the circumferential joints shall be designed by the manufacturer to seal the joints and hold the jacket in place.

2.2.7.2 Polyvinyl Chloride (PVC) Jackets

Polyvinyl chloride (PVC) jacket and fitting covers shall have high impact strength, ultraviolet (UV) resistant rating or treatment and moderate chemical resistance with minimum thickness 0.030 inch.

2.2.7.3 Vapor Barrier/Weatherproofing Jacket

Vapor barrier/weatherproofing jacket shall be laminated self-adhesive, greater than 3 plies standard grade, silver, white, black and embossed or greater than 8 ply (minimum 2.9 mils adhesive); with 0.0000 permeability when tested in accordance with ASTM E96/E96M, using the water transmission rate test method; heavy duty, white or natural; and UV resistant. Flexible Elastomeric exterior foam with factory applied, UV Jacket made with a cold weather acrylic adhesive. Construction of laminate designed to provide UV resistance, high puncture, tear resistance and excellent Water Vapor Transmission (WVT) rate.

2.2.8 Vapor Retarder Required

ASTM C921, Type I, minimum puncture resistance 50 Beach units on all surfaces where a minimum puncture resistance of 25 Beach units is acceptable. Minimum tensile strength, 35 pounds/inch width. ASTM C921, Type II, minimum puncture resistance 25 Beach units, tensile strength minimum 20 pounds/inch width. Jackets used on insulation exposed in finished areas shall have white finish suitable for painting without sizing. Based on the application, insulation materials that require manufacturer or fabricator applied pipe insulation jackets are cellular glass, when all joints are sealed with a vapor barrier mastic, and mineral fiber. All non-metallic jackets shall have a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84.

2.2.8.1 White Vapor Retarder All Service Jacket (ASJ)

ASJ is for use on hot/cold pipes, ducts, or equipment indoors or outdoors if covered by a suitable protective jacket. The product shall meet all physical property and performance requirements of ASTM C1136, Type I, except the burst strength shall be a minimum of 85 psi. ASTM D2863 Limited Oxygen Index (LOI) shall be a minimum of 31.

In addition, neither the outer exposed surface nor the inner-most surface contacting the insulation shall be paper or other moisture-sensitive material. The outer exposed surface shall be white and have an emittance of not less than 0.80. The outer exposed surface shall be paintable.

2.2.8.2 Laminated Film Vapor Retarder

ASTM C1136, Type I, maximum moisture vapor transmission 0.02 perms, minimum puncture resistance 50 Beach units on all surfaces except concealed ductwork; where Type II, maximum moisture vapor transmission 0.02 perms, a minimum puncture resistance of 25 Beach units is acceptable. Vapor retarder shall have a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84. Flexible Elastomeric exterior foam with factory applied UV Jacket. Construction of laminate designed to provide UV resistance, high puncture, tear resistance and an excellent WVT rate.

2.2.8.3 Polyvinylidene Chloride (PVDC) Film Vapor Retarder

The PVDC film vapor retarder shall have a maximum moisture vapor transmission of 0.02 perms, minimum puncture resistance of 150 Beach units, a minimum tensile strength in any direction of 30 lb/inch when tested in accordance with ASTM D882, and a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84.

2.2.8.4 Polyvinylidene Chloride Vapor Retarder Adhesive Tape

Requirements must meet the same as specified for Laminated Film Vapor Retarder above.

2.2.8.5 Vapor Barrier/Weather Barrier

The vapor barrier shall be greater than 3 ply self adhesive laminate -white vapor barrier jacket- superior performance (less than 0.0000 permeability when tested in accordance with ASTM E96/E96M). Vapor barrier shall meet UL 723 or ASTM E84 25 flame and 50 smoke requirements; and UV resistant. Minimum burst strength 185 psi in accordance with ISO 2758. Tensile strength 68 lb/inch width (PSTC-1000). Tape shall be as specified for laminated film vapor barrier above.

2.2.9 Wire

Soft annealed ASTM A580/A580M Type 302, 304 or 316 stainless steel, 16 or 18 gauge.

2.2.10 Insulation Bands

Insulation bands shall be 1/2 inch wide; 26 gauge stainless steel.

2.2.11 Sealants

Sealants shall be chosen from the butyl polymer type, the styrene-butadiene rubber type, or the butyl type of sealants. Sealants shall have a maximum permeance of 0.02 perms based on Procedure B for ASTM E96/E96M, and a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84.

2.3 PIPE INSULATION SYSTEMS

2.3.1 Aboveground Cold Pipeline (-30 to 60 deg. F)

Insulation for outdoor, indoor, exposed or concealed applications, shall be as follows:

2.3.1.1 Cellular Glass

ASTM C552, Type II, and Type III. Supply the insulation from the fabricator with (paragraph WHITE VAPOR RETARDER ALL SERVICE JACKET (ASJ)) ASJ vapor retarder and installed with all longitudinal overlaps sealed and all circumferential joints ASJ taped or supply the insulation unfaced from the fabricator and install with all longitudinal and circumferential joints sealed with vapor barrier mastic.

2.3.1.2 Flexible Elastomeric Cellular Insulation

Closed-cell, foam- or expanded-rubber materials containing anti-microbial additive, complying with ASTM C534/C534M, Grade 1, Type I or II. Type I, Grade 1 for tubular materials. Type II, Grade 1, for sheet materials. Type I and II shall have vapor retarder/vapor barrier skin on one or both sides of the insulation, and require an additional exterior vapor retarder covering for high relative humidity and below ambient temperature applications.

2.3.2 Aboveground Hot Pipeline (Above 60 deg. F)

Insulation for outdoor, indoor, exposed or concealed applications shall meet the following requirements. Supply the insulation with manufacturer's recommended factory-applied jacket/vapor barrier.

2.3.2.1 Mineral Fiber

ASTM C547, Types I, II or III, supply the insulation with manufacturer's recommended factory-applied jacket.

2.3.2.2 Calcium Silicate

ASTM C533, Type I indoor only, or outdoors above 250 degrees F pipe temperature. Supply insulation with the manufacturer's recommended factory-applied jacket/vapor barrier.

2.3.2.3 Cellular Glass

ASTM C552, Type II and Type III. Supply the insulation with manufacturer's recommended factory-applied jacket.

2.3.2.4 Flexible Elastomeric Cellular Insulation

Closed-cell, foam- or expanded-rubber materials containing anti-microbial additive, complying with ASTM C534/C534M, Grade 1, Type I or II to 220 degrees F service. Type I for tubular materials. Type II for sheet materials.

2.4 DUCT INSULATION SYSTEMS

2.4.1 Factory Applied Insulation

2.4.1.1 Rigid Insulation

Rigid mineral fiber in accordance with ASTM C612, Class 2 (maximum surface temperature 400 degrees F), 3 pcf average, 1-1/2 inch thick, Type IA, IB, II, III, and IV. Alternately, minimum thickness may be calculated in accordance with ASHRAE 90.1 - IP.

2.4.1.2 Blanket Insulation

Blanket flexible mineral fiber insulation conforming to ASTM C585, Type 1, Class B-3, 3/4 pcf nominal, 2.0 inches thick or Type II up to 250 degrees F. Also ASTM C1290 Type III may be used.

2.4.2 Duct Insulation Jackets

2.4.2.1 All-Purpose Jacket

Provide insulation with insulation manufacturer's standard reinforced fire-retardant jacket with or without integral vapor barrier as required by the service. In exposed locations, provide jacket with a white surface suitable for field painting.

2.4.2.2 Metal Jackets

2.4.2.2.1 Aluminum Jackets

ASTM B209, Temper H14, minimum thickness of 27 gauge (0.016 inch), with factory-applied polyethylene and kraft paper moisture barrier on inside surface. Provide smooth surface jackets for jacket outside dimension 8 inches and larger. Provide corrugated surface jackets for jacket outside dimension 8 inches and larger. Provide stainless steel bands, minimum width of 1/2 inch.

2.4.2.2.2 Stainless Steel Jackets

ASTM A167 or ASTM A240/A240M; Type 304, minimum thickness of 33 gauge (0.010 inch), smooth surface with factory-applied polyethylene and kraft paper moisture barrier on inside surface. Provide stainless steel bands, minimum width of 1/2 inch.

2.4.2.3 Vapor Barrier/Weatherproofing Jacket

Vapor barrier/weatherproofing jacket shall be laminated self-adhesive (minimum 2 mils adhesive, 3 mils embossed) less than 0.0000 permeability, (greater than 3 ply, standard grade, silver, white, black and embossed or greater than 8 ply (minimum 2.9 mils adhesive), heavy duty white or natural).

2.4.3 Weatherproof Duct Insulation

Provide ASTM C552, cellular glass thermal insulation, and weatherproofing as specified in manufacturer's instruction. Multi-ply, Polymeric Blend Laminate Jacketing: Construction of laminate designed to provide UV resistance, high puncture, tear resistance and an excellent WVT rate.

PART 3 EXECUTION

3.1 APPLICATION - GENERAL

Insulation shall only be applied to unheated and uncooled piping and equipment. Flexible elastomeric cellular insulation shall not be compressed at joists, studs, columns, ducts, hangers, etc. The insulation shall not pull apart after a one hour period; any insulation found to pull apart after one hour, shall be replaced.

3.1.1 Installation

Except as otherwise specified, material shall be installed in accordance with the manufacturer's written instructions. Insulation materials shall not be applied until tests and heat tracing specified in other sections of this specification are completed. Material such as rust, scale, dirt and moisture shall be removed from surfaces to receive insulation. Insulation shall be kept clean and dry. Insulation shall not be removed from its shipping containers until the day it is ready to use and shall be returned to like containers or equally protected from dirt and moisture at the end of each workday. Insulation that becomes dirty shall be thoroughly cleaned prior to use. If insulation becomes wet or if cleaning does not restore the surfaces to like new condition, the insulation will be rejected, and shall be immediately removed from the jobsite. Joints shall be staggered on multi layer insulation. Mineral fiber thermal insulating cement shall be mixed with demineralized water when used on stainless steel surfaces. Insulation, jacketing and accessories shall be installed in accordance with MICA Insulation Stds plates except where modified herein or on the drawings.

3.1.2 Installation of Flexible Elastomeric Cellular Insulation

Install flexible elastomeric cellular insulation with seams and joints sealed with rubberized contact adhesive. Flexible elastomeric cellular insulation shall not be used on surfaces greater than 220 degrees F. Stagger seams when applying multiple layers of insulation. Protect insulation exposed to weather and not shown to have vapor barrier weatherproof jacketing with two coats of UV resistant finish or PVC or metal jacketing as recommended by the manufacturer after the adhesive is dry and cured.

3.1.2.1 Adhesive Application

Apply a brush coating of adhesive to both butt ends to be joined and to both slit surfaces to be sealed. Allow the adhesive to set until dry to touch but tacky under slight pressure before joining the surfaces. Insulation seals at seams and joints shall not be capable of being pulled apart one hour after application. Insulation that can be pulled apart one hour after installation shall be replaced.

3.1.2.2 Adhesive Safety Precautions

Use natural cross-ventilation, local (mechanical) pickup, and/or general area (mechanical) ventilation to prevent an accumulation of solvent vapors, keeping in mind the ventilation pattern must remove any heavier-than-air solvent vapors from lower levels of the workspaces. Gloves and spectacle-type safety glasses are recommended in accordance with safe installation practices.

3.1.3 Welding

No welding shall be done on or without written approval of the Contracting Officer. .

3.1.4 That Require Insulation

Insulation is required on all or except for omitted items as specified.

3.2 PIPE INSULATION SYSTEMS INSTALLATION

3.2.1 Pipe Insulation

3.2.1.1 General

Pipe insulation shall be installed on aboveground hot and cold pipeline systems as specified below to form a continuous thermal retarder/barrier, including straight runs, fittings and appurtenances unless specified otherwise. Installation shall be with full length units of insulation and using a single cut piece to complete a run. Cut pieces or scraps abutting each other shall not be used.

3.2.1.2 Pipes Passing Through Hangers

Insulation, whether hot or cold application, shall be continuous through hangers. All horizontal pipes 2 inches and smaller shall be supported on hangers with the addition of a Type 40 protection shield to protect the insulation in accordance with MSS SP-69. Whenever insulation shows signs of being compressed, or when the insulation or jacket shows visible signs of distortion at or near the support shield, insulation inserts as specified below for piping larger than 2 inches shall be installed, or factory insulated hangers (designed with a load bearing core) can be used.

3.2.1.2.1 Horizontal Pipes Larger Than 2 Inches and Below 60 Degrees F

Supported on hangers with the addition of a Type 40 protection shield in accordance with MSS SP-69. An insulation insert of cellular glass, prefabricated insulation pipe hangers, or perlite above 80 degrees F shall be installed above each shield. The insert shall cover not less than the bottom 180-degree arc of the pipe. Inserts shall be the same thickness as the insulation, and shall extend 2 inches on each end beyond the protection shield. When insulation inserts are required in accordance with the above, and the insulation thickness is less than 1 inch, wooden or cork dowels or blocks may be installed between the pipe and the shield to prevent the weight of the pipe from crushing the insulation, as an option to installing insulation inserts. The insulation jacket shall be continuous over the wooden dowel, wooden block, or insulation insert.

3.2.1.2.2 Vertical Pipes

Supported with either Type 8 or Type 42 riser clamps with the addition of two Type 40 protection shields in accordance with MSS SP-69 covering the 360-degree arc of the insulation. An insulation insert of cellular glass or calcium silicate shall be installed between each shield and the pipe. The insert shall cover the 360-degree arc of the pipe. Inserts shall be the same thickness as the insulation, and shall extend 2 inches on each end beyond the protection shield. When insulation inserts are required in accordance with the above, and the insulation thickness is less than 1 inch,

wooden or cork dowels or blocks may be installed between the pipe and the shield to prevent the hanger from crushing the insulation, as an option instead of installing insulation inserts. The insulation jacket shall be continuous over the wooden dowel, wooden block, or insulation insert. The vertical weight of the pipe shall be supported with hangers located in a horizontal section of the pipe. When the pipe riser is longer than 30 feet, the weight of the pipe shall be additionally supported with hangers in the vertical run of the pipe that are directly clamped to the pipe, penetrating the pipe insulation. These hangers shall be insulated and the insulation jacket sealed as indicated herein for anchors in a similar service.

3.2.1.2.3 Inserts

Covered with a jacket material of the same appearance and quality as the adjoining pipe insulation jacket, overlap the adjoining pipe jacket 1-1/2 inches, and seal as required for the pipe jacket. The jacket material used to cover inserts in flexible elastomeric cellular insulation shall conform to ASTM C1136, Type 1, and is allowed to be of a different material than the adjoining insulation material.

3.2.1.3 Flexible Elastomeric Cellular Pipe Insulation

Flexible elastomeric cellular pipe insulation shall be tubular form for pipe sizes 6 inches and less. Grade 1, Type II sheet insulation used on pipes larger than 6 inches shall not be stretched around the pipe. On pipes larger than 12 inches, the insulation shall be adhered directly to the pipe on the lower 1/3 of the pipe. Seams shall be staggered when applying multiple layers of insulation. Sweat fittings shall be insulated with miter-cut pieces the same size as on adjacent piping. Screwed fittings shall be insulated with sleeved fitting covers fabricated from miter-cut pieces and shall be overlapped and sealed to the adjacent pipe insulation. Type II requires an additional exterior vapor retarder/barrier covering for high relative humidity and below ambient temperature applications.

3.2.1.4 Pipe Insulation Material and Thickness

TABLE 1

Insulation Material for Piping

Service					
	Material	Specification	Type	Class	VR/VB Req'd
Chilled Water (Supply & Return, Dual Temperature Piping, 40 F nominal)					
	Cellular Glass	ASTM C552	II	2	Yes
	Flexible Elastomeric Cellular	ASTM C534/C534M	I		Yes
	Mineral Fiber with Wicking Material	ASTM C547	I		Yes

TABLE 1

Insulation Material for Piping

Service					
	Material	Specification	Type	Class	VR/VB Req'd
Compressed Air Discharge, Steam and Condensate Return (201 to 250 Degrees F					
	Cellular Glass	ASTM C552	II		No
	Mineral Fiber	ASTM C547	I	1	No
	Calcium Silicate	ASTM C533	I		No
	Faced Phenolic Foam	ASTM C1126	III		Yes
	Perlite	ASTM C610			No
	Flexible Elastomeric Cellular	ASTM C534/C534M	I	2	No
Medium Temperature Hot Water, Steam and Condensate (251 to 350 Degrees F)					
	Mineral Fiber	ASTM C547	I	1	No
	Calcium Silicate	ASTM C533	I		No
	Cellular Glass	ASTM C552	I or II		No
	Perlite	ASTM C610			No
	Flexible Elastomeric Cellular	ASTM C534/C534M	I	2	No

TABLE 2

Piping Insulation Thickness (inch)
Do not use integral wicking material in Chilled water applications exposed to outdoor ambient conditions in climatic zones 1 through 4.

Service						
	Material	Tube And Pipe Size (inch)				
		<1	1-<1.5	1.5-<4	4-<8	> or = >8
Chilled Water (Supply & Return, Dual Temperature Piping, 40 Degrees F nominal)						
	Cellular Glass	1.5	2	2	2.5	3
	Mineral Fiber with Wicking Material	1	1.5	1.5	2	2
	Flexible Elastomeric Cellular	1	1	1	N/A	N/A

TABLE 2						
Chilled Water (Supply & Return, Dual Temperature Piping, 40 Degrees F nominal)						
	Cellular Glass	1.5	1.5	1.5	1.5	2
	Flexible Elastomeric Cellular	1	1	1	N/A	N/A
	Mineral Fiber with Wicking Material	1	1.5	1.5	2	2
Compressed Air Discharge, Steam and Condensate Return (201 to 250 Degrees F						
	Mineral Fiber	1.5	1.5	2	2	2
		1.5*	2*	2.5*	3*	3.5*
	Calcium Silicate	2.5	3	4	4	4.5
	Cellular Glass	2	2.5	3	3	3
	Perlite	2.5	3	4	4	4.5
	Flexible Elastomeric Cellular	1	1	1	N/A	N/A
Medium Temperature Hot Water, Steam and Condensate (251 to 350 Degrees F)						
	Mineral Fiber	1.5	3	3	4	4
		2.5*	*	3.5*		
	Calcium Silicate	2.5	3.5	4.5	4.5	5
	Perlite	2.5	3.5	4.5	4.5	5
	Flexible Elastomeric Cellular	1	1	1	N/A	N/A

3.2.2 Aboveground Cold Pipelines

The following cold pipelines for minus 30 to plus 60 degrees F, shall be insulated in accordance with Table 2 except those piping listed in subparagraph Pipe Insulation in PART 3 as to be omitted. This includes but is not limited to the following:

d. Chilled water.

3.2.2.1 Insulation Material and Thickness

Insulation thickness for cold pipelines shall be determined using Table 2.

3.2.2.2 Factory or Field applied Jacket

Insulation shall be covered with a factory applied vapor retarder jacket/vapor barrier or field applied seal welded PVC jacket or greater than 3 ply laminated self-adhesive (minimum 2 mils adhesive, 3 mils embossed) vapor barrier/weatherproofing jacket - less than 0.0000

permeability, standard grade, sliver, white, black and embossed for use with Mineral Fiber, Cellular Glass, and Phenolic Foam Insulated Pipe. Insulation inside the building, to be protected with an aluminum jacket or greater than 3ply vapor barrier/weatherproofing self-adhesive (minimum 2 mils adhesive, 3 mils embossed) product, less than 0.0000 permeability, standard grade, Embossed Silver, White & Black, shall have the insulation and vapor retarder jacket installed as specified herein. The aluminum jacket or greater than 3ply vapor barrier/weatherproofing self-adhesive (minimum 2 mils adhesive, 3 mils embossed) product, less than 0.0000 permeability, standard grade, embossed silver, White & Black, shall be installed as specified for piping exposed to weather, except sealing of the laps of the aluminum jacket is not required.

3.2.2.3 Installing Insulation for Straight Runs Hot and Cold Pipe

Apply insulation to the pipe with tight butt joints. Seal all butted joints and ends with joint sealant and seal with a vapor retarder coating, greater than 3 ply laminate jacket - less than 0.0000 perm adhesive tape or PVDC adhesive tape.

3.2.2.3.1 Longitudinal Laps of the Jacket Material

Overlap not less than 1-1/2 inches. Provide butt strips 3 inches wide for circumferential joints.

3.2.2.3.2 Laps and Butt Strips

Secure with adhesive and staple on 4 inch centers if not factory self-sealing. If staples are used, seal in accordance with paragraph STAPLES below. Note that staples are not required with cellular glass systems.

3.2.2.3.3 Factory Self-Sealing Lap Systems

May be used when the ambient temperature is between 40 and 120 degrees F during installation. Install the lap system in accordance with manufacturer's recommendations. Use a stapler only if specifically recommended by the manufacturer. Where gaps occur, replace the section or repair the gap by applying adhesive under the lap and then stapling.

3.2.2.3.4 Staples

coat all staples, including those used to repair factory self-seal lap systems, with a vapor retarder coating or PVDC adhesive tape or greater than 3 ply laminate jacket - less than 0.0000 perm adhesive tape. Coat all seams, except those on factory self-seal systems, with vapor retarder coating or PVDC adhesive tape or greater than 3 ply laminate jacket - less than 0.0000 perm adhesive tape.

3.2.2.3.5 Breaks and Punctures in the Jacket Material

Patch by wrapping a strip of jacket material around the pipe and secure it with adhesive, staple, and coat with vapor retarder coating or PVDC adhesive tape or greater than 3 ply laminate jacket - less than 0.0000 perm adhesive tape. Extend the patch not less than 1-1/2 inches past the break.

3.2.2.3.6 Penetrations Such as Thermometers

Fill the voids in the insulation and seal with vapor retarder coating or

PVDC adhesive tape or greater than 3 ply laminate jacket - less than 0.0000 perm adhesive tape.

3.2.2.3.7 Flexible Elastomeric Cellular Pipe Insulation

Install by slitting the tubular sections and applying them onto the piping or tubing. Alternately, whenever possible slide un-slit sections over the open ends of piping or tubing. Secure all seams and butt joints and seal with adhesive. When using self seal products only the butt joints shall be secured with adhesive. Push insulation on the pipe, never pulled. Stretching of insulation may result in open seams and joints. Clean cut all edges. Rough or jagged edges of the insulation are not be permitted. Use proper tools such as sharp knives. Do not stretch Grade 1, Type II sheet insulation around the pipe when used on pipe larger than 6 inches. On pipes larger than 12 inches, adhere sheet insulation directly to the pipe on the lower 1/3 of the pipe.

3.2.2.4 Insulation for Fittings and Accessories

a. Pipe insulation shall be tightly butted to the insulation of the fittings and accessories. The butted joints and ends shall be sealed with joint sealant and sealed with a vapor retarder coating or PVDC adhesive tape or greater than 3 ply laminate jacket - less than 0.0000 perm adhesive tape.

b. Precut or preformed insulation shall be placed around all fittings and accessories and shall conform to MICA plates except as modified herein: 5 for anchors; 10, 11, and 13 for fittings; 14 for valves; and 17 for flanges and unions. Insulation shall be the same insulation as the pipe insulation, including same density, thickness, and thermal conductivity. Where precut/preformed is unavailable, rigid preformed pipe insulation sections may be segmented into the shape required. Insulation of the same thickness and conductivity as the adjoining pipe insulation shall be used. If nesting size insulation is used, the insulation shall be overlapped 2 inches or one pipe diameter. Elbows insulated using segments shall conform to MICA Tables 12.20 "Mitered Insulation Elbow'.

c. Upon completion of insulation installation on flanges, unions, valves, anchors, fittings and accessories, terminations, seams, joints and insulation not protected by factory vapor retarder jackets or PVC fitting covers shall be protected with PVDC or greater than 3 ply laminate jacket - less than 0.0000 perm adhesive tape or two coats of vapor retarder coating with a minimum total thickness of 1/16 inch, applied with glass tape embedded between coats. Tape seams shall overlap 1 inch. The coating shall extend out onto the adjoining pipe insulation 2 inches. Fabricated insulation with a factory vapor retarder jacket shall be protected with either greater than 3 ply laminate jacket - less than 0.0000 perm adhesive tape, standard grade, silver, white, black and embossed or PVDC adhesive tape or two coats of vapor retarder coating with a minimum thickness of 1/16 inch and with a 2 inch wide glass tape embedded between coats. Where fitting insulation butts to pipe insulation, the joints shall be sealed with a vapor retarder coating and a 4 inch wide ASJ tape which matches the jacket of the pipe insulation.

d. Anchors attached directly to the pipe shall be insulated for a sufficient distance to prevent condensation but not less than 6 inches from the insulation surface.

e. Insulation shall be marked showing the location of unions, strainers, and check valves.

3.2.2.5 Optional PVC Fitting Covers

At the option of the Contractor, premolded, one or two piece PVC fitting covers may be used in lieu of the vapor retarder and embedded glass tape. Factory precut or premolded insulation segments shall be used under the fitting covers for elbows. Insulation segments shall be the same insulation as the pipe insulation including same density, thickness, and thermal conductivity. The covers shall be secured by PVC vapor retarder tape, adhesive, seal welding or with tacks made for securing PVC covers. Seams in the cover, and tacks and laps to adjoining pipe insulation jacket, shall be sealed with vapor retarder tape to ensure that the assembly has a continuous vapor seal.

3.2.3 Aboveground Hot Pipelines

3.2.3.1 General Requirements

All hot pipe lines above 60 degrees F, except those piping listed in subparagraph Pipe Insulation in PART 3 as to be omitted, shall be insulated in accordance with Table 2. This includes but is not limited to the following:

b. Steam.

c. Condensate & compressed air discharge.

Insulation shall be covered, in accordance with manufacturer's recommendations, with a factory applied Type I jacket or field applied aluminum where required or seal welded PVC.

3.2.3.2 Insulation for Fittings and Accessories

Pipe insulation shall be tightly butted to the insulation of the fittings and accessories. The butted joints and ends shall be sealed with joint sealant. Insulation shall be marked showing the location of unions, strainers, check valves and other components that would otherwise be hidden from view by the insulation.

3.2.3.2.1 Precut or Preformed

Place precut or preformed insulation around all fittings and accessories. Insulation shall be the same insulation as the pipe insulation, including same density, thickness, and thermal conductivity.

3.2.3.2.2 Rigid Preformed

Where precut/preformed is unavailable, rigid preformed pipe insulation sections may be segmented into the shape required. Insulation of the same thickness and conductivity as the adjoining pipe insulation shall be used. If nesting size insulation is used, the insulation shall be overlapped 2 inches or one pipe diameter. Elbows insulated using segments shall conform to MICA Tables 12.20 "Mitered Insulation Elbow".

3.3 DUCT INSULATION SYSTEMS INSTALLATION

Except for oven hood exhaust duct insulation, corner angles shall be installed on external corners of insulation on ductwork in exposed finished spaces before covering with jacket. Air conditioned spaces shall be defined as those spaces directly supplied with cooled conditioned air (or provided with a cooling device such as a fan-coil unit) and heated conditioned air (or provided with a heating device such as a unit heater, radiator or convector).

3.3.1 Duct Insulation Thickness

Duct insulation thickness shall be in accordance with Table 4.

Table 4 - Minimum Duct Insulation (inches)	
Cold Air Ducts	2.0
Fresh Air Intake Ducts	1.5
Warm Air Ducts	2.0
Fresh Air Intake Ducts	1.5

3.3.2 Insulation and Vapor Retarder/Vapor Barrier for Cold Air Duct

Insulation and vapor retarder/vapor barrier shall be provided for the following cold air ducts and associated equipment.

a. Supply ducts.

b. Return air ducts.

c. Relief ducts.

d. Flexible run-outs (field-insulated).

e. Plenums.

f. Duct-mounted coil casings.

g. Coil headers and return bends.

h. Coil casings.

i. Fresh air intake ducts.

j. Filter boxes.

k. Mixing boxes (field-insulated).

l. Supply fans (field-insulated).

m. Site-erected air conditioner casings.

n. Ducts exposed to weather.

o. Combustion air intake ducts.

Insulation for rectangular ducts shall be flexible type where concealed, minimum density 3/4 pcf, and rigid type where exposed, minimum density 3 pcf. Insulation for both concealed or exposed round/oval ducts shall be flexible type, minimum density 3/4 pcf or a semi rigid board, minimum density 3 pcf, formed or fabricated to a tight fit, edges beveled and joints tightly butted and staggered. Insulation for all exposed ducts shall be provided with either a white, paint-able, factory-applied Type I jacket or a field applied vapor retarder/vapor barrier jacket coating finish as specified, the total field applied dry film thickness shall be approximately 1/16 inch. Insulation on all concealed duct shall be provided with a factory-applied Type I or II vapor retarder/vapor barrier jacket. Duct insulation shall be continuous through sleeves and prepared openings except firewall penetrations. Duct insulation terminating at fire dampers, shall be continuous over the damper collar and retaining angle of fire dampers, which are exposed to unconditioned air and which may be prone to condensate formation. Duct insulation and vapor retarder/vapor barrier shall cover the collar, neck, and any un-insulated surfaces of diffusers, registers and grills. Vapor retarder/vapor barrier materials shall be applied to form a complete unbroken vapor seal over the insulation. Sheet Metal Duct shall be sealed in accordance with Section 23 00 00 AIR SUPPLY, DISTRIBUTION, VENTILATION, AND EXHAUST SYSTEM.

3.3.2.1 Installation on Exposed Duct Work

a. For rectangular ducts, rigid insulation shall be secured to the duct by mechanical fasteners on all four sides of the duct, spaced not more than 12 inches apart and not more than 3 inches from the edges of the insulation joints. A minimum of two rows of fasteners shall be provided for each side of duct 12 inches and larger. One row shall be provided for each side of duct less than 12 inches. Mechanical fasteners shall be as corrosion resistant as G60 coated galvanized steel, and shall indefinitely sustain a 50 lb tensile dead load test perpendicular to the duct wall.

b. Form duct insulation with minimum jacket seams. Fasten each piece of rigid insulation to the duct using mechanical fasteners. When the height of projections is less than the insulation thickness, insulation shall be brought up to standing seams, reinforcing, and other vertical projections and shall not be carried over. Vapor retarder/barrier jacket shall be continuous across seams, reinforcing, and projections. When height of projections is greater than the insulation thickness, insulation and jacket shall be carried over. Apply insulation with joints tightly butted. Neatly bevel insulation around name plates and access plates and doors.

c. Impale insulation on the fasteners; self-locking washers shall be installed and the pin trimmed and bent over.

d. Seal joints in the insulation jacket with a 4 inch wide strip of tape. Seal taped seams with a brush coat of vapor retarder coating.

e. Breaks and ribs or standing seam penetrations in the jacket material shall be covered with a patch of the same material as the jacket. Patches shall extend not less than 2 inches beyond the break or penetration and shall be secured with tape and stapled. Staples and joints shall be sealed with a brush coat of vapor retarder coating.

f. At jacket penetrations such as hangers, thermometers, and damper operating rods, the voids in the insulation shall be filled and the penetrations sealed with a flashing sealant.

g. Insulation terminations and pin punctures shall be sealed and flashed with a reinforced vapor retarder coating finish. The coating shall overlap the adjoining insulation and un-insulated surface 2 inches. Pin puncture coatings shall extend 2 inches from the puncture in all directions.

3.3.3 Ducts Handling Air for Dual Purpose

For air handling ducts for dual purpose below and above 60 degrees F, ducts shall be insulated as specified for cold air duct.

3.3.4 Duct Test Holes

After duct systems have been tested, adjusted, and balanced, breaks in the insulation and jacket shall be repaired in accordance with the applicable section of this specification for the type of duct insulation to be repaired.

3.3.5 Duct Exposed to Weather

3.3.5.1 Installation

Ducts exposed to weather shall be insulated and finished as specified for the applicable service for exposed duct inside the building. After the above is accomplished, the insulation shall then be further finished as detailed in the following subparagraphs.

3.3.5.2 Fittings

Fittings and other irregular shapes shall be finished as specified for rectangular ducts.

3.3.5.3 Rectangular Ducts

Two coats of weather barrier mastic reinforced with fabric or mesh for outdoor application shall be applied to the entire surface. Each coat of weatherproof mastic shall be 1/16 inch minimum thickness. The exterior shall be a metal jacketing applied for mechanical abuse and weather protection, and secured with screws or vapor barrier/weatherproofing jacket less than 0.0000 permeability greater than 3 ply, standard grade, silver, white, black, and embossed or greater than 8 ply, heavy duty white and natural. Membrane shall be applied overlapping material by 3 inches. No bands or caulking needed-see manufacturing recommend installation instructions.

-- End of Section --

SECTION 23 09 23.13 20

DIRECT DIGITAL CONTROL SYSTEMS FOR HVAC
06/12

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AIR MOVEMENT AND CONTROL ASSOCIATION INTERNATIONAL (AMCA)

AMCA 500-D	(1998) Laboratory Methods of Testing Dampers for Rating

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI/ATA 878.1	(1999) ARCNET - Local Area Network: Token Ring

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE 135	(2008; Addenda J,L,Q,R,S,V 2009; Errata 1 & 2 2009:INT 1 & 2 2009) BACnet—A Data Communication Protocol for Building Automation and Control Networks

ASME INTERNATIONAL (ASME)

ASME B16.5	(2009) Standard for Pipe Flanges and Flanged Fittings: NPS 1/2 Through NPS 24
ASME B31.1	(2007; Addenda 2008; Addenda 2009) Power Piping

ASTM INTERNATIONAL (ASTM)

ASTM A 126	(2004) Standard Specification for Gray Iron Castings for Valves, Flanges, and Pipe Fittings
ASTM B 117	(2009) Standing Practice for Operating Salt Spray (Fog) Apparatus

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C57.13	(2008) Standard Requirements for Instrument Transformers
IEEE C62.41.1	(2002; R 2008) IEEE Guide on the Surges Environment in Low-Voltage (1000 V and Less) AC Power Circuits

IEEE C62.41.2	(2002) IEEE Recommended Practice on Characterization of Surges in Low-Voltage (1000 V and Less) AC Power Circuits
IEEE C62.45	(2002; R 2008) Surge Testing for Equipment Connected to Low-Voltage (1000v and less)AC Power Circuits

INTERNATIONAL ORGANIZATION FOR STANDARDIZATION (ISO)

ISO/IEC 8802	(2000) Telecommunications and Information Exchange Between Systems

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition
NFPA 72	(2010) National Fire Alarm Code
NFPA 90A	(2008; Errata 2009) Standard for the Installation of Air Conditioning and Ventilating Systems

NATIONAL FLUID POWER ASSOCIATION (NFLPA)

NFLPA C12.10	(2004) Watthour Meters

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

SMACNA 1966	(2005) HVAC Duct Construction Standards Metal and Flexible

UNDERWRITERS LABORATORIES (UL)

UL 1449	(2006; Rev thru Sep 2009) Surge Protective Devices
UL 506	(2000; Rev thru May 2006) Standard for Specialty Transformers
UL 508A	(2001; Rev thru Sep 2009) Standard for Industrial Control Panels
UL 916	(2007) Energy Management Equipment

1.2 DEFINITIONS

1.2.1 ANSI/ASHRAE Standard 135

ANSI/ASHRAE Standard 135: BACnet - A Data Communication Protocol for Building Automation and Control Networks, referred to as "BACnet". ASHRAE developed BACnet to provide a method for diverse building automation devices to communicate and share data over a network.

1.2.2 ARCNET

ANSI/ATA 878.1 - Attached Resource Computer Network. ARCNET is a

deterministic LAN technology; meaning it's possible to determine the maximum delay before a device is able to transmit a message.

1.2.3 BACnet

Building Automation and Control Network; the common name for the communication standard ASHRAE 135. The standard defines methods and protocol for cooperating building automation devices to communicate over a variety of LAN technologies.

1.2.4 BACnet/IP

An extension of BACnet, Annex J, defines this mechanism using a reserved UDP socket to transmit BACnet messages over IP networks. A BACnet/IP network is a collection of one or more IP subnetworks that share the same BACnet network number. See also "BACnet Broadcast Management Device".

1.2.5 BACnet Internetwork

Two or more BACnet networks, possibly using different LAN technologies, connected with routers. In a BACnet internetwork, there exists only one message path between devices.

1.2.6 BACnet Network

One or more BACnet segments that have the same network address and are interconnected by bridges at the physical and data link layers.

1.2.7 BACnet Segment

One or more physical segments of BACnet devices on a BACnet network, connected at the physical layer by repeaters.

1.2.8 BBMD

BACnet Broadcast Management Device (BBMD). A communications device, typically combined with a BACnet router. A BBMD forwards BACnet broadcast messages to BACnet/IP devices and other BBMDs connected to the same BACnet/IP network. Every IP subnetwork that is part of a BACnet/IP network must have only one BBMD. See also "BACnet/IP".

1.2.9 BAS

Building Automation Systems, including DDC (Direct Digital Controls) used for facility automation and energy management.

1.2.10 BAS Owner

The regional or local user responsible for managing all aspects of the BAS operation, including: network connections, workstation management, submittal review, technical support, control parameters, and daily operation. The BAS Owner for this project is Cherry Point.

1.2.11 BIBBs

BACnet Interoperability Building Blocks. A collection of BACnet services used to describe supported tasks. BIBBs are often described in terms of "A" (client) and "B" (server) devices. The “A” device uses data provided by the "B" device, or requests an action from the “B” device.

1.2.12 BI

BACnet International, formerly two organizations: the BACnet Manufacturers Association (BMA) and the BACnet Interest Group - North America (BIG-NA).

1.2.13 BI/BTL

BACnet International/BACnet Testing Laboratories (Formerly BMA/BTL). The organization responsible for testing products for compliance with the BACnet standard, operated under the direction of BACnet International.

1.2.14 Bridge

Network hardware that connects two or more network (or BACnet internetwork) segments at the physical and data link layers. A bridge may also filter messages.

1.2.15 Broadcast

A message sent to all devices on a network segment.

1.2.16 Device

Any control system component, usually a digital controller, that contains a BACnet Device Object and uses BACnet to communicate with other devices. See also "Digital Controller".

1.2.17 Device Object

Every BACnet device requires one Device Object, whose properties represent the network visible properties of that device. Every Device Object requires a unique Object Identifier number on the BACnet internetwork. This number is often referred to as the device instance.

1.2.18 Device Profile

A collection of BIBBs determining minimum BACnet capabilities of a device, defined in ASHRAE Standard 135-2004, Annex L. Standard device profiles include BACnet Operator Workstations (B-OWS), BACnet Building Controllers (B-BC), BACnet Advanced Application Controllers (B-AAC), BACnet Application Specific Controllers (B-ASC), BACnet Smart Actuator (B-SA), and BACnet Smart Sensor (B-SS). Each device used in new construction is required to have a PICS statement listing BIBBs supported.

1.2.19 Digital Controller

An electronic controller, usually with internal programming logic and digital and analog input/output capability, which performs control functions. In most cases, synonymous with a BACnet device described in this specification. See also "Device".

1.2.20 Direct Digital Control (DDC)

Digital controllers performing control logic. Usually the controller directly senses physical values, makes control decisions with internal programs, and outputs control signals to directly operate switches, valves, dampers, and motor controllers.

1.2.21 DDC System

A network of digital controllers, communication architecture, and user interfaces. A DDC system may include programming, sensors, actuators, switches, relays, factory controls, operator workstations, and various other devices, components, and attributes.

1.2.22 Ethernet

A family of local-area-network technologies providing high-speed networking features over various media.

1.2.23 Firmware

Software programmed into read only memory (ROM), flash memory, electrically erasable programmable read only memory (EEPROM), or erasable programmable read only memory (EPROM) chips.

1.2.24 Gateway

Communication hardware connecting two or more different protocols, similar to human language translators. The Gateway translates one protocol into equivalent concepts for the other protocol. In BACnet applications, a gateway has BACnet on one side and non-BACnet (usually proprietary) protocols on the other side.

1.2.25 Half Router

A device that participates as one partner in a BACnet point-to-point (PTP) connection. Two half-routers in an active PTP connection combine to form a single router.

1.2.26 Hub

A common connection point for devices on a network.

1.2.27 Internet Protocol (IP, TCP/IP, UDP/IP)

A communication method, the most common use is the World Wide Web. At the lowest level, it is based on Internet Protocol (IP), a method for conveying and routing packets of information over various LAN media. Two common protocols using IP are User Datagram Protocol (UDP) and Transmission Control Protocol (TCP). UDP conveys information to well-known "sockets" without confirmation of receipt. TCP establishes "sessions", which have end-to-end confirmation and guaranteed sequence of delivery.

1.2.28 Input/Output (I/O)

Physical inputs and outputs to and from a device, although the term sometimes describes software, or "virtual" I/O. See also "Points".

1.2.29 I/O Expansion Unit

An I/O expansion unit provides additional point capacity to a digital controller.

1.2.30 IP subnet

Internet protocol (IP) identifies individual devices with a 32-bit number

divided into four groups from 0 to 255. Devices are often grouped and share some portion of this number. For example, one device has IP address 209.185.47.68 and another device has IP address 209.185.47.82. These two devices share Class C subnet 209.185.47.00

1.2.31 Local-Area Network (LAN)

A communication network that spans a limited geographic area and uses the same basic communication technology throughout.

1.2.32 LonTalk

ANSI/EIA 709. A communication protocol developed by Echelon Corp. LonTalk is an optional physical and data link layer for BACnet.

1.2.33 MAC Address

Media Access Control address. The physical node address that identifies a device on a Local Area Network.

1.2.34 Master-Slave/Token-Passing (MS/TP)

ISO/IEC 8802 (Part 3). One of the LAN options for BACnet. MSTP uses twisted-pair wiring for relatively low speed and low cost communication (up to 4,000 ft at 76.8K bps).

1.2.35 Native BACnet Device

A device that uses BACnet as its primary, if not only, method of communication with other BACnet devices without intermediary gateways. A system that uses native BACnet devices at all levels is a native BACnet system.

1.2.36 Network

Communication technology for data communications. BACnet approved network types are BACnet over Internet Protocol (IP), Point to Point (PTP) Ethernet, ARCNET, MS/TP, and LonTalk®.

1.2.37 Network Number

A site-specific number assigned to each network segment to identify for routing. This network number must be unique throughout the BACnet internetwork.

1.2.38 Object

The concept of organizing BACnet information into standard components with various associated properties. Examples include analog input objects and binary output objects.

1.2.39 Object Identifier

An object property used to identify the object, including object type and instance. Object Identifiers must be unique within a device.

1.2.40 Object Properties

Attributes of an object. Examples include present value and high limit

properties of an analog input object. Properties are defined in ASHRAE 135; some are optional and some are required. Objects are controlled by reading from and writing to object properties.

1.2.41 Peer-to-Peer

Peer-to-peer refers to devices where any device can initiate and respond to communication with other devices.

1.2.42 Performance Verification Test (PVT)

The procedure for determining if the installed BAS meets design criteria prior to final acceptance. The PVT is performed after installation, testing, and balancing of mechanical systems. Typically the PVT is performed by the Contractor in the presence of the Government.

1.2.43 PID

Proportional, integral, and derivative control; three parameters used to control modulating equipment to maintain a setpoint. Derivative control is often not required for HVAC systems (leaving "PI" control).

1.2.44 PICS

Protocol Implementation Conformance Statement (PICS), describing the BACnet capabilities of a device. See BACnet, Annex A for the standard format and content of a PICS statement.

1.2.45 Points

Physical and virtual inputs and outputs. See also "Input/Output".

1.2.46 PTP

Point-to-Point protocol connects individual BACnet devices or networks using serial connections like modem-to-modem links.

1.2.47 Repeater

A network component that connects two or more physical segments at the physical layer.

1.2.48 Router

A BACnet router is a component that joins together two or more networks using different LAN technologies. Examples include joining a BACnet Ethernet LAN to a BACnet MS/TP LAN.

1.2.49 Stand-Alone Control

Refers to devices performing equipment-specific and small system control without communication to other devices or computers for physical I/O, excluding outside air and other common shared conditions. Devices are located near controlled equipment, with physical input and output points limited to 64 or less per device, except for complex individual equipment or systems. Failure of any single device will not cause other network devices to fail. BACnet "Smart" actuators (B-SA profile) and sensors (B-SS profile) communicating on a network with a parent device are exempt from stand-alone requirements.

1.3 SUBCONTRACTOR SPECIAL REQUIREMENTS

Perform all work in this section in accordance with the paragraph entitled "Subcontractor Special Requirements" in Section 01 30 00 ADMINISTRATIVE REQUIREMENTS. The paragraph specifies that all contract requirements of this section shall be accomplished directly by a first tier subcontractor. No work required shall be accomplished by a second tier subcontractor.

1.4 DIRECT DIGITAL CONTROL SYSTEMS FOR HVAC DESCRIPTION

Provide a BACnet compliant DDC systems including associated equipment and accessories. Manufacturer's products, including design materials, fabrication, assembly, erection, examination, inspections, and testing shall be in accordance with ASME B31.1 and NFPA 70, except as modified herein or indicated otherwise. The new DDC system shall interface and communicate with the existing Energy Management and Control System (EMCS) central server at MCAS Cherry Point, Building 137 utilizing the existing EMCS Ethernet network.

1.4.1 Design Requirements

1.4.1.1 Control System Drawings Title Sheet

Provide a title sheet for the control system drawing set. Include the project title, project location, contract number, the controls contractor preparing the drawings, an index of the control drawings in the set, and a legend of the symbols and abbreviations used throughout the control system drawings.

1.4.1.2 List of I/O Points

Also known as a Point Schedule, provide for each input and output point physically connected to a digital controller: point name, point description, point type (Analog Output (AO), Analog Input (AI), Binary Output (BO), Binary Input (BI)), point sensor range, point actuator range, point address, BACnet object, associated BIBBS (where applicable), and point connection terminal number. Typical schedules for multiple identical equipment are allowed unless otherwise requested in design or contract criteria.

1.4.1.3 Control System Components List

Provide a complete list of control system components installed on this project. Include for each controller and device: control system schematic name, control system schematic designation, device description, manufacturer, and manufacturer part number. For sensors, include point name, sensor range, and operating limits. For valves, include body style, Cv, design flow rate, pressure drop, valve characteristic (linear or equal percentage), and pipe connection size. For actuators, include point name, spring or non-spring return, modulating or two-position action, normal (power fail) position, nominal control signal operating range (0-10 volts DC or 4-20 milliamps), and operating limits.

1.4.1.4 Control System Schematics

Provide control system schematics. Typical schematics for multiple identical equipment are allowed unless otherwise requested in design or contract criteria. Include the following:

a. Location of each input and output device

b. Flow diagram for each piece of HVAC equipment

c. Name or symbol for each control system component, such as V-1 for a valve

d. Setpoints, with differential or proportional band values

e. Written sequence of operation for the HVAC equipment

f. Valve and Damper Schedules, with normal (power fail) position

1.4.1.5 HVAC Equipment Electrical Ladder Diagrams

Provide HVAC equipment electrical ladder diagrams. Indicate required electrical interlocks.

1.4.1.6 Component Wiring Diagrams

Provide a wiring diagram for each type of input device and output device. Indicate how each device is wired and powered; showing typical connections at the digital controller and power supply. Show for all field connected devices such as control relays, motor starters, actuators, sensors, and transmitters.

1.4.1.7 Terminal Strip Diagrams

Provide a diagram of each terminal strip. Indicate the terminal strip location, termination numbers, and associated point names.

1.4.1.8 Communication Architecture Schematic

Provide a schematic showing the project's entire communication network, including addressing used for LANs, LAN devices including media converters, switches, routers and bridges, gateways, controllers, workstations, and field interface devices. If applicable, show connection to existing networks. Show bus routing and component locations on a separate floor plan.

1.5 SUBMITTALS

Submit detailed and annotated manufacturer's data, drawings, and specification sheets for each item listed, that clearly show compliance with the project specifications.

Submit the following according to 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Include the following in the project's control system drawing set:

Control system drawings title sheet

List of I/O Points

Control System Components List

Control system schematics

HVAC Equipment Electrical Ladder diagrams

Component wiring diagrams

Terminal strip diagrams

Communication architecture schematic

SD-03 Product Data

Direct Digital Controllers

Include BACnet PICS for each controller/device type, including smart sensors (B-SS) and smart actuators (B-SA).

BACnet Gateways

Include BACnet and workstation display information; bi-directional communication ability; compliance with interoperability schedule; expansion capacity; handling of alarms, events, scheduling and trend data; and single device capability (not depending on multiple devices for exchanging information from either side of the gateway).

BACnet Protocol Analyzer

Include capability to store and report data traffic on BACnet networks, measure bandwidth usage, filter information, and identify BACnet devices.

DDC Software

Sensors and Input Hardware

Output Hardware

Surge and transient protection

Indicators

Duct smoke detectors

SD-05 Design Data

Performance Verification Testing Plan

Pre-Performance Verification Testing Checklist

SD-06 Test Reports

Performance Verification Testing Report

SD-07 Certificates

Contractor's Qualifications

SD-09 Manufacturer's Field Reports

Pre-PVT Checklist

SD-10 Operation and Maintenance Data

Comply with requirements for data packages in Section 01 78 23 OPERATION AND MAINTENANCE DATA, except as supplemented and modified in this specification.

BACnet Direct Digital Control Systems, Data Package 4

SD-11 Closeout Submittals

Training documentation

1.6 QUALITY ASSURANCE

1.6.1 Standard Products

Provide material and equipment that are standard manufacturer's products currently in production and supported by a local service organization.

1.6.2 Delivery, Storage, and Handling

Handle, store, and protect equipment and materials to prevent damage before and during installation according to manufacturer's recommendations, and as approved by the Contracting Officer. Replace damaged or defective items.

1.6.3 Operating Environment

Protect components from humidity and temperature variation, dust, and contaminants. If components are stored before installation, keep them within the manufacturer's limits.

1.6.4 Finish of New Equipment

New equipment finishing shall be factory provided. Manufacturer's standard factory finishing shall be proven to withstand 125 hours in a salt-spray fog test. Equipment located outdoors shall be proven to withstand 500 hours in a salt-spray fog test.

Salt-spray fog test shall be according to ASTM B 117, with acceptance criteria as follows: immediately after completion of the test, the finish shall show no signs of degradation or loss of adhesion beyond 0.125 inch on either side of the scratch mark.

1.6.5 Verification of Dimensions

The contractor shall verify all dimensions in the field, and advise the Contracting Officer of any discrepancy before performing work.

1.6.6 Contractor's Qualifications

Submit documentation certifying the controls Contractor performing the work has completed at least three DDC systems installations of a similar design to this project, and programmed similar sequences of operation for at least two years.

1.6.7 Modification of References

The advisory provisions in ASME B31.1 and NFPA 70 are mandatory. Substitute "shall" for "should" wherever it appears and interpret all references to the "authority having jurisdiction" and "owner" to mean the Contracting Officer.

1.6.8 Project Sequence

The control system work for this project shall proceed in the following order:

a. Submit and receive approval on the Shop Drawings, Product Data, and Certificates specified under the paragraph entitled "SUBMITTALS."

b. Perform the control system installation work, including all field check-outs and tuning.

c. Provide support to TAB personnel as specified under the paragraph "TEST AND BALANCE SUPPORT."

d. Submit and receive approval of the Controls System Operators Manual specified under the paragraph "CONTROLS SYSTEM OPERATORS MANUALS."

e. Submit and receive approval of the Performance Verification Testing Plan and the Pre-PVT Checklist specified under the paragraph "PERFORMANCE VERIFICATION TESTING."

f. Perform the Performance Verification Testing.

g. Submit and receive approval on the PVT Report.

h. Submit and receive approval on the Training Documentation specified under the paragraph "INSTRUCTION TO GOVERNMENT PERSONNEL". Submit at least 30 days before training.

i. Deliver the final Controls System Operators Manuals.

j. Conduct the Phase I Training.

k. Conduct the Phase II Training.

l. Submit and receive approval of Closeout Submittals.

PART 2 PRODUCTS

2.1 DDC SYSTEM

a. Provide new DDC systems including associated equipment, accessories and communication media. Manufacturer's products, including design materials, fabrication, assembly, erection, examination, inspections, and testing shall be in accordance with ASME B31.1 and NFPA 70, except as modified herein or indicated otherwise. The new DDC system shall interface and communicate with the existing Energy Management and Control System (EMCS) at MCAS Cherry Point, Building 137. The new DDC system shall use Cherry Point's Point Naming Nomenclature and Graphical Standards attached at the end of this section. The new DDC system via the supervisory building controller shall be capable of

upload/download from the central server at Building 137. All DDC points whether physical or pseudo, shall be exposed as BACnet objects and accessible by the Metasys server in Building 137 for purposes of monitoring status, controlling operation, or modifying values. The new DDC system shall have the capability of managing its loads using the existing EMCS Johnson Control load management programming.

b. The Energy Management and Control System (EMCS) at MCAS Cherry Point is an enterprise system that actively receives energy and building condition information from multiple sources and provides load shedding, electric metering, alarming, trending, scheduling, set point adjusting, device communications status of all SBC and TCU for maintenance personnel. The existing EMCS system is Johnson Controls and incorporates the Metasys System that communicates over the Ethernet communications network to the supervisory building controllers. The existing EMCS central server is located at Building 137.

c. If applicable, provide a supervisory building controller (SBC) for the new DDC system. Provide all necessary hardware, drivers, software, material, and equipment, which shall allow communication between the SBC and the existing EMCS system via the UMAC Ethernet network. The SBC shall act as the interface between the existing EMCS system and the new DDC system. The SBC shall perform closed-loop, modulating control of building equipment, provide all programming and communication with the DDC system such that it shall maintain stable temperature control and all other conditions as indicated. The end-to-end accuracy of the system, including temperature sensor error, wiring error, A/D conversion, and display, shall be 1 degree F or less.

d. Provide a complete fully BACnet Open Protocol compatible Direct Digital Control (DDC) system. The system shall have stand-alone digital controllers that are connected to the SBC. All BACnet devices shall be BACnet Testing Laboratories (BTL) certified and listed. The DDC system shall be capable of controlling and monitoring all spaces and all HVAC systems. The manufacturer's control system shall have a successful, proven, in use history of at least 2 years. The DDC control system object configuration and communication - shall be totally native BACnet Open protocol with no other programming language protocol, interface, or gateways utilized, except as required by the Project documents.

e. The contractor shall update the existing Johnson Controls server, ADX-1, located in Building 137 to incorporate and integrate the new DDC system. The update requirements include, but are not limited to the EMCS server database, graphics for the new DDC system and any other affected graphics, and programming of all load management functions.

The contractor shall fully test and verify all levels of control and communication of all the DDC system controllers from the existing Johnson Controls ECMS server in Building 137. The contractor shall also test and verify all levels of control and communication of the new DDC system.

2.1.1 Direct Digital Controllers

All new direct digital controllers shall be native BACnet and UL 916 rated.

2.1.1.1 I/O Point Limitation

The total number of I/O hardware points used by a single stand-alone digital controller, including I/O expansion units, shall not exceed 64, except for complex individual equipment or systems. Place I/O expansion units in the same cabinet as the digital controller.

2.1.1.2 Environmental Limits

Controllers shall be suitable for, or placed in protective enclosures suitable for the environment (temperature, humidity, dust, and vibration) where they are located.

2.1.1.3 Stand-Alone Control

Provide stand-alone digital controllers.

2.1.1.4 Internal Clock

Provide internal clocks for all BACnet Building Controllers (B-BC) and BACnet Advanced Application Controllers (B-AAC) using BACnet time synchronization services. Automatically synchronize system clocks daily from an operator-designated controller. The system shall automatically adjust for daylight saving time.

2.1.1.5 Memory

Provide sufficient memory for each controller to support the required control, communication, trends, alarms, and messages. Protect programs residing in memory with EEPROM, flash memory, or by an uninterruptible power source (battery or uninterruptible power supply). The backup power source shall have capacity to maintain the memory during a 72-hour continuous power outage. Rechargeable power sources shall be constantly charged while the controller is operating under normal line power. Batteries shall be replaceable without soldering. Trend and alarm history collected during normal operation shall not be lost during power outages less than 72 hours long.

2.1.1.6 Immunity to Power Fluctuations

Controllers shall operate at 90 percent to 110 percent nominal voltage rating.

2.1.1.7 Transformer

The controller power supply shall be fused or current limiting and rated at 125 percent power consumption.

2.1.1.8 Wiring Terminations

Use screw terminal wiring terminations for all field-installed controllers. Provide field-removable modular terminal strip or a termination card connected by a ribbon cable for all controllers other than terminal units.

2.1.1.9 Input and Output Interface

Provide hard-wired input and output interface for all controllers as follows:

a. Protection: Shorting an input or output point to itself, to another point, or to ground shall cause no controller damage. Input or output point contact with sources up to 24 volts AC or DC for any duration shall cause no controller damage.

b. Binary Inputs: Binary inputs shall have a toggle switch and monitor on and off contacts from a "dry" remote device without external power, and external 5-24 VDC voltage inputs.

c. Pulse Accumulation Inputs: Pulse accumulation inputs shall conform to binary input requirements and accumulate pulses at a resolution suitable to the application.

d. Analog Inputs: Analog inputs shall monitor low-voltage (0-10 VDC), current (4-20 mA), or resistance (thermistor or RTD) signals.

e. Binary Outputs: Binary outputs shall have a toggle switch and send a pulsed 24 VDC low-voltage signal for modulation control, or provide a maintained open-closed position for on-off control. For HVAC equipment and plant controllers, provide for manual overrides, either with three-position (on-off-auto) override switches and status lights, or with an adjacent operator display and interface. Where appropriate, provide a method to select normally open or normally closed operation.

f. Analog Outputs: Analog outputs shall send modulating 0-10 VDC or 4-20 mA signals to control output devices.

g. Tri-State Outputs: Tri-State outputs shall provide three-point floating control of terminal unit electronic actuators.

2.1.1.10 BACnet Gateways

Provide BACnet communication ports, whenever available as a plant equipment OEM standard option, for DDC integration via a single communication cable. Typical BACnet controlled plant equipment includes, but is not limited to, boilers, chillers, and variable frequency motor drives.

Provide gateways to connect BACnet to legacy systems, existing non-BACnet devices, and existing non-BACnet DDC controlled plant equipment, only when specifically requested and approved by the Government, and shown on the Government approved BACnet Communication Architecture Schematic. Provide with each gateway an interoperability schedule, showing each point or event on the legacy side that the BACnet "client" will read, and each parameter that the BACnet network will write to. Describe this interoperability in terms of BACnet services, or Interoperability Building Blocks (BIBBS), defined in ASHRAE 135 Annex K. Provide two-year minimum warranty for each gateway, including parts and labor.

The following minimum capabilities are required:

a. Gateways shall be able to read and view all readable object properties listed in the interoperability schedule on the non-BACnet network to the BACnet network and vice versa where applicable.

b. Gateways shall be able to write to all writeable object properties listed in the interoperability schedule on the non-BACnet network from the BACnet network and vice versa where applicable.

c. Gateways shall provide single-pass (only one protocol to BACnet without intermediary protocols) translation from the non-BACnet protocol to BACnet and vice versa.

d. Gateways shall meet the requirements of Data Sharing Read Property (DS-RP-B), Data Sharing Write Property (DS-WP-B), Device Management Dynamic Device Binding-B (DM-DDB-B), and Device Management Communication Control (DM-DCC-B) BIBBs, in accordance with ASHRAE 135.

e. Gateways shall include all hardware, software, software licenses, and configuration tools for operator-to-gateway communications. Provide backup programming and parameters on CD media and the ability to modify, download, backup, and restore gateway configuration.

2.1.1.11 Digital Controller Cabinet

Provide each digital controller in a factory fabricated cabinet enclosure. Cabinets located indoors shall protect against dust and have a minimum NEMA 1 rating, except where indicated otherwise. Cabinets located outdoors or in damp environments shall protect against all outdoor conditions and have a minimum NEMA 4 rating. Outdoor control panels and controllers must be able to withstand extreme ambient conditions, without malfunction or failure, whether or not the controlled equipment is running. If necessary, provide a thermostatically controlled panel heater in freezing locations, and an internal ventilating fan in locations exposed to direct sunlight. Cabinets shall have a hinged lockable door and an offset removable metal back plate, except controllers integral with terminal units, like those mounted on VAV boxes. Provide like-keyed locks for all hinged panels provided and a set of two keys at each panel, with one key inserted in the lock.

2.1.1.12 Main Power Switch and Receptacle

Provide each control cabinet with a main external power on/off switch located inside the cabinet. Also provide each cabinet with a separate 120 VAC duplex receptacle.

2.1.2 DDC System Integration and Monitoring

a. A workstation shall not be provided unless other wise noted.

b. All interface to the DDC system shall be provided through the existing EMCS server at Building 137. The workstation via the EMCS server at Building 137 shall be capable of monitoring, troubleshooting, and making adjustments to the program or operating parameters of all DDC controllers, including TCU's. The workstation shall also be capable of remotely programming of all controllers, including TCU's. The contractor shall provide a temporary workstation for system interface and start-up until the connection to the EMCS server at Building 137 is completed, tested, and verified.

c. DDC system shall routinely operate continuously without connection to the workstation. Information at the workstation is not

required for day to day operations of the direct digital controllers.

2.1.2.1 Software

The EMCS server (ADX-1) uses Johnson Controls Incorporation (JCI) Metasys Extended Architecture (MESA) software. Modify and update the existing EMCS server at Building 137 as necessary for proper interface with the new DDC system. The MESA software shall be configured to operate according to the DDC system manufacturer's specifications. Software shall be installed in the supervisoty building controller (SBC) that permits monitoring and troubleshooting of the DDC system using the ADX-1 server. The ADX-1 in conjunction with the SBC software shall permit modification of controller parameters and control for all controllers, both high level and low level application specific. Operations shall be menu selected. Menu selections shall be made with a mouse.

a. Menu System: Menu system shall allow an operator to select a particular function or access a particular screen through successive menu penetration or icon selection.

b. Controller Parameter Modification: The ADX-1 software shall be an interface for performance specified in paragraph entitled "Parameter Modification" and available through a workstation logged into the ADX-1 server. Parameter modification shall require only that an operator "fill in the blank" for a parameter on a screen requesting the information in plain language. Parameter modifications shall download to the appropriate controllers at the operator request.

2.1.2.2 Graphic-Based Software

Update the existing graphics located on the ADX-1 server in Building 137 to incorporate and integrate the new DDC system. Create new graphics as required for the new DDC controllers. Graphic-based software shall provide graphical location of the building on the map, the building floor plan, the building mechanical systems, and the DDC system. The current value and point name of every I/O point shall be shown on at least one graphic and in its appropriate physical location relative to building and mechanical systems.

a. Graphic shall closely follow the style of the control drawings in representing mechanical systems, sensors, controlled devices and point names.

b. Graphic Title: Graphics shall have an identifying title visible when the graphic is viewed.

c. Dynamic Update: When the ADX-1 server is on-line with the control system, point data shall update dynamically on the graphic images.

d. Graphic Penetration: Provide graphic penetration using buttons to select graphics with more detail or to select different equipment.

e. Graphic Types: Graphic-based software shall have graphics of the building exterior, building section, floor plans, and mechanical systems. At a minimum, provide the following graphics:

(1) Building Exterior Graphic: Show exterior architecture, major

landmarks, and building number.

(2) Building Section Graphic: Show floors in section graphic with appropriate floor name on each floor.

(3) Floor Plan Graphics: Provide a single graphic for each floor, unless the graphic will contain more information than can reasonably be shown on a single graphic. Each heating or cooling zone within a floor plan shall have a zone name and its current temperature displayed within the zone outline. Show each controlled variable in the zone. Provide visual warning for each point in alarm. Show existing and new bus routings on floor plan as physically installed in the building.

(4) Mechanical System Graphics: Provide two-dimensional drawings to symbolize mechanical equipment; do not use line drawings. Show controlled or sensed mechanical equipment. Each graphic shall consist of a single mechanical system; examples are a graphic for an air handling unit, a graphic for a VAV box, a graphic for a heating water system and a graphic for a chiller system. Place point name and point value adjacent to sensor or controlled device. Provide visual warning of each point in alarm. Point values shall update dynamically on the graphic.

2.1.3 DDC Software

2.1.3.1 Programming

Provide programming to execute the sequence of operation indicated. Provide all programming and tools to configure and program all controllers. Provide programming routines in simple, easy-to-follow logic with detailed text comments describing what the logic does and how it corresponds to the project's written sequence of operation.

a. Graphic-based programming shall use a library of function blocks made from pre-programmed code designed for BAS control. Function blocks shall be assembled with interconnecting lines, depicting the control sequence in a flowchart. If providing a computer with device programming tools as part of the project, graphic programs shall be viewable in real time showing present values and logical results from each function block.

b. Menu-based programming shall be done by entering parameters, definitions, conditions, requirements, and constraints.

c. For line-by-line and text-based programming, declare variable types (local, global, real, integer, etc.) at the beginning of the program. Use descriptive comments frequently to describe the programming.

d. If providing a computer with device programming tools as part of the project, provide a means for detecting program errors and testing software strategies with a simulation tool. Simulation may be inherent within the programming software suite, or provided by physical controllers mounted in a NEMA 1 test enclosure. The test enclosure shall contain one dedicated controller of each type provided under this contract, complete with power supply and relevant accessories.

2.1.3.2 Parameter Modification

All writeable object properties, and all other programming parameters

needed to comply with the project specification shall be adjustable for devices at any network level, including those accessible with web-browser communication, and regardless of programming methods used to create the applications.

2.1.3.3 Short Cycling Prevention

Provide setpoint differentials and minimum on/off times to prevent equipment short cycling.

2.1.3.4 Equipment Status Delay

Provide an adjustable delay from when equipment is commanded on or off and when the control program looks to the status input for confirmation.

2.1.3.5 Run Time Accumulation

Use the Elapsed Time Property to provide re-settable run time accumulation for each Binary Output Object connected to mechanical loads greater than 1 HP, electrical loads greater than 10 KW, or wherever else specified.

2.1.3.6 Timed Local Override

Provide an adjustable override time for each push of a timed local override button.

2.1.3.7 Time Synchronization

Provide time synchronization, including adjustments for leap years, daylight saving time, and operator time adjustments.

2.1.3.8 Scheduling

Provide operating schedules as indicated, with equipment assigned to groups. Changing the schedule of a group shall change the operating schedule of all equipment in the group. Groups shall be capable of operator creation, modification, and deletion. Provide capability to view and modify schedules in a seven-day week format. Provide capability to enter holiday and override schedules one full year at a time.

2.1.3.9 Object Property Override

Allow writeable object property values to accept overrides to any valid value. Where specified or required for the sequence of control, the Out_Of_Service property of Objects shall be modifiable using BACnet's write property service. When documented, exceptions to these requirement are allowed for life, machine, and process safeties.

2.1.3.10 Alarms and Events

Alarms and events shall be capable of having programmed time delays and high-low limits. When a computer workstation or web server is connected to the BACnet internetwork, alarms/events shall report to the computer, printer, e-mail, as defined by an authorized operator. Otherwise alarms/events shall be stored within a device on the BACnet network until connected to a user interface device and retrieved. Provide alarms/events in agreement with the point schedule, sequence of operation, and the BAS Owner. At a minimum, provide programming to initiate alarms/events any time a piece of equipment fails to operate, a control point is outside

normal range or condition shown on schedules, communication to a device is lost, a device has failed, or a controller has lost its memory.

2.1.3.11 Trending

Provide trend services on the supervisory building controller capable of trending all object present values set points, and other parameters indicated for trending on project schedules. Trends may be associated into groups, and a trend report may be set up for each group. Trends are stored within a device on the BACnet network, with operator selectable trend intervals from 10 seconds up to 60 minutes and/or change of value set points. The minimum number of consecutive trend values stored at one time shall be 100 per variable. When trend memory is full, it shall be selectable to stop trending or overwrite the oldest data. Upon reaching 3/4 of the device buffer limit (via Notification_Threshold property), by operator request, or by time schedule for archiving. Archived and real-time trend data shall be available for viewing numerically and graphically for at the EMCS server and connected notebook computers.

2.1.3.12 Device Diagnostics

Each controller shall have diagnostic LEDs for power, communication, and device fault condition. The DDC system shall recognize and report a non-responsive controller.

2.1.3.13 Power Loss

Upon restoration of power, the DDC system shall perform an orderly restart and restoration of control.

2.1.4 BACnet Protocol Analyzer

Provide a BACnet protocol analyzer and required cables and fittings for connection to the BACnet network. The analyzer shall include the following minimum capabilities:

a. Capture and store to a file data traffic on all network levels.

b. Measure bandwidth usage.

c. Filtering options with ability to ignore select traffic.

2.2 SENSORS AND INPUT HARDWARE

Coordinate sensor types with the BAS Owner to keep them consistent with existing installations.

2.2.1 Field-Installed Temperature Sensors

Where feasible, provide the same sensor type throughout the project. Avoid using transmitters unless absolutely necessary.

2.2.1.1 Thermistors

Precision thermistors may be used in applications below 200 degrees F. Sensor accuracy over the application range shall be 0.36 degree F or less between 32 to 150 degrees F. Stability error of the thermistor over five years shall not exceed 0.25 degrees F cumulative. A/D conversion resolution error shall be kept to 0.1 degrees F. Total error for a

thermistor circuit shall not exceed 0.5 degrees F.

2.2.1.2 Resistance Temperature Detectors (RTDs)

Provide RTD sensors with platinum elements compatible with the digital controllers. Encapsulate sensors in epoxy, series 300 stainless steel, anodized aluminum, or copper. Temperature sensor accuracy shall be 0.1 percent (1 ohm) of expected ohms (1000 ohms) at 32 degrees F. Temperature sensor stability error over five years shall not exceed 0.25 degrees F cumulative. Direct connection of RTDs to digital controllers without transmitters is preferred. When RTDs are connected directly, lead resistance error shall be less than 0.25 degrees F. The total error for a RTD circuit shall not exceed 0.5 degrees F.

2.2.1.3 Temperature Sensor Details

a. Room Type: Provide the sensing element components within a decorative protective cover suitable for surrounding decor. Provide room temperature sensors with timed override button, setpoint adjustment lever, digital temperature display.

b. Duct Probe Type: Ensure the probe is long enough to properly sense the air stream temperature.

c. Duct Averaging Type: Continuous averaging sensors shall be one foot in length for each 4 square feet of duct cross-sectional area, and a minimum length of 6 feet.

d. Pipe Immersion Type: Provide minimum three-inch immersion. Provide each sensor with a corresponding pipe-mounted sensor well, unless indicated otherwise. Sensor wells shall be stainless steel when used in steel piping, and brass when used in copper piping. Provide the sensor well with a heat-sensitive transfer agent between the sensor and the well interior.

e. Outside Air Type: Provide the sensing element on the building's north side with a protective weather shade that positions the sensor approximately 3 inches off the wall surface, does not inhibit free air flow across the sensing element, and protects the sensor from snow, ice, and rain.

2.2.2 Transmitters

Provide transmitters with 4 to 20 mA or 0 to 10 VDC linear output scaled to the sensed input. Transmitters shall be matched to the respective sensor, factory calibrated, and sealed. Size transmitters for an output near 50 percent of its full-scale range at normal operating conditions. The total transmitter error shall not exceed 0.1 percent at any point across the measured span. Supply voltage shall be 12 to 24 volts AC or DC. Transmitters shall have non-interactive offset and span adjustments. For temperature sensing, transmitter drift shall not exceed 0.03 degrees F a year.

2.2.2.1 Relative Humidity Transmitters

Provide transmitters with an accuracy equal to plus or minus 3 percent from 0 to 90 percent scale, and less than one percent drift per year. Sensing elements shall be the polymer type.

2.2.2.2 Pressure Transmitters

Provide transmitters integral with the pressure transducer.

2.2.3 Current Transducers

Provide current transducers to monitor motor amperage, unless current switches are shown on design drawings or point tables.

2.2.4 Pneumatic to Electric Transducers

Pneumatic to electronic transducers shall convert a 0 to 20 psig signal to a proportional 4 to 20 mA or 0 to 10 VDC signal (operator scaleable). Supply voltage shall be 24 VDC. Accuracy and linearity shall be 1.0 percent or better.

2.2.5 Air Quality Sensors

Provide power supply for each sensor.

2.2.5.1 CO2 Sensors

Provide photo-acoustic type CO2 sensors with integral transducers and linear output. The devices shall read CO2 concentrations between 0 and 2000 ppm with full scale accuracy of at least plus or minus 100 ppm.

2.2.5.2 Air Quality Sensors

Provide full spectrum air quality sensors using a hot wire element based on the Taguchi principle. The sensor shall monitor a wide range of gaseous volatile organic components common in indoor air contaminants like paint fumes, solvents, cigarette smoke, and vehicle exhaust. The sensor shall automatically compensate for temperature and humidity, have span and calibration potentiometers, operate on 24 VDC power with output of 0-10 VDC, and have a service rating of 32 to 140 degrees F and 5 to 95 percent relative humidity.

2.2.6 Input Switches

2.2.6.1 Timed Local Overrides

Provide buttons or switches to override the DDC occupancy schedule programming for each major building zone during unoccupied periods, and to return HVAC equipment to the occupied mode. This requirement is waived for zones clearly intended for 24 hour continuous operation.

2.2.7 Freeze Protection Thermostats

Provide special purpose thermostats with flexible capillary elements 20 feet minimum length for coil face areas up to 40 square feet. Provide longer elements for larger coils at 1-foot of element for every 4 square feet of coil face area, or provide additional thermostats. Provide switch contacts rated for the respective motor starter's control circuit voltage. Include auxiliary contacts for the switch's status condition. A freezing condition at any 18-inch increment along the sensing element's length shall activate the switch. The thermostat shall be equipped with a manual push-button reset switch so that when tripped, the thermostat requires manual resetting before the HVAC equipment can restart.

2.2.8 Air Flow Measurement Stations

Air flow measurement stations shall have an array of velocity sensing elements and straightening vanes inside a flanged sheet metal casing. The velocity sensing elements shall be the RTD or thermistor type, traversing the ducted air in at least two directions. The air flow pressure drop across the station shall not exceed 0.08 inch water gage at a velocity of 2,000 fpm. The station shall be suitable for air flows up to 5,000 fpm, and a temperature range of 40 to 120 degrees F. The station's measurement accuracy over the range of 125 to 2,500 fpm shall be plus or minus 3 percent of the measured velocity. Station transmitters shall provide a linear, temperature-compensated 4 to 20 mA or 0 to 10 VDC output. The output shall be capable of being accurately converted to a corresponding air flow rate in cubic feet per minute. Transmitters shall be a 2-wire, loop powered device. The output error of the transmitter shall not exceed 0.5 percent of the measurement.

2.2.9 Energy Metering

2.2.9.1 Electric Meters

Provide kilowatt-hour (kWh) meter(s) shown in accordance with NFLPA C12.10, suitable for the intended voltage, phases, and wye/delta configuration, with three current transformers and an output signal compatible with the DDC system. The meter shall have a box-mounted socket and an automatic circuit-closing bypass. Provide the meter with at least four pointer-type kWh registers, provisions for pulse initiation, and universal Class 2 indicating maximum kW demand register, sweep pointer indicating type, and a 60 minute interval. The meter accuracy shall be within plus or minus one percent of the actual kWh. Provide the correct multiplier on the meter face. Provide the current transformers in accordance with IEEE C57.13, with 600-volt insulation, and rated for metering with voltage, IL, momentary, and burden ratings coordinated with the ratings of corresponding meters. Provide butyl-molded donut or window type transformers mounted on a bracket to allow secondary cables to connect to the transformer bushings. Provide wiring identification of the current transformer secondary feeders to permit field measurements to be taken with hook-on ammeters.

2.2.9.2 Steam Meters

Steam meters shall be the vortex type, with pressure compensation, a minimum turndown ratio of 10 to 1, and an output signal compatible with the DDC system.

2.3 OUTPUT HARDWARE

2.3.1 Control Dampers

Provide factory manufactured galvanized steel dampers where indicated. Control dampers shall comply with SMACNA 1966 except as modified or supplemented by this specification. Published damper leakage rates and respective pressure drops shall have been verified by tests in compliance with AMCA 500-D requirements.

Provide damper assembly frames constructed of 0.064 inch minimum thickness galvanized steel channels with mitered and welded corners. Damper axles shall be 0.5 inches minimum diameter plated steel rods supported in the damper frame by stainless steel or bronze bearings. Blades mounted vertically shall be supported by thrust bearings.

Dampers shall be rated for not less than 2000 fpm air velocity. The pressure drop through each damper when full-open shall not exceed 0.04 inches water gage at 1000 fpm face velocity. Damper assemblies in ductwork subject to above 3-inch water gauge static air pressure shall be constructed to meet SMACNA Seal Class "A" construction requirements.

Provide the damper operating linkages outside of the air stream, including crank arms, connecting rods, and other hardware that transmits motion from the damper actuators to the dampers, shall be adjustable. Additionally, operating linkages shall be designed and constructed to have a 2 to 1 safety factor when loaded with the maximum required damper operating force. Linkages shall be brass, bronze, galvanized steel, or stainless steel.

Provide access doors or panels in hard ceilings and walls for access to all concealed damper operators and damper locking setscrews.

For field-installed control dampers, a single damper section shall have blades no longer than 48 inches and no higher than 72 inches. The maximum damper blade width shall be 12 inches. Larger sized dampers shall be built using a combination of sections.

Frames shall be at least 2 inches wide. Flat blades shall have edges folded for rigidity. Blades shall be provided with compressible gasket seals along the full length of the blades to prevent air leakage when closed.

The damper frames shall be provided with jamb seals to minimize air leakage. Seals shall be suitable for an operating temperature range of minus 40 degrees F to 200 degrees F.

The leakage rate of each damper when full-closed shall be no more than 4 cfm per sq. foot of damper face area at 1.0 inches water gage static pressure.

2.3.2 Control Valves

2.3.2.1 Valve Assembly

Valve bodies shall be designed for 125 psig minimum working pressure or 150 percent of the operating pressure, whichever is greater. Valve stems shall be Type 316 stainless steel. Valve leakage ratings shall be 0.01 percent of rated Cv value. Class 125 copper alloy valve bodies and Class 150 steel or stainless steel valves shall meet the requirements of ASME B16.5. Cast iron valve components shall meet the requirements of ASTM A 126 Class B or C.

2.3.2.2 Butterfly Valves

Butterfly valves shall be the threaded lug type suitable for dead-end service and for modulation to the fully-closed position, with stainless steel shafts supported by bearings, non-corrosive discs geometrically interlocked with or bolted to the shaft (no pins), and EPDM seats suitable for temperatures from minus 20 degrees F to plus 250 degrees F. Valves shall have a means of manual operation independent of the actuator.

2.3.2.3 Two-Way Valves

Two-way modulating valves shall have an equal percentage characteristic.

2.3.2.4 Three-Way Valves

Three-way valves shall have an equal percentage characteristic.

2.3.2.5 Valves for Chilled Water, Condenser Water, and Glycol Fluid Service

a. Bodies for valves 1-1/2 inches and smaller shall be brass or bronze, with threaded or union ends. Bodies for valves from 2 inches to 3 inches inclusive shall be of brass, bronze, or iron. Bodies for 2 inch valves shall have threaded connections. Bodies for valves from 2-1/2 to 3 inches shall have flanged connections.

b. Internal valve trim shall be brass or bronze, except that valve stems shall be stainless steel.

c. Unless indicated otherwise, provide modulating valves sized for 2 psi minimum and 4 psi maximum differential across the valve at the design flow rate.

d. Valves 4 inches and larger shall be butterfly valves, unless indicated otherwise.

2.3.2.6 Valves for Steam Service

The entire body for valves 1-1/2 inches and smaller shall be brass or bronze, with threaded or union ends. Bodies for valves from 2 to 3 inches inclusive shall be of brass, bronze, or carbon steel. Bodies for valves 4 inches and larger shall be carbon steel. Bodies for 2 inch valves shall have threaded connections. Bodies for valves 2-1/2 inches and larger shall have flanged connections. Steam valves shall be sized for 15 psig inlet steam pressure with a maximum 13 psi differential through the valve at rated flow, except where indicated otherwise. Internal valve trim shall be Type 316 stainless steel.

2.3.3 Actuators

Provide direct-drive electric actuators for all control applications, except where indicated otherwise.

2.3.3.1 Electric Actuators

Each actuator shall deliver the torque required for continuous uniform motion and shall have internal end switches to limit the travel, or be capable of withstanding continuous stalling without damage. Actuators shall function properly within 85 to 110 percent of rated line voltage. Provide actuators with hardened steel running shafts and gears of steel or copper alloy. Fiber or reinforced nylon gears may be used for torques less than 16 inch-pounds. Provide two-position actuators of single direction, spring return, or reversing type. Provide modulating actuators capable of stopping at any point in the cycle, and starting in either direction from any point. Actuators shall be equipped with a switch for reversing direction, and a button to disengage the clutch to allow manual adjustments. Provide the actuator with a hand crank for manual adjustments, as applicable. Thermal type actuators may only be used on terminal fan coil units, terminal VAV units, convectors, and unit heaters. Spring return actuators shall be provided on all control dampers and all control valves except terminal fan coil units, terminal VAV units, convectors, and unit heaters; unless indicated otherwise. Each actuator shall have distinct markings indicating the full-open and full-closed

position, and the points in-between.

2.3.4 Output Switches

2.3.4.1 Control Relays

Field installed and DDC panel relays shall be double pole, double throw, UL listed, with contacts rated for the intended application, indicator light, and dust proof enclosure. The indicator light shall be lit when the coil is energized and off when coil is not energized. Relays shall be the socket type, plug into a fixed base, and replaceable without tools or removing wiring. Encapsulated "PAM" type relays may be used for terminal control applications.

2.4 ELECTRICAL POWER AND DISTRIBUTION

2.4.1 Transformers

Transformers shall conform to UL 506. For control power other than terminal level equipment, provide a fuse or circuit breaker on the secondary side of each transformer.

2.4.2 Surge and Transient Protection

Provide each digital controller with surge and transient power protection. Surge and transient protection shall consist of the following devices, installed externally to the controllers.

2.4.2.1 Power Line Surge Protection

Provide surge suppressors on the incoming power at each controller or grouped terminal controllers. Surge suppressors shall be rated in accordance with UL 1449, have a fault indicating light, and conform to the following:

a. The device shall be a transient voltage surge suppressor, hard-wire type individual equipment protector for 120 VAC/1 phase/2 wire plus ground.

b. The device shall react within 5 nanoseconds and automatically reset.

c. The voltage protection threshold, line to neutral, shall be no more than 211 volts.

d. The device shall have an independent secondary stage equal to or greater than the primary stage joule rating.

e. The primary suppression system components shall be pure silicon avalanche diodes.

f. The secondary suppression system components shall be silicon avalanche diodes or metal oxide varistors.

g. The device shall have an indication light to indicate the protection components are functioning.

h. All system functions of the transient suppression system shall be individually fused and not short circuit the AC power line at any time.

i. The device shall have an EMI/RFI noise filter with a minimum attenuation of 13 dB at 10 kHz to 300 MHz.

j. The device shall comply with IEEE C62.41.1 and IEEE C62.41.2, Class "B" requirements and be tested according to IEEE C62.45.

k. The device shall be capable of operating between minus 20 degrees F and plus 122 degrees F.

2.4.2.2 Telephone and Communication Line Surge Protection

Provide surge and transient protection for DDC controllers and DDC network related devices connected to phone and network communication lines, in accordance with the following:

a. The device shall provide continuous, non-interrupting protection, and shall automatically reset after safely eliminating transient surges.

b. The protection shall react within 5 nanoseconds using only solid-state silicon avalanche technology.

c. The device shall be installed at the distance recommended by its manufacturer.

2.4.2.3 Controller Input/Output Protection

Provide controller inputs and outputs with surge protection via optical isolation, metal oxide varistors (MOV), or silicon avalanche devices. Fuses are not permitted for surge protection.

2.4.3 Wiring

Provide complete electrical wiring for the DDC System, including wiring to transformer primaries. Unless indicated otherwise, provide all normally visible or otherwise exposed wiring in conduit. Where conduit is required, control circuit wiring shall not run in the same conduit as power wiring over 100 volts. Circuits operating at more than 100 volts shall be in accordance with Section 26 20 00, INTERIOR DISTRIBUTION SYSTEM. Run all circuits over 100 volts in conduit, metallic tubing, covered metal raceways, or armored cable. Use plenum-rated cable for circuits under 100 volts in enclosed spaces. Examples of these spaces include HVAC plenums, within walls, above suspended ceilings, in attics, and within ductwork.

2.4.3.1 Power Wiring

The following requirements are for field-installed wiring:

a. Wiring for 24 V circuits shall be insulated copper 18 AWG minimum and rated for 300 VAC service.

b. Wiring for 120 V circuits shall be insulated copper 14 AWG minimum and rated for 600 VAC service.

2.4.3.2 Analog Signal Wiring

Field-installed analog signal wiring shall be 18 AWG single or multiple twisted pair. Each cable shall be 100 percent shielded and have a 20 AWG

drain wire. Each wire shall have insulation rated for 300 VAC service. Cables shall have an overall aluminum-polyester or tinned-copper cable-shield tape.

2.5 FIRE PROTECTION DEVICES

2.5.1 Duct Smoke Detectors

Provide duct smoke detectors in HVAC ducts in accordance with NFPA 72 and NFPA 90A, except as indicated otherwise. Provide UL listed or FM approved detectors, designed specifically for duct installation.

Provide ionization or photoelectric type detectors. Detectors shall detect both visible and invisible particles of combustion, and shall not be susceptible to undesired operation by changes to relative humidity. Provide each detector with an approved duct housing mounted exterior to the duct, and an integral perforated sampling tube extending across the width of the duct. The detector housing shall have indicator lamps that light when the detector is powered and when the detector is activated. Each detector shall have an integral test port , test switch and or , remote keyed test device. Connect new detectors to the building's new existing fire alarm control panel. Provide control and power modules required for the operation of the detectors in their own new control unit or integral with the existing fire alarm panel. A ground fault, break, or open condition in the electrical circuitry to any detector or its control or power unit shall cause activation of a trouble signal at the building fire alarm panel. Electrical supervision of wiring used exclusively for air-handling unit shutdown is not required, provided a break in the wiring would cause shutdown of the associated unit. Equipment and devices shall be compatible and operable in all respects with, and shall in no way impair the reliability or operational functions of, the new existing fire alarm system. The building's existing fire alarm control panel was manufactured by METASYS Notifier IFC3030. Provide descriptive zone labels at the existing fire alarm panel indicating which new air-handling unit detectors they serve and their location. Label zones modified in order to accomplish the work.

2.6 INDICATORS

2.6.1 Thermometers

Provide bi-metal type thermometers at locations shown. Thermometers shall have either 9 inch long scales or 3.5 inch diameter dials, with insertion, immersion, or averaging elements. Provide matching thermowells for pipe-mounted installations. Select scale ranges suitable for the intended service, with the normal operating temperature near the scale's midpoint. The thermometer's accuracy shall be plus or minus 2 percent of the scale range.

PART 3 EXECUTION

3.1 INSTALLATION

Perform the installation under the supervision of competent technicians regularly employed in the installation of DDC systems.

3.1.1 BACnet Naming and Addressing

Coordinate with the BAS Owner and provide unique naming and addressing for

BACnet networks and devices using the attached Point Naming Convention.

a. MAC Address

Every BACnet device shall have an assigned and documented MAC Address unique to its network. For Ethernet networks, document the MAC Address assigned at its creation. For ARCNET or MS/TP, assign from 00 to 64.

b. Network Numbering

Assign unique numbers to each new network installed on the BACnet internetwork. Provide ability for changing the network number; either by device switches, network computer, or field operator interface. The BACnet internetwork (all possible connected networks) can contain up to 65,534 possible unique networks.

c. Device Object Identifier Property Number

Assign unique Device "Object_Identifier" property numbers or device instances for each device on the BACnet internetwork. Provide for future modification of the device instance number; either by device switches, network computer, or field interface. BACnet allows up to 4,194,302 possible unique devices per internetwork.

d. Device Object Name Property Text

The Device Object Name property field shall support 32 minimum printable characters. Assign unique Device "Object_Name" property names with plain-English descriptive names for each device
For example, the Device Object Name that for the device controlling the chiller plant at Building 3408 would be:

Device Object_Name = CW System B3408

A Device Object Name for a VAV box controller might be:

Device Object_Name = VAV BOX25

e. Object Name Property Text (Other than Device Objects)

The Object Name property field shall support 32 minimum printable characters. Assign Object Name properties with plain-English names descriptive of the application. Examples include "Zone 1 Temperature" and "Fan Start/Stop".

f. Object Identifier Property Number (Other than Device Objects)

Assign Object Identifier property numbers according to design drawings or tables if provided. If not provided, Object Identifier property numbers may be assigned at the Contractor's discretion but must be approved by the Government. In this case they must be documented and unique for like object types within the device.

3.1.2 Minimum BACnet Object Requirements

a. Use of Standard BACnet Objects

For the following points and parameters, use standard BACnet objects, where all relevant object properties can be read using BACnet's Read

Property Service, and all relevant object properties can be modified using BACnet's Write Property Service:
all device physical inputs and outputs, all set points, all PID tuning parameters, all calculated pressures, flow rates, and consumption values, all alarms, all trends, all schedules, and all equipment and lighting circuit operating status.

b. BACnet Object Description Property

The Object Description property shall support 32 minimum printable characters. For each object, complete the description property field using a brief, narrative, plain English description specific to the object and project application. For example: "HW Pump 1 Proof." Document compliance, length restrictions, and whether the description is writeable in the device PICS.

c. Analog Input, Output, and Value Objects

Support and provide Description and/or Device_Type text strings matching signal type and engineering units shown on the points list.

d. Binary Input, Output, and Value Objects

Support and provide Inactive_Text and Active_Text property descriptions matching conditions shown on the points list.

e. Calendar Object

For devices with scheduling capability, provide at least one Calendar Object with ten-entry capacity. All operators may view Calendar Objects; authorized operators may make modifications from a workstation. Enable the writeable Date List property and support all calendar entry data types.

f. Schedule Object

Use Schedule Objects for all building system scheduling. All operators may view schedule entries; authorized operators may modify schedules from a workstation.

g. Loop Object or Equal

Use Loop Objects or equivalent BACnet objects in each applicable field device for PID control. Regardless of program method or object used, allow authorized operators to adjust the Update Interval, Setpoint, Proportional Constant, Integral Constant, and Derivative Constant using BACnet read/write services.

3.1.3 Minimum BACnet Service Requirements

a. Command Priorities

Use commandable BACnet objects to control machinery and systems, providing the priority levels listed below. If the sequence of operation requires a different priority, obtain approval from the Contracting Officer.

Priority Level	Application
1	Manual-Life Safety

2	Automatic-Life Safety
3	(User Defined)
4	(User Defined)
5	Critical Equipment Control
6	Minimum On/Off
7	(User Defined)
8	Manual Operator
9	(User Defined)
10	(User Defined)
11	Load Shedding
12	(User Defined)
13	(User Defined)
14	(User Defined)
15	(User Defined)
16	(User Defined)

b. Alarming

(1) Alarm Priorities - Coordinate alarm and event notification with the BAS Owner.

(2) Notification Class - Enable writeable Priority, Ack Required, and Recipient List properties of Notification Class objects.

(3) Event Notification Message Texts - Use condition specific narrative text and numerical references for alarm and event notification.

c. Updating Displayed Property Values

Allow workstations to display property values at discrete polled intervals, or based on receipt of confirmed and unconfirmed Change of Value notifications. The COV increment shall be adjustable by an operator using BACnet services, and polled intervals shall be adjustable at the operator workstation.

3.1.4 Local Area Networks

Obtain Government approval before connecting new networks with existing networks. Network numbers and device instance numbers shall remain unique when joining networks. Do not change existing network addressing without Government approval. See also "BACnet Naming and Addressing".

3.1.5 BACnet Routers, Bridges, and Switches

Provide the quantity of BACnet routers, bridges, and switches necessary for communications shown on the BACnet Communication Architecture schematic. Provide BACnet routers with BACnet Broadcast Message Device (BBMD) capability on each BACnet internetwork communicating across an IP network. Configure each BACnet device and bridge, router, or switch to communicate on its network segment.

3.1.6 Wiring Criteria

a. Run circuits operating at more than 100 volts in rigid or flexible conduit, metallic tubing, covered metal raceways, or armored cable.

b. Do not run binary control circuit wiring in the same conduit as power wiring over 100 volts. Where analog signal wiring requires conduit, do

not run in the same conduit with AC power circuits or control circuits operating at more than 100 volts.

c. Provide circuit and wiring protection required by NFPA 70.

d. Run all wiring located inside mechanical rooms in conduit.

e. Do not bury aluminum-sheathed cable or aluminum conduit in concrete.

f. Input/output identification: Permanently label each field-installed wire, cable, and pneumatic tube at each end with descriptive text using a commercial wire marking system that fully encircles the wire, cable, or tube. Locate the markers within 2 inches of each termination. Match the names and I/O number to the project's point list. Similarly label all power wiring serving control devices, including the word "power" in the label. Number each pneumatic tube every six feet. Label all terminal blocks with alpha/numeric labels. All wiring and the wiring methods shall be in accordance with UL 508A.

g. For controller power, provide new 120 VAC circuits, with ground. Provide each circuit with a dedicated breaker, and run wiring in its own conduit, separate from any control wiring. Connect the controller's ground wire to the electrical panel ground; conduit grounds are not acceptable.

h. Surge Protection: Install surge protection according to manufacturer's instructions. Multiple controllers fed from a common power supply may be protected by a common surge protector, properly sized for the total connected devices.

i. Grounding: Ground controllers and cabinets to a good earth ground as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Conduit grounding is not acceptable; all grounding shall have a direct path to the building earth ground. Ground sensor drain wire shields at the controller end.

j. The Contractor shall be responsible for correcting all associated ground loop problems.

k. Run wiring in panel enclosures in covered wire track.

3.1.7 Accessibility

Install all equipment so that parts requiring periodic inspection, operation, maintenance, and repair are readily accessible. Install digital controllers, data ports, and concealed actuators, valves, dampers, and like equipment in locations freely accessible through access doors.

3.1.8 Digital Controllers

a. Install as stand alone control devices (see definitions).

b. Locate control cabinets at the locations shown on the drawings. If not shown on the drawings, install in the most accessible space, close to the controlled equipment.

3.1.9 Hand-Off-Auto Switches

Wire safety controls such as smoke detectors and freeze protection

thermostats to protect the equipment during both hand and auto operation.

3.1.10 Temperature Sensors

Install temperature sensors in locations that are accessible and provide a good representation of sensed media. Installations in dead spaces are not acceptable. Calibrate sensors according to manufacturer's instructions. Do not use sensors designed for one application in a different application.

3.1.10.1 Room Temperature Sensors

Mount the sensors on interior walls to sense the average room temperature at the locations indicated. Avoid locations near heat sources such as copy machines or locations by supply air outlet drafts. Mount the center of the sensor 5 feet above the finished floor.

3.1.10.2 Duct Temperature Sensors

a. Probe Type: Provide a gasket between the sensor housing and the duct wall. Seal the duct penetration air tight. Seal the duct insulation penetration vapor tight.

b. Averaging Type (and coil freeze protection thermostats): Weave the capillary tube sensing element in a serpentine fashion perpendicular to the flow, across the duct or air handler cross-section, using durable non-metal supports. Prevent contact between the capillary and the duct or air handler internals. Provide a duct access door at the sensor location. The access door shall be hinged on the side, factory insulated, have cam type locks, and be as large as the duct will permit, maximum 18 by 18 inches. For sensors inside air handlers, the sensors shall be fully accessible through the air handler's access doors without removing any of the air handler's internals.

3.1.10.3 Immersion Temperature Sensors

Provide thermowells for sensors measuring piping, tank, or pressure vessel temperatures. Locate wells to sense continuous flow conditions. Do not install wells using extension couplings. Where piping diameters are smaller than the length of the wells, provide wells in piping at elbows to sense flow across entire area of well. Wells shall not restrict flow area to less than 70 percent of pipe area. Increase piping size as required to avoid restriction. Provide thermal conductivity material within the well to fully coat the inserted sensor.

3.1.11 Damper Actuators

Where possible, mount actuators outside the air stream in accessible areas.

3.1.12 Thermometers and Gages

Mount devices to allow reading while standing on the floor or ground, as applicable.

3.1.13 Pressure Sensors

Locate pressure sensors as indicated.

3.1.14 Component Identification Labeling

Using an electronic hand-held label maker with white tape and bold black block lettering, provide an identification label on the exterior of each new control panel, control device, actuator, and sensor. Also provide labels on the exterior of each new control actuator indicating the (full) open and (full) closed positions. For labels located outdoors, use exterior grade label tape, and provide labels on both the inside and outside of the panel door or device cover. Acceptable alternatives are white plastic labels with engraved bold black block lettering permanently attached to the control panel, control device, actuator, and sensor. Have the labels and wording approved by the BAS Owner prior to installation.

3.2 TEST AND BALANCE SUPPORT

The controls contractor shall coordinate with and provide on-site support to the test and balance (TAB) personnel specified under Section 23 05 93 TESTING, ADJUSTING AND BALANCING. This support shall include:

a. On-site operation and manipulation of control systems during the testing and balancing.

b. Control setpoint adjustments for balancing all relevant mechanical systems, including VAV boxes.

c. Tuning control loops with setpoints and adjustments determined by TAB personnel.

3.3 PERFORMANCE VERIFICATION TESTING (PVT)

3.3.1 General

The PVT shall demonstrate compliance of the control system work with the contract requirements. The PVT shall be performed by the Contractor and witnessed and approved by the Government. If the project is phased, provide separate testing for each phase. A Pre-PVT meeting to review the Pre-PVT Checklist is required to coordinate all aspects of the PVT and shall include the Contractor's QA representative, the Contractor's PVT administrator, the Contracting Officer's representative, and the BAS Owner.

3.3.2 Performance Verification Testing Plan

Submit a detailed PVT Plan of the proposed testing for Government approval. Develop the PVT Plan specifically for the control system in this contract. The PVT Plan shall be an clear list of test items arranged in a logical sequence. Include the intended test procedure, the expected response, and the pass/fail criteria for every component tested.

The plan shall clearly describe how each item is tested, indicate where assisting personnel are required (like the mechanical contractor), and include what procedures are used to simulate conditions. Include a separate column for each checked item and extra space for comments. Where sequences of operations are checked, insert each corresponding routine from the project’s sequence of operation. For each test area, include signature and date lines for the Contractor's PVT administrator, the Contractor's QA representative, the Contracting Officer's representative, and the BAS Owner to acknowledge successful completion. The BAS Owner can provide sample PVT forms and procedures upon request.

3.3.3 PVT Sample Size

Test all central plant equipment and primary air handling unit controllers unless otherwise directed. Twenty percent sample testing is allowed for identical controllers typical of terminal control like VAV boxes and fan coil units. The Government may require testing of like controllers beyond a statistical sample if sample controllers require retesting or do not have consistent results.

The Government may witness all testing, or random samples of PVT items. When only random samples are witnessed, the Government may choose which ones.

3.3.4 Pre-Performance Verification Testing Checklist

Submit the following as a list with items checked off once verified. Provide a detailed explanation for any items that are not completed or verified.

a. Verify all required mechanical installation work is successfully completed, and all HVAC equipment is working correctly (or will be by the time the PVT is conducted).

b. Verify HVAC motors operate below full-load amperage ratings.

c. Verify all required control system components, wiring, and accessories are installed.

d. Verify the installed control system architecture matches approved drawings.

e. Verify all control circuits operate at the proper voltage and are free from grounds or faults.

f. Verify all required surge protection is installed.

g. Verify the A/C Power Table specified in "CONTROLS SYSTEM OPERATORS MANUALS" is accurate.

h. Verify all DDC network communications function properly, including uploading and downloading programming changes.

i. Using the BACnet protocol analyzer (if provided or required in this specification), verify communications are error free.

j. Verify each digital controller’s programming is backed up.

k. Verify all wiring, components, and panels are properly labeled.

l. Verify all required points are programmed into devices.

m. Verify all TAB work affecting controls is complete.

n. Verify all valve and actuator zero and span adjustments are set properly.

o. Verify all sensor readings are accurate and calibrated.

p. Verify each control valve and actuator goes to normal position upon

loss of power.

q. Verify all control loops are tuned for smooth and stable operation. View trend data where applicable.

r. Verify each controller works properly in stand-alone mode.

s. Verify all safety controls and devices function properly, including freeze protection and interfaces with building fire alarm systems.

t. Verify all electrical interlocks work properly.

u. Verify all workstations, notebooks and maintenance personnel interface tools are delivered, all system and database software is installed, and graphic pages are created for each workstation and notebook.

v. Verify the as-built (shop) control drawings are completed.

3.3.5 Conducting Performance Verification Testing

a. Conduct Government-witnessed PVT after approval of the PVT Plan and the completed Pre-PVT Checklist. Notify the Contracting Officer of the planned PVT at least 15 days prior to testing. Provide an estimated time table required to perform the testing. Furnish personnel, equipment, instrumentation, and supplies necessary to perform all aspects of the PVT. Ensure that testing personnel are regularly employed in the testing and calibration of DDC systems. Using the project's as-built control system (shop) drawings, the project's mechanical design drawings, the approved Pre-PVT Checklist, and the approved PVT Plan, conduct the PVT.

b. During testing, identify any items that do not meet the contract requirements and if time permits, conduct immediate repairs and re-test. Otherwise, deficiencies shall be investigated, corrected, and re-tested later. Document each deficiency and corrective action taken.

c. If re-testing is required, follow the procedures for the initial PVT. The Government may require re-testing of any control system components affected by the original failed test.

3.3.6 Controller Capability and Labeling

Test the following for each controller:

a. Memory: Demonstrate that programmed data, parameters, and trend/ alarm history collected during normal operation is not lost during power failure.

b. Direct Connect Interface: Demonstrate the ability to connect directly to each type of digital controller with a portable electronic device like a notebook computer or PDA. Show that maintenance personnel interface tools perform as specified in the manufacturer's technical literature.

c. Stand Alone Ability: Demonstrate controllers provide stable and reliable stand-alone operation using default values or other method for values normally read over the network.

d. Wiring and AC Power: Demonstrate the ability to disconnect any

controller safely from its power source using the AC Power Table. Demonstrate the ability to match wiring labels easily with the control drawings. Demonstrate the ability to locate a controller's location using the BACnet Communication Architecture Schematic and floor plans.

e. Nameplates and Tags: Show the nameplates and tags are accurate and permanently attached to control panel doors, devices, sensors, and actuators.

3.3.7 Workstation and Software Operation

For every user workstation or notebook provided:

a. Show points lists agree with naming conventions.

b. Show that graphics are complete.

c. Show the UPS operates as specified.

3.3.8 BACnet Communications and Interoperability Areas

Demonstrate proper interoperability of data sharing, alarm and event management, trending, scheduling, and device and network management. If available or required in this specification, use a BACnet protocol analyzer to assist with identifying devices, viewing network traffic, and verifying interoperability. These requirements must be met even if there is only one manufacturer of equipment installed. Testing includes the following:

a. Data Presentation: On each BACnet Operator Workstation, demonstrate graphic display capabilities.

b. Reading of Any Property: Demonstrate the ability to read and display any used readable object property of any device on the network.

c. Setpoint and Parameter Modifications: Show the ability to modify all setpoints and tuning parameters in the sequence of control or listed on project schedules. Modifications are made with BACnet messages and write services initiated by an operator using workstation graphics, or by completing a field in a menu with instructional text.

d. Peer-to-Peer Data Exchange: Show all BACnet devices are installed and configured to perform BACnet read/write services directly (without the need for operator or workstation intervention), to implement the project sequence of operation, and to share global data.

e. Alarm and Event Management: Show that alarms/events are installed and prioritized according to the BAS Owner. Demonstrate time delays and other logic is set up to avoid nuisance tripping, e.g., no status alarms during unoccupied times or high supply air during cold morning start-up. Show that operators with sufficient privilege can read and write alarm/event parameters for all standard BACnet event types. Show that operators with sufficient privilege can change routing (BACnet notification classes) for each alarm/event including the destination, priority, day of week, time of day, and the type of transition involved (TO-OFF NORMAL, TO-NORMAL, etc.).

f. Schedule Lists: Show that schedules are configured for start/stop, mode change, occupant overrides, and night setback as defined in the sequence of operations.

g. Schedule Display and Modification: Show the ability to display any schedule with start and stop times for the calendar year. Show that all calendar entries and schedules are modifiable from any connected workstation by an operator with sufficient privilege.

h. Archival Storage of Data: Show that data archiving is handled by the operator workstation/server, and local trend archiving and display is accomplished with BACnet Trend Log objects.

i. Modification of Trend Log Object Parameters: Show that an operator with sufficient privilege can change the logged data points, sampling rate, and trend duration.

j. Device and Network Management: Show the following capabilities:

(1) Display of Device Status Information

(2) Display of BACnet Object Information

(3) Silencing Devices that are Transmitting Erroneous Data

(4) Time Synchronization

(5) Remote Device Reinitialization

(6) Backup and Restore Device Programming and Master Database(s)

(7) Configuration Management of Half-Routers, Routers and BBMDs

3.3.9 Execution of Sequence of Operation

Demonstrate that the HVAC system operates properly through the complete sequence of operation. Use read/write property services to globally read and modify parameters over the internetwork.

3.3.10 Control Loop Stability and Accuracy

For all control loops tested, give the Government trend graphs of the control variable over time, demonstrating that the control loop responds to a 20 percent sudden change of the control variable set point without excessive overshoot and undershoot. If the process does not allow a 20 percent set point change, use the largest change possible. Show that once the new set point is reached, it is stable and maintained. Control loop trend data shall be in real-time with the time between data points 30 seconds or less.

3.3.11 Performance Verification Testing Report

Upon successful completion of the PVT, submit a PVT Report to the Government and prior to the Government taking use and possession of the facility. Do not submit the report until all problems are corrected and successfully re-tested. The report shall include the annotated PVT Plan used during the PVT. Where problems were identified, explain each problem and the corrective action taken. Include a written certification that the installation and testing of the control system is complete and meets all of the contract's requirements.

3.4 TRAINING REQUIREMENTS

Provide a qualified instructor (or instructors) with two years minimum field experience with the installation and programming of similar BACnet DDC systems. Orient training to the specific systems installed. Coordinate training times with the Contracting Officer and BAS Owner after receiving approval of the training course documentation. Training shall take place at the job site and/or a nearby Government-furnished location. A training day shall occur during normal working hours, last no longer than 8 hours and include a one-hour break for lunch and two additional 15-minute breaks. The project's approved Controls System Operators Manual shall be used as the training text. The Contractor shall ensure the manuals are submitted, approved, and available to hand out to the trainees before the start of training.

3.4.1 Training Documentation

Submit training documentation for review 30 days minimum before training. Documentation shall include an agenda for each training day, objectives, a synopses of each lesson, and the instructor's background and qualifications. The training documentation can be submitted at the same time as the project's Controls System Operators Manual.

3.4.2 Training

The training shall be divided into 2 separate sessions, with each session lasting one day and be conducted at the DDC system workstation, at a notebook computer connected to the DDC system in the field, and at other site locations as necessary. One training session should focus on the mechanical equipment involved and the DDC system operations. The other session shall focus on the DDC software design, configuration and maintenance. Upon completion of the training, each trainee should fully understand the project's DDC system operation. The training sessions shall include, but not limited to the following:

a. A walk-through tour of the mechanical system and the installed DDC components (controllers, valves, dampers, surge protection, switches, thermostats, sensors, etc.)

b. A discussion of the components and functions at each DDC panel

c. Logging-in and navigating at each operator interface type

d. Using each operator interface to find, read, and write to specific controllers and objects

e. Modifying and downloading control program changes

f. Modifying setpoints

g. Creating, editing, and viewing trends

h. Creating, editing, and viewing alarms

i. Creating, editing, and viewing operating schedules and schedule objects

j. Backing-up and restoring programming and data bases

k. Modifying graphic text, backgrounds, dynamic data displays, and links

to other graphics

l. Creating new graphics and adding new dynamic data displays and links

m. Alarm and Event management

n. Adding and removing network devices

Point Naming Convention

Format - Supervisory Controller/Bus . Application Specific Controller . Point Type
(Spaces added for clarity separating parts for the 'Fully Qualified Reference')
Example - adx-1:NAE-0298-1/N2-1.011047UN.ZN-T

Supervisory Controller Server: **NAE-XXXX-X**
Example - adx-1: **NAE-0298-1**

ASC Controllers (Bus & Identifier are created when insert field device and can't be changed later)

Bus Bus type - Bus # Example: adx-1:NAE-0298-1/**N2-1**
N2-1 or N2-2
FC-1 or FC-2 for BacNet
(BacNet over IP may be limited by the controllers when added)

Identifier (Item reference) *Server: NAE name/bus*.**XXX N2 address controller type**
Example - *adx-1: NAE-0298-1/N2-1*.**011047UN**

ASC controller Name **4 digit bldg #.011XXXYY** Where X=N2 address & Y in type identifier
Use **011** for bus #1 and **012** for bus #2
Example - **0298.011047UN** (bldg 298 bus #1 N2 address 047 UNT)
Note: (use **FE** for FEC controllers.)

Points (Insert field point) **See separate list for point type nomenclatures**.

Identifier (Item reference) *Server: NAE name/bus.N2 address & controller type*.**point type**
(Identifier are created when inserting a field device and can't be changed later)
(*Shows up with mouse over on graphics*.)
Example - *adx-1: NAE-0298-1/N2-1.011047UN*.**ZN-T**

Point Name **bldg#.controller name.point type** (Shows up as Item in event viewer)
Example - **0298.AHU-8.ZN-T**

Description **Description of point**
Examples - Zone Temp , Sup Fan Status, Hot Water Pump Status

EMCS Graphic Conventions

Any deviations from these conventions shall be approved in advance.

All graphics: All new graphics should match the appearance of existing graphics.

Sample of current graphics will be made available.

Background images are Visio 2003 SVGZ files.

Data values should be shown as black text in a white box and a black border.

Text should be black with a transparent background with no border. Some graphics use blue text for contrast for special items such as names of devices.

Buttons to select other graphics are gray with white text in a vertical column on the right side of the page.

Attention should be given to the general alignment and centering of objects.

Floor Plans

- should come from CAD drawings if available.
- Display against a light pale yellow background.
- Show Temperature sensors on the floor plan in their true location and source reference
- Zone temp backgrounds should turn red when in alarm state.
- Show all communication equipment locations and bus routing.
- Show location of all controllers and their status.
- Include a legend as appropriate.

Systems

- Information such as set points, modes & other data not specifically shown as a point on the system graphic should be in a gray framed box in the bottom left portion of the page. This box should include outside air temp and humidity for all systems.
- The status of dynamic values such as running, alarm, etc should be indicated both with text and color or moving dynamic symbols. Color preferences used:

  Alarms: Normal- green or white for temperature background, Alarm - red

  Run status: On/running - green,
  Off/stopped - red for moving symbols/
  white for text backgrounds.

  Load Shed: Shedding - Red, Not Shedding - white

(See Table 1 below for RGB color specifications)

- All system graphics should include a framed boxed in the lower right corner showing controller and load shedding status.

- Include a legend as appropriate.

Table 1: Common Colors Used In Graphics

Use	Description	RGB Color
Floor Plan Background	Pale Yellow	255,255,153
Main Background on most graphics	Violet	146,132,255
Gray Background for framed boxes	Gray	193,193,193
Alternant Gray (System gray preference)	Lighter Gray	204,204,204
Run status Off, Alarm Condition, Load	RED	255 , 0 , 0
Run Status On, Normal condition, Com. Ok	Green	0 , 255 , 0

Modify any existing graphic or add to an existing common graphic if affected by the project.

Existing common graphics include but not limited to:

Station map showing building location with a link to the buildings floor plan.

Load shedding status.

Network communications page for NAEs, etc.

Power meter summary pages.

Special pages for Well and Lift Station data.

-- End of Section --

EMCS Equipment and Points Nomenclature for Cherry Point

In using this list of acronyms, use the format of Item-Point. Combine as needed to discribe the item.
Examples: ACTHTG-SP for Actual Heating Set Point BYPVLV-O for Bypass Valve Open
In some cases a point acronym may be used as part of the item. Example SAT-SP for Supply Air Temp Set Point

Item / Equipment

ACT or A	Actual
AHU	Air-Handling Unit
B	Boiler
BYP	Bypass
CD	Cold Deck
Ch	Chiller or Chilled
CLG	Cooling
COM	Communication
COMP	Compressor
Cond	Condenser
CRAC	Computer Room AC
CT	Cooling Tower
CTRL	Control
CU	Condensing Unit
CW	Chilled Water or Cold Water
D	Discharge
DHW	Domestic Hot Water
DPR or DMP	Damper
DTS	Dual Temperature System
DH	Dehumidifier
E	Emergency
ECT	Evaporative Cooling Tower
EF	Exhaust Fan
ELEC	Electric
EST	Elevated Storage Tank
F	Fan
FCU	Fan Coil Unit

Point / Condition

ADJ	Adjust (Offset)
ALM	Alarm
CFM	Cubic Feet Per Minute
CLD	Closed
CMD	Command
DMD	Demand
DP	Differential Pressure
EN	Enable
Fail	Failure
FLO	Flow
FLT	Fault
GPM	GPM
H	Humidity
HI	High
HRN	Horn
LO	Low
LVL	Level
O	Open
OVR	Override
P	Pressure
RH	Relative Humidity
RST	Reset
S	Status
SIL	Silence
SP	Set Point
SW	Switch
T	Temperature

FLTR	Filter
GLBT	Ground Level Booster tank
HD	Hot deck
HP	Heat Pump (On Ground)
HR	Heat Recovery
HRW	Heat Recovery Wheel
HTG	Heating
HV	Heating Ventilating Unit
HX	Steam HW Converter / Heat Exchanger
HYD	Hydraulic
INST	Instantaneous
INTR	Intrusion
INTV	Interval
KW	Kilowatt
LS	Lift Station
LP	Loop
MA	Mixed Air
MAU	Make-up Air Unit
MAX	Maximum
MIN	Minimum
MTR	Meter
MZ	Multizone Unit
OCC	Occupied
OA	Outside Air
PACU	Packaged AC Unit
PH	PreHeat
PNL	Panel
PHP	Packaged Heat Pump (On Ground)
P	Pump
PWR	Power
PX	Plate Exchanger
R	Return
RA	Return air
RAF	Return air fan

REV	Reverse or Reversing
RM	Room
RTU	Roof Top Unit (Packaged DX)
RTHP	Roof Top Heat Pump
RVS-VLV	Reversing Valve
S	Supply
SA	Supply Air
SF	Supply Fan
SDWN	Shutdown
SMKD	Smoke Detector
SP	Static Pressure
STG	Stage
STM	Steam
WWTP	Waste Water Treatment Plant
SUP	Supplemental
SUM	Summer
SV	Solenoid Valve/Steam Valve
SYS	System
Temp	Temporary
T w/circle	T-Stat
TMR	Timer
Tnk	Tank
Tot	Total
TWAC	Thru-Wall Air Conditioner
TWHP	Thru-Wall Heat Pump
TWR	Tower
UNOCC	Unoccupied
UH	Unit Heater
VLV	Valve
VAV	Variable Air Volume
VFD	Variable Frequency Drive
W	Water
WAC	Window Air Conditioner
WC	Warm / Cool

WS	Work Station
WSHP	Water Source Heat Pump
WTP	Water Treatment Plant
WIN	Winter
WP	Well Pump
ZN	Zone

SECTION 23 22 26.00 20

STEAM SYSTEM AND TERMINAL UNITS
02/10

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AIR-CONDITIONING, HEATING AND REFRIGERATION INSTITUTE (AHRI)

AHRI 410	(2001; Addendum 1 2002; Addendum 2 2005; Addendum 3 2011) Forced-Circulation Air-Cooling and Air-Heating Coils

AMERICAN WELDING SOCIETY (AWS)

AWS Z49.1	(2012) Safety in Welding and Cutting and Allied Processes

ASME INTERNATIONAL (ASME)

ASME A13.1	(2007; R 2013) Scheme for the Identification of Piping Systems
ASME B1.1	(2003; R 2008) Unified Inch Screw Threads (UN and UNR Thread Form)
ASME B1.20.1	(2013) Pipe Threads, General Purpose (Inch)
ASME B16.11	(2011) Forged Fittings, Socket-Welding and Threaded
ASME B16.20	(2012) Metallic Gaskets for Pipe Flanges - Ring-Joint, Spiral Wound, and Jacketed
ASME B16.21	(2011) Nonmetallic Flat Gaskets for Pipe Flanges
ASME B16.24	(2011) Cast Copper Alloy Pipe Flanges and Flanged Fittings: Classes 150, 300, 600, 900, 1500, and 2500
ASME B16.3	(2011) Malleable Iron Threaded Fittings, Classes 150 and 300
ASME B16.34	(2013) Valves - Flanged, Threaded and Welding End
ASME B16.39	(2009) Standard for Malleable Iron Threaded Pipe Unions; Classes 150, 250, and 300
ASME B16.5	(2013) Pipe Flanges and Flanged Fittings:

	NPS 1/2 Through NPS 24 Metric/Inch Standard
ASME B16.9	(2012) Standard for Factory-Made Wrought Steel Buttwelding Fittings
ASME B18.2.1	(2012; Errata 2013) Square and Hex Bolts and Screws (Inch Series)
ASME B18.2.2	(2010) Nuts for General Applications: Machine Screw Nuts, Hex, Square, Hex Flange, and Coupling Nuts (Inch Series)
ASME B31.1	(2012; INT 2-6, 8-10, 13, 15, 17-25, 27-31 and 42-46) Power Piping
ASME B40.100	(2013) Pressure Gauges and Gauge Attachments
ASME BPVC	(2010) Boiler and Pressure Vessels Code
ASME BPVC SEC IX	(2010) BPVC Section IX-Welding and Brazing Qualifications
ASME BPVC SEC VIII D1	(2010) BPVC Section VIII-Rules for Construction of Pressure Vessels Division 1

ASTM INTERNATIONAL (ASTM)

ASTM A106/A106M	(2013) Standard Specification for Seamless Carbon Steel Pipe for High-Temperature Service
ASTM A194/A194M	(2013) Standard Specification for Carbon and Alloy Steel Nuts for Bolts for High-Pressure or High-Temperature Service, or Both
ASTM A307	(2012) Standard Specification for Carbon Steel Bolts and Studs, 60 000 PSI Tensile Strength
ASTM A53/A53M	(2012) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

MSS SP-58	(2009) Pipe Hangers and Supports - Materials, Design and Manufacture, Selection, Application, and Installation
MSS SP-69	(2003; Notice 2012) Pipe Hangers and Supports - Selection and Application (ANSI Approved American National Standard)
MSS SP-80	(2013) Bronze Gate, Globe, Angle and Check Valves

U.S. DEPARTMENT OF DEFENSE (DOD)

MIL-V-18436	(1987; Rev F) Valves, Check, Bronze, Cast Iron, and Steel Body

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

CID A-A-1689	(Rev B) Tape, Pressure-Sensitive Adhesive, (Plastic Film)
CID A-A-50494	(Basic; Notice 1) Exhaust Head, Steam
CID A-A-59617	(Basic) Unions, Brass or Bronze, Threaded Pipe Connections and Solder-Joint Tube Connections
CID A-A-60001	(Rev A) Traps, Steam
FS F-V-2906	(Basic) Valves, Air Venting, Steam
FS WW-S-2739	(Basic; Notice 1) Strainers, Sediment: Pipeline, Water, Air, Gas, Oil, or Steam

1.2 GENERAL REQUIREMENTS

Section 23 03 00.00 20 BASIC MECHANICAL MATERIALS AND METHODS, applies to this section, with the additions and modifications specified herein. This section includes steam and condensate pipingand steam coils used for heating within the building. Steam boilers, feedwater treatment equipment, process steam terminal units, boiler feed piping, and blow-off piping are not covered in this section.

1.2.1 Classes and Maximum Working Pressures

Equipment, piping, and piping components shall be suitable for use under the maximum working pressure indicated. Except as modified herein, the pressure temperature limitations shall be as specified in the referenced standards and specifications.

1.2.2 Standard Commercial Product

The terminal units provided shall, as a minimum, comply with the features specified herein and shall be the manufacturer's standard commercial product. Additional or better features which are not specifically prohibited herein but which are a part of the manufacturer's standard commercial product, shall be included in the terminal units being furnished. A standard commercial product is a product which has been sold or is currently being offered for sale, on the commercial market through advertisements or manufacturer's catalogs or brochures. Provide Institute of Boiler and Radiator Manufacturer (IBR) or Steel Boiler Institute (SBI) rating for required capacity.

1.2.3 Welding Safety

AWS Z49.1.

1.2.4 Definitions

1.2.4.1 High Pressure Piping System

A system whose pressure is greater than 15 psig and shall conform to ASME B31.1.

1.2.4.2 Low Pressure Piping System

A system whose pressure is 15 psig or less.

1.2.4.3 Terminal Unit

An enclosed unit that provides heated air from a steam coil and includes natural convection units, radiation, and forced air units.

1.2.4.4 Piping and Piping System

Includes pipe, tubing, flanges, bolting, gaskets, valves, safety valves, fittings, and pressure containing parts of other piping components, hangers, supports, guides, expansion joints, anchors, and other equipment items necessary to prevent overstressing the pressure containing parts.

1.3 SUBMITTALS

The following shall be submitted in accordance with SUBMITTAL PROCEDURES:

SD-03 Product Data

Steam to air heating coils

Valves

Valve operating mechanism

Traps

Strainers

Instrumentation

SD-06 Test Reports

Steam piping tests

Valves tests

Instrumentation tests

Pipe and pipe system

Steam to air heating coils tests

Submit reports of tests required by the reference specification and standards.

SD-07 Certificates

Welding procedure

Welder's Performance Qualification Record

List of welders and welder's symbols

1.4 QUALITY ASSURANCE

1.4.1 Welding Procedure

Submit welding procedure specification for metals included in the work, together with proof of the procedure's qualifications as outlined in ASME B31.1.

1.4.2 Welder's Performance Qualification Record

Submit to the Contracting Officer the Welder's Performance Qualification Record in conformance with ASME B31.1 for each welder, showing that the welder was tested under the approved procedure specification submitted by the Contractor. In addition, the Contractor shall submit list of welders and welder's symbols, assigned number, or letter which shall be used to identify the work of the welder which shall be affixed immediately upon completion of the weld. Welders making defective welds after passing a qualification test shall be required to take a requalification test. Welders failing the requalification tests will not be permitted to work under this contract.

1.4.3 Previous Qualifications

Welding procedures, welders, and welding operators previously qualified by test may be accepted for this contract without requalification subject to approval if the conditions specified in ASME B31.1 are met before a procedure can be used.

PART 2 PRODUCTS

2.1 PIPE AND PIPE SYSTEM

2.1.1 High Pressure Steam Piping System (Over 15 psig)

ASME B31.1 for a steam working pressure of 50 psig and a temperature of 297 degrees F, a condensate pressure f 0 psig, and a temperature of 220 degrees F.

2.1.1.1 High Pressure Steam Piping

ASTM A106/A106M or ASTM A53/A53M, Grade B, Schedule 40, black steel, electric-resistance welded. Use ASTM A53/A53M pipe for bending.

2.1.2 Low Pressure Steam Piping System

ASME B31.1 for a steam working pressure of 15 psig or less, a condensate pressure of 0 psig, and a temperature of 220 degrees F.

2.1.2.1 Low Pressure Steam Piping

a. Steel Piping: ASTM A53/A53M, Schedule 40, black, electric-resistance welded. Use ASTM A53/A53M pipe for bending.

2.1.3 Condensate Return Piping (100 psig or Less)

2.1.3.1 Steel Piping

ASTM A106/A106M or ASTM A53/A53M, Grade B, Schedule 80, black, electric-resistance welded.

2.1.4 Fittings

Provide fittings compatible in all respects (material, size, pressure, and temperature limitations) with the pipe being used and within any further limitations of ASME B31.1.

2.1.4.1 Fittings for Steel Pipe

a. Sizes 1/8 to 2 inches:

(1) Steel Fittings: ASME B16.11, socket welding or threaded. Where pressure exceeds 15 psig, provide socket-welding type only.

(2) Malleable Iron Fittings: ASME B16.3, threaded.

b. Sizes 2 1/2 inches and larger:

(1) Steel Fittings: ASME B16.9, buttwelding or ASME B16.5, flanged.

(2) Bronze Fittings: ASME B16.24, flanged. Sizes larger than 8 inches are not permitted.

2.1.5 Unions

2.1.5.1 Unions for Steel Pipe

ASME B16.39, threaded.

2.1.5.2 Unions for Copper Tubing

CID A-A-59617, solder joint end type.

2.1.6 Flanges

Remove the raised faces on flanges when used with flanges having a flat face.

2.1.6.1 Steel Flanges

ASME B16.5, forged steel, welding type.

2.1.6.2 Bronze Flanges

ASME B16.24, threaded.

2.1.7 Valves

Shall conform to the following paragraphs. End connections shall conform to paragraph entitled "End Connections."

2.1.7.1 Gate Valves

a. Bronze Gate Valves: MSS SP-80, Type 2 (solid wedge, inside screw, rising stem), 3 inches and smaller, threaded or solder joint ends, and not less than Class 150.

b. Steel Gate Valves: ASME B16.34. Provide outside screw and yoke type with solid wedge or flexible wedge disc, and with trim suitable for the service temperature and pressure.

2.1.7.2 Check Valves

a. Bronze Check Valves: MSS SP-80, Type 3 (swing check, metal disc to metal seat), 3 inches and smaller, threaded or solder joint ends, Class 200, regrinding type.

b. Steel Check Valves: MIL-V-18436, with trim suitable for the service temperature and pressure.

(1) Swing Check Valves: Shall have bolted caps.

(2) Lift Check Valves: Shall have threaded or bolted caps.

2.1.7.3 Air Vent Valves

FS F-V-2906, with vacuum holding device, pressure rated for the intended service, and with a capacity based on manufacturer's standard for the connection size, cast iron prohibited.

2.1.7.4 Valve Operating Mechanism

Provide power operators and extension stems where indicated and as specified.

c. Power Operators: Shall be electric. Power operated valves shall open and close at rates no slower than 10 inches per minute for gate valves and 4 inches per minute for globe and angle valves. Valves shall open fully or close tightly without requiring further attention when the actuating control is moved to the open or close position. A predetermined thrust exerted on the stem during operation resulting from an obstruction in the valve shall cause the motor to automatically stop. Power operators shall be complete with all gearing and controls necessary for the size of valve being provided. Power operators shall be designed to operate on the electric power supply indicated.

d. Extension Stem: Shall be corrosion resisting steel designed for rising and non-rising stems, as applicable, and for connection to the valve stem by a sleeve coupling or universal joint. Provide in length required to connect the valve stem and the handwheel and of sufficient cross section to transfer the torque required to operate the valve.

2.1.7.5 Safety Valves

MIL-V-18436, Type 1, Class 150, Style A, and sized in accordance with ASME BPVC. Set point shall be as indicated, cast iron prohibited.

2.1.8 End Connections

2.1.8.1 Steel Piping

Sizes 2 inches and smaller threaded or socket welded; sizes 2 1/2 inches and larger flanged or butt welded.

a. Threaded Joints: ASME B1.20.1.

b. Flanged Joints: Flanges shall conform to paragraph entitled "Flanges." Bolting and gaskets shall be as follows:

(1) Bolting: Material used for bolts and studs shall conform to ASTM A307, Grade B; and material for nuts shall conform to ASTM A194/A194M, Grade 2. Dimensions of bolts, studs, and nuts shall conform to ASME B18.2.1 and ASME B18.2.2 with threads conforming to ASME B1.1coarse type, with Class 2A fit for bolts and studs, and Class 2B fit for nuts. Bolts or bolt-studs shall extend completely through the nuts and may have reduced shanks of a diameter not less than the diameter at root of threads. Carbon steel bolts shall have American Standard regular square or heavy hexagon heads and shall have American Standard heavy semifinished hexagonal nuts, conforming to ASME B18.2.1 and ASME B18.2.2.

(2) Gaskets: Gaskets shall be as follows:

Working Conditions	Material
Saturation	
50 psig 297 degrees F	Composition or Copper
Superheated Steam, Less Than 750 degrees F	
90 psig 330 degrees F	Metal-Jacketed Composition, Monel, Steel, or Soft Steel

Gaskets shall be as thin as the finish of surfaces will permit. Metal or metal-jacketed non-asbestos gaskets shall be used with small male and female or small tongue-and-groove flanges or flanged fittings; they may be used with steel flanges with lapped, large male and female, large tongue-and-groove, or raised faces. Full faced gaskets shall be used with flat-faced bronze flanges. Lapped steel flanges, or raised-face steel flanges shall have ring gaskets with an outside diameter extending to the inside of the bolt holes. Widths of gaskets for small male and female and for tongue-and-groove joints shall be equal to the widths of the male face or tongue. Gaskets shall have an inside diameter equal to or larger than the port openings. Rings for ring joints shall be in accordance with dimensions in ASME B16.20, suitable for the service conditions encountered, and shall be softer than the flanges. Dimensions for non-metallic gaskets shall be in accordance with ASME B16.21.

c. Butt Weld Joints: ASME B31.1. The use of backing rings shall conform to ASME B31.1. Ferrous rings shall be of good weldable quality and shall not exceed 0.05 percent sulfur; for alloy pipe, backing rings shall be of material compatible with the chemical composition of the parts to be welded and preferably of the same composition. Backing

rings shall be continuous machined or split band type.

d. Socket Weld Joints: ASME B31.1.

2.1.9 Instrumentation

2.1.9.1 Pressure and Vacuum Gages

ASME B40.100 with restrictor, locate as indicated. Provide scale range for intended service. Scale range not to exceed two times (2X) the indicated pressure of piping.

2.1.9.2 Indicating Thermometers

Thermometers shall be dial type with an adjustable angle suitable for the service. Provide thermowell sized for each thermometer in accordance with the thermowell specification. Fluid-filled thermometers (mercury is not acceptable) shall have a nominal scale diameter of 5 inches. Construction shall be stainless-steel case with molded glass cover, stainless-steel stem, and bulb. Stem shall be straight, length as required to fit well. Bimetal thermometers shall have a scale diameter of 3 1/2 inches. Case shall be hermetic. Case and stem shall be constructed of stainless steel. Bimetal stem shall be straight and of a length as required to fit the well.

2.1.10 Miscellaneous Pipeline Components

2.1.10.1 Air Traps

CID A-A-60001 for float-operated steam traps (non-thermostatic), except that the valve mechanism shall be inverted so as to be closed, not opened, by rising water. Arrange float-controlled valves to close promptly when water enters the traps. Locate traps as indicated.

2.1.10.2 Steam Traps

CID A-A-60001, Type VI, Class 4, thermostatic and non-thermostatic steam traps. Provide traps with separate strainers and locate as indicated.

2.1.10.3 Strainers

FS WW-S-2739, Style Y (Y pattern) for Class 125 and 250 piping in sizes 1/2 to 8 inches, inclusive, locate as indicated, cast iron prohibited.

2.1.10.4 Exhaust Heads

CID A-A-50494, for atmospheric discharge of exhaust steam.

2.1.10.5 Hangers, Supports, Spacing Requirements, and Attachments

MSS SP-58 and ASME B31.1 for materials, design, and manufacture. MSS SP-69 for selection and application.

2.2 STEAM TO AIR HEATING COILS

Heating and ventilating units for steam system shall be as specified in Section 23 00 00 AIR SUPPLY, DISTRIBUTION, VENTILATION, AND EXHAUST SYSTEMS, except that steam coils shall be provided in lieu of water coils. Coils for factory fabricated air handlers and reheat coils shall be constructed

as follows: Construct steam distribution (nonfreeze type) coils of cast semi-steel, welded-steel, or copper headers, red brass or copper tubes, and copper or aluminum fins mechanically bonded or soldered or helically wound to tubes. Roll and bush, braze, or weld tubes into headers. Condensing tubes shall be not less than 5/8 inch outside diameter. Distributing tubes shall be not less than 3/8 inch outside diameter, with orifices to discharge steam to condenser tubes and shall be held securely in position. The maximum length of a single coil shall be limited to 120 times the outside diameter of the tube. Coil casings and tube support sheets, with collars of ample width, shall be not lighter than 16 gage 0.0635 inch thick galvanized steel, formed to provide structural strength. When required, provide multiple tube supports to prevent tube sag. The finned tube and header section shall float within the casing to allow free expansion of tubing for coils subject to high pressure steam service. Factory test coils at 250 psig hydrostatic test pressure or under water at 250 psig air pressure. Coils shall be suitable for 200 psig steam working pressure. Test rate coils in accordance with AHRI 410.

PART 3 EXECUTION

3.1 INSTALLATION

Work material and equipment into a complete, convenient, and economical system or systems; and provide apparatus, parts, materials, and accessories which are necessary to accomplish this result.

3.1.1 Piping

Fabricate, assemble, weld, solder, braze, and install piping and pipe system in accordance with ASME B31.1 and as further qualified herein. Piping shall follow the general arrangement shown. Cut piping accurately to measurements established, for the work shown, by the Contractor, and work into place without springing or forcing, except where cold-springing is indicated. Locate piping and equipment within buildings entirely out of the way of lighting fixtures, conduit, and doors, windows, and other openings. Run overhead piping in buildings in the most inconspicuous positions. Provide adequate clearances from walls, ceilings, and floors to permit the welding of joints; at least 6 inches for pipe sizes 4 inches and smaller, 10 inches for pipe sizes larger than 4 inches, and in corners provide sufficient clearance to permit the welder to work between the pipe and one wall. Make provision for expansion and contraction of pipe lines. Do not bury, conceal, or insulate piping until it has been inspected, tested, and approved. Do not conceal piping in walls, partitions, underground, or under the floor except as indicated. Where pipe passes through building structure, do not conceal pipe joints, but locate where they may be readily inspected and not weaken building structure. Run insulated pipe as shown and as required with sufficient clearance to permit application of insulation. Use flanged joints only where necessary for normal maintenance and where required to match valves and equipment. Gaskets, packing, and thread compounds shall be suitable for the service. Apply joint compound or tape on male thread only. Use long radius ells wherever possible to reduce pressure drops. Pipe bends may be used in lieu of welding fittings where space permits. Pipe bends shall have a uniform radius of at least five times the pipe diameter and shall be free from any appreciable flattening, wrinkling, or thinning of the pipe. Mitering of pipe to form elbows, notching straight runs to form full sized tees, or any similar construction shall not be used. Make branch connections with welding tees except factory made forged welding branch outlets or nozzles having integral reinforcements conforming to ASME B31.1 may be used,

provided the nominal diameter of the branch is at least one pipe size less than the nominal diameter of the run. Run piping as indicated, and avoid interference with other piping, conduit, or equipment. Run vertical piping plumb and straight and parallel to walls, except where specifically shown otherwise. Do not trap lines, except where indicated. Use reducing fittings for changes in pipe sizes. The use of bushings is prohibited. In horizontal lines 2 1/2 inches and larger, use reducing fittings of the eccentric type to maintain the bottom of the lines in the same plane for steam lines and to maintain the top of the lines in the same plane for condensate lines except where a trap or pocket would result. Provide suitable size sleeves for lines passing through building structure. Install piping connected to equipment to provide flexibility for thermal stresses and for vibration. Support and anchor pipe so that strain from weight and thermal movement of piping is not imposed on the equipment. Thoroughly clean each section of pipe, fittings, and valves of foreign matter before erection. Before placing in position, clean the inside of black steel pipe by rapping along its full length to loosen sand, mill scale, and other foreign matter; pipe 2 inches and larger shall have a wire brush of a diameter larger than that of the inside of the pipe drawn through its entire length several times. Before final connections are made to the apparatus, thoroughly wash out the piping interior with water. Blow out steam piping with high-pressure steam, if available, or compressed air, removing rust, oil, chips, sand, and other material. Plug or cap open ends of mains during shutdown periods. Do not leave lines open at any place where any foreign matter might accidentally enter pipe.

3.1.1.1 Welding

a. Welding of Piping: Welding of joints in piping, butt welds, fillet welds, bends, loops, offsets, and preparation and cleaning of pipe shall be in accordance with ASME B31.1. Welds shall be visually examined and meet acceptance standards indicated in Chapter VI of ASME B31.1.

b. Quality of Welds: Quality of welds, correction of defects, stress relieving, and preheating shall be in accordance with ASME B31.1.

c. Arc Welding and Gas Welding: In accordance with ASME BPVC SEC IX.

3.1.1.2 Hangers and Supports

Unless otherwise indicated, horizontal and vertical piping attachments shall conform to MSS SP-58. Continuous inserts and expansion bolts may be used.

3.1.1.3 Grading and Venting of Pipe Lines

Unless otherwise indicated, install horizontal lines of steam and return piping to grade down in the direction of flow with a pitch of not less than one inch in 30 feet, except in loop mains and main headers where the flow may be in either direction. When counterflow of condensate within the steam pipe occurs in a portion of a pipeline, pitch up in the direction of steam flow a minimum of 6 inches per 100 feet and increase pipe diameters by one standard pipe size. Steam mains pitched away from the boiler shall contain drip connection and air vent valves at the extreme end. Air vents shall be provided at the highest point of any vertical riser. Drip connections shall not be interconnected above the water line of the boiler.

3.1.1.4 Unions and Flanges

Provide unions and flanges where necessary to permit easy disconnection of piping and apparatus, and as indicated. Provide a union for each threaded end valve. Place unions or flanges no farther apart than 100 feet. Use unions on piping smaller than 2 inches in diameter, and use flanges on piping 2 inches and larger in diameter. Provide dielectric unions or flanges between ferrous and non-ferrous piping, equipment, and fittings; except that bronze valves and fittings may be used without dielectric couplings for ferrous-to-ferrous or non-ferrous to non-ferrous connections. Dielectric fittings shall utilize a non-metallic filler which will prevent current flow. The spacer shall be suitable for the pressure and temperature of the service. The fittings shall otherwise conform to the requirements of paragraph entitled "Fittings."

3.1.1.5 Traps and Connections

Traps shall be of the type and capacity for the service and shall be properly supported and connected. Except for thermostatic traps in pipe coils, radiators, and convectors, install traps with a dirt pocket and strainer between it and the piping or apparatus it drains. When necessary to maintain in continuous service apparatus or piping which is to be drained, provide a three-valve bypass so that the trap may be removed and repaired and condensate may drain through the throttled bypass valve. Provide a check valve on the discharge side of the trap whenever the trap is installed for lift or operating against a back pressure, or discharges into a common return line. When a thermodynamic trap is used, a check valve is not required or recommended. Provide test connections on the discharge side of the high and medium pressure traps when they are specifically required. The test connection shall include a 1/2 inch globe valve with uncapped nipple.

3.1.2 Valves

3.1.2.1 General

Install valves in conformance with ASME B31.1, ASME BPVC SEC VIII D1, and as required herein, at the locations indicated and elsewhere as required for the proper functioning of the system. Use gate valves unless otherwise directed. Install stop valves in the supply lines equipped or located so as to permit operation from floor level, or provided with safe access in the form of walkways or ladders. Install valves in positions accessible for operation and repair.

3.1.2.2 Safety Valves

Provide with drip pan elbows.

3.1.3 Pressure Gages

Install a shutoff valve or petcock between each pressure gage and the line, and gages on steam lines shall have a syphon installed ahead of the gage.

3.1.4 Thermometers

Provide thermometers and thermal sensing elements of control valves with a separable socket. Install separable sockets in pipe lines in such a manner to sense the temperature of the flowing fluid and minimize obstruction to flow.

3.1.5 Strainers

Provide strainers with meshes suitable for the services where indicated, and where dirt might interfere with the proper operation of valve parts, orifices, and moving parts of equipment.

3.1.6 Cleaning of System

As installations of the various system components are completed, clean before final closing. Remove foreign matter from equipment and surrounding areas. Preliminary or final tests shall not be performed until the cleaning is approved.

3.1.7 Identification of Piping

Labels for pipes 3/4 inch diameter and larger shall bear printed legends to identify contents of pipes and arrows to shown direction of flow. Labels shall have color coded background to signify levels of hazard in accordance with ASME A13.1. Legends and type and size of characters shall also conform as ASME A13.1. Make labels of plastic sheet CID A-A-1689 with pressure sensitivity suitable for the intended applications, or they may be premolded of plastic to fit over pipe. For pipe smaller than 3/4 inch diameter, provide brass identification tags 1 1/2 inches in diameter with legends in depressed black filled characters.

3.2 FIELD TESTS AND INSPECTIONS

Field inspections, field tests, and trial operations specified in this section shall be performed by the Contractor. The Contractor shall provide gas, oil, labor, equipment, and incidentals required for testing, except that in accordance with Division 1 the Government will provide water or electric power required for tests. The Contractor shall give the Contracting Officer 14 days' advance written notice of the dates and times scheduled for tests and trial operations.

3.2.1 Field Inspections

Inspect piping system prior to initial operation, for conformance to drawings, specifications, and ASME B31.1. Equipment, material, or work rejected because of defects or non-conformance with drawings, specifications, and ASME B31.1 shall be replaced or corrected by the Contractor, as directed by the Contracting Officer.

3.2.2 Field Tests

Conduct the following tests after completion of the piping installation and prior to initial operation.

3.2.2.1 Piping System

Test piping system hydrostatically using water not exceeding 100 degrees F. Conduct tests in accordance with the requirements of ASME B31.1 and as follows. Test the piping system after the lines have been cleaned as herein specified and before any insulation covering has been applied. Test piping system at 1 1/2 times the system pressure or 50 psig whichever is greater. Before performing tests, remove or valve off from the system, gages, traps, and other apparatus which may be damaged by the test pressure. Install a calibrated test pressure gage in the system to observe

any loss in pressure. Maintain the required test pressure for a sufficient length of time to enable an inspection to be made of joints and connections. Perform tests after installation and prior to acceptance.

3.2.2.2 Start-Up and Operational Test

Start-up the system and initially operate with components operating. During the test, periodically clean the various strainers until no further accumulation of foreign material occurs. Exercise care so that minimum loss of steam occur when strainers are cleaned. Adjust safety and automatic control instruments as necessary to place them in proper operation and sequence.

3.2.2.3 Extent of Field Tests

After installation and before acceptance, subject the work of this section to necessary field tests, including those herein specified, and in Section 23 05 93 TESTING, ADJUSTING AND BALANCING.

-- End of Section --

SECTION 26 00 00.00 20

BASIC ELECTRICAL MATERIALS AND METHODS
07/06

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM D 709	(2001; R 2007) Laminated Thermosetting Materials

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C2	(2007; Errata 2007; INT 2008) National Electrical Safety Code
IEEE Std 100	(2000) The Authoritative Dictionary of IEEE Standards Terms

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA 250	(2003) Enclosures for Electrical Equipment (1000 Volts Maximum)

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2008; AMD 1 2008) National Electrical Code - 2008 Edition

1.2 RELATED REQUIREMENTS

This section applies to certain sections of Divisions 22 and 23, PLUMBING and HEATING VENTILATING AND AIR CONDITIONING. This section applies to all sections of Division 26 and 33, ELECTRICAL and UTILITIES, of this project specification unless specified otherwise in the individual sections.

1.3 DEFINITIONS

a. Unless otherwise specified or indicated, electrical and electronics terms used in these specifications, and on the drawings, shall be as defined in IEEE Std 100.

b. The technical sections referred to herein are those specification sections that describe products, installation procedures, and equipment operations and that refer to this section for detailed description of submittal types.

c. The technical paragraphs referred to herein are those paragraphs in PART 2 - PRODUCTS and PART 3 - EXECUTION of the technical sections that describe products, systems, installation procedures, equipment, and test methods.

1.4 ELECTRICAL CHARACTERISTICS

Electrical characteristics for this project shall be 277/480 kV primary, three phase, four wire, 60 Hz, and 120/220 volts secondary, three phase, four wire.

1.5 ADDITIONAL SUBMITTALS INFORMATION

Submittals required in other sections that refer to this section must conform to the following additional requirements as applicable.

1.5.1 Shop Drawings (SD-02)

Include wiring diagrams and installation details of equipment indicating proposed location, layout and arrangement, control panels, accessories, piping, ductwork, and other items that must be shown to ensure a coordinated installation. Wiring diagrams shall identify circuit terminals and indicate the internal wiring for each item of equipment and the interconnection between each item of equipment. Drawings shall indicate adequate clearance for operation, maintenance, and replacement of operating equipment devices.

1.5.2 Product Data (SD-03)

Submittal shall include performance and characteristic curves.

1.6 QUALITY ASSURANCE

1.6.1 Regulatory Requirements

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "shall" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction," or words of similar meaning, to mean the Contracting Officer. Equipment, materials, installation, and workmanship shall be in accordance with the mandatory and advisory provisions of NFPA 70 unless more stringent requirements are specified or indicated.

1.6.2 Standard Products

Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design and workmanship. Products shall have been in satisfactory commercial or industrial use for 2 years prior to bid opening. The 2-year period shall include applications of equipment and materials under similar circumstances and of similar size. The product shall have been on sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2-year period. Where two or more items of the same class of equipment are required, these items shall be products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in the technical section.

1.6.2.1 Alternative Qualifications

Products having less than a 2-year field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturers' factory or laboratory tests, is

furnished.

1.6.2.2 Material and Equipment Manufacturing Date

Products manufactured more than 3 years prior to date of delivery to site shall not be used, unless specified otherwise.

1.7 WARRANTY

The equipment items shall be supported by service organizations which are reasonably convenient to the equipment installation in order to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

1.8 POSTED OPERATING INSTRUCTIONS

Provide for each system and principal item of equipment as specified in the technical sections for use by operation and maintenance personnel. The operating instructions shall include the following:

a. Wiring diagrams, control diagrams, and control sequence for each principal system and item of equipment.

b. Start up, proper adjustment, operating, lubrication, and shutdown procedures.

c. Safety precautions.

d. The procedure in the event of equipment failure.

e. Other items of instruction as recommended by the manufacturer of each system or item of equipment.

Print or engrave operating instructions and frame under glass or in approved laminated plastic. Post instructions where directed. For operating instructions exposed to the weather, provide weather-resistant materials or weatherproof enclosures. Operating instructions shall not fade when exposed to sunlight and shall be secured to prevent easy removal or peeling.

1.9 MANUFACTURER'S NAMEPLATE

Each item of equipment shall have a nameplate bearing the manufacturer's name, address, model number, and serial number securely affixed in a conspicuous place; the nameplate of the distributing agent will not be acceptable.

1.10 FIELD FABRICATED NAMEPLATES

ASTM D 709. Provide laminated plastic nameplates for each equipment enclosure, relay, switch, and device; as specified in the technical sections or as indicated on the drawings. Each nameplate inscription shall identify the function and, when applicable, the position. Nameplates shall be melamine plastic, 0.125 inch thick, white with black center core. Surface shall be matte finish. Corners shall be square. Accurately align lettering and engrave into the core. Minimum size of nameplates shall be one by 2.5 inches. Lettering shall be a minimum of 0.25 inch high normal block style.

1.11 WARNING SIGNS

Not Used.

1.12 ELECTRICAL REQUIREMENTS

Electrical installations shall conform to IEEE C2, NFPA 70, and requirements specified herein.

1.13 INSTRUCTION TO GOVERNMENT PERSONNEL

Where specified in the technical sections, furnish the services of competent instructors to give full instruction to designated Government personnel in the adjustment, operation, and maintenance of the specified systems and equipment, including pertinent safety requirements as required. Instructors shall be thoroughly familiar with all parts of the installation and shall be trained in operating theory as well as practical operation and maintenance work. Instruction shall be given during the first regular work week after the equipment or system has been accepted and turned over to the Government for regular operation. The number of man-days (8 hours per day) of instruction furnished shall be as specified in the individual section. When more than 4 man-days of instruction are specified, use approximately half of the time for classroom instruction. Use other time for instruction with equipment or system. When significant changes or modifications in the equipment or system are made under the terms of the contract, provide additional instructions to acquaint the operating personnel with the changes or modifications.

PART 2 PRODUCTS

2.1 FACTORY APPLIED FINISH

Electrical equipment shall have factory-applied painting systems which shall, as a minimum, meet the requirements of NEMA 250 corrosion-resistance test.

PART 3 EXECUTION

3.1 FIELD APPLIED PAINTING

Paint electrical equipment as required to match finish of adjacent surfaces or to meet the indicated or specified safety criteria. Painting shall be as specified in the section specifying the associated electrical equipment.

3.2 FIELD FABRICATED NAMEPLATE MOUNTING

Provide number, location, and letter designation of nameplates as indicated. Fasten nameplates to the device with a minimum of two sheet-metal screws or two rivets.

3.3 WARNING SIGN MOUNTING

Provide the number of signs required to be readable from each accessible side, but space the signs a maximum of 30 feet apart.

-- End of Section --

SECTION 26 20 00

INTERIOR DISTRIBUTION SYSTEM
02/14

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM B1	(2013) Standard Specification for Hard-Drawn Copper Wire
ASTM B8	(2011) Standard Specification for Concentric-Lay-Stranded Copper Conductors, Hard, Medium-Hard, or Soft
ASTM D709	(2013) Laminated Thermosetting Materials

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 100	(2000; Archived) The Authoritative Dictionary of IEEE Standards Terms
IEEE 81	(2012) Guide for Measuring Earth Resistivity, Ground Impedance, and Earth Surface Potentials of a Ground System
IEEE C2	(2012; Errata 2012; INT 1-4 2012; INT 5-7 2013) National Electrical Safety Code

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

ANSI C80.1	(2005) American National Standard for Electrical Rigid Steel Conduit (ERSC)
ANSI C80.3	(2005) American National Standard for Electrical Metallic Tubing (EMT)
NEMA 250	(2008) Enclosures for Electrical Equipment (1000 Volts Maximum)
NEMA BU 1.1	(2010) General Instructions for Proper Handling, Installation, Operation and Maintenance of Busway Rated 600 V or Less
NEMA FU 1	(2012) Low Voltage Cartridge Fuses
NEMA ICS 1	(2000; R 2008; E 2010) Standard for Industrial Control and Systems: General Requirements
NEMA ICS 6	(1993; R 2011) Enclosures

NEMA KS 1	(2001; R 2006) Enclosed and Miscellaneous Distribution Equipment Switches (600 V Maximum)
NEMA WD 1	(1999; R 2005; R 2010) Standard for General Color Requirements for Wiring Devices
NEMA WD 6	(2012) Wiring Devices Dimensions Specifications
NEMA Z535.4	(2011) American National Standard for Product Safety Signs and Labels

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2014; AMD 1 2013; Errata 1 2013; AMD 2 2013; Errata 2 2013) National Electrical Code
NFPA 70E	(2012; Errata 2012) Standard for Electrical Safety in the Workplace

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.147	Control of Hazardous Energy (Lock Out/Tag Out)

UNDERWRITERS LABORATORIES (UL)

UL 1	(2005; Reprint Jul 2012) Standard for Flexible Metal Conduit
UL 1660	(2004; Reprint Apr 2013) Liquid-Tight Flexible Nonmetallic Conduit
UL 198M	(2003; Reprint Feb 2013) Standard for Mine-Duty Fuses
UL 20	(2010; Reprint Feb 2012) General-Use Snap Switches
UL 360	(2013; Reprint May 2013) Liquid-Tight Flexible Steel Conduit
UL 4248-1	(2007; Reprint Oct 2013) UL Standard for Safety Fuseholders - Part 1: General Requirements
UL 4248-12	(2007; Reprint Dec 2012) UL Standard for Safety Fuseholders - Part 12: Class R
UL 467	(2007) Grounding and Bonding Equipment
UL 486A-486B	(2013; Reprint Dec 2013) Wire Connectors
UL 486C	(2013; Reprint Dec 2013) Splicing Wire Connectors

UL 489	(2013) Molded-Case Circuit Breakers, Molded-Case Switches, and Circuit-Breaker Enclosures
UL 498	(2012; Reprint Aug 2013) Attachment Plugs and Receptacles
UL 50	(2007; Reprint Apr 2012) Enclosures for Electrical Equipment, Non-environmental Considerations
UL 510	(2005; Reprint Jul 2013) Polyvinyl Chloride, Polyethylene and Rubber Insulating Tape
UL 514A	(2013) Metallic Outlet Boxes
UL 514B	(2012) Conduit, Tubing and Cable Fittings
UL 514C	(1996; Reprint Nov 2011) Nonmetallic Outlet Boxes, Flush-Device Boxes, and Covers
UL 6	(2007; reprint Nov 2010) Electrical Rigid Metal Conduit-Steel
UL 67	(2009; Reprint Jan 2013) Standard for Panelboards
UL 797	(2007; Reprint Dec 2012) Electrical Metallic Tubing -- Steel
UL 817	(2001; Reprint Feb 2014) Standard for Cord Sets and Power-Supply Cords
UL 83	(2008) Thermoplastic-Insulated Wires and Cables
UL 857	(2009; Reprint Dec 2011) Busways
UL 869A	(2006) Reference Standard for Service Equipment
UL 943	(2006; Reprint Jun 2012) Ground-Fault Circuit-Interrupters

1.2 DEFINITIONS

Unless otherwise specified or indicated, electrical and electronics terms used in these specifications, and on the drawings, are as defined in IEEE 100.

1.3 SUBMITTALS

Submit in accordance with SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Panelboards

Busway

SD-03 Product Data

Receptacles

Circuit breakers

Switches

Enclosed circuit breakers

SD-06 Test Reports

600-volt wiring test

Grounding system test

Ground-fault receptacle test

SD-07 Certificates

Fuses

1.4 QUALITY ASSURANCE

1.4.1 Regulatory Requirements

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "shall" or "must" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction," or words of similar meaning, to mean the Contracting Officer. Provide equipment, materials, installation, and workmanship in accordance with the mandatory and advisory provisions of NFPA 70 unless more stringent requirements are specified or indicated.

1.4.2 Standard Products

Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design and workmanship and:

a. Have been in satisfactory commercial or industrial use for 2 years prior to bid opening including applications of equipment and materials under similar circumstances and of similar size.

b. Have been on sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2-year period.

c. Where two or more items of the same class of equipment are required, provide products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in this section.

1.4.2.1 Alternative Qualifications

Products having less than a 2-year field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturers' factory or laboratory tests, is furnished.

1.4.2.2 Material and Equipment Manufacturing Date

Products manufactured more than 3 years prior to date of delivery to site are not acceptable.

1.5 WARRANTY

Provide equipment items supported by service organizations that are reasonably convenient to the equipment installation in order to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

PART 2 PRODUCTS

2.1 MATERIALS AND EQUIPMENT

As a minimum, meet requirements of UL, where UL standards are established for those items, and requirements of NFPA 70 for all materials, equipment, and devices.

2.2 CONDUIT AND FITTINGS

Conform to the following:

2.2.1 Rigid Metallic Conduit

2.2.1.1 Rigid, Threaded Zinc-Coated Steel Conduit

ANSI C80.1, UL 6.

2.2.2 Electrical, Zinc-Coated Steel Metallic Tubing (EMT)

UL 797, ANSI C80.3.

2.2.3 Flexible Metal Conduit

UL 1.

2.2.3.1 Liquid-Tight Flexible Metal Conduit, Steel

UL 360.

2.2.4 Fittings for Metal Conduit, EMT, and Flexible Metal Conduit

UL 514B. Ferrous fittings: cadmium- or zinc-coated in accordance with UL 514B.

2.2.4.1 Fittings for Rigid Metal Conduit and IMC

Threaded-type. Split couplings unacceptable.

2.2.4.2 Fittings for EMT

Steel compression type.

2.2.5 Liquid-Tight Flexible Nonmetallic Conduit

UL 1660.

2.3 BUSWAY

NEMA BU 1.1, UL 857. Provide the following:

a. Buses: copper.

b. Busways: rated 208 volts, three-phase, four wire, and include integral or internal ground bus.

c. Short circuit rating: root mean square (rms) symmetrical amperes minimum to match existing busway.

d. Busway systems: suitable for use indoors.

e. Enclosures: steel.

f. Hardware: plated or otherwise protected to resist corrosion.

g. Joints: one-bolt type with through-bolts, which can be checked for tightness without deenergizing system.

h. Maximum hot spot temperature rise at any point in busway at continuous rated load: do not exceed 55 degrees C above maximum ambient temperature of 40 degrees C in any position.

i. Internal barriers to prevent movement of superheated gases.

j. Coordinate proper voltage phasing of entire bus duct system, for example where busway interfaces with transformers, switchgear, switchboards, motor control centers, and other system components.

2.3.1 Plug-In Busways

Unventilated type. Provide the following:

a. Plug-in units: circuit breaker-type.

b. Bus bars: covered with insulating material throughout, except at joints and other connection points.

2.4 OUTLET BOXES AND COVERS

UL 514A, cadmium- or zinc-coated, if ferrous metal. UL 514C, if nonmetallic.

2.5 CABINETS, JUNCTION BOXES, AND PULL BOXES

Volume greater than 100 cubic inches, UL 50, hot-dip, zinc-coated, if sheet steel.

2.6 WIRES AND CABLES

Provide wires and cables in accordance applicable requirements of NFPA 70 and UL for type of insulation, jacket, and conductor specified or indicated. Do not use wires and cables manufactured more than 12 months prior to date of delivery to site.

2.6.1 Conductors

Provide the following:

a. Conductor sizes and capacities shown are based on copper.

b. Conductors No. 8 AWG and larger diameter: stranded.

c. Conductors No. 10 AWG and smaller diameter: solid.

d. Conductors for remote control, alarm, and signal circuits, classes 1, 2, and 3: stranded unless specifically indicated otherwise.

e. All conductors: copper

2.6.1.1 Minimum Conductor Sizes

Provide minimum conductor size in accordance with the following:

a. Branch circuits: No. 12 AWG.

b. Class 1 remote-control and signal circuits: No. 14 AWG.

c. Class 2 low-energy, remote-control and signal circuits: No. 16 AWG.

d. Class 3 low-energy, remote-control, alarm and signal circuits: No. 22 AWG.

2.6.2 Color Coding

Provide color coding for service, feeder, branch, control, and signaling circuit conductors.

2.6.2.1 Ground and Neutral Conductors

Provide color coding of ground and neutral conductors as follows:

a. Grounding conductors: Green.

b. Neutral conductors: White.

c. Exception, where neutrals of more than one system are installed in same raceway or box, other neutrals color coding: white with a different colored (not green) stripe for each.

2.6.2.2 Ungrounded Conductors

Provide color coding of ungrounded conductors in different voltage systems as follows:

a. 208/120 volt, three-phase

(1) Phase A - black

(2) Phase B - red

(3) Phase C - blue

b. 480/277 volt, three-phase

(1) Phase A - brown

(2) Phase B - orange

(3) Phase C - yellow

2.6.3 Insulation

Unless specified or indicated otherwise or required by NFPA 70, provide power and lighting wires rated for 600-volts, Type THWN/THHN conforming to UL 83, except that grounding wire may be type TW conforming to UL 83; remote-control and signal circuits: Type TW or TF, conforming to UL 83. Where lighting fixtures require 90-degree Centigrade (C) conductors, provide only conductors with 90-degree C insulation or better.

2.6.4 Bonding Conductors

ASTM B1, solid bare copper wire for sizes No. 8 AWG and smaller diameter; ASTM B8, Class B, stranded bare copper wire for sizes No. 6 AWG and larger diameter.

2.6.5 Cord Sets and Power-Supply Cords

UL 817.

2.7 SPLICES AND TERMINATION COMPONENTS

UL 486A-486B for wire connectors and UL 510 for insulating tapes. Connectors for No. 10 AWG and smaller diameter wires: insulated, pressure-type in accordance with UL 486A-486B or UL 486C (twist-on splicing connector). Provide solderless terminal lugs on stranded conductors.

2.8 DEVICE PLATES

Provide the following:

a. UL listed, one-piece device plates for outlets to suit the devices installed.

b. For metal outlet boxes, plates on unfinished walls: zinc-coated sheet steel or cast metal having round or beveled edges.

e. Plates on finished walls: satin finish stainless steel or brushed-finish aluminum, minimum 0.03 inch thick.

f. Screws: machine-type with countersunk heads in color to match finish of plate.

g. Sectional type device plates are not be permitted.

h. Plates installed in wet locations: gasketed and UL listed for "wet

locations."

2.9 SWITCHES

2.9.1 Toggle Switches

NEMA WD 1, UL 20, single pole, heav-duty, totally enclosed with bodies of thermoplastic or thermoset plastic and mounting strap with grounding screw. Include the following:

a. Handles: brown thermoplastic.

b. Wiring terminals: screw-type, side-wired.

c. Contacts: silver-cadmium and contact arm - one-piece copper alloy.

d. Switches: rated quiet-type ac only, 120/277 volts, with current rating and number of poles indicated.

2.9.2 Disconnect Switches

NEMA KS 1. Provide heavy duty-type switches where indicated, where switches are rated higher than 240 volts, and for double-throw switches. Utilize Class R fuseholders and fuses for fused switches, unless indicated otherwise. Provide horsepower rated for switches serving as the motor-disconnect means. Provide switches in NEMA enclosure as indicated per NEMA ICS 6.

2.10 FUSES

NEMA FU 1. Provide complete set of fuses for each fusible switch. Coordinate time-current characteristics curves of fuses serving motorsfor proper operation. Submit coordination data for approval. Provide fuses with a voltage rating not less than circuit voltage.

2.10.1 Fuseholders

Provide in accordance with UL 4248-1.

2.10.2 Cartridge Fuses, Current Limiting Type (Class R)

UL 198M, ClassRK-5 time-delay type. Provide only Class R associated fuseholders in accordance with UL 4248-12.

2.11 RECEPTACLES

Provide the following:

a. UL 498, hard use (also designated heavy-duty), grounding-type.

b. Ratings and configurations: as indicated.

c. Bodies: brown as per NEMA WD 1.

d. Face and body: thermoplastic supported on a metal mounting strap.

e. Dimensional requirements: per NEMA WD 6.

f. Screw-type, side-wired wiring terminals or of the solderless pressure

type having suitable conductor-release arrangement.

g. Grounding pole connected to mounting strap.

h. The receptacle: containing triple-wipe power contacts and double or triple-wipe ground contacts.

2.11.1 Weatherproof Receptacles

Provide receptacles, UL listed for use in "wet locations". Include cast metal box with gasketed, hinged, lockable and weatherproof while-in-use, die-cast metal/aluminum cover plate.

2.11.2 Ground-Fault Circuit Interrupter Receptacles

UL 943, duplex type for mounting in standard outlet box. Provide device capable of detecting current leak of 6 milliamperes or greater and tripping per requirements of UL 943 for Class A ground-fault circuit interrupter devices. Provide screw-type, side-wired wiring terminals or pre-wired (pigtail) leads.

2.12 PANELBOARDS

Provide panelboards in accordance with the following:

a. UL 67 and UL 50 having a short-circuit current rating as indicated.

b. Panelboards for use as service disconnecting means: additionally conform to UL 869A.

c. Panelboards: circuit breaker-equipped.

d. Designed such that individual breakers can be removed without disturbing adjacent units or without loosening or removing supplemental insulation supplied as means of obtaining clearances as required by UL.

e. "Specific breaker placement" is required in panelboards to match the breaker placement indicated in the panelboard schedule on the drawings.

f. Use of "Subfeed Breakers" is not acceptable unless specifically indicated otherwise.

g. Main breaker: "separately" mounted "above" or "below" branch breakers.

h. Where "space only" is indicated, make provisions for future installation of breakers.

i. Directories: indicate load served by each circuit in panelboard.

j. Directories: indicate source of service to panelboard (e.g., Panel PA served from Panel MDP).

k. Provide new directories for existing panels modified by this project as indicated.

l. Type directories and mount in holder behind transparent protective covering.

m. Panelboards: listed and labeled for their intended use.

n. Panelboard nameplates: provided in accordance with paragraph FIELD FABRICATED NAMEPLATES.

2.12.1 Enclosure

Provide panelboard enclosure in accordance with the following:

a. UL 50.

b. Cabinets mounted outdoors or flush-mounted: hot-dipped galvanized after fabrication.

c. Cabinets: painted in accordance with paragraph PAINTING.

d. Outdoor cabinets: NEMA 3R raintight witha removable steel plate 1/4 inch thick in the bottom for field drilling for conduit connections.

e. Front edges of cabinets: form-flanged or fitted with structural shapes welded or riveted to the sheet steel, for supporting the panelboard front.

f. All cabinets: fabricated such that no part of any surface on the finished cabinet deviates from a true plane by more than 1/8 inch.

g. Holes: provided in the back of indoor surface-mounted cabinets, with outside spacers and inside stiffeners, for mounting the cabinets with a 1/2 inch clear space between the back of the cabinet and the wall surface.

h. Flush doors: mounted on hinges that expose only the hinge roll to view when the door is closed.

i. Each door: fitted with a combined catch and lock, except that doors over 24 inches long provided with a three-point latch having a knob with a T-handle, and a cylinder lock.

j. Keys: two provided with each lock, with all locks keyed alike.

k. Finished-head cap screws: provided for mounting the panelboard fronts on the cabinets.

2.12.2 Panelboard Buses

Support bus bars on bases independent of circuit breakers. Design main buses and back pans so that breakers may be changed without machining, drilling, or tapping. Provide isolated neutral bus in each panel for connection of circuit neutral conductors. Provide separate ground bus identified as equipment grounding bus per UL 67 for connecting grounding conductors; bond to steel cabinet.

2.12.3 Circuit Breakers

UL 489, thermal magnetic-type having a minimum short-circuit current rating equal to the short-circuit current rating of the panelboard in which the circuit breaker will be mounted. Breaker terminals: UL listed as suitable for type of conductor provided. Series rated circuit breakers and plug-in circuit breakers are unacceptable.

2.12.3.1 Multipole Breakers

Provide common trip-type with single operating handle. Design breaker such that overload in one pole automatically causes all poles to open. Maintain phase sequence throughout each panel so that any three adjacent breaker poles are connected to Phases A, B, and C, respectively.

2.12.3.2 Circuit Breakers for HVAC Equipment

Provide circuit breakers for HVAC equipment having motors (group or individual) marked for use with HACR type and UL listed as HACR type.

2.13 ENCLOSED CIRCUIT BREAKERS

UL 489. Individual molded case circuit breakers with voltage and continuous current ratings, number of poles, overload trip setting, and short circuit current interrupting rating as indicated. Enclosure type as indicated. Provide solid neutral.

2.14 MANUAL MOTOR STARTERS (MOTOR RATED SWITCHES)

Three pole designed for surface mounting with overload protection.

2.15 LOCKOUT REQUIREMENTS

Provide disconnecting means capable of being locked out for machines and other equipment to prevent unexpected startup or release of stored energy in accordance with 29 CFR 1910.147. Comply with requirements of Division 23, "Mechanical" for mechanical isolation of machines and other equipment.

2.16 GROUNDING AND BONDING EQUIPMENT

2.16.1 Ground Rods

UL 467. Ground rods: solid copper, with minimum diameter of 3/4 inch and minimum length 10 feet. Sectional ground rods are permitted.

2.17 MANUFACTURER'S NAMEPLATE

Provide on each item of equipment a nameplate bearing the manufacturer's name, address, model number, and serial number securely affixed in a conspicuous place; the nameplate of the distributing agent will not be acceptable.

2.18 FIELD FABRICATED NAMEPLATES

Provide field fabricated nameplates in accordance with the following:

a. ASTM D709.

b. Provide laminated plastic nameplates for each equipment enclosure, relay, switch, and device; as specified or as indicated on the drawings.

c. Each nameplate inscription: identify the function and, when applicable, the position.

d. Nameplates: melamine plastic, 0.125 inch thick, black with white center core.

e. Provide red laminated plastic label with white center core for fire alarm and where indicated.

f. Surface: matte finish. Corners: square. Accurately align lettering and engrave into the core.

g. Minimum size of nameplates: one by 2.5 inches.

h. Lettering size and style: a minimum of 0.25 inch high normal block style.

2.19 WARNING SIGNS

Provide warning signs for flash protection in accordance with NFPA 70E and NEMA Z535.4 for switchboards, panelboards, industrial control panels, and motor control centers that are in other than dwelling occupancies and are likely to require examination, adjustment, servicing, or maintenance while energized. Provide field installed signs to warn qualified persons of potential electric arc flash hazards when warning signs are not provided by the manufacturer. Provide marking that is clearly visible to qualified persons before examination, adjustment, servicing, or maintenance of the equipment.

2.20 FACTORY APPLIED FINISH

Provide factory-applied finish on electrical equipment in accordance with the following:

a. NEMA 250 corrosion-resistance test and the additional requirements as specified herein.

b. Interior and exterior steel surfaces of equipment enclosures: thoroughly cleaned followed by a rust-inhibitive phosphatizing or equivalent treatment prior to painting.

c. Exterior surfaces: free from holes, seams, dents, weld marks, loose scale or other imperfections.

d. Interior surfaces: receive not less than one coat of corrosion-resisting paint in accordance with the manufacturer's standard practice.

e. Exterior surfaces: primed, filled where necessary, and given not less than two coats baked enamel with semigloss finish.

f. Equipment located indoors: ANSI Light Gray, and equipment located outdoors: ANSI Light Gray.

g. Provide manufacturer's coatings for touch-up work and as specified in paragraph FIELD APPLIED PAINTING.

PART 3 EXECUTION

3.1 INSTALLATION

Electrical installations, including weatherproof and hazardous locations and ducts, plenums and other air-handling spaces: conform to requirements of NFPA 70 and IEEE C2 and to requirements specified herein.

3.1.1 Wiring Methods

Provide insulated conductors installed in rigid steel conduitor EMT, except where specifically indicated or specified otherwise or required by NFPA 70 to be installed otherwise. Grounding conductor: separate from electrical system neutral conductor. Provide insulated green equipment grounding conductor for circuit(s) installed in conduit and raceways. Minimum conduit size: 3/4 inch in diameter for low voltage lighting and power circuits.

3.1.1.1 Pull Wire

Install pull wires in empty conduits. Pull wire: plastic having minimum 200-pound force tensile strength. Leave minimum 36 inches of slack at each end of pull wire.

3.1.2 Conduit Installation

Unless indicated otherwise, conceal conduit under floor slabs and within finished walls, ceilings, and floors. Keep conduit minimum 6 inches away from parallel runs of flues and steam or hot water pipes. Install conduit parallel with or at right angles to ceilings, walls, and structural members where located above accessible ceilings and where conduit will be visible after completion of project.

3.1.2.1 Restrictions Applicable to EMT

a. Do not install underground.

b. Do not encase in concrete, mortar, grout, or other cementitious materials.

c. Do not use in areas subject to severe physical damage including but not limited to equipment rooms where moving or replacing equipment could physically damage the EMT.

d. Do not use in hazardous areas.

e. Do not use outdoors.

f. Do not use in fire pump rooms.

g. Do not use when the enclosed conductors must be shielded from the effects of High-altitude Electromagnetic Pulse (HEMP).

3.1.2.2 Restrictions Applicable to Flexible Conduit

Use only as specified in paragraph FLEXIBLE CONNECTIONS. Do not use when the enclosed conductors must be shielded from the effects of High-altitude Electromagnetic Pulse (HEMP).

3.1.2.3 Conduit Support

Support conduit by pipe straps, wall brackets, threaded rod conduit hangers, or ceiling trapeze. Fasten by wood screws to wood; by toggle bolts on hollow masonry units; by concrete inserts or expansion bolts on concrete or brick; and by machine screws, welded threaded studs, or spring-tension clamps on steel work. Threaded C-clamps may be used on rigid steel conduit

only. Do not weld conduits or pipe straps to steel structures. Do not exceed one-fourth proof test load for load applied to fasteners. Provide vibration resistant and shock-resistant fasteners attached to concrete ceiling. Do not cut main reinforcing bars for any holes cut to depth of more than 1 1/2 inches in reinforced concrete beams or to depth of more than 3/4 inch in concrete joints. Fill unused holes. In partitions of light steel construction, use sheet metal screws. In suspended-ceiling construction, run conduit above ceiling. Do not support conduit by ceiling support system. Conduit and box systems: supported independently of both (a) tie wires supporting ceiling grid system, and (b) ceiling grid system into which ceiling panels are placed. Do not share supporting means between electrical raceways and mechanical piping or ducts. Coordinate installation with above-ceiling mechanical systems to assure maximum accessibility to all systems. Spring-steel fasteners may be used for lighting branch circuit conduit supports in suspended ceilings in dry locations. Where conduit crosses building expansion joints, provide suitable expansion fitting that maintains conduit electrical continuity by bonding jumpers or other means. For conduits greater than 2 1/2 inches inside diameter, provide supports to resist forces of 0.5 times the equipment weight in any direction and 1.5 times the equipment weight in the downward direction.

3.1.2.4 Directional Changes in Conduit Runs

Make changes in direction of runs with symmetrical bends or cast-metal fittings. Make field-made bends and offsets with hickey or conduit-bending machine. Do not install crushed or deformed conduits. Avoid trapped conduits. Prevent plaster, dirt, or trash from lodging in conduits, boxes, fittings, and equipment during construction. Free clogged conduits of obstructions.

3.1.2.5 Locknuts and Bushings

Fasten conduits to sheet metal boxes and cabinets with two locknuts where required by NFPA 70, where insulated bushings are used, and where bushings cannot be brought into firm contact with the box; otherwise, use at least minimum single locknut and bushing. Provide locknuts with sharp edges for digging into wall of metal enclosures. Install bushings on ends of conduits, and provide insulating type where required by NFPA 70.

3.1.2.6 Flexible Connections

Provide flexible steel conduit between 3 and 6 feet in length for recessed and semirecessed lighting fixtures; for equipment subject to vibration, noise transmission, or movement; and for motors. Install flexible conduit to allow 20 percent slack. Minimum flexible steel conduit size: 1/2 inch diameter. Provide liquidtight flexible conduit in wet and damp locations for equipment subject to vibration, noise transmission, movement or motors. Provide separate ground conductor across flexible connections.

3.1.3 Busway Installation

Comply at minimum with NFPA 70. Install busways parallel with or at right angles to ceilings, walls, and structural members. Support busways at 5 foot maximum intervals, and brace to prevent lateral movement. Provide fixed type hinges on risers; spring-type are unacceptable. Provide flanges where busway makes penetrations through walls and floors, and seal to maintain smoke and fire ratings. Provide waterproof curb where busway riser passes through floor. Seal gaps with fire-rated foam and caulk.

Provide expansion joints, but only where bus duct crosses building expansion joints. Provide supports to resist forces of 0.5 times the equipment weight in any direction and 1.5 times the equipment weight in the downward direction.

3.1.4 Boxes, Outlets, and Supports

Provide boxes in wiring and raceway systems wherever required for pulling of wires, making connections, and mounting of devices or fixtures. Boxes for metallic raceways: cast-metal, hub-type when located in wet locations, when surface mounted on outside of exterior surfaces, when surface mounted on interior walls exposed up to 7 feet above floors and walkways, and when specifically indicated. Boxes in other locations: sheet steel. Provide each box with volume required by NFPA 70 for number of conductors enclosed in box. Boxes for mounting lighting fixtures: minimum 4 inches square, or octagonal, except that smaller boxes may be installed as required by fixture configurations, as approved. Boxes for use in masonry-block or tile walls: square-cornered, tile-type, or standard boxes having square-cornered, tile-type covers. Provide gaskets for cast-metal boxes installed in wet locations and boxes installed flush with outside of exterior surfaces. Provide separate boxes for flush or recessed fixtures when required by fixture terminal operating temperature; provide readily removable fixtures for access to boxes unless ceiling access panels are provided. Support boxes and pendants for surface-mounted fixtures on suspended ceilings independently of ceiling supports. Fasten boxes and supports with wood screws on wood, with bolts and expansion shields on concrete or brick, with toggle bolts on hollow masonry units, and with machine screws or welded studs on steel. In open overhead spaces, cast boxes threaded to raceways need not be separately supported except where used for fixture support; support sheet metal boxes directly from building structure or by bar hangers. Where bar hangers are used, attach bar to raceways on opposite sides of box, and support raceway with approved-type fastener maximum 24 inches from box. When penetrating reinforced concrete members, avoid cutting reinforcing steel.

3.1.4.1 Boxes

Boxes for use with raceway systems: minimum 1 1/2 inches deep, except where shallower boxes required by structural conditions are approved. Boxes for other than lighting fixture outlets: minimum 4 inches square, except that 4 by 2 inch boxes may be used where only one raceway enters outlet. Mount outlet boxes flush in finished walls.

3.1.4.2 Pull Boxes

Construct of at least minimum size required by NFPA 70 of code-gauge galvanized sheet steel, except where cast-metal boxes are required in locations specified herein. Provide boxes with screw-fastened covers. Where several feeders pass through common pull box, tag feeders to indicate clearly electrical characteristics, circuit number, and panel designation.

3.1.5 Mounting Heights

Mount panelboards, enclosed circuit breakers, and disconnecting switches so height of operating handle at its highest position is maximum 78 inches above floor. Mount lighting switches 48 inches above finished floor. Mount receptacles 18 inches above finished floor, unless otherwise indicated.

Mount other devices as indicated. Measure mounting heights of wiring devices and outlets to center of device or outlet.

3.1.6 Conductor Identification

Provide conductor identification within each enclosure where tap, splice, or termination is made. For conductors No. 6 AWG and smaller diameter, provide color coding by factory-applied, color-impregnated insulation. For conductors No. 4 AWG and larger diameter, provide color coding by plastic-coated, self-sticking markers; colored nylon cable ties and plates; or heat shrink-type sleeves. Identify control circuit terminations in accordance with Section 23 09 23.13 20 LONWORKS DIRECT DIGITAL CONTROL FOR HVAC AND OTHER BUILDING CONTROL SYSTEMS.

3.1.6.1 Marking Strips

Provide marking strips in accordance with the following:

a. Provide white or other light-colored plastic marking strips, fastened by screws to each terminal block, for wire designations.

b. Use permanent ink for the wire numbers

c. Provide reversible marking strips to permit marking both sides, or provide two marking strips with each block.

d. Size marking strips to accommodate the two sets of wire numbers.

e. Assign a device designation in accordance with NEMA ICS 1 to each device to which a connection is made. Mark each device terminal to which a connection is made with a distinct terminal marking corresponding to the wire designation used on the Contractor's schematic and connection diagrams.

f. The wire (terminal point) designations used on the Contractor's wiring diagrams and printed on terminal block marking strips may be according to the Contractor's standard practice; however, provide additional wire and cable designations for identification of remote (external) circuits for the Government's wire designations.

3.1.7 Splices

Make splices in accessible locations. Make splices in conductors No. 10 AWG and smaller diameter with insulated, pressure-type connector. Make splices in conductors No. 8 AWG and larger diameter with solderless connector, and cover with insulation material equivalent to conductor insulation.

3.1.8 Covers and Device Plates

Install with edges in continuous contact with finished wall surfaces without use of mats or similar devices. Plaster fillings are not permitted. Install plates with alignment tolerance of 1/16 inch. Use of sectional-type device plates are not permitted. Provide gasket for plates installed in wet locations.

3.1.9 Electrical Penetrations

Seal openings around electrical penetrations through walls, partitions, floors, or ceilings.

3.1.10 Grounding and Bonding

Provide in accordance with NFPA 70. Ground exposed, non-current-carrying metallic parts of electrical equipment, metallic raceway systems, grounding conductor in metallic and nonmetallic raceways, and neutral conductor of wiring systems. Interconnect all grounding media in or on the structure to provide a common ground potential. Where ground fault protection is employed, ensure that connection of ground and neutral does not interfere with correct operation of fault protection.

3.1.10.1 Ground Rods

Provide cone pointed ground rods. Measure the resistance to ground using the fall-of-potential method described in IEEE 81. Do not exceed 25 ohms under normally dry conditions for the maximum resistance of a driven ground. If this resistance cannot be obtained with a single rod, additional rods, spaced on center, not less than twice the distance of the length of the rod, or if sectional type rods are used, additional sections may be coupled and driven with the first rod. If the resultant resistance exceeds 25 ohms measured not less than 48 hours after rainfall, notify the Contracting Officer who will decide on the number of ground rods to add.

3.1.10.2 Grounding Connections

Make grounding connections which are buried or otherwise normally inaccessible, excepting specifically those connections for which access for periodic testing is required, by exothermic weld or compression connector.

a. Make exothermic welds strictly in accordance with the weld manufacturer's written recommendations. Welds which are "puffed up" or which show convex surfaces indicating improper cleaning are not acceptable. Mechanical connectors are not required at exothermic welds.

b. Make compression connections using a hydraulic compression tool to provide the correct circumferential pressure. Provide tools and dies as recommended by the manufacturer. Use an embossing die code or other standard method to provide visible indication that a connector has been adequately compressed on the ground wire.

3.1.10.3 Resistance

Maximum resistance-to-ground of grounding system: do not exceed 5 ohms under dry conditions. Where resistance obtained exceeds 5 ohms, contact Contracting Officer for further instructions.

3.1.11 Equipment Connections

Provide power wiring for the connection of motors and control equipment under this section of the specification. Except as otherwise specifically noted or specified, automatic control wiring, control devices, and protective devices within the control circuitry are not included in this section of the specifications and are provided under the section specifying the associated equipment.

3.1.12 Repair of Existing Work

Perform repair of existing work, demolition, and modification of existing electrical distribution systems as follows:

3.1.12.1 Workmanship

Lay out work in advance. Exercise care where cutting, channeling, chasing, or drilling of floors, walls, partitions, ceilings, or other surfaces is necessary for proper installation, support, or anchorage of conduit, raceways, or other electrical work. Repair damage to buildings, piping, and equipment using skilled craftsmen of trades involved.

3.1.12.2 Existing Concealed Wiring to be Removed

Disconnect existing concealed wiring to be removed from its source. Remove conductors; cut conduit flush with floor, underside of floor, and through walls; and seal openings.

3.1.12.3 Removal of Existing Electrical Distribution System

Removal of existing electrical distribution system equipment includes equipment's associated wiring, including conductors, cables, exposed conduit, surface metal raceways, boxes, and fittings, back to equipment's power source as indicated.

3.1.12.4 Continuation of Service

Maintain continuity of existing circuits of equipment to remain. Maintain existing circuits of equipment energized. Restore circuits wiring and power which are to remain but were disturbed during demolition back to original condition.

3.2 FIELD FABRICATED NAMEPLATE MOUNTING

Provide number, location, and letter designation of nameplates as indicated. Fasten nameplates to the device with a minimum of two sheet-metal screws or two rivets.

3.3 WARNING SIGN MOUNTING

Provide the number of signs required to be readable from each accessible side. Space the signs in accordance with NFPA 70E.

3.4 FIELD APPLIED PAINTING

Paint electrical equipment as required to match finish of adjacent surfaces or to meet the indicated or specified safety criteria.

3.5 FIELD QUALITY CONTROL

Furnish test equipment and personnel and submit written copies of test results. Give Contracting Officer 5 working days notice prior to each test.

3.5.1 Devices Subject to Manual Operation

Operate each device subject to manual operation at least five times, demonstrating satisfactory operation each time.

3.5.2 600-Volt Wiring Test

Test wiring rated 600 volt and less to verify that no short circuits or accidental grounds exist. Perform insulation resistance tests on wiring No. 6 AWG and larger diameter using instrument which applies voltage of

approximately 500 volts to provide direct reading of resistance. Minimum resistance: 250,000 ohms.

3.5.3 Ground-Fault Receptacle Test

Test ground-fault receptacles with a "load" (such as a plug in light) to verify that the "line" and "load" leads are not reversed.

3.5.4 Grounding System Test

Test grounding system to ensure continuity, and that resistance to ground is not excessive. Test each ground rod for resistance to ground before making connections to rod; tie grounding system together and test for resistance to ground. Make resistance measurements in dry weather, not earlier than 48 hours after rainfall. Submit written results of each test to Contracting Officer, and indicate location of rods as well as resistance and soil conditions at time measurements were made.

-- End of Section --

SECTION 28 31 64.00 10

FIRE DETECTION AND ALARM SYSTEM, ADDRESSABLE
08/09

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ACOUSTICAL SOCIETY OF AMERICA (ASA)

ASA S3.41	(1990; R 2008) Audible Emergency Evacuation Signal (ASA 96)

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2014; AMD 1 2013; Errata 1 2013; AMD 2 2013; Errata 2 2013) National Electrical Code
NFPA 72	(2013) National Fire Alarm and Signaling Code
NFPA 90A	(2012) Standard for the Installation of Air Conditioning and Ventilating Systems

UNDERWRITERS LABORATORIES (UL)

UL 1242	(2006; Reprint Jul 2012) Standard for Electrical Intermediate Metal Conduit -- Steel
UL 268	(2009) Smoke Detectors for Fire Alarm Systems
UL 268A	(2008; Reprint Sep 2009) Smoke Detectors for Duct Application
UL 521	(1999; Reprint May 2010) Heat Detectors for Fire Protective Signaling Systems
UL 6	(2007; reprint Nov 2010) Electrical Rigid Metal Conduit-Steel
UL 797	(2007; Reprint Dec 2012) Electrical Metallic Tubing -- Steel

1.2 SUBMITTALS

Submit the following in accordance with SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Detail Drawings

SD-06 Test Reports

Testing

SD-07 Certificates

Equipment
Qualifications

1.3 QUALITY ASSURANCE

1.3.1 Qualifications

Submit proof of qualifications for required personnel. The installer shall submit proof of experience for the Professional Engineer, fire alarm technician, and the installing company.

1.3.1.1 Installer

The installing Contractor shall provide the following: NICET Fire Alarm Technicians to perform the installation of the system. A NICET Level 4 Fire Alarm Technician shall supervise the installation of the fire alarm system. NICET Level 2 or higher Fire Alarm Technician shall install and terminate fire alarm devices, cabinets and panels. An electrician or NICET Level 1 Fire Alarm Technician shall install conduit for the fire alarm system. Fire Alarm Technicians to perform the installation of the system. A Fire Alarm Technician with a minimum of 4 years of experience shall perform/supervise the installation of the fire alarm system. Fire Alarm Technicians with a minimum of 2 years of experience shall be utilized to assist in the installation and terminate fire alarm devices, cabinets and panels. An electrician shall be allowed to install wire or cable and to install conduit for the fire alarm system. The Fire Alarm technicians installing the equipment shall be factory trained in the installation, adjustment, testing, and operation of the equipment specified herein and on the drawings.

1.3.2 Detail Drawings

Submit detail drawings consisting of a complete list of equipment and material, including manufacturer's descriptive and technical literature, catalog cuts, and installation instructions. Note that the contract drawings show layouts based on typical audible appliances. Check the layout based on the actual audible devices to be installed and make any necessary revisions in the detail drawings. The detail drawings shall also contain complete wiring and schematic diagrams for the equipment furnished, equipment layout, and any other details required to demonstrate that the system has been coordinated and will properly function as a unit. Detail drawings and detailed point-to-point wiring diagram shall be prepared and signed by a Registered Professional Engineer or a NICET Level 4 Fire Alarm Technician showing points of connection. Diagram shall include connections between system devices, appliances, control panels, supervised devices, and equipment that is activated or controlled by the panel.

1.4 DELIVERY, STORAGE, AND HANDLING

Protect equipment delivered and placed in storage from the weather, humidity and temperature variation, dirt, dust, and any other contaminants.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

Project includes modification of the existing Johnson Controls Inc. METASYS fire alarm system to support the removal of existing penthouses and the addition of new roof top air handling units. Specifications include removal of existing devices and connection of new devices to the existing microprocessor controlled, intelligent reporting fire alarm system as required to form a complete coordinated system ready for operation. It shall include, but not be limited to, alarm initiating devices, auxiliary control devices, and wiring as shown on the Drawings and specified herein. System modifications shall comply with NFPA 72.

2.1.1 Operation

Activate the system into the alarm mode by actuation of any alarm initiating device. The system will remain in the alarm mode until the initiating device is reset and the fire alarm control panel is reset and restored to normal. Alarm and supervisory initiating devices shall be individually addressable. Alarm initiating devices shall be connected to initiating device circuits (IDC), to signal line circuits (SLC), in accordance with NFPA 72. Connect alarm notification appliances to notification appliance circuits (NAC), in accordance with NFPA 72. Provide a looped conduit system so that if the conduit and all conductors within are severed at any point, all IDC, NAC and SLC will remain functional. The conduit loop requirement is not applicable to the signal transmission link from the local panels (at the protected premises) to the Supervising Station (fire station, fire alarm central communication center). Textual, audible, and visual appliances and systems shall comply with NFPA 72. Fire alarm system components requiring power, except for the control panel power supply, shall operate on 24 Volts dc. Addressable system shall be microcomputer (microprocessor or microcontroller) based with a minimum word size of eight bits and shall provide the following features:

b. Individual identity of each addressable device for the following conditions: alarm; trouble; open; short; and appliances missing/failed remote detector - sensitivity adjustment from the panel for smoke detectors.

c. Capability of each addressable device being individually disabled or enabled from the panel.

2.1.2 Operational Features

The system shall have the following operating features:

a. Monitor electrical supervision of IDC, SLC, and NAC.

b. Monitor electrical supervision of the primary power (ac) supply, battery voltage, placement of alarm zone module (card, PC board) within the control panel, and transmitter tripping circuit integrity.

c. A trouble buzzer and trouble LED/LCD (light emitting diode/liquid crystal diode) to activate upon a single break, open, or ground fault condition which prevents the required normal operation of the system. The trouble signal shall also operate upon loss of primary power (ac) supply, low battery voltage, removal of alarm zone module (card, PC

board), and disconnection of the circuit used for transmitting alarm signals off-premises. A trouble alarm silence switch shall be provided which will silence the trouble buzzer, but will not extinguish the trouble indicator LED/LCD. Subsequent trouble and supervisory alarms shall sound the trouble signal until silenced. After the system returns to normal operating conditions, the trouble buzzer shall again sound until the silencing switch returns to normal position, unless automatic trouble reset is provided.

d. A one person test mode. Activating an initiating device in this mode will activate an alarm for a short period of time, then automatically reset the alarm, without activating the transmitter during the entire process.

e. A transmitter disconnect switch to allow testing and maintenance of the system without activating the transmitter but providing a trouble signal when disconnected and a restoration signal when reconnected.

f. Evacuation alarm silencing switch which, when activated, will silence alarm devices, but will not affect the zone indicating LED/LCD displays on the control panel nor the operation of the transmitter. This switch shall be over-ridden upon activation of a subsequent alarm from an unalarmed device and the NAC devices will be activated.

g. Electrical supervision for circuits used for supervisory signal services (i.e., sprinkler systems, valves, etc.). Supervision shall detect any open, short, or ground.

h. Confirmation or verification of all smoke detectors. The control panel shall interrupt the transmission of an alarm signal to the system control panel for a factory preset period. This interruption period shall be adjustable from 1 to 60 seconds and be factory set at 20 seconds. Immediately following the interruption period, a confirmation period shall be in effect during which time an alarm signal, if present, will be sent immediately to the control panel. Fire alarm devices other than smoke detectors shall be programmed without confirmation or verification.

i. The fire alarm control panel shall provide supervised addressable relays for HVAC shutdown. An override at the HVAC panel shall not be provided.

k. The fire alarm control panel shall monitor the fire sprinkler system, or other fire protection extinguishing system.

l. The control panel and field panels shall be software reprogrammable to enable expansion or modification of the system without replacement of hardware or firmware. Examples of required changes are: adding or deleting devices or zones; changing system responses to particular input signals; programming certain input signals to activate auxiliary devices.

2.1.3 Alarm Functions

An alarm condition on a circuit shall automatically initiate the following functions:

a. Transmission of a signal over the station fire reporting system. The signal shall be common for any device.

b. Visual indications of the alarmed devices on the fire alarm control panel display.

c. Continuous sounding or operation of alarm notification appliances as required by ASA S3.41.

d. Closure of doors held open by electromagnetic devices.

e. Operation of the smoke control system.

f. Deactivation of the air handling units.

g. Shutdown of power to the data processing equipment in the alarmed area.

2.1.4 Primary Power

Operating power shall be provided as required by paragraph Power Supply for the System. Transfer from normal to emergency power or restoration from emergency to normal power shall be fully automatic and not cause transmission of a false alarm. Loss of ac power shall not prevent transmission of a signal via the fire reporting system upon operation of any initiating circuit.

2.1.5 Battery Backup Power

Battery backup power shall be through use of rechargeable, sealed-type storage batteries and battery charger.

2.1.6 Interface With Existing Fire Alarm Equipment

The equipment specified herein shall operate as an extension to an existing configuration. The new equipment shall be connected to an existing control panel in the existing part of the building. Existing monitoring equipment shall be expanded, modified, or supplemented as necessary to extend the existing monitoring functions to the new points or zones. New components shall be capable of merging with the existing configuration without degrading the performance of either system. The scope of the acceptance tests of paragraph Testing shall include aspects of operation that involve combined use of both new and existing portions of the final configuration.

2.1.7 Interface With other Equipment

Interfacing components shall be furnished as required to connect to subsystems or devices which interact with the fire alarm system, such as supervisory or alarm contacts in suppression systems, operating interfaces for smoke control systems, door releases, etc.

2.2 STANDARD PRODUCTS

Provide material and equipment which are the standard products of a manufacturer regularly engaged in the manufacture of the products for at least 2 years prior to bid opening. Equipment shall be supported by a service organization that can provide service within 24 hours of notification.

2.3 NAMEPLATES

Major components of equipment shall have the manufacturer's name, address,

type or style, voltage and current rating, and catalog number on a noncorrosive and nonheat-sensitive plate which is securely attached to the equipment. Equipment shall be completely compatable with and integratable to Johnson Controls, Inc. "METASYS" system, including programming.

2.4 FIRE DETECTING DEVICES

Fire detecting devices shall comply with the applicable requirements of NFPA 72, NFPA 90A, UL 268, UL 268A, and UL 521. The detectors shall be provided as indicated. Detector base shall have screw terminals for making connections. No solder connections will be allowed. Detectors located in concealed locations (above ceiling, raised floors, on the roof, etc.) shall have a remote visible indicator LED/LCD. Addressable fire detecting devices, except flame detectors, shall be dynamically supervised and uniquely identified in the control panel. All fire alarm initiating devices shall be individually addressable, except where indicated. Installed devices shall conform to NFPA 70 hazard classification of the area where devices are to be installed.

2.4.1 Smoke Detectors

Design smoke detectors for detection of abnormal smoke densities. Smoke detectors shall be photoelectric type. Detectors shall contain a visible indicator LED/LCD that shows when the unit is in alarm condition. Detectors shall not be adversely affected by vibration or pressure. Detectors shall be the plug-in type in which the detector base contains terminals for making wiring connections. Detectors that are to be installed in concealed locations (above false ceilings, raised floors, on the roof, etc.) shall be provided with a remote indicator LED/LCD suitable for mounting in a finished, visible location.

2.4.1.1 Duct Detectors

Duct-mounted photoelectric smoke detectors shall be furnished and installed where indicated and in accordance with NFPA 90A. Units shall consist of a smoke detector as specified in paragraph Photoelectric Detectors, mounted in a special housing fitted with duct sampling tubes. Detector circuitry shall be mounted in a metallic enclosure exterior to the duct. Detectors shall have a manual reset. Detectors shall be rated for air velocities that include air flows between 500 and 4000 fpm. Detectors shall be powered from the fire alarm panel. Sampling tubes shall run the full width of the duct. The duct detector package shall conform to the requirements of NFPA 90A, UL 268A, and shall be UL listed for use in air-handling systems. The control functions, operation, reset, and bypass shall be controlled from the fire alarm control panel. Lights to indicate the operation and alarm condition; and the test and reset buttons shall be visible and accessible with the unit installed and the cover in place. Detectors mounted above 6 feet and those mounted below 6 feet that cannot be easily accessed while standing on the floor, shall be provided with a remote detector indicator panel containing test and reset switches. Remote lamps and switches as well as the affected fan units shall be properly identified in etched plastic placards. Detectors shall have auxiliary contacts to provide control, interlock, and shutdown functions specified in Section 23 09 23.13 20 BACnet DIRECT DIGITAL CONTROL FOR HVAC. The detectors shall be supplied by the fire alarm system manufacturer to ensure complete system compatibility.

2.5 FIRE DETECTION AND ALARM SYSTEM PERIPHERAL EQUIPMENT

2.5.1 Conduit

Conduit and fittings shall comply with NFPA 70, UL 6, UL 1242, and UL 797.

2.5.2 Wiring

Wiring shall conform to NFPA 70. Wiring for 120 Vac power shall be No. 12 AWG minimum. The SLC wiring shall be fiber optic or copper cable in accordance with the manufacturers requirements. Wiring for fire alarm dc circuits shall be No. 14 AWG minimum. Voltages shall not be mixed in any junction box, housing, or device, except those containing power supplies and control relays. Wiring shall conform to NFPA 70. System field wiring shall be solid copper and installed in metallic conduit or electrical metallic tubing, except that rigid plastic conduit may be used under slab-on-grade. Conductors shall be color coded. Conductors used for the same functions shall be similarly color coded. Wiring code color shall remain uniform throughout the circuit. Pigtail or T-tap connections to initiating device circuits, supervisory alarm circuits, and notification appliance circuits are prohibited. T-tapping using screw terminal blocks is allowed for style 5 addressable systems.

PART 3 EXECUTION

3.1 EXAMINATION

After becoming familiar with details of the work, verify dimensions in the field and advise the Contracting Officer of any discrepancy before performing the work.

3.2 INSTALLATION

Install all work as shown, in accordance with NFPA 70 and NFPA 72, and in accordance with the manufacturer's diagrams and recommendations, unless otherwise specified. Smoke detectors shall not be installed until construction is essentially complete and the building has been thoroughly cleaned.

3.2.1 Wiring

Conduit size for wiring shall be in accordance with NFPA 70. Wiring for the fire alarm system shall not be installed in conduits, junction boxes, or outlet boxes with conductors of lighting and power systems. Not more than two conductors shall be installed under any device screw terminal. The wires under the screw terminal shall be straight when placed under the terminal then clamped in place under the screw terminal. The wires shall be broken and not twisted around the terminal. Circuit conductors entering or leaving any mounting box, outlet box enclosure, or cabinet shall be connected to screw terminals with each terminal and conductor marked in accordance with the wiring diagram. Connections and splices shall be made using screw terminal blocks. The use of wire nut type connectors in the system is prohibited. Wiring within any control equipment shall be readily accessible without removing any component parts. The fire alarm equipment manufacturer's representative shall be present for the connection of wiring to the control panel.

3.2.2 Detectors

Detectors shall be located and installed in accordance with NFPA 72. Detectors shall be connected into signal line circuits or initiating device circuits as indicated on the drawings. Detectors shall be at least 12 inches from any part of any lighting fixture. Detectors shall be located at least 3 feet from diffusers of air handling systems. Each detector shall be provided with appropriate mounting hardware as required by its mounting location. Detectors installed in concealed locations (above ceiling, raised floors, on the roof, etc.) shall have a remote visible indicator LED/LCD as indicated.

3.2.3 Addressable Initiating Device Circuits Module

The initiating device circuits module shall be used to connect supervised conventional initiating devices (water flow switches, water pressure switches, manual fire alarm stations, high/low air pressure switches, and tamper switches). The module shall mount in an electrical box adjacent to or connected to the device it is monitoring and shall be capable of Style B supervised wiring to the initiating device. In order to maintain proper supervision, there shall be no T-taps allowed on style B lines. Addressable initiating device circuits modules shall monitor only one initiating device each.

3.2.4 Addressable Control Module

Addressable and control modules shall be installed in the outlet box or adjacent to the device they are controlling. If a supplementary suppression releasing panel is provided, then the monitor modules shall he mounted in a common enclosure adjacent to the suppression releasing panel and both this enclosure and the suppression releasing panel shall be in the same room as the releasing devices. All interconnecting wires shall be supervised unless an open circuit or short circuit abnormal condition does not affect the required operation of the fire alarm system. If control modules are used as interfaces to other systems, such as HVAC or elevator control, they shall be within the control panel or immediately adjacent to it. Control modules that control a group of notification appliances shall be adjacent to the first notification appliance in the notification appliance circuits. Control modules that connect to devices shall supervise the notification appliance circuits. Control modules that connect to auxiliary systems or interface with other systems (non-life safety systems) and where not required by NFPA 72, shall not require the secondary circuits to be supervised.

3.3 GROUNDING

Grounding shall be provided by connecting to building ground system.

3.4 SUPERVISING STATION PROVISIONS

3.4.1 Revisions to Existing Facilities

Existing supervising components shall be modified as indicated on the drawings and programming shall be updated if required to accommodate the revised configuration. Acceptance testing shall include procedures that would demonstrate that operation of existing equipment has not been degraded and that the revised configuration plus interfacing components operates compatibly with the new fire alarm system at the protected premises. Work on existing equipment shall be performed in accordance with

the manufacturer's instructions or under supervision of the manufacturer's representative.

3.4.2 Additions to Existing Facilities

Supplemental components shall be added to the existing supervising equipment as required to accommodate the new fire alarm system to be installed at the protected premises. All present functions shall be extended, including recording and storage in memory, and programming shall be updated if required to accommodate the revised configuration. Acceptance testing shall include procedures that would demonstrate that operation of existing equipment has not been degraded and that the expanded configuration operates compatibly with the new fire alarm system.

3.5 TESTING

Notify the Contracting Officer at least 10 days before the preliminary and acceptance tests are to be conducted. Perform the tests in accordance with the approved test procedures in the presence of the Contracting Officer. The control panel manufacturer's representative shall be present to supervise tests. Furnish instruments and personnel required for the tests.

3.5.1 Preliminary Tests

Upon completion of the installation, subject the system to functional and operational performance tests including tests of each installed initiating and notification appliance, when required. Tests shall include the meggering of system conductors to determine that the system is free from grounded, shorted, or open circuits. Conduct the megger test prior to the installation of fire alarm equipment. If deficiencies are found, corrections shall be made and the system shall be retested to assure that it is functional. After completing the preliminary testing complete and submit the NFPA 72, Certificate of Completion and Testing Form.

3.5.2 Acceptance Test

Acceptance testing shall not be performed until the Contractor has completed and submitted the Certificate of Completion. Conduct testing in accordance with NFPA 72. The recommended tests in NFPA 72 are considered mandatory and shall verify that previous deficiencies have been corrected. The Fire alarm Technician supervising the installation of the fire alarm system shall attend the testing of the system. The test shall include all requirements of NFPA 72 and the following:

a. Test of each function of the control panel.

b. Test of each circuit in both trouble and normal modes.

c. Tests of each alarm initiating devices in both normal and trouble conditions.

d. Tests of each control circuit and device.

e. Tests of each alarm notification appliance.

f. Tests of the battery charger and batteries.

g. Complete operational tests under emergency power supply.

h. Visual inspection of wiring connections.

i. Opening the circuit at each alarm initiating device and notification appliance to test the wiring supervisory feature.

j. Ground fault.

k. Short circuit faults.

l. Stray voltage.

m. Loop resistance.

-- End of Section --